

(1) Number of pages 14
(2) Date of repair 12.2.87
(3) Initials of the Referencer low

TAMIL NADU ARCHIVES

GOVERNMENT OF TAMIL NADU

PUBLIC WORKS. DEPARTMENT

G.O. No. 2903.W.
B.P. No.

Press.
Mis.

Dated 19-11-1881.

197.

2.5

Not to be folded or roughly handled

GOVERNMENT OF MADRAS.
PUBLIC WORKS DEPARTMENT.

19th November 1881, No. 2903 W.

Buildings and Roads.
Military Works.

Read the following papers:—

No. 97. From the Superintending Engineer, Fourth Circle, dated 28th October 1881, No. 461.

No. 97-A. Memorandum to the Military Department, dated 5th November 1881, No. 2567.

No. 97-B. Proceedings of the Madras Government in the Military Department, dated 15th November 1881, No. 6037.

From the Public Works Department No. 2567, dated 5th November 1881, submitting for approval estimate, &c., amounting to Rs. 2,450 for constructing a Committee Stand at the Remount Depot, Hosūr.

Approved.
(True Extract.)

(Signed) E. L. HANKIN, Colonel,
Ag. Secy. to Govt., Mily. Dept.

No. 98. ORDER THEREON, 19th November 1881, No. 2903 W.

THE estimate, amounting to Rs. 2,450, for reconstructing the Committee Stand at the Remount Depot, Hosūr, is sanctioned.

2. The outlay will be debited against the allotment of the Salem Division for Minor Works under Military.

3. This sanction has been registered as Imperial Ordinary No. 49 W. of 1881-82, and classified as Military, Original Works.

(True Extract.)

(Signed) R. H. SANKEY, Colonel, R.E.,
Secretary to Govt., P.W.D.

To the Superintending Engineer, Fourth Circle, with four enclosures.
" Examiner of Public Works Accounts, with duplicate Abstract Estimate.
" Military Department.

Encl. E. C. Shunker.
Spare Copies

BUILDINGS AND ROADS
MILITARY WORKS.

Govt. of (1881) Madrid.
PUBLIC WORKS.

THE SUPERINTENDING ENGINEER,
FOURTH CIRCLE.

Date November, 1881.

Land

Rest

G.O. 1922 November 1881, No. 2891 B.

NOVEMBER.
Nos. 97-98.

Committee Stand at the Remount Depot
at Madrid - Estimate of Rs. 2,450 for reconstruction.
*including the new design.

No. 461

2403
✓

Report on the plan and estimate
Enclosures amounting to Rupees 2,450 for reconstruction.
1 Site Plan -ing the Committee Stand at Remount
1 Plan Depot. Odsot.
2 Duplicate Abstracts
1 Specification.

The present building is reported
by the Executive Engineer to be in
very bad order and not worth repairing.

A new building is required for the
purpose of the Committee Stand which
place is also used by the Remount Agent
and his subordinates where they spend
the hottest hours of the day for many
days together in examining horses &c.

A new design has been prepared in
communication with the Remount
Agent and it is proposed to construct
it on the site of the existing building
which is to be demolished.

Id

It will consist of an open room
in rear being formed of four sides of an
Octagon, the roof to be supported on a
truss with rafters radiating from centre
to each of the corners. Each side of
the room will have windows with
shutters. In front of this, there will
be two verandahs, the first will be 46
feet in length and $11\frac{1}{4}$ feet broad,
and the second $68\frac{1}{2} \times 12\frac{1}{4}$ feet. The
roof to be surmounted with a slope of 1
in 20 and will have parapet wall
all round and a binding wall across
over centre pillars. A glazed
sky light also provided in the roof
for giving additional light.

The Verandah roof will be sup-
ported on 17 hollow cast iron posts
 $6\frac{1}{4}$ inches diameter to outside, being
 $8\frac{1}{8}$ thick and the base will rest on a
block of cut stone having a foundation

7707/37
of $3\frac{1}{2}$ feet of brick in mortar and will
be fixed to it by means of 4 iron bolts
and nuts on the stone. The brasses
over pillars will be kept in their places
by 2 long screw nails let through the
caps or upper flange.

The plan and estimate, the latter
amounting to Rs 2,450 have been
countersigned by the Quarter Master
General on the approval of the Commander
in chief. It is requested that the
estimate may be sanctioned and funds
allotted for its execution.

The work may be finished within
4 months if commenced in the favour-
able season.


Comibator } Major R.E.
28 October 1881 } Supy: Engineer & Co. etc.

To The Chief Engineer
D. P. W.

From
The Superintending,
Second Circle.

29034.

C. Est. 2567 of 5. 11. 81

Noted 28th
Accepted 29th } October 1881

No. 151

Inc 5. (Copy)

Committee Stand, Remount
Dept. Colours:-

Report on the
Plan & Estimate of
Rs. 2450 for reconstruct-
ing the —

In S. G. 14781

Military Buildings.

No. 6037
Government of Madras.

MILITARY DEPARTMENT.

Fort St. George, the 15th November 1881.

From the Public Works Dept.
N. 2567 dated 5th November 1881, submitting
for approval estimate of Rs. 2450 for constructing a Committee
Stand at the Remount Depot, Arcot.

Order.

Approved.

(True Extract)

L. H. Mullis Colonel.
Secy. Secretary to Government.

The Public Works Department,
all enclosures returned.

C. E. No. 2567. 5-11-81.

Proc. of Govt.
Mil. Dept.
No. 6037

Dy 15th Nov/81.
By 16th —

Approving estimate of
amounting to Rs 2450 for
constructing a Committee stand
at the Remount Depot Hosur.

C. 17. 11.

No 2903 W

b B & A
clerk's mark

PUBLIC WORKS DEPARTMENT.

PROCEEDINGS OF THE MADRAS GOVERNMENT.

Under date the 19th Nov/81
Read the following:—

From the S. D. Circle H.S. No 461 of 28 Oct 81.
Memo. to the Mil. Dept. " 2567 of 5 Nov 81.
From the " " 6037 of 15 " " "

85

The estimate amounting
to Rs 2450, for reconstructing
the Committee stand at
the Remount Depot, Hosur,
is sanctioned.

2. The outlay will be
debited against the
allotment of the Salem
Division, for minor works
under Military.

3. This sanction has been
registered as Imperial Order
No 496 of 1881-82, & classified
as Military, Original works.

To the S. D. Circle
with 4 enclosures.
" Secy P. W. D. with
14th enclosure
" Military Department
Dated 1-12-81-

17. 11. 81

Att

6703.

Govt. of Madras.

PUBLIC WORKS.

To

Dated

Issued

Recd.

Encl.

G. O. 19th Dec. 1881, No. 2913 W.

Nos. 97 to 98

Committee to hand over
the Remains of the
at G. O. 19th Dec.

Rebate of Rs. 245/-
for the construction
the ————

Settled in Receipt Repr.