

(1) Number of pages 16
(2) Date of repair Feb 1987
(3) Initials of the Referencer low

TAMIL NADU ARCHIVES

GOVERNMENT OF TAMIL NADU

P N

DEPARTMENT

G.O. No.	885 (W)	Press.
B.P. No.		Mis.
Dated	3. 4. 1882	197.

Not to be folded or roughly handled

885
1

GOVERNMENT OF MADRAS.

PUBLIC WORKS DEPARTMENT.

Buildings and Roads.
Civil Works.

No. 9.

READ—the following letter from Colonel H. L. PRENDERGAST, R.E., Superintending Engineer, Fifth Circle, to the Chief Engineer, Public Works Department, dated Chepauk, 23rd March 1882, No. 1461.

3 Detailed Estimates with Abstract Estimates. I have the honor to submit for sanction plans and estimates for improvements to the Buckingham Canal, viz.:—
3 Duplicate Abstracts.
18 Sheets of Levels.
2 Do. of Survey.

For diversion of the canal from 27½ miles at Coromandel to	Rs.
Thettapet, at 36 miles	99,000
For improvements to the canal from 36½ miles to the 38th mile...	7,350
For diversion of the canal from 97½ miles to 97 miles 7 furlongs	
and for a new cut for a drainage channel between 95 miles	
5 furlongs and 96 miles 7 furlongs	6,340

2. With a view to isolate the canal from the open Pulicat lake, and to take it sufficiently away from the border of the lake, the estimate provides for a new canal 8½ miles in length. The bank on the west side will be made up to the full standard section. On the east side the bank need only be made to tow-path level. There can be but little land drainage, and this will be received into the canal by open cuts. It is intended to provide hereafter, in the general completion estimate, for a head sluice, in the west bank at 36 miles, to produce a scour in the channel down to the 28th mile, as proposed in paragraph 17 of the Chief Engineer's observations of April 1880. It is also proposed to provide, in the completion estimate, for a flood gate at the southern end of this section of the canal.

3. In the 37th and 38th miles the only work proposed consists in clearing the bed to full depth, raising the west bank to 4 feet above highest water level, and providing a towing-path on both banks.

4. In the 98th mile it is proposed to make a diversion and cut a new canal for a length of rather more than half a mile, as approved upon Captain Awdry's report of inspection of June 1880. Both banks of the canal are to be made up to the full standard height. The estimate includes also a drainage channel on the west for a length of a mile and a quarter. This drainage channel is to have a bottom width of 15 feet, the excavation will be thrown on the east side to make up the canal bank; on the west side the channel will be open to carry off the land drainage.

No. 10.

ORDER—dated 3rd April 1882, No. 885 W., Public Works.

The undermentioned estimates, amounting to Rs. 1,12,690, for improvements to the Buckingham Canal, are sanctioned:—

(1) Diversion of the canal from 27½ miles at
Coromandel to Thettapet at the 36th
mile Rs. 99,000, Register No. 2/1 W. of 1882-83,

- (2) Improvements to the canal from 36½ miles to the 38th mile ... Rs. 7,350, Register No. 2/2 W. of 1882-83.
- (3) Diversion of the canal from 97½ miles to 97 miles 7 furlongs and for a new cut for a drainage channel between 95 miles 5 furlongs to 96 miles 7 furlongs. „ 6,340, „ „ 2/3 W. of „
2. The work will be carried out from the budget grant for the Buckingham Canal.
3. This sanction has been registered as Provincial No. 2/1, 2, 3 W. of 1882-83 and classified as 33, Irrigation and Navigation, Works for which Capital and Revenue Accounts are kept, Capital, Works.

(True Extract.)

(Signed) R. H. SANKEY, Colonel, R.E.,
Secretary to Govt., P.W.D.

To the Superintending Engineer, Fifth Circle, with twenty-three enclosures.
„ Examiner, Public Works Accounts, with three duplicate Abstract Estimates.
„ Chief Engineer for Irrigation.
„ Board of Revenue.

Exd. S. T. Austin.
Spare Copies

BUILDINGS AND ROADS.
CIVIL WORKS.

Gobt. of (1882) Madras
PUBLIC WORKS.

To
THE SUPERINTENDING ENGINEER,
FIFTH CIRCLE

Dated April, 1882.

Issued

Recd.

Encl.

G.O., 3rd April 1882, No. 885 W.

APRIL,
Nos. 9-10.

Buckingham Canal.—Sanctions estimates,
amounting to Rs. 1,12,690, for improvements
to the —

C. No.

P. W. Secretariat.

Note by Budget Section.

885/3

Work

Improvements to the
Buckingham Canal

Remarks and References.

Fund	Provincial
Service Head	53 Irrigation & navigation for which Govt. works are kept
Departmental Head	C. Works
Amount of estimate	Rs. 1,12,690
Expenditure in previous year	"
Allotment in current year	"
Balance required to complete	"
Total Rs.	"

Note of available funds.

The work is classed as Protective Irrigation & navigation & according to ruling of the Govt. of India the Budget Estimate for Irrigation & navigation works ^{Chapter 13} provide the necessary funds in like manner as is provided for Agricultural works. Vide G.O. No. 531 W of 1st March/82

M. V.
24/3
Budget Clerk.

Note by Budget Section.

No. 1461.

SUPERINTENDING ENGINEER'S OFFICE,

8570 5th Circle,
MADRAS,
Chepauk 23rd March 1882.

From

Col. H. L. Prud'homme, R.E.
SUPERINTENDING ENGINEER,
5th Circle,

To

THE Chief Engineer
D. S. R.

SIR,

Enclosures. 26.

3 Dtd. Copies with
M. S. R. R. R.
3 Dup. of M. S. R. R. R.
18 Sheet. of Plans
2 Dtd. of Survey.

I have the honor to submit for
Sanction Plans and Estimates for
improvements to the Buckingham
Canal Viz.

For Diversion of the
Canal from _____ Miles
at Coromandel, to Thettapettai. 36

R. 99,000

For improvements to the Canal from 36 $\frac{1}{4}$ mile
to the 38 mile _____ R. 7,350.

For diversion of the Canal from 97 $\frac{1}{4}$ mile
to 97 $\frac{1}{2}$ m 7 f; and for a new cut for a
drainage channel between 95 m 5 f
and 96 m 7 furlongs _____ R. 6,340

2.

With a view to isolate the
Canal

Canal from the open Pulicat lake, and to take it sufficiently away from the border of the lake, the estimate provides for a new Canal $8\frac{1}{2}$ miles in length. The bank on the West side will be made up to the full Standard section. On the East side the bank need only be made to tow-path level. There can be but little land drainage, and this will be received into the Canal by open cuts. This intended to provide hereafter, in the general completion estimate, for a head sluice, in the West bank at 36 mile, to produce a scour in the Channel down to the 28 mile, as proposed in para 17 of the Chief Engineer's observations of April 1880. It is also proposed to provide, in the completion estimate, for a flood gate at the Southern end of this section of the Canal.

3 In the 37 and 38 miles, the only work proposed consists in clearing the bed to full depth, raising the West bank to 4 feet above highest water level, and

and providing a towing-path on both banks.

885/5

4 In the 98 mile, it is proposed to make a diversion, and cut a new Canal for a length of rather more than half a mile, as approved upon Captain Audry's Report of inspection of June 1880. Both banks of the Canal are to be made up to the full Standard height. The estimate includes also a drainage channel on the West, for a length of a mile and a quarter. This drainage channel is to have a bottom width of 15 feet: the excavation will be thrown on the East side to make up the Canal bank; on the West side the Channel will be open to carry off the land drainage.

I have the honor to be
Sir

Yours Most Obedt Servant
A. W. Sander at Fall P. O.

Superintending Engineer
S. L. Sander

From

J. W. C. Ho. 1935
The Superintending Engineer,
5th Circle,

To

The Chief Engineer
P.W. Dept.
Madras.

Dated

23rd March 1882.

Recd.

ENCLOSURES.

26. (20 Plans)

No. 1461.

Improvements to the
Buckingham Canal.

Submits for sanc-
tion estimates for

Cur 31.3.82

Rt. 3/4

No. 885 W.

885/6

B. R. Clark

PUBLIC WORKS DEPARTMENT.

PROCEEDINGS OF THE MADRAS GOVERNMENT.

Under date the *3 April 1882*

Read the following:—

From the Suptg. Engr. 5 Circle. N.E. No. 1461 of 23rd March 82

The undermentioned
estimates amounting to
Rs 12,690, for improvements
to the Buckingham Canal
are sanctioned:—

(1) Diversion of the Canal
from 27½ miles at Coro-
mandel to Thettapett
at the 36¼ mile
Rs 99,000. Register No. $\frac{2}{1}$ W
of 1882-83

(2) Improvements to the Canal
from 36¼ miles to the 38
mile.
Rs 7,350. Register No. $\frac{1}{2}$ W
of 1882-83

(3) Diversion of the Canal
from 97½ miles to 97 miles
7 furlongs and for a new
cut for a drainage chan-
nel between 95 miles 5
furlongs to 96 miles 7
furlongs.
Rs 6,340. Register No. $\frac{2}{3}$ W
of 1882-83.

2. The work will be carried out from the Budget grant for the Buckingham Canal.

3. This sanction has been registered as Provincial No. 2 of 1882-83 and classified as 33 Irrigation and Navigation, works for which Capital and Revenue accounts are kept, Capital Works.

On 30.3.82

31/3/82

To The No. 5 circle with 23 enclos.
" Ex. P.W. Accounts with 3 duplicate abet. rates
" Chf. Engr for Sarg.
" Board of Rev.
Sept 21-4-82

On 31.3.82 Rt. 3/4

P. W. DEPARTMENT-1881-82.

MEMORANDUM.

885/7

Current No. 1936.

Letter Number 1161.

dated the 23rd March 1882.

from the Supg. Engineer & 5th Circle.

Note of Remark No.

The Estimate with Surveys Sections & Reports for Surveys, amounts to the Buckingham Canal amounts to Rs 99,000, Rs 7350 & Rs 6340, respectively, as follows.

- 1- Division of the Canal from 27 1/2 miles at Con. Mandel to Thellapett at 36th mile. Rs 99,000.
- 2- Improvements to the Canal from 36 1/4 mile to the 38 mile. Rs 7350.
- 3- Division of the Canal from 97 1/2 miles to 97th mile 7 fur. & for a new cut for a drainage Channel between 95 miles 5 fur & 96 miles 7 fur. Rs 6340.

The Estimates provide for Earth Work Cutting & banking, Surfing, Planting, Cleaning silt &c & providing a tow path on each side of the bank, & includes also a drainage Channel on the West for a length of a mile & a quarter. And Compensation has been included in the Estimate. The Rates more or less agree with the Dist Schedule.

27th March 1882.

[Signature]

1936

Govt. of (1881) Madras.

PUBLIC WORKS.

To

Dated

11/11

Issued

Recd.

Encl.

G. O., 3^d April 1882 No. 883W

Nos.

9 to 10

Buckingham Canal

Sanctions estimate amounting
to Rs. 7,12,690 for improvement
to the —

Entered in Receipt Register