Enclosure to Circular No. VI Public Works.

Cost of weirs on Midnapore Canal.

Division.	Name of weirs.	Date of completion.	Description of weir.	Total length between abutments.	Under Sluices.		Height above general level of river bed.	Height of abutments above tops of weir posts.	Cost.	Rate per foot run.
					No. of Bays.	Width of each.				
				Feet.		Feet.		Feet.	Rs.	Rs.
Cossye ...	Midnapore weir across Cossye River.	March 1876 ...	Rubble masonry weir and curtain walls on kutcha wells 6 feet deep. The curtain wall 32 feet from weir wall; this space packed with rubble, and a talus 55 feet below curtain wall; posts and planks tops of weir. Scouring sluices on flank.	1,705	3	50	For 1,215 feet the weir 8 feet high with 2 feet posts and planks, and for 300 feet the weir 6 feet high with 4 feet posts and planks.	12½	3,68,767	216
Ditto ...	Panchkoorah weir across Cossye River.	March 1872 ...	Brick masonry weir with vertical drop unto block stone flooring, 20 feet wide, with packed concrete block apron 20 feet width. The foundations on kutcha wells 3 feet in depth. Posts and planks on top of weir and scouring sluices on either flank.	333	2	50	Masonry 4 feet above bed, posts and planks 4 feet above masonry.	20	1,06,503	319

J. H. APJOHN, C. E.,

Executive Engineer, Cossye Division.

Cost of Specimen Locks on Midnapore Canal.

Division.	Name of lock.	Date of completion.	Description of lock.	Description of foundations.	Length of chamber in the clear.	Width of chamber.	Height of lift.	Height from invert to coping.	Cost.	Rate per foot of lift.	Rate per foot of height from invert to Coping.	Rate per 100 c. ft. of chamber capacity.
					Feet.	Feet.		Feet.	Rs.	Rs.	Rs.	Rs.
	Midnapore Head Lock	July 1871 ...	Head lock from non-tidal river, rubble masonry, wooden gates.	Foundations in sand on Madras wells	150	20	Varies with height of river, maximum rise of which is about 21	22	71,615	...	3,252	108
	Goalagurriah ...	September 1873	Lift lock of rubble stone masonry with road bridge over tail bay, wooden gates.	On stiff clay without wells or piling.	150	20	15 feet	22½	65,934	4,390	2,930	97
	Terapokeah ...	March 1873 ...	Tidal lock, iron gates, brick masonry ...	Silty tidal clay foundations on piles.	150	20	Varies with the tide	24	1,06,566	...	4,415	147
	Gowkbally ...	March 1874 ...	Ditto ditto ...	Rather stiff clay ...	150	20	Varies with state of tide.	28	1,72,413	...	6,159	205
	Kaulapooka ...	Under construction.	Ditto ditto ...	Tidal silty clay rather sloppy equipressure on each square foot of foundation.	150	20	Varies with the tide.	20½	about 1,00,000	...	4,880	162

J. H. APJOHN, C. E.,

Executive Engineer, Cossye Division.

Specimen Tidal Sluices.

Division.	Name of sluice.	Date of completion.	Description of sluice.	Nature of foundation.	Particulars of vents.			Total sectional area.	Number of square miles drained.	Sectional area per square mile.	Height from floor to crest of embankment.	Slopes of embankment.	Total cost.	Rate per square foot of sectional area.	Rate per square mile of area drained.
					Number.	Width of each.	Height of each.								
								S. ft.		S. ft.	Ft.		Rs.	Rs.	Rs.
	Peechabunee ...	March 1872 ...	Tidal sluice in sea dyke, brick-masonry, iron flap shutters on sea side, wooden draw shutters in masonry grooves with windlas hitting gear.	Very soft alluvial clay mixed with very fine sand foundations on grillage.	22	5	8·5	935	125	7·5	27·5	2 to 1 3 to 1	1,84,962	198	1,480
	Rashgachtolla ...	July 1877 ...	Sluice in Cossye River Embankment just within tidal influence, brick-masonry with wooden draw shutters in iron grooves worked by screw gear.	Very soft alluvial clay foundations on block work sunk to 5·5 feet below bottom of platform.	4	5	7	140	12	12	21·5	2 to 1 1½ to 1	about 20,545	146	1,712

J. H. APJOHN, C.E.,

Executive Engineer, Cossye Division.

Aqueducts.

Division.	Name of aqueduct.	Date of completion.	Description of aqueduct.	Nature of foundations.	Dimensions of Canal waterway.			Particulars of vents.					Total sectional area.	Cost.	Rate per foot of length.	Rate per square foot of waterway.
					Length.	Width.	Depth.	No.	Width.	Versed sine arch.	Versed sine invert.	Height of weir.				
													Sq. ft.	Rs.	Rs.	Rs.
Cossye ...	Keræ	March 1875 ...	Brick masonry across nullah ...	Good clay ...	260	40	8	10	20	4	2	7	2,200	1,09,646	421	50

J. H. APJOHN, C. E.,

Executive Engineer, Cossye Division.

Comparative cost of certain selected buildings.

Division.	Locality.	Description.	Description and height of walls, &c.								Cost.	Area.	Rate per square foot.
			Single or double storied.	Foundation.		Plinth.		Walls to top of wall plates.		Roof.	Floor.			
												Rs.		
Cossye.	Authra, Midnapore District.	1st Class Inspection Bungalow	Single ...	For clay.	3′	Pucka masonry earth filling.	3′	Pucka masonry.	13½	Terraced.	Terraced.	4,717	1,700	2·77
	Allunkarpore ditto ...	2nd ditto ditto	Ditto ...		3′		3′		13½			3,176	1,156	2·74
		Out-houses of the above Bungalows ...	Ditto ...		2′		2′		10			1,208	576	2·09

J. H. APJOHN, C. E.,

Executive Engineer, Cossye Division.

No. 365, P. W. D. Press—26-4-81—755.

Executive Engineer,
Northern Drainage and Embankment Division.

Enclosure to Circular No. VI Public Works.

PUBLIC WORKS DEPARTMENT, BENGAL.

IRRIGATION BRANCH.

Comparative cost of selected buildings in the Northern Drainage and Embankment Division.

Division.	Locality.	Name of buildings.	Description of height of walls, &c.										Cost.	Area.	Rate per superficial foot.	Remarks.
			Single or double storied.	Foundation.		Plinth.		Walls (to top of wall plates.)		Roof.	Floor.					
					Ft. In.		Ft. In.		Ft. In.				Rs.		Rs. A. P.	
Northern Drainage and Embankment Division.	Dabipore in Pergunnah Mooragatcha.	Ahmedpore Inspection Bungalow.	Single ...	Pucca ...	3 0	Pucca ...	2 0	Pucca ...	15 9	Terraced.	Terraced.		2,600	972 0	2 10 9	Single-story, and terraced roof well buildings.
	Diamond Harbour in Pergunnah Mooragatcha.	Hooghly Point Inspection Bungalow.	„ ...	„ ...	3 0	„ ..	1 6	„ ...	15 9	„ ...	„ ...		2,600	972 0	2 10 9	Ditto ditto ditto.
	Diamond Harbour in Pergunnah Mooragatcha.	Diamond Harbour Inspection Bungalow.	Demi-upper roomed.	„ ...	4 6	„ ...	1 0	„ ...	22 8	„ ...	„ ...		8,783	2,194½ 0	4 0 0	Built on arches 12 feet above the ground level.
	Barroipore in Pergunnah Madomull.	Soorjeepore Inspection Bungalow.	Single ...	„ ...	2 0	„ ...	2 0	„ ...	12 0	„ ...	Tiled and terraced.		2,886	1,022 0	2 13 0	Single-story, terraced roof.
	Burdwan in Pergunnah Burdwan.	Edilpore Inspection Bungalow.	„ ...	Cutcha-pucca.	2 0	Cutcha-pucca.	2 0	Cutcha-pucca.	14 6	„ ...	Terraced.		680	2,102 7	0 5 3	Purchased. Value put down does not represent the cost.
	Oolooberriah in Pergunnah Mundleghat.	Mohisrakha Inspection Bungalow.	„ ...	„ ...	5 6	„ ...	4 6	„ ...	15 0	Thatched	Tiled ...		5,000	3,477 0	1 7 0	Single-story, thatched roof, inferior construction.
	Shampore in Pergunnah Mundleghat	Shibgunge Inspection Bungalow.	„ ...	Pucca ...	2 6	Pucca ...	5 6	Pucca ...	15 0	Terraced.	Terraced.		5,046	934·125	5 4 8	This is abnormally high, there is nothing in the work or building to justify this high rate.
	Dasspore in Pergunnah Khariz Mundleghat.	Gopeegunge Inspection Bungalow.	„ ..	„ ...	7 5	„ ...	4 0	„ ...	10 0	„ ...	„ ...		1,306	1,049 11	1 2 3	Single-story, terraced roof, inferior construction.
	Kaisa in Pergunnah Senpaharee.	Satcooniah Inspection Bungalow.	„ ...	Cutcha-pucca.	2 2	Cutcha-pucca.	4 0	Cutcha-pucca.	15 9	Thatched	Tiled ...		2,600	2,820 1	0 14 2	Ditto ditto ditto.
	Raneegunge in Purgunnah Burdwan.	Rughoonathchuck Inspection Bungalow.	„ ...	Rubble masonry.	2 0	Masonry...	2 5	Rubble masonry.	17 5	Terraced.	Rough slate stone.		11,500	6,231 0	1 13 6	Not completed.

P. B. ROBERTS,

Executive Engineer,

Northern Drainage and Embankment Division.

PUBLIC WORKS DEPARTMENT, BENGAL.

IRRIGATION BRANCH.

Comparative cost of selected sluices in the Northern Drainage and Embankment Division.

Name of sluice.	Date of completion.	Description of sluice.	Kind and depth of foundation.	Number and size of space.	Width of roadway between parapets or railings.	Height of roadway above foundation or river bed.	Total length of bridge.	Total cost.	Cost per 100 feet length.	REMARKS.
					Ft. In.	Ft. In.	Ft. In.	Rs. A. P.	Rs.	
Meherpore sluice ...	1854 ...	Brick masonry sluice with iron gate and groove, and raised by screw gear.	6½ feet on concrete bed ...	One of 4 feet span ...	5 0	12 0	97 0	3,532 0 0	3,641	For drainage and irrigation of the cultivated lands.
Custom House protective embankment sluice at Diamond Harbour.	1874 ...	Brick masonry sluice with self-acting gates ...	One foot without concrete	One of 1½ feet ...	61 0	13 0	65 0	2,000 0 0	3,077	For drainage of Custom House compound only.
Soorjeepore sluice ...	August 1871	Brick masonry sluice of 6′ openings of 4′ 6″ span, each opening has two sets of iron gates. The upper gates move in grooves and are hoisted by differential pullies and chains. The lower gates are self-acting, and are intended to prevent the entrance of tidal water. The sluice has 20 feet of rough stone apron and revetments on the upper side, and 100 feet stone apron and revetments on the lower side. The lower apron has been extended by 100 more of tiles set in mortar.	Foundations of abutments and piers 5′ 6″ between the floor of the sluice resting on a layer of concrete 1′ in thickness.	Six openings of 4′ 6″ span each. Dimension of each opening 7′ 9″ × 4′ 6.″	18 0	15 6	65 0	29,330 0 0	45,123	For drainage and irrigation of the cultivated lands.
Kharee sluice	October 1873	Brick masonry sluice of 3 openings of 4′ 6″ span, each opening has one iron gate on the upper face, moving in iron grooves. The gates are hoisted by small cast iron winches, fixed on timber beams, supported by twelve posts. The sluice has a loose brick apron 10′ in length on the upper side with brick revetments, and on the lower side a brick apron 25 feet in length with brick revetments.	Abutments, piers, &c., rest on a bed of concrete 2 feet in thickness, and the total depth of foundation down to bottom of concrete is 3′ 3″ below the floor of sluice or bed of the khall.	Three of 4′ 6″ span each. Dimensions of each opening 6′ × 4′ 6″.	19 0	12 9	52 6	7,355 7 1	14,008	For drainage and irrigation of cultivated lands.
Putneeghatta sluice ...	...	Brick masonry sluice of 3 openings of 4′ 6″ span, each opening has one iron gate on the upper face, moving in iron grooves. The gates are hoisted by small cast iron winches, fixed on timber beams, supported by timber posts. The sluice has 10 feet of concrete block pitching and revetments on the up stream side and 30 feet of concrete block pitching and brick revetments on the down stream side.	Ditto ditto ...	Ditto ditto ...	19 0	12 9	52 6	Up to July 1880. 8,043 0 0		
Arapauch sluice ...	...	Brick masonry sluice of 3 openings of 5′ span, each opening has two sets of wooden gates. The upper gates move in stone grooves and are hoisted by screw gear. The lower gates are self-acting and are intended to prevent entrance of salt water. The sluice has 20 feet of brick-on-edge apron and revetment on the up stream side, and 50 feet of brick-on-edge apron and revetments on the down stream side.	Abutments, piers, &c., rest on a bed of concrete, 1′ 6″ in thickness, and the total depth of foundation down to bottom of concrete is 3′ below the floor of sluice or the bed of khall.	Three openings of 5′ span each. Dimension of each opening 7′ 6″ × 5′.	16 0	13 6	60 0	Up to July 1880. 14,247 0 0		
Biddabutty sluice ...	July 1873	Brick masonry sluice with laterite stone quoins has 3 openings 9 feet span, each opening has a set of iron lock gates inside, and wooden self-acting gate outside; all these gates move on iron anchors. The sluice has 50′ of rough stone apron and revetment outside and 20 feet inside.	The sluice rests on a bed of concrete 2′ 6″ in thickness and the total depth of foundation down to bottom of concrete is 5 feet below the floor or the bed of khall.	Three spans 9′ × 13″ ...	20 0	23 0	74 0	46,322 0 0	62,597	
Bouderbill sluice ..	July 1873	Ditto ditto openings 9′ 6″	Ditto ditto ...	Three spans 9′ 6″ × 13′ ..	20 0	21 0	78 0	46,776 0 0	59,969	
Kana Nuddee sluice ...	...	Brick masonry sluice of 4 openings, 5′ span, each opening has a wooden lifting gate outside, moving in stone grooves and lifted by screw gear. The sluice has 50 feet rough apron and revetments both inside and outside.	The sluice rests on a bed of concrete 1 foot in thickness, and the total depth of foundation down to bottom of concrete is 2′ 9″ below the floor or the bed of khall.	Four spans 5′ × 12′ ..	12 0	25 0	64 0	29,263 0 0	45,723	
Joogooty sluice ...	...	Brick masonry sluice of 2 openings, 4′ span, each opening has an iron lifting gate outside, moving in iron grooves and lifted by screw gear. The sluice has 20 feet jhama apron and brick-on-edge revetments both inside and outside.	The sluice rests on a bed of concrete 2′ 6″ in thickness, and total depth of foundation down to bottom of concrete is 4 feet below the floor or the bed of khall.	Two spans 4′ × 6′ ...	10 0	25 6	96 0	6,983 0 0	7,274	

P. B. ROBERTS, C.E.,

Executive Engineer,

Northern Drainage and Embankment Division.

No. 365, P. W. D. Press—26-4-81—755.

Pr. 2814/81
10

[For Heads of Departments.]

Circular No. VI Public Works.

GOVERNMENT OF INDIA.

PUBLIC WORKS DEPARTMENT.

CIVIL WORKS.

Miscellaneous.

To

THE GOVERNMENTS OF MADRAS, BOMBAY, BENGAL, THE NORTH WESTERN PROVINCES AND OUDH, AND THE PUNJAB, IN THE PUBLIC WORKS DEPARTMENT.

THE CHIEF COMMISSIONERS OF THE CENTRAL PROVINCES, BRITISH BURMA AND ASSAM.

THE RESIDENT AT HYDERABAD.

THE AGENTS TO THE GOVERNOR GENERAL FOR CENTRAL INDIA, RAJPUTANA AND BILUCHISTAN.

THE ACCOUNTANT GENERAL, PUBLIC WORKS DEPARTMENT.

THE INSPECTOR GENERAL OF MILITARY WORKS.

THE DIRECTOR GENERAL OF RAILWAYS.

THE FOREIGN DEPARTMENT FOR COMMUNICATION TO RESIDENT OF MYSORE AND CHIEF COMMISSIONER OF COORG.

Simla, April 19, 1881.

In continuation of Circular No. III P W, dated the 27th January 1881, the undersigned is directed to forward herewith, for information, statements of areas and cost of buildings, and memorandum of construction and cost of bridges exceeding 50 feet in length, in the Cossye and Northern Drainage and Embankment Divisions of the South-Western Circle in the Bengal Presidency.

Sent per packet-Per Dec 9/5

(Signed) W. P. TOMKINS, Captain, R. E.,
Asst. Secretary to the Govt. of India.

F. W. Lees Colonel,
Offg. Secy. to the Govt. of India, Mily. Dept.,
In charge P. W. Dept.

To
The Secy. to the Govt. of Madras
Public Works Department

P. W. C. No. 2814

GOVERNMENT OF INDIA.

PUBLIC WORKS DEPARTMENT.

CIVIL WORKS.

Miscellaneous.

To P. M. Fox-May

Circular No. VI Public Works.

Dated Simla, April 19, 1881.

Received 9th May 1881

Forwards, for information, statements of areas and cost of buildings, and memorandum of construction and cost of bridges exceeding 50 feet in length, in the Cossye and Northern Drainage and Embankment Divisions of the South-Western Circle in the Bengal Presidency.

No. 365, P. W. D. Press—25-4-81—755.

B

No. 1217 W. 14.5.81

Communicated to Offices of the P. W. Dept. in continuation of P. No. 117 W. dt. 15th January 1881.

Supt. Engrs
S. P. W.
C. E. for I.
C. E. for R
Comptr Archt
Secy Supt. P. W. Ws

14/5/81

1 - Copy to Dy-ca-5-81
No. 1217 W
Worthorder

Enclosure to Circular No. XXIV Public Works.

Statement of Construction, Cost and Length of Bridges exceeding 50 lineal feet in the Bengal Presidency.

Executive Division.	Name of bridge, or of river or nullah, and situation.	Date of completion.	Description of bridge.	Kind and depth of foundation.	No. and size of spans.	Width of roadway between parapets or railings.	Height of roadway above foundations or river-bed.	Total length of bridge.	Total cost.	Cost per 100 feet of length.	REMARKS.
									Rs.	Rs.	
CIRCULAR AND EASTERN CANALS DIVISION.	*Bridges over Tollys Nullah.*										
	Hastings Bridge ...	1875-76...	Lattice girder ...	Masonry on concrete, and depth 20 feet.	1 span of 162 feet	24 feet, with 2 footpaths of 5 feet each.	Above foundation 16 feet.	174	1,46,264	84,000	
	Kidderpore do ...	1869-70...	Do ...	Do and depth 19′ 9″	Do of 130 do.	24 feet, and 2 footpaths of 5 feet each.	Do 16 feet	140	1,17,343	83,800	
	Zeerut do ...	1856 ...	Warrens girder ...	Unknown ...	Do of 120 do.	19 feet ...	Do 6 inches. 14 feet	126′ 9″	Unknown	...	
	Allipore do ...	1862-63...	Plate girder on screw pile piers.	Do ...	3 spans Centre... 74 6 End ... 53 3 Do ... 54 3 / 182 0 / 2 piers 10 0 / 192 0	20 ,, ...	34 feet above lowest bed.	199	56,739	28,512	
	Kally Ghat do ...	1823 ...	Suspension foot bridge	Masonry on piles 8½ feet depth.	1 span of 138 feet	8 ,, ...	18½ feet above foundation.	141*	16,800	12,000	* Between points of suspension.
	Tallygunge do ...	1827 ...	Do bridge ...	Do 12 feet ..	Do of 101 do	14 ,, ..	16 do	111†	24,300	21,900	† Do do
	Gurreah do ...	1823 ...	Do do ...	Do do ...	Do of 105 do	14 ,, ...	14 do ...	114	17,596	15,435	
	Bridges over Circular Canal.										
	Chitpore Bridge ...	1834 ...	Suspension bridge ...	Not known ...	1 span of 99 feet	22 feet ...	34 feet above lock floor.	99	29,344	29,640	
	Barrackpore do ...	1870 ...	Lattice girder do ...	Do ...	1 do of 92′ 3″	20 feet, with 2 foot paths of 4 feet each.	18 feet above foundation.	99	52,869	53,403	
	Dum-Dum do ...	1831	Suspension do ...	Do ...	1 do of 100′	23 feet ...	15 feet do.	100	20,598	20,598	
	Ultadanga do ...	1842 ...	Do do	Do ...	1 do of 100′	18 ,, ...	17 feet 9 inches do.	102	17,000	16,666	
	Manicktulla do ...	1830 ...	Do do ...	Do ...	1 do of 100′	18 ,, ...	17 feet do.	100	15,576	15,576	
	Narkeldanga do ...	1830 ...	Do do ...	Do ...	1 do of 100′	18 ,, ...	17 feet 9 inches do.	100	17,125	17,125	
	Baliaghatta do ...	1860 ...	Warren girder do ...	Do ...	1 do of 93′	18 ,, ...	19 feet do.	104	33,399	32,114	
	Bridge over new canal.										
	New cut bridge ...	1859-60...	Warren girder bridge ...	Not known ...	1 span of 121′	18 feet ...	15 feet 9 inches above foundation.	134	44,187	32,975	

H. JOLL,
Executive Engineer,
Circular and Eastern Canals Division.

No. 391, P. W. D. Press—10-12-81—900.

PUBLIC WORKS DEPARTMENT, BENGAL.

Statement of Construction, Areas and Cost of Principal Buildings in the Bengal Presidency.

Abbreviations.—p, pucca; k p, kutcha pucca; p k p, pucca and kutcha pucca; d w, daub and wattle; cor, corrugated; d, dressed; ter, terraced; b l, brick-in-lime; b m, brick-in-mud; r, rubble; c r, coursed rubble; d s, dry stone; c, concrete; p s t, pent single tiled; p d t, pent double tiled; t, thatched; b f, brick flat; fl, flagged; in, inner; o, outer; u, upper; gr, ground.

Executive Division.	Locality.	Name of building.	Description and Height of Walls.													Cost.	Area.	Rate per superficial foot.
			Single or double storied.	Foundation. Concrete.	Foundation. Masonry.			Plinth.		Walls (to top of wall-plate). Ground.	Walls (to top of wall-plate). 1st floor.	Walls (to top of wall-plate). 2nd floor.	Roof.	Floor.				
									Average. Ft. In.	Ft. In.	Ft. In.	Ft. In.				Rs.		Rs.
1st Calcutta Division. 3rd Sub-Division.		*Imperial.*																
		Paper Currency ...	three ...	unknown	unknown	unknown	unknown	p	4 0	22 0	18 0	22 0	arched ...	costic tiles and marble stone.		2,69,088	11,212	24
		do Hall ...	single ...	...	...	...	...	...	...	...	...	35 0	...	...		1,24,448	7,778	16
		Old Opium Godown ...	do ..	...	...	...	...	...	1 0		...	16 0	ter ...	bk-on-edge ..		unknown	84,187-6	
Ditto ... 4th Sub-Division		University Main Building ...	do ...	...	3 0	...	10 6	...	4 10	40 0	...	...	do ...	stone ...		4,18,128	24,408	@ 17
		Government House consisting of—																
		South-East and South-West wings.	three ...	...	...	...	...	...	1 10½	14 5½	21 0½	22 5¼	do ...	ter ...		...	5,925	
		do corridors ...	...	...	...	...	...	...	1 8½	14 5¼	21 0	22 5½	...	...		...	849	
		North-East and North-West wings.	...	...	...	...	...	...	1 10	14 5½	21 0¾	22 5¼	...	...		...	4,720	
		do corridors	...	...	...	...	...	...	1 9	14 5½	21 0¼	22 5	...	...		...	849	
									varying from									
		Four staircase rooms ...	...	...	...	...	...	...	1-6 to 1-10	15 0	22 2¾	23 0	...	...		...	900	
		Centre portion ...	...	...	...	...	...	...	1-4 to 1-9	14 0	21 1	22 6	...	..		...	18,462	
		North Verandah ...	...	...	...	...	...	...	1 7	15 0	...	43 6	...	...		...	1,656	
		South do ...	...	...	...	...	...	...	1 8	14 9	...	43 0¾	...	...		14,17,522	1,440	
										mean								
		Two hot water houses ...	...	...	...	...	...	...	0 5	10 0	...	...	...	...		...	341	
		Malley's and Engineer's Godown No. 2.	single ...	...	...	...	...	...	1 6	13 10	...	...	...	...		...	205	
											varying from							
		Governor General's Body-guard house.	double ...	...	...	...	...	...	1 3	13 5	15 to 20½	...	...	bk-on-edge...		...	9,450	ground floor bk edge and 1 floor tiled.
										varying from								
		do Kitchen and Servants' quarters and coach-house.	do ...	...	...	...	...	...	0 6	14-6 to 18-9	10-0 to 15-0	...	...	do asphalted and tiled.		...	27,767	
										do do 1st floor								
		do Stable	do ...	...	...	...	...	...	1 0	16 to 21 & 13 gr floor	15 0	...	...	bk-on-edge...		...	2,270	
									Average									
		General Treasury ...	...	...	...	...	...	...	3 0	18 0	17 0	15 6	ter ...	ter, asphalted and stone.		97,371	6,388 9,879 3,440 946	
		Latrine for Europeans ...	...	...	...	...	...	...	0 6	10 1	...	...	...	ter ...		...	215	
		do for Natives ...	...	...	...	...	...	...	0 6	9 9	...	...	...	...		...	342	
		Legislative Council ...	...	...	...	...	...	...	2 0	15 6	20 9	11 9						
		Latrine	...	...	...	...	...	...	dismantled									
		Record rooms ...	...	..	...	...	...	...	1 6	15 7	11 9							

Executive Division.	Locality.	Name of building.	Single or double storied.	Foundation. Concrete.	Foundation. Masonry.			Plinth.	Average. Ft. In.	Walls (to top of wall-plate). Ground.	Walls (to top of wall-plate). 1st floor.	Walls (to top of wall-plate). 2nd floor.	Roof.	Floor.		Cost.	Area.	Rate per superficial foot.
		Stable and coach-house ...	...	...	...	...	...	...	0 11	14 2	...	...						
	Calcutta ...	Loudon's Buildings— ...	three ...															
		Home Office	...	...	...	...	...	...	2 9	15 6	17 5	14 6	ter	ter ...		...	5,140 2,408	
		Public Works Department...	...	...	...	...	...	...	3 0	14 2	17 3	14 2	...	...		...	14,417	
		Agriculture, Commerce and Revenue.	...	...	...	...	...	...	2 9	15 6	17 5	14 6	...	...		...	7,364	
																	mean.	
		Coach-house and stable, &c., Public Works Department, Native Latrine.	single ...	...	...	...	...	...	0 6	11 9	...	...	...	bk-on-edge		...	3,393	one story used by P. W, Home and Agricultural Departments.
										varying from								
2nd Sub-Division.		South-West Latrine and Tiffin room.	do ...	...	...	...	...	...	0 6	11-9 to 12-9	...	...	...	ter ...		1,00,000 ...	1,046-6	
		Out-office, Public Works Department. do, Central, for the Home Office. do, Agricultural Department.	one block	...	...	...	...	...	2 0	14 9	...	...	...	...		...	9,006	
		North-West Latrine ...	...	...	...	...	...	...	0 6	11 9	...	...	...	...		...	792	
		Foreign Secretariat ...	three ...	...	...	...	...	...	1 9	15 1	20½	14 1½	ter ...	ter ...		...	6,288	
		Record Office	single ...	...	...	...	...	...	1 3	15 3	...		...	...		...	4,355-8	
		Coach-house	do ...	...	...	...	...	...	0 6	16 3	...	...	...	bk-on-edge...		...	496-7	
										varying from								
		Printing Office, Centre ...	do ...	...	...	...	...	...	1 6	14-5 to 15-3	...	...	...	ter ...		...	1,348-6	
		do East ...	do ...	...	...	...	...	...	1 6	14 10	...	...	...	...		...	1,277-10	
		do do ...	do ...	...	...	...	...	...	1 6	14 9	...	...	...	asphalted and ter.		...	2,093-5	
		Library	double ...	...	...	...	...	...	0 6	9 10	18¼	...	...	...		99,600	799-6	
		Durwan's room ...	single ...	...	...	...	...	...	1 3	16 6	...	...	...	...		...	178-4	
		Persian Library ...	double ...	...	...	...	...	...	1 6	9 6	12 10	...	...	...		...	561-1	
		Cook-room	single ...	...	...	...	...	...	1 3	14 9	...	...	ter ...	asphalted and ter.		...	897-8	
		Stables	do ...	...	...	...	...	...	...	9 6	...	...	...	bk-on-edge		...	480-1	
		Latrines	do ...	...	...	...	...	...	1 3	13 7	...	...	...	cement ...		...	1,080	
		Toshakhannah	double ...	...	...	...	...	...	1 9	9 9	16 9	...	...	ter ...		...	1,455-8	
		do	do ...	...	...	...	...	..	1 9	9 3	10 0	...	...	...		...	1,214-9	
		New Opium Godown ...	single ...	...	...	...	...	...	2 0	28 3	...	...	ter ...	bk and ter...		1,77,010	49,675-6	
		New Post Office Main Building.	...	...	...	...	...	...	3 6	22 9	26½	...	...	ter and stone		...	32,026	
		do do ...	...	...	...	...	...	...	3 6	23 2	25 9	...	...	...		...	3,375	
		do do ...	...	...	...	...	...	...	3 6	23 3	25 11	..	...	...		...	20,662-6	
										mean								
		Main gates	...	...	...	...	...	...	...	15 9	...	...	...	...		...	325-6	
										mean								
		do	...	...	...	...	...	...	...	16 10	...	...	...	...		...	243-3	
		Range of out-houses for servants.	...	...	...	...	...	...	1 6	13 6	...	...	...	ter ...		6,30,510	3,703-2	
										average								
		Vans, Stables and Banghy Department.	...	...	...	...	...	...	1 5	12 9	...	...	...	do and bk-on-edge		.	3,566-3	
										average								
		Latrines and Vans and Store room.	...	...	...	...	...	...	1 6	12 10	...	...	...	...		...	3,744-11	
										average								
		do do ...	...	...	...	...	...	...	1 5	12 9	...	...	...	bk-on-edge...		...	2,953-6	
										average								
		do do ...	...	...	...	...	...	...	1 6	13 3	...	...	...	...		...	2,303	
		do do ...	...	...	...	...	...	...	1 5	12 10	...	...	...	...		...	384	
		New Telegraph Building ...	three ...	...	...	...	...	...	4 6	21 2	24 6	18 0	ter ...	patent stone tiles, and asphalted over terrace.		7,23,566	27,958	

Executive Division.	Locality.	Name of Building.	Description and Height of Walls. Single or double-storied.	Foundation. Concrete.	Foundation. Masonry.	Plinth.	Wall (to top of wall plate).	Roof.	Floor.	Cost.	Area.	Rate per superficial foot.
				Ft In.	Ft. In.	Ft. In.	Ft. In.			Rs.		
1st Calcutta Division. 5th Sub-Division.	*Imperial*—continued.	Government House	double ...	...	... p ...	2 3 p ...	1 3 p ...	36 6 ter ...	ter and cement	..	31,525	
		House No. 1	single ...	...	... p ...	4 0 p ...	1 10 p ...	17 7 do ...	do ...	...	10,031	
		do No. 2	do ...	...	... p ...	4 0 p ...	1 10 p ...	17 7 do ...	do ...	...	10,031	
		do No. 3	do ...	...	... p k p ...	3 0 p k p ...	1 6 p k p ...	15 9 do ...	ter, cement and asphalte.	...	7,785	
		Kitchen	do ...	...	... p ...	4 0 p ...	0 7 p ...	16 9 do ...	ter and stone	...	4,843	
		Flag staff house	do ...	...	... p k p ...	2 0 p k p ...	2 6 p k p ...	18 9 do ...	ter ...	...	10,253	
		Band Master's house	do ..	...	... p ...	2 4 p ...	2 6 p ...	18 3 do ...	do and cement	...	2,602	
		Cenatoph	do ...	...	0 3 p ...	4 0 p ...	5 0 p ...	20 0 Stone ...	vaulted ...	...	3,667	
		Survey Tower	four	...	... p ...	3 10 p ...	1 0 p ...	59 2 ter ...	brick-on-edge	...	415	
		Band Barrack	double ...	...	0 4 p ...	3 1 p ...	4 4 p ...	29 10 do ...	stone and tiled	...	5,260	
	Barrackpore	Park Superintendent's house ...	single ...	...	... k p ...	2 0 k p ...	2 8 k p ...	13 10 do ...	ter, asphalte and cement.	...	3,096	
		Dhobee house	do ...	...	... k p ...	2 8 k p ...	1 11 k p ...	13 3 do ...	tiled ...	...	1,899	
		Coachman's house	do ..	...	0 4 p ...	2 8 p ...	2 7 p ...	17 3 do ...	ter and cement	...	1,799	
		Old Menagerie	do ...	...	... p ...	4 0 p ...	... p ...	10 0 do ...	tiled ...	...	3,864	
		New „	do ...	...	... p ...	2 1 p ...	0 11 p ...	9 0 do ...	do ...	...	4,294	
		Old Aviary	do ...	...	... p ...	3 10 p ...	.. p ...	14 8 do ...	do and tiled	..	3,965	
		New do	do ...	...	... p ...	2 4 p ...	0 6 p ..	12 3 do ...	tiled ...	...	7,870	
		Stable No. 1	do ...	...	... p ...	2 10 p ...	... p ...	16 8 do ...	b l ..	...	9,840	
		do No. 2	do ...	...	... p ...	0 11 p ..	1 1 p ...	14 11 do ...	do ...	..	1,622	
		do No. 3	do ...	...	0 6 p ...	1 0 ...	... p ...	7 3 t ...	mud ...	...	4,530	
		do No. 4	do ...	...	... p ...	1 6 ...	... p ...	6 6 p s t ...	brick and mud	...	2,252	
		Seed house ...	...	...	... p ...	2 6 p ...	4 3 p ...	13 5 ter ...	ter and tiled...	...	3,541	
	Belgurriah ...	Stable at Belgurriah	...	...	... p ...	3 3 p ..	... p ...	13 3 do ...	b l ...	...	4,893	
		do bungalow at do	...	..	... p ...	3 3 p ...	... p ...	13 0 do ...	ter ...	...	1,750	

W. H. NIGHTINGALE, C. E.,

Executive Engineer, 1st Calcutta Division.

Executive Division.	Locality.	Name of building.	Description and Height of Walls. Single or double storied.	Foundation. Concrete.	Foundation. Masonry.	Plinth.	Walls (to top of wall-plate). 2nd.	Walls (to top of wall-plate). 1st.	Walls (to top of wall-plate). Ground.	Roof.	Floor.	Cost.	Area.	Rate per superfical foot.
														Rs. A. P.
1st Calcutta Division.		*Provincial.*			Average.	Average.								
				Ft. In.	Ft. In.	Ft. In.	Ft. In.	Ft. In.	Ft. In.			Rs.		
3rd Sub-Division.		Police Lock-up ...	double ...	unknown	unknown unknown	unknown p ...	3 0 ...	16 0	16 0	flat ter ...	ter, p c and bk-edge.	41,160	5,880	@ 7 0 0
		do Magistrate's Court ...	three ...	...	... ...	... ...	... 19 0	18 0	8 0	ter ...	ter, tiled, boarded and p c.	unknown	10,814	
		St. Andrew's Church ...	single ...	...	... ...	... ...	5 0 ...	...	34 0	do ...	arched and marble.	1,02,915	11,435	9 0 0
		Economic Museum ...	do ...	...	... ...	... ...	3 0 ...	...	19 0	do ...	bk-on-edge	13,779	2,716	5 0 0
		Custom House	double ...	...	... ...	... ...	1 0 ...	19 0	21 0	do ...	stone, ter and bk edge.	1,55,250	17,250	9 0 0
		do Double range	single ...	...	... ...	... ...	1 6 ...	...	18 0	do ...	bk-on-edge...	92,796	15,466	6 0 0
		N godown ...	...	...	... ...	... ...	1 0 ...	...	15 0	do ...	do	41,485	8,297	5 0 0
		W of D R Godown ...	...	...	... ...	... ...	1 0 ...	...	14 0	do & iron	do ...	49,350	9,870	5 0 0
		West shed ...	...	...	... ...	... ...	1 0 ...	...	11 6	ter ...	do ...	62,940	15,735	4 0 0
		Assistant Collector's residence	double ...	...	... ...	... ...	1 9 ...	15 0	14 0	do ...	ter ...	39,057	5,978	6 8 0
		East of above	...	...	... ...	... ...	1 0 ...	...	14 0	...	bk-on-edge...	83,860	16,772	5 0 0
		W of Main Building ...	...	...	... ...	... ...	1 0 ...	...	14 0	...	...	11,890	2,378	5 0 0
		W of A C's residence ...	...	...	... ...	... ...	1 0 ...	.	11 0	...	...	46,880	11,720	4 0 0
		S of E shed No. 1 ...	...	...	... ...	... ...	1 0 ...	...	11 0	...	...	50,464	12,616	4 0 0
		Writers' Building ...	three ...	...	... ...	... ...	1 6 15 0	17 0	16 0	...	ter ...	3,62,880	22,680	16 0 0
		do *New No. 1*	do ...	...	... ...	... ...	2 6 15 0	17 0	16 0	...	stone and sills patent tiles.	unknown	15,336	
	Calcutta ...	do do No. 2	...	...	... ...	... ...	... ...	...	...	...	...	...	11,557	
		do do No. 3	...	...	... ...	... ...	... ...	...	...	...	...	...	10,414	
4th Sub-Division.		Medical College, consisting of residence of Principal.	partly three	...	... ...	... ...	0 6 13 8	16 6	14 3	ter ...	ter ...	36,590	3,659-8	10 0 0
		Student's quarter ...	double ...	...	... ...	... ...	2 0 12 0	16 6	...	do ...	do and tiled	1,992	332-5	6 0 0
		do Superintendent's quarters.	do ...	...	... ...	... ...	2 0 12 0	16 6	...	do ...	do ...	13,272	2,272-3	6 0 0
		Staff Surgeon's quarter ...	do ..	...	... ...	... ...	2 0 12 0	16 6	...	do ...	do ...	10,074	1,679-3	6 0 0
		N. Students' quarters .	single ...	...	... ...	... ...	2 0 12 0	...	...	do ...	do ...	22,109	7,491-6	3 0 0
		Office Building Library ...	double ...	...	... ...	... ...	2 0 12 0	16 9	...	do ...	do ..	65,736	10,906-11	6 0 0
		Museum Building ...	single ...	...	... ...	... ...	4 6 18 0	...	...	do ...	do ...	40,520	8,104-11	5 0 0
		Resident Surgeon's and Purveyor's quarter.	double ...	...	... ...	2 0 ...	1 6 13 3	14 3	...	do ...	do ...	15,588	2,598-7	6 0 0
		Resident Physician and Apothecaries' quarter.	do ...	...	... ...	2 0 ...	1 6 13 3	14 3		do ...	do ...	22,800	3,800	6 0 0
		Medical College Hospital Main Building.	three ...	...	... ...	unknown ...	3 0 7 9	22 6	23 6	do ...	do and stone	1,54,448	9,653	16 0 0
		Chooney Lall Seal's Dispensary.	single ...	...	... ...	2 4 ...	1 8 16 6	...	...	do ...	ter ...	23,255	4,650-9	5 0 0
		Presidency College old Main Building.	double ...	...	... ...	... ...	3 8 16 3	19 9	...	do ...	cemented ...	...	12,000	unknown.
		East wing of do ...	single ...	...	... ...	... ...	4 0 22 0	...	...	do ...	do ...	1,852	6,240	3 0 0
		West wing of do ...	do ...	...	... ...	... ...	4 0 22 0	...	...	do ...	do ...	1,852	6,240	3 0 0

Executive Division.	Locality.	Name of building.	Description and Height of Walls. Single or double storied.	Foundation. Concrete.	Foundation. Masonry.	Plinth.	Walls (to top of wall-plate).	Roof.	Floor.	Cost.	Area.	Rate per superficial foot.
				Ft. In.	Average. Ft. In.	Average. Ft. In.	Ft. In. / Ft. In. / Ft. In.			Rs.		Rs. A. P.
1st Calcutta Division—contd.		*Provincial*—contd.										
	Calcutta	Presidency College—*contd.*										
		East detached wing	single	unknown	unknown	unknown	unknown	ter	cemented	11,010	3,870	@ 3 0 0
		West do	do					do	do	11,010	3,870	3 0 0
		Presidency College, New	three					do	stone	3,26,805	34,638	9 0 0
		Old Hare School	single					do	cemented	22,707	75,693-3	3 0 0
		Colootolah Branch School	double		3 0	10 0		do	stone	1,08,098	12,469	9 0 0
		Bethune School	single			2 0		do	ter and cemented.	30,632	6,640	6 0 0
		Lady Superintendent's House	double			unknown		do	do	19,292	4,189	6 0 0
		Small Cause Court	do					do	ter	34,400	5,630	7 0 0
		Resident of the Superintendent of Campbell Hospital.	do					do	tiled	27,400	3,751-6	9 0 0
		Police Court	do					do	ter	31,698	4,538-6	8 0 0
		Lock Hospital	do					do	do	17,513	2,621	8 0 0
	Sealdah	Deputy Superintendent's quarter, Campbell Hospital.	single					do	do	16,115	6,863	3 0 0
		Campbell Medical School	do			2 6		cor	bk-on-edge and stone.	66,136	16,534	4 0 0
		Lecture Theatre, No. 1	do			2 0		do	ter	5,200	1,325	4 0 0
		do No. 2	do	2 0		6 3		do	do	26,500	2,650	10 0 0
		Small Pox Hospital for Natives.	do	2 0		2 6		vaulted	do	19,352	4,838	4 0 0
		do for Europeans	double					do	do	7,812	1,302	6 0 0
		Manicktollah Distillery Ento	do					ter	ter	6,080	760	8 0 0
4th Sub-Division—*contd.*	Manicktolah	Revenue Board Office	three					do	do and boarded.		10,731-4	
		Stables, North side							bk-on-edge		1,295-11	
		Privy and Urinals									1,779-10	
		Coach-house and Servants' room and Tiffin room.	single							1,85,172	740-9	
		Record-keeper's godown, coach-house.	do								3,986-7	
		Durwan's Lodge	do								2,342-8	
		do do	do								156-3	
		New High Court						pent roof of cor iron.	stone paving	17,99,114	156-3	
		Northern out-offices to do						flat ter	bk-on-edge and paving.	7,866	1,02,000	
		Western do								9,187	2,128	
		Latrines to do								3,977	2,415	
		New Court of Small Causes						ter on iron girders and joists.	stone in public room, asphalte in Offices on beaten ter on iron girder and T joists.		960	
		Coach-house and stables						ter on wooden beams	bk-on-edge	3,17,200	17,168	This does not include a flight of steps to entrance.
		Sale rooms, godown, &c.							tiles and asphalted.		1,960	
		Privies and urinals							bk-on-edge		7,420	
		Stamp Office, Main Building						ter	do		1,460	
		do do									2,131-4	
		do do							ter		4,503	
		do do							boarded		319-4	
		do do							asphalted		8,097-2	
		North ranges, east							do		142-1	
		do west							do		7,951-6	
		Servants' house and urinals							ter and bk-on-edge.		1,909-6	
		Duftrys' room							ter		801-10	
		Godown, west							do		1,073-6	
		do							do		2,254-6	
		Babus' Tiffin room						tiled	rubbish		293-8	
		Coach house and stables						khoa	do		425-7	
		do							do		1,436-10	
2nd Sub-Division.		Store Godown, No. 1							bk-on-edge		181-3	
		do do 2							do		4,550	
		do do 3							do		2,961	
		do do 4							do		1,119-8	
		do do 5							do		913-6	
		Calcutta Collectorate, Main Building.							do		403	
		do do						ter	partly ter and asphalted.		2,161	
		do do							cemented		2,001	
		St. John's Church, Main Building.							do		1,368	
		do N. S. verandah						ter	ter, stone and marbled.		12,080	
		West portico							do		1,752-9	
		East godown							do		1,396-6	
		West „							khoa	1,95,946	1,207	
		Palki shed										
		Iron and wooden rail on compound wall with gateway						ter	ter		2,373	
		House No. 3, Koilah Ghaut Street.						do	do		4,401	
5th Sub-Division.	Barrackpore	Government School						do	ter and cement.		2,940	
		Magistrate's Court						do	stone and asphalt.		5,064	
		Police Building						do	ter		1,798	

W. H. NIGHTINGALE, C. E.,

Executive Engineer, 1st Calcutta Division.

Statement of Construction, Cost, and Length of Bridges exceeding 50 lineal feet in the Bengal Presidency.

Executive Division.	Name of bridge, or of river or nullah, and situation.	Date of completion.	Description of bridge.	Kind and depth of foundation.	No. and size of spans.	Width of roadway between parapets or railings.	Height of roadway above foundations or river-bed.	Total length of bridge.	Total cost.	Cost per 100 feet of length.	REMARKS.
1st Calcutta Division.	*Nil*	*Nil*	*Nil*	*Nil*	*Nil*	*Nil*	*Nil*	*Nil*	*Nil*	*Nil*	*Nil*

W. H. NIGHTINGALE, C. E.,

Executive Engineer, 1st Calcutta Division.

Executive Division.	Locality.	Name of building.	Description and Height of Walls.													Cost.	Area.	Rate per superficial foot.
			Single or double storied.	Foundation.				Plinth.		Walls (to top of wall-plate).				Roof.	Floor.			
				Concrete.		Masonry.												
					Ft. In.		Average Ft. In.		Average. Ft. In.	Ft. In.	Ft. In.	Ft. In.				Rs.		Rs. A. P.
		Orphan Asylum School.																
	Khidderpore	Main Building ...	three ...	...	...	...	...	p ...	0 9	8 0	19 3	18 9		terraced ...	terraced ...	1,18,142	12,436	9 8 0
		Secretary's House ...	double ...	...	...	p ...	2 0	p ...	1 10	15 0	17 0	...		do ...	tiled ...	35,259	5,825	6 1 0
		Hospital	do ...	...	...	...	...	p ...	1 0	12 0	11 0	...		do ...	terraced ...	22,380	4,476	5 0 0
		Telegraph store yard.																
		Cable machinery shed ...	single ...	...	...	...	...	p ...	1 0	15 0	...	...		do ...	bk-on-edge ...	16,090	1,462	10 15 0
		Instrument room ...	double ...	...	...	...	...	p ...	2 9	14 3	12 9	...		do ...	asphalte ...	18,936	2,066	9 3 0
		Blacksmith's shop ...	single ...	...	...	...	...	p ...	*Nil* ...	10 9	...	...		do ...	earth ...	17,446	8,845	1 13 9
		Workshop godown and Carpenter's Shop.	do ...	...	...	...	...	p ...	0 6	9 9	...	...		do ...	terraced ...	18,332	4,807	3 13 0
		Belvedere House.																
		New West Wing, Main Building.	partly 3 and partly 2.	...	...	...	...	p ...	8 6	19 6	16 9	...		do ...	ter and cement	84,232	6,250	13 10 3
		South-west do do ...	double ...	...	...	...	...	p ...	0 9	10 6	*19 6	...		do ...	ter and marble	39,789	4,422	9 0 0
		do east do do ...	do .	..	...	...	...	p ...	0 9	10 6	21 3	...		do ...	do ...	32,940	3,660	9 0 0
		Centre Block do ...	do ...	...	...	...	...	p ...	...	8 0	24 0	..		do ...	ornamental tile, slate and marble.	59,730	5,973	10 0 0
2nd Calcutta Division.	Alipore ...	East Wing do ...	three ...	...	...	...	...	p ...	...	8 0	20 0	16 9		do ...	ter, stone and cement.	71,503	6,600	10 13 3
		Alipore Jail.																
		Jail wards, south ..	double ...	...	...	...	...	p ...	1 0	12 0	13 9	...		do ..	terraced ...	1,21,016	13,722	8 1 6
		do west ...	do ...	...	...	...	...	p ...	1 0	12 0	13 9	...		do ..	do ...	86,744	13,878	6 4 0
		do north ...	do ...	...	..	..	...	p ..	1 0	12 0	13 9	...		do ...	do ...	1,21,016	13,722	8 1 6
		Jailor's quarters and Superintendent's Office.	do ...	...	...	...	...	p ...	1 0	11 10	13 8	...		do ...	tiled and ter ...	66,330	6,384	10 6 3
		Jute Factory	single ...	brick ...	1 0	p ...	4 0	p ...	3 0	17 0	...	...		do ...	stone ...	69,568	26,160	2 10 6
		Superintendent's dwelling house.	double ...		...	...	...	p ...	4 0	15 3	16 6	...		do ...	terraced ...	75,180	7,839	9 9 6
		Reformatory School ...	single ...	*Nil* ...	...	p ...	2 6	p ...	2 0	12 0	...	...		do ...	bk-on-edge ...	35,357	12,857	2 12 0
		Body Guard stable, Cavalry line.	do ..	*Nil* ...	...	p ...	2 0	p ...	2 0	14 1	...	...		do ...	do ...	43,164	10,792	4 0 0
		Meteorological Observatory, Main Building.	partly two	*Nil* ...	...	p ...	3 4½	p ...	4 0	16 6 up to spring	16 0 soffit	...		do ...	terraced ...	26,157	4,291	6 1 6
	Russa ...	Jail Building	single ...	...	...	..	...	p ...	1 3	11 9	13 9	...		vaulted ...	bk-on-edge ...	55,484	14,075	3 15 0
		Bridges over 50 feet in length, &c.	...	...	...	*Nil* ...	...	...	...	*Nil.*								

W. H. NIGHTINGALE, C. E.,

Offg. Executive Engineer, 2nd Calcutta Division.

Executive Division.	Locality.	Name of building.	Description and Height of Walls. Single or double storied.	Foundation. Concrete.	Foundation. Concrete. Ft. In.	Foundation. Masonry.	Foundation. Masonry. Average. Ft. In.	Plinth.	Plinth. Average. Ft. In.	Walls (to top of wall-plate). 1st floor. Ft. In.	Walls (to top of wall-plate). 2nd. Ft. In.	Walls (to top of wall-plate). 3rd. Ft. In.	Roof.	Floor.	Cost. Rs.	Area.	Rate per superficial foot. Rs. A. P.
2nd Calcutta	Calcutta Chowringhee.	Imperial Museum ...	double ...	brick ...	2 0	p	3 0	p	8 0	26 0	33 2	...	ter on girders and joists.	stone and cement	10,27,162	84,159	12 3 3
		Bengal Secretariat. General Department ...	three ...	...	...	p	unknown	p	0 6	9 0	15 0	18 6	ter on beams and burgahs.	ter and stone	1,99,508	14,345	13 14 6
		do Printing Department ...	single ...	...	...	p	...	p	3 0	18 9	...	...	do ...	terraced ...	52,250	13,238	3 15 0
	Calcutta Sudder Street.	do Main building ...	three ...	...	...	p	...	p	2 10	12 2	19 4	12 9	do ...	ter and stone	2,14,900	21,282	10 1 9
	do Brijeetalao	Lord Bishop's Palace ...	do ...	...	...	p	...	p	2 10	13 6	20 6	15 0	do ...	ter, stone and incostic tiled.	64,890	9,270	7 0 0
	do Maidan	*Presidency Jail Main buildings.*	do ...	*Nil*	...	p	5 0	p	2 0	10 5	15 4	18 11	terraced ...	ter, tile and bk-on-edge.	1,09,106	13,225	8 4 0
		do Native Doctor's quarters	double ...	...	...	p	2 6	p	3 0	8 3	12 6	...	do ...	tiled and ter and bk-on-edge.	22,048	2,756	8 0 0
		do Superintendent's do ...	do ...	*Nil*	...	p	5 3	p	2 0	14 0	17 0	...	do ...	tiled and ter...	36,099	5,157	7 0 0
		do Native Corridors (3) ...	do	*Nil*	...	p	2 0	p	3 0	12 3	14 9	...	do ...	do ...	66,000	13,200	5 0 0
		do Printing Office and Book Binder's Department.	partly 2 and partly 1 ...	...	...	p p	4 6	p p	3 0	9 3 / 10 2	9 9 / 15 3	... / ...	do ...	brick-on-edge and ter.	25,875	5,175	5 0 0
	Collinga ...	Madrasa College ...	do ...	*Nil*	...	p	2 6	p	1 10½	12 4	17 3	...	do ...	tiled and ter...	94,564	9,216	10 4 2
	Lower Circular Road.	St. James' Church ...	single ...	...	...	p	2 6	p	1 6	43 0	...	...	corrugated ...	ter and stone...	2,25,824	12,599	17 14 9
		do Parsonage ...	double ...	...	...	p	2 6	p	3 0	17 3	17 6	...	terraced ...	terraced ...	30,985	3,510	8 13 3
	Calcutta Park Street.	Mathematical Instrument Department.	do ...	...	...	p	2 9	p	2 9	16 0	17 9	...	do ...	stone, tiled and ter.	1,01,282	12,135	8 5 6
	Dhullundah	Native Lunatic Asylum, north Extension.	do ...	*Nil*	*Nil*	p	3 0	p	2 0	12 6	14 0	...	do ...	down story asphalted, 2nd story ter.	63,357	17,375	3 10 3
		General Hospital. Central building ...	double ...	*Nil*	*Nil*	p	4 0	p	1 6	15 9	20 3	...	do ...	stone ...	1,22,265	14,024	8 11 6
		Western do ...	three ...	*Nil*	*Nil*	p	4 0	p	1 0	8 3	12 0	14 0	do ...	ter, tile, tile ...	83,640	13,302	6 4 6
		Eastern do ...	do ...	*Nil*	*Nil*	p	4 0	p	1 0	8 6	11 9	14 0	do ...	tiled, ter, ter...	86,609	13,302	6 8 3
		Apothecary's quarter ...	single ...	...	...	...	...	p	2 9	12 0	...	...	do ...	tiled ...	30,015	12,006	2 8 0
		Medical Officer's do ...	double ...	...	...	p	3 6	p	3 9	12 6	17 3	...	do ...	terraced ...	1,12,290	18,715	6 0 0
		Nurse's do ...	do ...	...	...	...	...	p	3 0	14 0	14 0	...	do ...	do ...	30,000	4,200	7 2 3
		Female Hospital ...	single ...	...	...	...	...	p	4 3	17 0	...	...	do ...	stone ...	19,744	5,101	3 14 0
	Bhowanipore...	European Lunatic Asylum Superintendent's quarter.	double ...	...	...	p	2 0	p	1 6	14 9	17 6	...	do ...	do ...	30,150	6,672	4 8 3
	Khidderpore	St. Stephen's Church ...	single ...	...	...	...	...	p	4 0	25 0	...	...	sloped terraced on trusses.	ter and marble	60,460	7,140	8 7 0
		do Parsonage ...	double ...	...	...	...	...	p	1 6	12 3	13 6	...	terraced ...	tiled and ter ...	22,119	4,883	4 8 6

W. H. NIGHTINGALE, C. E.,

Offg. Executive Engineer, 2nd Calcutta Division.

Executive Division.	Locality.	Name of building.	Description and Height of Walls. Single or double storied.	Foundation. Concrete.	Foundation. Concrete. Ft. In.	Foundation. Masonry.	Foundation. Masonry. Average. Ft. In.	Plinth.	Plinth. Average. Ft. In.	Walls (to top of wall-plate). Ground floor. Ft. In.	Walls (to top of wall-plate). 1st floor. Ft. In.	Roof.	Floor.	Cost. Rs.	Area.	Rate per superficial foot. Rs. A. P.
2nd Calcutta	Alipore ...	Judges' Cutcherry ...	double ...	...	*Nil*	unknown	unknown	p ...	3 6	14 0	18 3	terraced ...	tiled ...	62,614	11,581	5 6 6
		Moonsiff's Court ...	single ...	*Nil*	*Nil*	p ...	2 0	p ...	3 0	varying from 12′ up to	18′, 15′ and spring soffit.	do ...	stone ...	26,526	6,237	4 4 0
		Collectorate ...	do ...	*Nil*	*Nil*	p ...	2 0	p ...	3 0	12 0	24 0	vaulted ...	tiled ...	36,748	10,160	3 9 9
		Magistrate's Court ...	do ...	*Nil*	*Nil*	p ...	2 0	p ...	3 0	11 0 / 9 0	19 0 / 15 0	a block verandah do.	do ...	64,972	16,422	3 15 3
		Municipal Office and Sunderbund Commissioner's Office, &c.	do	*Nil*	*Nil*	p ...	2 0	p ...	2 6	12 0	24 0	do ...	do ...	53,248	13,265	4 0 3
		Sub-Registry Office and District Engineer's Office.	do ...	*Nil*	*Nil*	p ...	3 0	p ...	2 6	16 0	...	terraced ...	do ...	24,421	5,868	4 2 6
	Diamond Harbour.	Moonsiff's Court ...	double ...	*Nil*	*Nil*	p ...	3 0	p ...	2 0	11 9	13 9	do ...	terrace ...	15,935	2,013	7 14 6
		Custom House ...	do ...	*Nil*	*Nil*	p ...	3 0	p ...	1 6	7 9	14 0	do ...	planked ...	32,256	6,868	4 10 9
		Telegraph Office ...	do ..	*Nil*	*Nil*	p ...	...	p ...	...	11 9	18 0	do ...	terraced ...	10,000	3,135	3 3 0
		Post Office ...	double ...	p ...	0 6	p ...	2 0	p ...	2 0	10 6	10 0	do ...	do ...	7,817	994	7 13 9
		Lock-up ...	single ...	*Nil*	*Nil*	p ...	...	p ...	1 3	17 0	...	pantile on trusses.	do ...	unknown ...	616	...
		Sub-Divisional Building ...	double ..	*Nil*	*Nil*	p ...	3 0	p ...	0 3	8 9	16 6	terraced ...	do and tiled	44,136	4,950	8 14 9
		do Cutcherry ...	single ...	*Nil*	*Nil*	p ...	2 0	p ...	3 0	16 0	...	do .	do ...	9,660	3,533	2 11 9
	Barripore ...	do do ...	do ...	*Nil*	*Nil*	p ...	1 6	p ...	2 3	13 3	...	thatched ...	do ...	6,066	3,240	1 14 0
	Port Canning	Police Building ...	double ...	*Nil*	*Nil*	unknown	unknown	p ...	3 9	14 3	16 6	terraced ...	tiled ...	unknown ...	2,528	...
	Atcheepore ...	Telegraph Office ...	2 or partly 3.	*Nil*	*Nil*	p ...	4 0	p ...	3 0	8 6	16 0	do ...	terraced ...	13,332	1,924	6 14 9
	Hoogly Point	do do ...	double ...	*Nil*	*Nil*	p ...	2 0	p ...	...	8 6	16 0	do ...	do ...	10,086	1,681	6 0 0
	Mudpoint ...	do do ...	do ...	*Nil*	*Nil*	p ...	2 0	p ...	...	8 6	16 0	do ...	do ...	10,086	1,681	6 0 0
		do do ...	do ...	*Nil*	*Nil*	p ...	2 0	p ...	4 0	14 6	13 6	do ...	do ...	32,936	1,530	21 8 3
	Saugore Island.	Lighthouse ...	single ...	*Nil*	*Nil*	p ...	8 0	p ...	7 0	...	72 0	vaulted, all iron, boarded.	do ...	unknown	1,600	...
		Superintendent's dwelling ...	double ..	...	...	p ...	4 0	p ...	6 0	7 6	14 6	terraced ...	boarded ...	do ...	1,230	...

W. H. NIGHTINGALE, C. E.,

Executive Engineer, 2nd Calcutta Division.

Statement of Construction, Cost and Length of Bridges exceeding 50 lineal feet in the Bengal Presidency.

Executive Division.	Name of bridge, or of river or nullah, and situation.	Date of completion.	Description of bridge.	Kind and depth of foundation.	No. and size of spans.	Width of roadway between parapets or railings.	Height of roadway above foundations or river-bed.	Total length of bridge.	Total cost.	Cost per 100 feet of length.	REMARKS.
							Ft. In.				
2nd Calcutta	Churial, over the Churial khal. River 15 miles, Budge Budge road.	Not known	Pucca masonry with six arches ...	Pucca, depth not known ...	Six arches, 15 ft. 3 in. each.	25 ft.	22 6	110	Not known	Not known.	

W. H. NIGHTINGALE, C. E.,

Executive Engineer, 2nd Calcutta Division.

Executive Division.	Locality.	Names of buildings.	Description and lengths of walls.										Cost.	Area.	Rate per superficial foot.
			Single or double-storied.	Foundation.				Plinth.		Wall to top of wall-plate.	Roof.	Floor.			
				Concrete.		Masonry.									
									Average.				Rs.		Rs. A. P.
Calcutta Workshop Division.	Sheebpore	Eastern block, Engineering College.	double ...	unknown	...	p ...	unknown	p m ...	2′6″ × 2′6″	no wall-plate, the thickness of the wall in ground floor 2 feet, 1st floor 1′-6″. Total length from plinth 35 feet.	terraced ...	ter, chunar stone and asphalting.	44,625	5,250 s. ft. 150 × 35	8 8 0
		Central block ...	do ...	do	...	p ...	do	do	2′6″ × 2′6″	do do ...	do ...	do ...	44,625	5,250	8 8 0
		South-western block ...	... ...	...	...	...	...	...	2′6″ × 2′6″	... ...	... ...	... ...	44,625	5,250	8 8 0
		St. Peter's Church & Library	double, only one room in 3rd story.	unknown	unknown	p m ...	unknown	p m ...	3′ × 3′	no wall-plate in the library; portion of the building under the beams, but in the Church portion there are two wall-plates. The thickness of the wall in the ground floor is 2′ 9″, and in 1st floor 2′ 6″; height from plinth 38′ 9″	ter, cor iron roof with iron trusses, ornamental ceiling.	ter, chunar stone and marble.	69,745	5,365 153 × 35	13 0 0
		Principal's block ...	... ...	...	...	...	...	...	3′ × 3′	no wall-plate; thickness of the wall ground floor 2′ 6″, and 1st floor 2 feet, height of building from plinth 38′ 9″	terraced ...	ter, chunar stone.	59,015	5,365 153 × 35	11 0 0
		Cook house, Coach house and Stable.	single ...	unknown	unknown	p m ...	unknown	p m ...	1′ × 2′	no wall-plate under the beams; thickness of wall 1′ 6″; length of building from plinth 13′ 6″.	do ...	tiled ter and cement plastering.	21,385	8,556	2 8 0
		Superintendent's house without office.	double ...	do	do ..	...	...	...	4′ × 2′ 6″	do do, thickness of the wall— 1st floor 1′ 9″ 2nd do 1′ 6″ height of building from plinth 36′	ter and sloped	flood ter; chunar stone and asphalting.	28,285	3,600 s. ft. 60 × 60	8 0 0
		Cook house attached to Superintendent's quarter.	single ...	...	...	...	...	...	2′ × 2′	do do, thickness of the wall 1′ 6″, height from plinth 12′	terraced ...	tiled and ter with cement plaster.	4,680	18,720 52 × 36	2 8 0
		Drawing Office for Engineering College.	do ...	unknown	unknown	p m ...	...	p m ...	3′ 6″ × 2′	no wall-plate under the beams; thickness of the wall 1′ 6″; height from plinth 20′.	do ...	flood and tiled	18,000	4,000 80 × 50	4 8 0
		Small house for the use of Assistant Surgeon.	... ...	...	...	...	...	...	1′ 6″ × 2¼″	do do thickness of the wall 1′ 8″, height from plinth 12′	do ...	tiled and cement plastering.	5,555	2,226 53 × 42	2 8 0
		Coock house attached to do do.	... ...	...	...	...	...	...	6′ × 1′ 3″	do do thickness of the wall 12″; height from plinth 9′	do ...	mud ...	525	262·6 25 × 10½	2 0 0

Executive Division.	Locality.	Names of buildings.	Description and lengths of walls. Single or double-storied.	Foundation. Concrete.	Foundation. Masonry.	Plinth.	Wall to top of wall-plate.	Roof.	Floor.	Cost.	Area.	Rate per superficial foot.
						Average.				Rs.		Rs. A. P.
Calcutta Workshop Division.—contd.	Sheebpore—contd.	Octagonal Bungalow No. 1...	single, upper thatch roof.	... ...	p m	p m ... 2′6″ × 1′10″	no wall-plate under the beams; thickness of the wall— ground floor 1′ 4″ upper floor 1′ 3″.	ter and thatched with ceiling cloth.	flood and chunar stone with cement plastering.	6,048	1,728	3 8 0
		Bungalow No. 2...	thatch roof ...	... ...	... ...	... ...	thatched roof ...	thatch with ceiling cloth.	flood, tiled and cement plaster.	2,736	1,824 s. ft.	1 8 0
		do No. 3...	...	... ...	... ...	... ...	... ..	...	...	2,736	1,824 do	1 8 0
		do 4...	...	... ...	... ...	... ..	... ...	...	...	2,736	1,824 do	1 8 0
		do 5...	...	*Nil* *Nil*	... 1′ × 1′3″	... 3′1½″ × 1¼″	wattle and daub wall ...	...	ter with cement plaster.	2,062	3,000 do	0 11 0
		do 6...	...	... ...	... 1′ × 10″	... 3′ × 10″	... ...	...	do with asphalting.	2,165	3,000	0 11 6
		do 7...	...	... ...	... 1′ × 1′3″	... 3′ × 1′ 3″	... ...	...	mud ...	1,500	3,000 s. ft.	0 8 0
		do 8...	...	... ...	... 1′ × 10′½″	... 5′3″ × 10′½″	... ..	...	...	1,500	3,000 do	0 8 0
		Temporary Hospital and Dispensary.	shed ...	*Nil* *Nil*	p ... bollen of posts 2′6″ × 6″	p ... 2′ × 3′	double durmah mat walling	thatched ...	Rustic, with 1½″ daub.	986	73 × 21	0 10 3½
		Temporary Lavatory ...	...	... ...	p ... 1′3″ × 1′	p ... 1′ 3″ × 1′	do do ...	...	tiled, bedded on mud.	250	31 × 16	0 8 1
		Durwan's lodge near North-east gate.	single ...	unknown unknown	... ...	... 1′ 6″ × 2′	no wall-plate under the beams, 1′ 6″ thick wall, 10′ height.	ter, sloped ...	terraced ...	460	176 s. ft.	2 8 0
		Do do river bank near ghât	do ...	... ...	... ...	... 1′ 6″ × 2′	do do plate, 1′ 6″ thick, 10′ height.	do ...	do ...	460	176 do	2 8 0
		Sentry box, North side ...	do ...	unknown unknown	p	p ... 1′ × 3″	no wall-plate under the beams, 1′ thick wall, 11′ height.	terraced ...	tiled ...	140	70 do	2 0 0
		Cook room for the use of Native students.	do ...	do ... do ...	p	... 6′ × 2′	do do under the beams, 1′ 6″ thick wall, 12′ height.	do ...	do ...	903	361 do	2 8 0
		Temple of Ease for the use of European students.	...	... ...	... ...	... 2′ × 2′	no wall-plate under the beams, 1′ 6″ wall, 14′ height.	do ...	do ..	672	224	3 0 0
		Temporary privy for the use of Native students, Engineering College.	*Nil*	*Nil* ...	... 4′ × 1′	p ... 4′ × 1′	p ... *Nil.*	*Nil.*	cement plastering.	108	144 s. ft.	0 12 0
		Workshop building ...	single, only 2 rooms in 2nd floor.	*Nil* *Nil*	p ... 3′ 11½″ 5′ × 2′6″ / 2	p ... 2′ × 6″	p ... no wall-plate, 1′ 8″ thick wall, 22′ height.	terraced ...	mud ...	1,54,615	31,775 400 × 65 50 × 46 50 × 46 50 × 23′6″	4 13 10

CHAS. FOURACRES,
Supdt., Calcutta Workshop Division.

Executive Division.	Locality.	Name of building.	Description and Height of Walls. Single or double storied.	Foundation. Concrete. Ft. In.	Foundation. Masonry. Average. Ft. In.	Plinth. Average. Ft. In.	Walls (to top of wall-plate). Ft. In.	Roof.	Floor.	Cost.	Area.	Rate per superficial foot.
										Rs.		Rs. A. P.
Darjeeling	Darjeeling...	Shrubbery old portion ...	double ...	*Nil*	r l ... 6 6	r l ... 0 6	r l ... 14 6	cor ...	planked ...	98,702	5,250	9 6 0
		New portion with portico ...	do ...	.....	r l ... 6 6	r l ... 2 0	r l ... 14 6	shingled ...	do ...		5,244	
		Mount Pleasant with portico	do ...	no concrete ...	c r ... 2 0	p ... 0 6	lower story 7 6; upper „ 13 0	cor ...	lower do ...; upper ...	24,291	8,107	3 0 0
		Deputy Commissioner's Cutcherry.	do ...	owing to drains all round, foundation taken in the front plinth.	p and c r 2 0	p ... 0 12	p ... 15 6	do ...	planked ...	26,820	12,000	2 4 0
		Additional building to Bhootia Boarding School.	do ...	.....	c r ... 1 6	c r ... 0 6	p ... 16 0	shingled ...	do ...	7,957	2,684	3 0 0
		Old Post Office or Bhootia Boarding School.	single ...	upon hard soil ...	c r ... 0 9	p ... 0 9	p ... 12 0	do ...	do ...	6,000	2,720	2 4 0
		Post and Telegraph Office ...	do ...	no concrete ...	c r ... 2 0	c r ... 1 9	p ... 12 0	cor ...	do ...	9,085	2,856	3 2 0
		Police Hospital ...	do ...	do ...	c r ... 0 12	p ... 1 6	p ... 10 0	do ...	do ...	10,684	4,266	2 8 0
		Circuit house ...	do ...	do ...	c r and p 2 6	p ... 0 9	p ... 13 6	do ...	do ...	7,036	2,976	2 8 0
		Church ...	gable ...	0 6	c r ... 2 6	p ... 2 1	p ... 17 9	do ...	do ...	29,815	2,850	10 8 0
		Zillah School ...	single ...	no concrete ...	c r ... 2 0	c r ... 5 6	c r ... 13 3	shingled ...	do & c ...	10,661	4,140	2 8 0
		Thorn Cottage ...	double ...	do ...	c r ... 2 9	c r ... 1 9	k & p ... 18 0	cor & shingled	planked ...	12,493	4,935	2 8 0
	Dowhill ...	Circuit house ...	single ...	do ...	r s l .. 2 6	r s l ... 2 6	r s l ... 15 0	do ...	do ...	19,765	4,070	4 12 0
		Boarding School ...	do ...	do ...	r s l ... 2 6	r s l .. 2 0	r s m ... 14 0	cor ...	do ...	28,574	7,390	3 13 0
	Kurseong ...	Dâk bungalow ..	do ...	do ...	r s m ... 1 6	r s m ... 2 0	r s m ... 12 0	do ...	do ...	14,257	3,419	4 2 0
		Constantia or Sub-divisional cutcherry.	do ...	do ...	r s m ... 2 0	r s m ... 3 6	b m ... 12 0	do ...	do ...	not known	6,277	not known
		Jail.										
	Darjeeling...	New jail wards ...	single ...	Cannot be known. ...	r ... 3 0	b l ... 2 0	b l ... 12 6	cor ...	planked ...	...	2,994	6 12 0
		Hajut ward and cells ...	do ...	...	r ... 2 0	b l ... 1 6	b l ... 12 6	do ...	do ...	...	1,028	
		Female ward and cells ...	do ...	...	r ... 2 0	b l ... 1 6	b l ... 12 6	do ...	do ...	...	1,020	
		Civil jail, now hospital ...	do ...	...	r ... 2 0	b l ... 1 6	b l ... 12 6	do ...	do ...	...	309	
		Insane wards and hospital, now godown.	do ...	...	r ... 2 6	b l ... 1 6	b l ... 12 0	do ...	do ...	...	515	
		do do, now civil jail ...	do ...	...	r ... 2 6	b l ... 1 6	b l ... 12 0	do ...	do ...	...	371	
		Store-rooms with passage	do ...	...	r ... 2 6	b l ... 1 6	b l ... 8 6	planked ..	do ...	95,845	664	
		Upper-story or Office ..	...	...	... ...	... ...	b l ... 12 0	cor ...	do ...	...	640	
		Cook-house, now wheat grinding-shed.	single ...	...	r ... 2 0	b l ... 1 6	b l ... 7 9	do ...	ter ...	...	230	
		do do ...	do ...	...	r ... 2 0	b l ... 1 6	b l ... 7 9	do ...	do ...	...	230	
		Cook-house ...	do ...	...	r ... 2 0	b l ... 1 6	b l ... 8 0	do ...	do ...	...	126	
		Guards' room with cook-house	do ...	...	r ... 2 0	b l ... 1 6	b l ... 10 av.	do ...	planked ...	...	247	
		do do ...	do ...	...	r ... 2 0	b l ... 1 6	b l ... 10 0	do ...	do ...	...	247	

Executive Division.	Locality.	Name of building.	Description and Height of Walls.																			Cost.	Area.	Rate per superfical foot.
			Single or double storied.	Foundation.																				
				Concrete.			Masonry.					Plinth.		Walls (to top of wall-plate).				Roof.	Floor.					
								Average.					Average.											
					Ft.	In.		Ft.	In.				Ft.	In.			Ft.	In.				Rs.		Rs. A. P.
Darjeeling...	Darjeeling...	Work-shed, now wheat granary	single ...	Cannot be known.	...		r ...	2	6	b l ...		1	6	b l ...		8	6	cor ...	planked ...			364		
		do do sifting-shed ...	do ...		...		r ...	2	0	b l ...		1	6	b l ...		8	6	do ...	do ...			364		
		Cook-house for prisoners ...	do ...		...		r ...	2	0	b l ...		1	6	b l ...		7	9	do ...	ter ...			185		
		Privy ...	do ...		...		r ...	2	0	b l ...		1	6	b l ...		7 av.		do ...	do ...			102		
		do ...	do ...		...		r ...	2	0	b l ...		1	6	b l ...		7	0	do ...	do ...			102		
		Cook-house, now blacksmith's shop.	do ...		...		r ...	2	0	b l ...		1	6	b l ...		8	0	do ...	mud floor...			185		
		Jail bakery, now jailor's quarters.	do ...		...		r ...	2	0	b l ...		1	6	b l ...		9	6	do ...	planked ...		95,845	1,401		6 12 0
		New jail bakery ...	do ...	c	0	12	r ...	7	6	c r ...		2	8	c r ...		7	0	do ...	ter ...			2,626		
		Compound wall ...	...	cannot be known			r ...	5	0	b l ...		2	0	b l ...		13	6 av.	*Nil.*	*Nil.*			...		
		do (inside) ...	...				r ...	2	6	b l ...		1	6	b l ...		6	3	*Nil.*	*Nil.*			...		

W. B. CHRISTIE,

Executive Engineer, Darjeeling Division.

Statement of construction, cost, and length of bridges exceeding 50 lineal feet in the Bengal Presidency.

Executive Division.	Name of bridge, or of river or nullah, and situation.	Date of completion.	Description of bridge.	Kind and depth of foundation.	No. and size of spans.	Width of roadway between parapets or railings.		Height of roadway above foundations or river-bed.	Total length of bridge.		Total cost.	Cost per 100 feet of length.	Remarks.
						Ft.	In.		Ft.	In.	Rs.	Rs.	
Darjeeling...	Punchani Bridge over Mattigurah Diversion road.	Mar 1880 ...	Wooden-bridge on piles ...	Piles of sal bullas 12 feet in depth.	20 spans of 18 feet average.	8	0	12 to 4 feet above river bed.	360	0	5,834	1,620	
	Champta Bridge over Mattigurah Diversion road.	do ...	do do	do do ...	10 spans of 18 feet average.	8	0	12 to 6 feet do	180	0	4,104	2,280	
	Old Mohanuddy Bridge over road from Silligoree to Mattigurah.	...	do do ...	do do believed to be 12 feet.	48 spans, 20 feet average.	9	0	9 to 2 „ do	972	0	not known...	...	Being dismantled under a sanctioned estimate, No. 1121 of 1880-81, Superintending Engineer's Office.
	Old Champta Bridge on road from Silligoree to Mattigurah.	...	do do ...	do do 10 feet ...	17 spans, 11 feet average.	8	3	4 to 1 „	196	0	...	...	
	Pathariaghatta Bridge on road from Mattigurah to Bisserbatty.	...	do do ...	do do 7 „ ...	15 spans, each 9 feet 6 inches.	7	7	10 to 4 „	150	0	...	...	
	Khuprail Bridge on road from Mattigurah to Bisserbatty.	...	do do ...	do do 8 to 9 „ ...	15 spans of 19 feet 6 inches.	8	0	7 to 8 „	303	0	...	...	
	Pugla Jhora Bridge on road from Mattigurah to Bisserbatty.	...	do do ...	do do 7 to 8 „ ...	7 spans of 13 feet.	8	6	8′ 6″ to 11 feet	98	0			
	Ruktee Bridge on road from Mattigurah to Bisserbatty.	...	do do ...	do do 7 to 8 „ ..	15 spans of 20 feet.	8	0	6 to 12′ 6″	319	0			
	Garudara Bridge on road from Mattigurah to Bisserbatty.	...	do do ...	do do 9 „ ...	6 spans of 19 feet 6 inches.	8	0	8 to 11 feet	119	0			

W. B. CHRISTIE,

Executive Engineer, Darjeeling Division.

Executive Division.	Locality.	Name of Building.	Description and Height of Walls. Single or double storied.	Foundation. Concrete. Ft. In.	Foundation. Masonry.	Average. Ft. In.	Plinth.	Average. Ft. In.	Walls (to top of wall-plate).	Ft. In.	Roof.	Floor.	Cost. Rs.	Area.	Rate per superficial foot. Rs. A. P.
Burdwan Division.	Dum Dum...	Lock-up	single ...	... ...	p ..	2 0	p ...	2 6	p ...	16 3	n tiled ...	tiled ...	...	4,260	
		Police Building	double ...	... ...	p ...	1 3	p ...	1 6	k p ...	19 9	terraced ...	do ...	...	2,408	
		Hajut Ward	do ...	... ...	p ...	1 3	p ...	1 6	p ...	19 9	n tiled ...	do ...	...	753	
	Baraset ...	Cutcherry	do ...	... ...	p ...	2 0	p ...	1 6	p ...	25 9	terraced ...	ter ...	30,000	3,501	
		Residence	do ...	.. ...	p ...	2 0	p ...	1 6	p ...	33 9	do ...	do ...	40,000	5,819	
		School	do ...	... ...	p ...	2 0	p ...	1 6	p ...	30 3	do ...	do ...	10,000	2,707	
		Hostel	single ...	... ...	p ...	...	p ...	...	p ...	...	do ...	do ...	1,716	1,178	
		Jail Building	3 storied...	... ...	p ..	2 0	p ..	3 0	p ...	35 3	do ...	tiled ...	59,000	6,294	
		Inspection Bungalow	single ...	... ...	k p .	0 6	k p ...	3 0	k p ...	10 6	do ...	ter ...	...	956	
	Chougda ...	Inspection Bungalow ..	do ...	.. ...	...	...	k p ...	1 6	mat ...	14 3	thatched ...	do ...	...	...	
	Bongong ...	Cutcherry	do ..	... ..	p ...	1 6	p ...	2 0	p ...	16 9	terraced ...	tiled ...	8,000	2,241	
		Residence	do ...	... ...	p ...	2 0	p ...	2 0	p ...	17 0	do ...	ter ...	11,000	3,510	
		Lock-up	do ...	... ...	p ...	1 6	p ...	2 6	p ...	15 6	tiled ...	do ..	5,225	3,619	
		Dâk Bungalow	do ...	... ...	p ...	3 0	p ...	1 0	p ...	12 0	vaulted ...	do ...	...	3,595	
	Jessore ...	Collectorate	do ...	... ...	p ...	1 0	p ...	5 0	p ...	16 0	arched and ter	tile and ter	27,484	16,093	
		Judge's and Magistrate's Court	do ...	... ...	p ...	2 6	p ...	2 6	p ...	17 0	do ...	do ...	38,011	42,607	
		Small Cause Court ...	do ...	... ...	p ...	1 3	p ...	2 0	k p ...	14 6	ter and tiled	terraced ...	2,696	3,599	
		Registry Office	do ...	... ...	p ...	3 0	p ...	5 0	p ...	15 9	terraced ...	tiled ...	7,724	2,094	
		Circuit House	do ...	... ...	p ...	2 6	p ..	2 0	p ...	15 6	do ...	terraced ..	9,936	5,406	
		School	do ...	... ...	p ...	2 6	...	2 0	p ...	16 0	do ..	tiled ...	6,856	7,361	
		Distillery at Mohungunge ...	do ...	... ...	p ...	3 0	p ...	1 0	p ...	12 0	do ...	mud and ter	3,539	2,310	
		Burial ground	do ...	... ...	p ...	1 3	...	..	p ...	5 9	...	...	1,721	3,672	
		Dâk Bungalow	do ...	... ...	p ...	1 9	p ...	3 0	k p ...	16 6	thatched ...	tiled ...	...	2,344	
		Post Office	do ...	... ...	p ...	2 6	p ...	1 6	p ...	10 0	terraced ...	terraced ...	3,624	934	
		Jailor's House	double ...	c 1 0	p ...	3 0	p ...	3 9	p ...	s 12 6 / d 12 6	do ...	do ...	15,391	2,575	
		Wards for mail convicts ...	do ...	... ...	p ...	3 0	p ..	2 0	p ...	d 14 0 / s 13 2	do and arched.	do ...	...	17,797	
		Civil Ward	single ...	... ...	p ...	2 0	p ..	1 0	p ...	9 6	terraced ...	tiled ...	..	400	
		Powder Magazine ...	do ...	... ...	p ...	3 0	p ...	3 0	p ...	15 0	vaulted ...	terraced ...	1,876	485	
		Police Barrack	do ...	... ...	p ...	1 0	p ...	2 0	mat ...	12 0	thatched ...	tiled	2,897	3,990	
		Hospital	do ...	... ...	p ...	2 6	...	5 0	p ...	15 0	terraced ...	terraced ...	64,639	163	
		Mad Cell	do ...	... ...	p ...	1 0	p ...	1 0	p ...	10 6	arched ...	do ...	...	190	
	Narail ...	Sub-Divisional dwelling-house	double ...	... ...	p ...	3 0	p ...	2 3	p ...	s 14 3 / d 17 4	terraced ...	tiled ...	15,034	2,718	
		Lock-up	single ...	... ...	p ...	2 0	p ...	1 6	p ...	15 6	tiled ...	terraced ..	5,225	7,267	
	Magoorah ...	Cutcherry	do ...	... ...	p ...	1 6	p ...	2 0	p ...	16 0	terraced ..	ter and tiled	29,844	5,231	
		Lock-up	do ...	... ...	p ...	2 0	p ...	3 0	p ...	12 0	thatched ...	terraced ...	5,000	14,673	
	Jenidah ..	Sub-Divisional dwelling-house	do ...	... ...	p ...	1 6	p ...	2 0	p ...	16 0	terraced ...	tiled ...	..	3,456	
		Cutcherry	do ...	... ...	p ...	1 6	p ...	2 0	p ..	16 0	do ...	do ...	29,411	3,249	
		Small Cause Court ...	do ...	... ...	p ...	1 6	p ...	2 0	p ...	16 0	do ...	do ...	...	2,473	
		Lock-up	do ...	... ...	p ..	1 6	p ...	2 0	p ...	16 0	tiled	do ...	5,000	7,182	
		Circuit House	do ...	... ...	p m ...	2 3	p m ...	1 10	p m ...	15 0	terraced ...	terraced ..	10,900	5,885	
		Collector's Cutcherry ...	do ...	... ...	p ...	3 4	p m .	3 9	p	20 0	...	do ...	30,000	9,921	
		College	do ...	brick concrete. 0 11	p ...	1 9	p m ...	7 3	p ...	21 6	terraced ...	stone ...	96,000	30,800	

Executive Division.	Locality.	Name of Building.	Description and Height of Walls. Single or double storied.	Foundation. Concrete. Ft. In.	Foundation. Masonry.	Average. Ft. In.	Plinth.	Average. Ft. In.	Walls (to top of wall-plate).	Ft. In.	Roof.	Floor.	Cost. Rs.	Area.	Rate per superficial foot. Rs. A. P.
Burdwan	Kishnaghur	Small Cause and Moonsiff's Court.	do ...	... ...	p ...	3 0	p m ...	2 6	p ...	20 0	do ...	tiled ...	10,990	4,875	
		P W Godown ...	do ...	... ...	p m ...	2 0	p m ...	2 0	p m ...	9 0	do ...	terraced ...	2,000	255	
		Judge's Cutcherry ...	do ...	... ...	p m ...	2 0	p m ...	3 0	p m ...	12 3	do ...	do ...	30,283	15,750	
		Joint Magistrate and Deputy Collector's Court and Treasury.	do ...	... ...	p m ...	2 0	p m ...	2 9	p m ...	10 0	do ...	do ...	...	9,060	
		Post Office	do ...	... ...	k p ...	2 5	k p ...	1 3	k p ..	7 10	thatched ...	do ..	3,624	1,845	
		Jail Ward	do at two ends double	... ...	p m ...	1 7	p m ...	2 3	p ...	13 6	arched and ter	stone tiled	5,311	17,448	
		Jail Hospital and Female Ward	single ...	... ...	p m ...	2 3	p m ...	2 2	p ...	11 6	terraced ...	terraced ...	13,257	4,299	
		Jailor's residence ..	do ...	... ...	k p ...	2 0	k p ...	3 5	k p ...	10 0	thatched ...	do ...	1,700	1,508	
		Cemetery	...	... ...	...	...	...	...	p ...	...	*Nil*	*Nil*	2,000	64,505	
		Sub-Registry Office ...	single ...	... ...	p m ...	1 7	p m ...	3 0	p ...	14 0	terraced ...	terraced ...	5,011	1,837	
		Physical Science Lecture Building.	do ...	... ...	p ...	2 3	p ...	4 0	p ...	16 0	do ...	do ...	11,137	2,252	
	Meherpore ...	Cutcherry	do ...	... ...	p m ...	2 0	p m ...	2 0	p ...	15 0	do ...	tiled ...	10,823	3,781	
		Lock-up	do ...	... ...	p m ...	2 0	p m ...	2 0	p ...	15 0	tiled ...	terraced ...	5,000	623	
		Dwelling-house	do ...	... ...	p m ...	2 0	p m ...	1 3	p .	15 6	terraced ...	tiled ...	11,000	3,443	
	Kooshteah ...	Cutcherry	do ...	... ...	p ...	3 0	p ...	5 0	p ...	20 0	do ...	terraced do	32,257	8,566	
		Lock-up	do ...	... ...	p ...	3 6	p ...	5 0	p ...	16 0	tiled ...	do ...	5,000	2,221	
		Dwelling-house	do ...	... ...	p ...	2 0	p ..	5 0	p ...	16 0	thatched ...	do ...	13,057	2,849	
	Koomercolly...	Burial ground	...	... ...	p ...	1 0	...	...	p ...	6 0	*Nil*	*Nil*	1,018	5,313	
	Chooadanga	Cutcherry	single ...	... ...	p ...	1 6	p ...	2 0	p ...	16 0	terraced ...	tiled ...	11,000	3,396	
		Lock-up	do ...	... ...	p ...	2 0	p ...	2 0	p ...	16 0	tiled ...	terraced ...	5,000	598	
		Dwelling-house	do ...	... ...	p ...	2 0	p ...	2 0	p ...	16 0	terraced ...	tiled ...	11,689	2,382	
	Ranaghat ...	Cutcherry	do ...	... ...	p m ...	2 0	p m ...	1 6	p ...	...	do ...	do ...	10,454	3,327	
		Lock-up	do ...	... ...	p ...	2 0	p ...	2 0	p ...	16 0	tiled ...	bk-on-edge...	5,000	632	
		Dwelling-house	do ...	... ...	p m ...	2 0	p m ...	1 8	p ...	16 6	terraced ...	tiled ...	11,000	3,445	
	Kauchraparah	Post Office	...	... ...	k p ...	1 6	k p ...	1 0	k p ...	11 0	thatched ...	do ...	1,999	1,513	
	Hooghly (Station.)	Post Office	single ...	... not	known ...	...	...	1 6	k p ...	10 6	ter and tiles	asphalte, tiles and ter.	1,577	1,192½	1 5 2
		Out-offices	do ...	... ...	do ...	...	...	1 0	k p ...	11 0	do ...	terraced ...	100	410	0 3 10
		Judge's Court	do ...	... ...	do ...	...	...	4 0	k p ...	18 0	do ...	do ...	40,525	10,360	3 14 2
		Stables	do ...	... ...	do ...	...	...	0 6	k p ...	11 6	do ...	do ...	300	660	0 7 3
		Privy	do ...	... ...	do ...	...	*Nil*	*Nil*	k p ...	8 0	do ...	do ...	174	148½	1 2 9
		Magistrate's Court ...	do ...	... ...	do ...	...	...	2 0	k p ...	15 9	do ...	do ...	12,914	5,544	2 5 3
		Hajut Guard	do ...	... ...	do ...	...	...	...	p ...	mean 11 3	do ...	tiled ...	3,876	693½	5 9 5
		Coach house	do ...	... ...	do ...	...	*Nil*	*Nil*	p ...	10 6	do ...	bk-on-edge...	273	324	0 13 5
		Range of out-offices ...	do ...	... ...	do ...	...	*Nil*	*Nil*	p ...	11 9	tiled ...	k ...	285	1,183	0 3 10
		Guard Room	...	... ...	do ...	...	...	...	k p ...	9 8	flat ...	tiled ...	830	1,6·3	0 7 10
		River side ghat	single ...	... ...	do ...	...	*Nil*	*Nil*	k p ...	18 0	do ...	do ...	14,000	9,590 covered 2,056	1 4 7
		Collector's Court ...	double ...	*Nil* *Nil*	p ...	2 0	*Nil*	*Nil*	p ...	34 0	ter and tile	terraced ...	7,124	10,080	
		Out-offices	single ...	... not	known	...	p ...	0 9	p ...	9 0	terraced ...	plank and tiles.		768	0 9 6
		do	do ...	... ...	do ...		*Nil*	*Nil*	p ...	10 2	do ...	terraced ...		1,092	...
		Enclosure wall	...	... ...	...	...	...	...	rails ...	...	...	...	...	...	...
		Branch School	single ...	*Nil* *Nil*	p ...	3 0	p ...	3 0	p ...	17 0	terraced ...	asphalte ...	3,909	5,695¼	0 11 0
		Out-offices	do ...	... not	known ...	...	p ...	1 0	p ...	mean 8 6	ter and thatch	do ...	...	1,016	...
		Privy	do ...	... ...	do ...	...	*Nil*	*Nil*	p ...	6 0	terraced ...	terraced ...	..	140	...
		Durwan's house ...	do ...	... ...	do ...	...	*Nil*	*Nil*	p ...	8 6	do ...	do ...	...	315	...
		Enclosure wall	...	... ...	...	...	...	...	balustrade	...	...	...	...	...	...
		Distillery	single ...	... not	known ...	...	*Nil*	*Nil*	p ...	mean 7 0	tiled ...	terraced ...	...	4,921	...

Executive Division.	Locality.	Name of Building.	Description and Height of Walls. Single or double storied.	Foundations. Concrete.	Foundations. Masonry.	Plinth.	Walls (to top of wall-plate).	Roof.	Floor.	Cost.	Area.	Rate per superficial foot.
				Ft. In.	Average. Ft. In.	Average. Ft. In.	Ft. In.			Rs.		Rs. A. P.
	Hooghly (Station).	Out-offices	single ...	... ...	... ...	... ...	p	thatched ...	mud ...	...	104	...
		Criminal Jail	do ...	... not	known	p ... 1 0	mean					
		Compound wall	...	... ...	... ...	... ...	p ... 14 6	terraced ...	terraced ...	43,798	21,907	1 15 11
		Cook-rooms	single ...	... not	known	Nil Nil	p ... 16 0	...	...	...	...	...
		Hospital	do ...	Nil Nil	p ... 2 6	p ... 2 0	p ... 5 0	flat ...	k ...	...	1,240	...
		Cooking shed	do ...	... not	known	Nil Nil	p ... 17 9	do ..	p ...	7,842	5,880	1 5 4
		Out-offices	do ...	Nil Nil	p ... 2 6	p ... 2 0	p ... 8 6	tiled ...	k ...	720	972	0 11 10
		Dead-house	do ...	Nil Nil	p ... 2 6	p ... 2 0	p ... 10 0	pitched ...	terraced	2,326	640	3 10 1
		Hospital compound wall ...	...	... ...	... ...	... ...	p ... 12 9	terraced ...	do ...	...	400	...
		Dewany Jail	single ...	... not	known	p ... 1 0	p ... 14 0	...	...	...	...	...
		Ditto enclosure wall ...	...	... ...	... ...	... ...	p ... 12 0	flat ...	terraced ...	12,082	3,150	3 13 4
		Female Jail with four solitary cells.	single ...	Nil Nil	p ... 2 0	Nil Nil	p ... 16 0	...	...	...	...	...
		Two additional rooms ...	...	... ...	... ...	... ...	p ... 13 0	terraced ...	terraced ...	4,610	1,110	4 2 5
		Enclosure wall ...	...	... ...	... ...	... ...	p	do ...	do ...	565	900	0 10 0
		Jailor's quarters ...	double ...	... not	known	p ... 1 0	p ... 26 6	flat ...	terraced ...	3,176	2,128	1 7 10
		Godown	single ...	Nil Nil	p ... 2 0	Nil Nil	mean					
		Six solitary cells ...	do ...	Nil Nil	p ... 2 0	p ... 1 6	p ... 7 0	do ...	do ...	...	1,296	...
		Guard-room	do ...	... not	known ...	p ... 0 6	p ... 11 6	terraced ...	do ...	4,231	1,829¾	2 5 0
		Four Sentry boxes ...	...	... ...	... ...	... ...	p ... 10 0	sloping ...	do ...	...	1,751	...
		Hajut	...	... not	known	p ... 2 0	p	flat ...	do ...	...	1,600	...
		Record Office	single ...	... ...	do	p ... 3 0	p ... 11 0	terraced ...	...	...	1,253	...
		Sub-Registrar's Office ...	do ...	... 1 0	p ... 3 0	p ... 2 0	mean					
	Bandel (Station).	Commissioner's Office ...	double ...	... not	known	p ... 1 0	p ... 14 6	do ...	terraced ...	8,484	7,700	1 1 7
		Range of out-offices ...	single ...	... ...	do	Nil Nil	p ... 18 0	do ...	do ...	4,588	1,284½	3 9 2
		do of stables ...	do ...	... ...	do	Nil Nil	p ... 31 6	tiles and ter	do ...	...	9,984	...
		Boarding House ...	double ...	... ...	do	... ...	p ... 11 10	do ...	do ...	...	5,320	...
	Chinsurah (Station).	Out-offices	single ...	Nil Nil	Nil 2 0	... 2 0	k p ... 10 6	do ...	stone ...	...	867	...
		Compound wall	...	... ...	... ...	... 1 0	k p ... 27 0	ter and tiles	ter marble and tiles.	36,048	30,625	1 2 10
		Cook-room	...	... ...	... ...	... ...	k p ... 9 11	tiled ...	tiled ...	580	1,170	0 7 11
		Latrine	double ...	Nil Nil	p ... 3 0	Nil Nil	k p	...	...	...	...	...
		Chinsurah Reserve Police Barracks.	single ...	... not	known	... 1 6	p ... 9 11	terraced ...	flag stones...	2,483	1,048	2 5 10
		College of Mohamed Moshin	double ...	... ...	do	p ... 1 6	p ... 19 0	do ...	asphalt ...	1,777	323½	5 10 0
		Range of out-offices ...	single ...	... ...	do	p ... 2 0	... 10 6	...	...	...	...	...
		Two Darwans' houses ...	do ...	... ...	do	p ... 1 5	p ... 46 6	flat ...	terraced ...	48,480	33,288	1 7 3¾
		Store-room	...	... ...	... ...	... ...	p ... 12 6	do ...	do ...	6,652	3,225¾ / 181¼ / 282¾	1 12 10
		Pucca ghat	...	... ...	... ...	... ...	p ... 9 0	do ...	do ...			
		Compound wall... ...	...	... ...	... ...	... ...	p ... 9 6	do ...	do ...			
		Public drain	...	... ...	... ...	... ...	p ... 24 0	...	...	2,827	2,940	0 15 4
		New privy	single ...	... 0 6	p ... 1 6	p .. 4 0	p	...	...	3,476	1,820	1 14 6
		Laboratory, Chinsurah College	do ...	... 1 0	p ... 2 9	p ... 2 0	p ... 10 0	flat ...	terraced ...	1,766	520¼	3 6 4
		Protestant Church Cemetery	...	... ...	... ...	... ...	p ... 20 0	terraced ...	do ...	7,253	2,212¾	3 4 5
							p	flat ...	do ...	16,000	5,760	2 12 5

Executive Division.	Locality.	Name of Building.	Description and Height of Walls. Single or double storied.	Foundations. Concrete.	Foundations. Masonry.	Plinth.	Walls (to top of wall-plate).	Roof.	Floor.	Cost.	Area.	Rate per superficial foot.
Burdwan ...	Serampore (Station).	Magistrate's dwelling ...	single ...	... not	known	... 3 0	k p ... 21 6	flat ...	terraced ...	16,000	11,875	1 5 6
		Stable No. 1, &c. ...	do ...	... ..	do	... ...	k p ... 11 0	do ...	do ...	...	...	...
		Pucca ghat	...	... ...	... ...	... ...	k p	...	...	...	...	...
		Jugul Addy's Ghat ...	single ...	... not	known	... 0 6	k p ... 12 0	terraced ...	...	6,000	covered part 1,188 4,420	1 1 1
		Court-house	do ...	... ...	do	... 1 6	mean k p ... 16 0	flat ...	terraced ...	3,000	2,900	1 0 6
		Out-offices	do ...	... ...	do	... 1 6	k p ... 7 6	do ...	do ...	...	1,487½	...
		Jail	do ...	Nil Nil	... 3 0	... 2 0	k p ... 11 9	do ...	do ...	4,500	714	6 4 10
		Criminal Hazut	do ...	Nil Nil	... 3 0	... 2 0	k p ... 12 0	do ...	do ...	4,000	697	5 11 9
		Cook-room	...	... ...	... ...	... ...	k p ... 0 0	do ...	do ...	...	310½	...
		Solitary cells	...	... ...	... ...	... ...	k p ... 0 0	do ...	do ...	2,000	483	4 2 3
		Female ward	single ...	... not	known	... 1 9	k p ... 9 3	do ...	do ...	1,000	1,540	0 10 4
		Hospital	do ...	Nil Nil	p ... 3 0	p ... 2 0	p ... 11 9	terraced ...	do ...	7,966	402½ / 305½ / 182	8 15 2
		Cook-room to do ...	do ...	... not	known	p ... 1 9	p ... 7 3	do ...	do ...			
		European ward	do ...	Nil Nil	p ... 3 0	p ... 2 0	p ... 11 9	do ...	do ...			
		Cook-house of Dewany Jail...	do ...	Nil Nil	p ... 3 0	... 2 0	k p ... 11 9	flat ...	mud ...	2,000	471½	4 3 11
		Do for female ward ...	do ...	Nil Nil	not known ...	... 1 9	k p ... 7 3	sloped ...	do ...	...	1,149½	...
		Jailor's room	do ...	... ...	do	... 1 9	k p ... 9 3	flat ...	p ...	...	271¼	...
		Constable's cook-room ...	do ...	... ...	do	... 1 9	k p ... 9 3	do ...	p ...		603¾	...
		Post Office	do ...	... ...	do	p ... 2 4	p ... 12 0	do ...	p ...	...	1,369¼	...
		Church	do ...	... ...	do	... 2 0	k p ... 23 6	do ...	p ...	8,181	5,040	1 9 11
		Out-offices	...	... ...	... ...	... ...	... ...	...	...	...	800	...
		Flag staff ghat	...	... ...	... ...	... ...	p ... 12 0	...	...	3,600	1,890	1 14 6
		Kutcherry or godown ghat ...	...	... ...	... ...	... ...	p ... 12 0	terraced ...	terraced ...	5,050	1,619¼	3 1 10
	Mahesh (Station).	Distillery	single ...	Nil Nil	p ... 1 6	p ... 1 6	p ... 9 0	flat and sloped	...	3,500	6,889 / 682½ / 259½	0 5 8
		Darogah's house... ...	do ...	Nil Nil	p ... 1 6	p ... 2 0	p ... 10 0	terraced ...	terraced ...			
		Spirit godown	do ...	... not	known	... ...	p ... 10 3	tiled ...	do ...			
	Grand Trunk Road.	Toll House at Mugrah ...	...	...	do	... ...	... ...	terraced ...	terraced ...	3,500	1,512 / 225 / 126	1 14 0
		Cook-room	...	— ...	... ...	... ...	p	thatch ...	do ..			
		Privy	...	... ...	... ...	.. ...	p	do ...	do ...			
		Post Office	single ...	... not	known	... ...	k p 13 6	thatched ...	do ...	1,661	2,829¾	0 9 4
		Out-offices	do ...	... ...	do	... ...	k p ... 8 9	do ..	do ...	346	1,326	0 4 2
		Road Chowkee at Pundooah...	do ...	... ...	do	k p ... 1 0	k p ... 14 0	terraced ...	do ...	854	522¾	1 10 1
		Stable	...	... ...	... ...	... ...	k p	thatched ...	bk-on-edge...	...	517	...
	Bansberriah (Station).	Police building	single ...	Nil Nil	... 2 0	... 1 6	k p ... mean 10 0	tiled ...	terraced ...	1,996	987	1 0 6
		Cook-room	do ...	Nil Nil	... 2 0	... 1 6	k p ... mean 10 0	do ...	do ...		192½	
		Constables' barrack and cook-room.	do ...	Nil Nil	... 2 0	... 1 6	k p ... mean 10 0	do ...	do ...		756	
	Ooterparah (Station).	Government School ...	double ...	... not	known	p ... 2 6	p ... 31 0	terraced ...	do ...	10,966	3,920	2 12 9
		Out-office	single ...	... ...	do	p ... 0 9	p ... 8 9	do	do ...	...	611½	...
		Post Office	do ...	Nil Nil	p ... 1 6	p ... 1 6	p ... 14 0	thatched ...	do ...	2,000	2,790	0 11 5
	Salkea (Station).	Salt Golahs Nos. 1 and 6 ...	do ...	Nil Nil	p ... 2 0	p ... 1 0	p ... 19 9	terraced ...	mud ...	6,48,446	7,040	1 7 8
		do Nos. 2 and 7 ...	...	... ...	... ...	... ...	p	do ...	do ...		9,309	
		do Nos. 3 and 8 ...	...	... ...	... ...	... ...	p	do ...	do ...		9,309	
		do Nos. 4 and 9 ...	...	... ...	... ...	... ...	p	do ...	do ...		9,309	
		do No. 5 ...	...	... ...	... ...	... ...	p	do ...	do ...		4,815	
		do Nos. 10 and 15 ..	...	... ...	... ...	... ...	p	do ...	do ..		9,309	
		do Nos. 11 to 19 ..	...	... ...	... ...	... ...	p	do ...	do ...		38,520	
		do Nos. 20, 25, 30...	...	... ...	... ...	... ...	p	do ...	do ...		15,768	
		do Nos. 21 to 24, 26 to 29, and 31 and 32.	...	... ...	... ...	... ...	p	do ...	do ...		48,150	

Executive Division.	Locality.	Name of Building.	Description and Height of Walls. Single or double storied.	Foundation. Concrete. Ft. In.	Foundation. Masonry. Average. Ft. In.	Plinth. Average. Ft. In.	Walls (to top of wall-plate). Ft. In.	Roof.	Floor.	Cost. Rs. A. P.	Area.	Rate per superficial foot. Rs. A. P.
	Salkea (Station).	Salt Golahs, Nos. 33, 36, 39...	...	...	...	...	...	p	terraced ...	mud ...	6,48,446 0 0	15,836	1 7 8
		do Nos. 34, 37, 40...	...	...	...	...	...	p	do ...	do ...		15,836	
		do No. 41 ...	...	...	...	...	...	p	do ...	do ...		6,105	
		do Nos. 35 and 38...	...	...	...	...	...	p	do ...	do ...		9,416	
		do Nos. 42, 45, 49...	...	...	...	...	...	p	do ...	do ...		13,910	
		do Nos. 43, 46, 50...	...	...	...	...	...	p	do ...	do ...		13,910	
		do Nos. 44, 47, 51...	...	...	...	...	...	p	do ...	do ...		13,910	
		do No. 48 ...	...	...	...	...	...	p	do ...	do ...		3,195	
		do Nos. 52, 54, 59...	...	...	...	...	...	p	do ...	do ...		13,910	
		do Nos. 53, 55, 60...	...	...	...	...	...	p	do ...	do ...		11,700	
		do Nos. 56, 57 ...	...	...	...	...	...	p	do ...	do ...		9,630	
		do Nos. 61, 66 and 71; 52, 67, 72; 58, 63, 68; 64, 69, 74; 65, 70, 75.	...	...	...	...	...	p	do ...	do ..		69,550	
		do No. 79 ...	...	...	...	...	...	p	do ...	do ...		4,815	
		do Nos. 73 and 78...	...	...	...	...	...	p	do ...	do ...		9,309	
		do Nos. 76, 80, 82, 77, 81, 83.	...	...	...	...	...	p	do ...	do ...		27,820	
		do E. G. I. and M....	...	...	...	...	...	p	do ...	do ...		21,300	
		Office of Superintendent ...	single ...	...	not known ...	...	p ... 1 0	p ... 15 6	do ...	stone		4,760	
		Out-office ...	do ...	...	... do ...	...	Nil Nil	p ... 10 6	do ...	terraced ...		1,586	
		S. shed on verandah ...	...	...	... ...	...	... ...	p	terraced ...	mud ...		8,400	
		Middle do ...	...	...	... ...	...	... ...	p	do ..	do ...		8,400	
		Weigh godown ...	...	...	... ..	...	... ...	p	do ...	terraced ...		650	
		Main Guard house ...	...	...	... ...	...	... ...	p	do ...	stone ...		5,166	
		do do small ...	...	...	... ...	...	... ...	p	do ...	terraced ...		925	
		Out-office	...	...	... ..	...	... ...	p	do ..	do ...		610	
		Distillery godown ...	single ...	...	Nil p ...	2 0	p ... 1 6	p ... 10 0	tiled ...	do ...	...	600	
		Guard house	...	...	... ...	...	... ...	durmah mats. ...	thatched ...	mud	335 0 0	450	0 4 5
		Magistrate's Court ...	double, and part 3 storied.	...	Nil p ...	3 0	p ... 3 0	p ... 39 6	terraced ...	tiled and ter	1,42,284 0 0	17,750	8 0 3
		2 Servants and cook-room east side.	...	...	no sections	...	... ...	p	do ...	terraced ...	2,379 0 0	793	3 0 0
		do west side ...	...	...	... do ...	...	... ...	p	do ...	do ...	2,457 0 0	819	3 0 0
		Latrine	...	...	... do ...	...	.. ...	p	do ...	do ...	1,383 0 0	735	1 14 1
		Magistrate's residence ...	double ...	...	Nil p ..	3 0	p ... 5 3	p ... 34 0	do ...	do ...	52,174 0 0	6,138	4 12 5
		Out-office, south side ...	...	...	no sections	...	... ...	p	do ...	do ...		1,365	
		do west do ...	...	...	... do ...	...	... ...	p	do ...	do ...		832	
		do north do ...	...	...	... do ...	...	... ...	p	do ...	do ...		1,365	
		do east do ...	...	...	... do ...	...	... ...	p	do	do ...		923	
		Durwan's room ...	...	...	... do ...	...	... ...	p	tiled ..	do ...		297	
		Jail.											
		Ward, Nos. 1 and 2 ...	No. 1 single	...	Nil p ...	2 0	p ... 2 0	p ... 10 6	terraced ...	terraced ...	740 0 0	3,920	0 3 0
			No. 2 do	...	Nil p ...	3 0	p ... 2 0	... 12 0	vaulted ...	...	...	...	...

Executive Division.	Locality.	Name of Building.	Single or double storied.	Concrete.	Masonry.	Plinth.	Walls.	Roof.	Floor.	Cost.	Area.	Rate per superficial foot.
Burdwan...	Howrah (Station).	Ward No. 3	single	Nil	p ... 2 0	p ... 1 0	p ... 10 6	vaulted ...	terraced ...	15,697 0 0	1,012	3 3 8
		do No. 4	do	Nil	p ... 2 0	p ... 1 0	p ... 10 6	do ...	do ...		989	
		do No. 5	do	Nil	p ... 2 0	p .. 1 6	p ... 9 9	do ...	do ...		616	
		do No. 6	do	Nil	p ... 2 0	Nil Nil	p ... 10 0	do ...	do ...		476	
		Condemned cell... ...	...	...	...	...	p	do ...	do ...		168	
		Guard-room	single	Nil	p ... 2 0	Nil Nil	p ... 7 6	do ...	do ...		715	
		Privy	...	...	...	...	p	do ...	do ...		170	
		Jailor's office and cook-room ..	single	Nil	p 2 0	Nil Nil	p ... 10 0	terraced ...	do		715	
		St. Thomas' Church	do	not	known	p .. 3 0	p .. 20 0	do ...	ter marble flags.	10,448 0 0	5,474	1 12 7
		Servant's Pantry room ...	... ..	...	... ...	... ...	p ..	do ...	terraced ...		299	
		do Goomty ...	... ...		... ...	... ...	p	do ...	do ...		64	
		New Burial Ground ...	single	not	known ...	p ... 2 0	p ... 12 6	tiled ...	do ...	13,121 0 0	1,098	11 15 2
		School	do	Nil	p ... 2 0	p ... 4 0	p ... 10 0	terraced ...	do ...	19,380 0 0	4,845	4 0 0
		do additional room ...	do	Nil	p ... 2 0	p ... 4 0	p ... 16 0	...	...	...	..	...
		Urinal attached to School ...	... ..	...	... ...	... ...	p	terraced ...	tiled ...	...	451	...
		Old Post Office	single	not	known ...	p ... 3 3	p .. 12 0	do ...	asphalt ...	1,576 0 0	818	1 14 9
		New do	do	Nil	p 2 6	p ... 2 6	p .. 16 6	do ...	terraced ..	9,880 0 0	2,628	3 2 9
		Out-office	do	Nil	p ... 2 0	p ... 1 3	p ... 10 0	do ...	do ...		483	
		Botanical Gardens.										
		Superintendent's house ...	double	not	known	... ...	p ... 35 9	do ...	do ..	59,136 0 0	7,392	8 0 0
		Out-office ...	single ...	...	... ...	p ... 1 6	p ... 12 0	do ...	do ...	17,100 0 0	11,400	1 8 0
		Head nursery man's house ...	... ...	...	... .	... ..	p	do ..	do ...	1,914 0 0	1,033½	1 13 8
		Out-office for do ...	... ...	...	... ...	... ...	k p	do ...	do ...	304 0 0	607¾	0 8 0
		Seed-house	double	Nil	p ... 1 6	p ... 3 0	p ... 29 0	ter and cor iron.	ter and as-phalt.	22,400 0 0	4,480	5 0 0
		Tool-house	single	Nil	p ... 1 3	p ... 0 9	p ... 10 0	tiled ...	brick on edge	267 0 0	357	0 12 0
		Gardener's store... ...	do	Nil	p ... 2 0	p ... 2 0	p ... 10 0	do ...	do ...	810 0 0	1,080	0 12 0
	Seebpore (Station).	Assistant Overseers' house ...	do	Nil	p ... 2 0	p ... 3 0	p ... average 14 ½	terraced ...	ter and tiles	11,280 0 0	2,900	3 14 3
		Cook-room and godown ...	do	Nil	p ... 2 0	p ... 2 0	p ... 10 0	do ...	do ...	2,044 0 0	954	2 2 3
		Propagatory shed ...	do	...	... ...	... ...	p	tiled ...	brick on edge	587 0 0	1,175	0 8 0
		Conservatory No. 1 ...	do	Nil	p ... 2 0	Nil Nil	do on posts 10 6	covered by creeper.	mud ...	1,158 0 0	3,090	0 6 0
		do Nos. 2, 3 ...	do	Nil	p ... 2 0	Nil Nil	do ... 10 6	thatched ...	do ...	1,027 0 0	2,733¾	0 6 0
		do No. 4 ...	do	Nil	p ... 2 0	Nil Nil	do ... 10 6	covered by creeper.	do ...	1,334 0 0	3,414	0 6 3
		Kids' Monument ...	... ...	...	... ...	... ...	p	domed ...	terraced ...	882 0 0	441	2 0 0
		Pucca Ghat	... ...	...	... ...	... ...	p	...	...	2,772 0 0	924	2 5 11
		Curators' house	double	2 0	p ... 2 0	p ... 2 6	p ... 26 8	terraced ...	Pucca ...	11,467 0 0	1,498	6 4 6
		Out office	single	1 6	p ... 1 6	p ... 1 3	p ... 9 9	do ...	do ...		327	
		Curators' servant's house ...	do	1 6	p ... 1 6	... 2 9	k p ... 9 8½	do ...	terraced ..	1,061 0 0	507½	2 1 5
		2nd Gardener's residence ...	do	Nil	p ... 2 0	p ... 3 0	p ... 16 0	do ...	do ...	8,639 0 0	2,341¼	3 11 0
	Juggutbul-lubpore (Station).	Police Station	double	not	known	p ... 1 0	p ... 24 6	do ...	do ...	5,323 0 0	1,950	2 11 8
	Chinsurah (Station).	Barracks, I, I, I, ...	single		do	p ... 1 6	p ... 10 6 mean	tiled ...	tiled ...	42,073 0 0	9,393	2 13 1
		do I	do		do	p ... 1 6	p ... 12 6	ter and tiles	terraced...		3,570	
		do I	do		do	p ... 1 6	p ... 13 6	do ...	do ...		1,960	
	Burdwan (Station).	*Criminal Jail.*										
		Male ward ...	single	not	known	p ... 1 3	p ... 12 0	vaulted ...	terraced ...	57,000 0 0	18,550	3 1 2
		Jailor's house ...	do	upper	floor only ...	... ...	p ... 16 0	terraced ...	do ...	6,551 0 0	2,123¼	3 1 4
		Cook-shed ...	do	not	known	Nil Nil	p ... 10 0	do ...	mud ...	1,330 10 10	2,266	0 9 4
		do ...	do	...	do	Nil Nil	terraced... 10 0	do ..	do ...	...	252	...
		Hospital ...	do	...	do	p ... 2 3	p ... 16 0	do ...	terraced ...	8,600 0 0	3,627	2 5 11
		do cook-shed ...	do	...	do	Nil Nil	p ... 7 4	do ...	mud ...	200 0 0	654½	0 4 10
		Female ward ...	do	...	do	p ... 1 3	p ... 12 0	do ...	terraced ...	...	1,128	...

Executive Division.	Locality.	Name of building.	Description and Height of Walls. Single or double-storied.	Foundation. Concrete. Ft. In.	Foundation. Masonry. Average. Ft. In.	Plinth. Average Ft. In.	Walls (to top of wall-plate).	Roof.	Floor.	Cost. Rs. A. P.	Area.	Rate per superficial foot. Rs. A. P.
Burdwan	Burdwan (Station).	Guard-room	single	not	known	p 2 0	p 12 6	terraced	terraced	5,000 0 0	1,642¼	3 0 8
		do godown	do		do	p 1 9	p 12 3	do	do		4,557	
		do	do		do	p 1 9	p 12 3	do	do		2,394	
		Six solitary cells	do	*Nil* *Nil*	p 2 0	p 1 0	p 13 0	do	kunkur and ter.	3,369 4 9	2,445	1 6 0
		Tank and ghat					p			3,600 0 0	10,800	0 5 4
		Compound wall					p				3,827¼	
		Judge's Court house	single	not	known	p 2 0	p 17 6	vaulted	terraced	27,763 4 3	14,028¾	1 15 8
		N. side attached	do		do	p 2 0	p 15 0	terraced	do	5,369 14 4	1,162	4 9 11
		Sub-Judge's Court house	do		do	p 2 0	p 18 0	thatched and er.	do	5,750 0 0	58,742	0 15 8
		Judge's English Office	do		do	p 2 0	p 17 6	terraced	do		1,890	
		do attached parches					p	do	do		212	
		do					p	do	do		185¼	
		Malkhana	single	not	known	p 1 0	p 9 9	do	do	1,231 2 1	877½	1 6 5
		Municipal Commissioner's Office	do	*Nil* *Nil*	p 3 0	p 3 0	p 17 0 side walls 11 feet.	sloping ter.	do	2,125 0 0	2,573½	0 13 2
		Magistrate's and Collector's Cutcherry.	do	*Nil*	p 3 0	p 4 0	p 20 0	sloping ter.	do	1,28,918 7 9	17,353½	7 2 8
		Attached Treasury	do	not	known	p 4 0	p 15 0	terraced	do		631½	
		Guard-room	do	*Nil*	p 4 0	p 5 0	p 10 0	do	do	unknown	1,620	
		Stable	do	not	known	*Nil* *Nil*	p 12 0	do	mud	100 0 0	665	0 2 4
		Cook shed	do	*Nil*	p 4 0	p 5 0	p 10 0	sloping ter.	do	179 4 1	236¼	0 12 1
		Joint Magistrate's and Police Court.	do	*Nil*	p 3 0	p 4 9	p 17 9	terraced	terraced	12,309 9 9	7,776	1 9 3
		Out-offices	do	not	known	p 1 0	p 9 10	do	do	659 6 2	1,145½	0 9 2
		do	do		do	p 1 0	k p 9 0	thatched	tiled	100 0 0	1,239½	0 1 3
		Circuit house	do		do	p 2 9	p 15 6	vaulted and ter.	terraced	16,500 0 0	8,616¼	1 14 7
		Out-offices	do		do	*Nil* *Nil*	p 9 6	terraced	do	3,208 3 10	2,838	1 2 1
		Charitable Hospital	do		do	p 2 0	p 10 0	vaulted	do	9,500 0 0	7,370	1 4 7
		Compound wall					p				1,032	
		Tank and Ghat					p			1,200 0 0	18,000	0 1 1
		Grave-yard wall					p			1,700 0 0	106½	1 9 8
		Burdwan Store Godown	single	*Nil*	p 3 0	p 1 0	p 9 6	vaulted and ter.	terraced	unknown	1,866	
		Post Office	do	*Nil*	p 2 0	p 1 0	p 11 6	thatched, vaulted and ter.	do	3,415 5 11	4,482	0 12 2
		Out-office	do	not	known	p 1 0	p 9 0	vaulted and thatched.	do	300 0 0	1,586	0 3 0
		Compound wall					p			150 0 0		
		Telegraph Office	p	*Nil*	p 3 0	p 3 0	p 14 0	terraced	terraced	7,293 12 8 including out-houses.	3,422¼	1 6 10
		Range of out-offices	p	*Nil*	p 3 0	*Nil* *Nil*	p 7 6	thatched	do		1,061¾	
	Cutwa (Station).	Godown	single	*Nil* *Nil*	p 2 0	p 1 0	p 9 6	terraced	terraced		282	
		Cook-room	do	*Nil* *Nil*	p 2 0	p 1 0	p 8 6	do	do	7,293 12 8	232½	1 6 10
		Wall					p				2,827	
		Sub-Registrar's Office	single	not	known		p 14 0	terraced	terraced	5,191 8 8	1,785¼	2 14 6
		Deputy Magistrate's dwelling-house.	do		do	p 2 0	p 16 6	do	do	unknown	3,599	
		Cook-house	do		do	*Nil* *Nil*	k 9 0	thatched	mud		620	
		Stable	do		do	*Nil* *Nil*	k 8 0	do	do		551	
		New Court-house	do	2 0	p 3 0	p 2 0	p 16 0	terraced	terraced	5,104 3 3	1,593	3 3 3
		Lock-up	do	not	known	p 1 6	p 15 0	do	do	unknown	1,033	
		Cook-house	do		do	p 0 9	p 10 0	do	do		107½	
		Compound wall					p				770	
		Cook shed	single		do	p 0 9	p 10 0	terraced	terraced		192	
	Culnah (Station).	Deputy Magistrate's dwelling-house.	do	*Nil* *Nil*	p 2 6	p 3 0	p 16 6	do	do	5,900 0 0	11,524	0 7 0
		Out-offices	do	*Nil* *Nil*	*Nil* *Nil*		p 5 6	do	do		640	
		do	do	*Nil* *Nil*	*Nil* *Nil*		p 8 6	do	do		1,287	
		Court-house	do	*Nil* *Nil*	p 2 0	p 2 0	p 16 0	do	do	unknown	3,850	
		Out-offices	do				p	do	do		240¼	
		Lock-up	do	*Nil*	p 3 0	p 3 0	p 14 6	do	do		1,010½	
		Cook-house	do	not	known	p 3 0	p 14 6	do	do		183¾	
		do	do		do	p 3 0	p 14 6	do	do		99¾	
		Compound wall					p				736	
	Jehanabad (Station).	Deputy Magistrate's Court house.	single	*Nil* *Nil*	p 1 6	p 2 0	p 16 0	terraced	terraced	231 0 6	1,883¾	0 1 11
		Do dwelling-house		not	known	not	known p 13 6	do	do	unknown	7,216	
		Compound wall					p				408	
		Lock-up	single	*Nil*		p 3 0	p 15 0	terraced	terraced		1,045	
		Out-houses	do	not	known	p 1 9	p 9 0	do	do		162¾	4 8 11
		do	do		do	p 1 9	p 9 0	do	do	8,468 0 0	99¾	
		Compound wall					p				549	
		Charitable Hospital	single	*Nil*	p 2 0	p 1 0	p 12 0	terraced	terraced	2,163 9 0	1,194	1 13 0
	Grand Trunk Road.	Gopalpore Inspection Bungalow.	do	*Nil*	2 0	1 0	k p 8 0	thatched	do	673 4 1¼	1,056¼	0 10 2
		Out-offices	do	*Nil*	1 6	*Nil* *Nil*	k p 8 0	do	mud	255 0 0	520	0 7 10
		Mohunpore Inspection Bungalow.	do	*Nil*	p 3 0	p 2 0	r 12 6	terraced	terraced	1,164 0 0	1,105	1 0 10
		Out-offices					r	do	do	217 12 7	809¼	0 4 3
	Bood Bood (Station).	Deputy Magistrate's Court and dwelling-house.	single	not	known	p 2 3	p 15 6	thatched	do		4,647½	
		Cook-room	do		do	1 0	k p 8 0	do	do	2,358 12 10	240	0 6 3
		Stable	do		do	*Nil* *Nil*	k p 8 0	do	mud		720	
		Servants' houses	do		do	0 6	k p 7 6	do	do		396	
		Treasury room	do	*Nil*	p 2 0	p 1 0	p 12 0	terraced	terraced	504 10 6	149	3 6 2
		Lock-up (male ward and hazut).	do	*Nil*	p 2 0	p 2 0	p 12 0	do	do		2,880	
		Female ward	do	*Nil*	p 2 0	p 2 0	p 12 0	do	do		704	
		Hospital	do	*Nil*	p 2 0	p 2 0	p 12 0	do	do		1,056¼	
		Cook shed female ward	do	*Nil*	p 2 0	p 2 0	p 12 0	do	do	5,806 8 8	192	0 12 8
		do Male ward	do	*Nil*	p 2 0	p 2 0	p 12 0	do	do		348	
		do Hospital	do	*Nil*	p 2 0	p 2 0	p 12 0	do	do		200	
		Guards' room	do	*Nil*	p 2 0	p 2 0	p 12 0	do	do		1,276	
		Dispensary	do	*Nil*	p 2 0	p 2 0	p 12 0	do	do		533¼	
		Moonsiffs' cutcherry	do	*Nil*	p 2 0	k p 3 0	k p 14 6	thatched	tiled	1,338 1 6	1,800	0 11 10

Executive Division.	Locality.	Name of Building.	Description and Height of Walls. Single or double storied.	Foundation. Concrete.	Foundation. Masonry.	Foundation. Average.	Plinth.	Plinth. Average.	Walls (to top of wall-plates).	Walls. Average.	Roof.	Floor.	Cost.	Area.	Rate per superficial foot.
				Ft. In.		Ft. In.		Ft. In.		Ft. In.			Rs. A. P.		Rs. A. P.
	Bood Bood (Station).	Police Station and out-houses	single ...	*Nil*	*Nil* ...	2 0	...	1 0	k p ...	12 0	terraced ...	terraced ...	1,657 0 0	1,769¼	0 15 0
		Bood Bood Inspection Bungalow.	do ...	*Nil*	*Nil* p ...	2 0	p ...	1 0	k p ...	8 0	thatched ...	do ...	712 0 0	1,056¼	0 10 9
		Out-offices	...	...	... ...	...	...	...	k p ...	...	do ...	do ...	187 0 0	809¼	0 3 7
	Raneegunge (Station).	Magistrate's dwelling-house	single ...	...	not known ...	...	p ...	3 0	p ...	16 0	terraced ...	do ...	6,680 0 0	6,440	1 0 7
		Out-offices	do ...	*Nil*	*Nil* p ...	4 0	*Nil*	*Nil*	p ...	10 0	do ...	do ...	496 0 0	715	0 11 1
		Stable	do ...	*Nil*	*Nil* p ...	1 6	p ...	1 0	p ...	11 6	do ...	do ...	296 0 0	500¼	0 9 5
		Court-House	do ...	...	not known ...	...	p ...	0 6	p ...	mean 14 0	do ...	do ...	6,387 0 0	4,125½	1 8 9
		Cook-room	do ...	*Nil*	*Nil* p ...	4 0	p ...	0 6	p ...	7 9	do ...	do ...	303 0 0	466⅔	0 10 4
		Stable	do ...	*Nil*	*Nil* p ...	4 0	p ...	1 0	p ...	11 9	do ...	do ...	565 0 0	500¼	1 2 0
		Jail Building	...	...	... ...	...	...	...	p ...	...	do ...	do ...	9,258 0 0	6,053	1 8 5
		Cook shed and	do ...	*Nil*	*Nil* p ...	3 0	*Nil*	*Nil*	p ...	7 0	do ...	do ...			
		Wards, &c.	do ...	*Nil*	*Nil* p ...	3 0	*Nil*	*Nil*	p ...	7 0	do ...	do ...			
		Police Station Building ...	do ...	*Nil*	*Nil* p ...	5 0	*Nil*	*Nil*	p ...	average 15 0	do ...	do ...	3,697 0 0	2,349	1 9 1
		Inspection Bungalow ...	...	...	... ...	...	...	...	p ...	...	thatched ...	do ...	2,150 0 0	2,196	0 12 2
		and Out-houses	...	...	... ...	...	...	...	p ...	...	do ...	do ...		...	
		Godown	...	...	... ...	...	...	...	k p ...	...	do ...	do ...		629	
		Church	single ...	*Nil*	*Nil* p ...	2 6	p ...	4 0	p ...	15 0	terraced ...	do ...	18,142 0 0	3,168	5 11 7
		Servants' house	do ...	*Nil*	*Nil* p ...	2 0	p ...	1 0	p ...	8 0	do ...	do ...	1,189 0 0	275	1 3 0
		Graveyard wall	...	...	... ...	...	...	...	p ...	...	...	...		723	
		Military graveyard wall ...	...	...	... ...	...	...	...	p ...	...	...	...	1,268 0 0	1,302	0 15 6
		Post Office	single ...	*Nil*	*Nil* p ...	2 6	p ...	1 0	p ...	12 6	terraced ...	terraced ...	2,297 0 0	1,457¼	1 4 10
		Cook-room	do ...	*Nil*	*Nil* p ...	2 6	p ...	1 0	p ...	9 9	do ...	do ...		190	
		Enclosure wall and privy ...	...	...	... ...	...	...	...	p ...	...	do ...	do ...		117	
		Telegraph Office... ...	single ...	*Nil*	*Nil* p ...	2 6	p ...	2 0	p ...	14 0	do ...	do ...	8,632 0 0	5,841	1 7 7
		Godown	do ...	*Nil*	*Nil* p ...	1 0	p ...	1 0	p ...	9 6	do ...	do ...		308⅔	
		Privy	do ...	...	not known ...	...	p ...	1 0	p ...	6 6	do ...	do ...		76⅓	
		Servants' house	do ...	*Nil*	*Nil* p ...	2 0	*Nil*	*Nil*	p ...	8 6	do ...	do ...	1,808 0 0	851⅔	0 11 0
		Cook-room	do ...	*Nil*	*Nil* p ...	2 0	*Nil*	*Nil*	p ...	8 6	do ...	do ...		232½	
		do houses	do ...	*Nil*	*Nil* ...	2 0	*Nil*	*Nil*	k ...	8 6	thatched ...	earth ...		1,042½	
		Well	...	...	... ...	...	...	...	p ...	...	...	...		113	
		Pucca buildings	single ...	...	not known ...	...	...	3 0	r ...	13 0	terraced ...	terraced ...	2,000 0 0	2,252½	0 14 2
		Out-houses	...	...	... ...	...	...	...	k ...	...	thatched ...	earth ...	50 0 0	630	0 1 3
		Toll house	single ...	...	not known ...	...	r ...	2 0	r ...	13 0	ter and cor iron	terraced ...	2,337 0 0	1,444	1 9 10
		Out do	...	...	not known ...	...	...	2 0	k ...	...	thatched	mud ...	89 0 0	600	0 2 4
	Burrakur (Station.)	Large Dâk Bungalow ...	do ...	...	not known ...	...	...	1 6	r (in mud)	16 0	do ...	terraced ...	2,000 0 0	6,075	0 5 3
		Out-house	do ...	...	... do ...	...	...	1 6	do ...	7 0	do ...	do and b l ...	200 0 0	1,627½	0 1 11
		do	do ...	...	... do ...	...	...	1 6	do ...	8 3	tiles and grass	earth ...	100 0 0	892½	0 1 9
		Overseer's bungalow	do ...	...	... do ...	...	...	1 6	do ...	14 0	thatched ...	terraced ...	625 0 0	652	0 15 4
		Out-house	do ...	...	... ...	...	...	...	do ...	...	do ...	earth ...	20 0 0	340	0 1 0
		Post Office	...	...	not known ...	...	...	2 0	do ...	11 0	do ...	terraced ...	1,000 0 0	1,776	0 9 6
		5th Class Post Office with enclosure wall.	do ...	*Nil*	*Nil* ...	3 0	...	2 0	r ...	11 0	terraced ...	ter and kunkur.	2,351 0 0	1,557½	1 4 6
	Assensole (Station.)	Out-offices	do ...	*Nil*	*Nil* ...	2 0	...	2 0	r ...	9 0	do ...	mud ...		275	

Executive Division.	Locality.	Name of Building.	Description and Height of Walls. Single or double storied.	Foundation. Concrete.	Foundation. Masonry.	Foundation. Average.	Plinth.	Plinth. Average.	Walls (to top of wall-plates).	Walls. Average.	Roof.	Floor.	Cost.	Area.	Rate per superficial foot.
Burdwan ...	Beerbhoom (Station).	Collector's Court ...	do ...	*Nil*	*Nil* p ...	1 6	p ...	4 0	p ...	mean. 19 0	flat ...	stone and tiles	45,154 0 0	21,925¾	2 0 11
		do Guard Room ...	do ...	...	not known ...	...	p ...	1 0	p ...	15 0	do ...	terrace ...	1,500 0 0	2,040	0 11 9
		Magistrate's Cutcherry ...	do ...	...	... do ...	...	p ...	2 0	p ...	20 4	thatched ...	do ...	12,000 0 0	7,385¾	1 9 11
		do Record Room ...	do ...	...	... do ...	...	p ...	1 0	p ...	12 6	vaulted ...	do ...	500 0 0	3,435	0 2 3
		Judge's new Cutcherry ...	do ...	*Nil*	*Nil* p ...	4 0	p ...	4 0	p ...	20 0	flat ...	stone and tiles	47,687 0 0	16,666¼	2 13 9
		School house	do ...	...	not known ...	...	p ...	1 3	p ...	15 10	do ...	terraced ...	7,500 0 0	7,070	1 0 11
		do residence ..	do ...	*Nil*	*Nil* p ...	2 0	*Nil*	*Nil*	k ...	11 9	thatched and tiled.	do ...	1,698 0 0	1,708¼	0 15 10
		do do out-office ...	do ...	...	not known ...	...	*Nil*	*Nil*	p ...	9 0	flat ...	do ...	96 0 0	727¾	0 2 1
		School godown No. 1 ...	...	...	... ...	...	...	...	k ...	...	thatched ...	mud ...	100 0 0	459	0 3 5
		do do No. 2 ...	single ...	*Nil*	*Nil* ...	1 0	*Nil*	*Nil*	k ...	9 6	do ...	do ...	75 0 0	566¾	0 2 1
		Jailor's quarters ...	double ...	...	not known ...	...	p ...	1 0	p ...	22 0	terraced ...	terraced ...	400 0 0	717¾	0 9 0
		Jail ward	single ...	...	... do ...	...	p ...	3 0	p ...	13 9	vaulted ...	do ...	66,740 0 0	17,728½	3 12 2
		Hajut cell in jail ...	do ...	*Nil*	*Nil* p ...	2 0	p ...	1 6	p ...	10 6	flat ...	do ...	3,150 0 0	906¾	3 7 6
		Jail out-office	do ...	...	not known ...	...	...	...	p ...	mean 8 0	terraced ...	mud ...	500 0 0	480¼	0 3 3
		do do							p ...		do ...	do ...		500	
		do do							p ...		do ...	do ...		464	
		do do							p ...		do ...	do ...		975	
		Jail Hospital	do ...	...	... do ...	...	p ...	3 0	p ...	13 9	do ...	tiled ...	5,275 0 0	1,514¾	3 7 8
		Guard Room	do ...	...	... do ...	...	p ...	3 0	p ...	13 9	do ...	terraced ...	500 0 0	4,071	0 2 0
		Jail tank ghat	...	...	... ...	...	...	...	p ...	...	...	...	740 0 0	1,051¼	0 11 3
		Old solitary cells ...	...	...	... ...	...	...	...	p ...	...	flat ...	terraced ...	276 0 0	298	0 13 10
		Circuit house	single ...	...	not known ...	...	p ...	1 6	p ...	15 6	terraced ...	do ...	16,000 0 0	9,487¾	1 10 11
		do godown	do ...	...	... do ...	...	*Nil*	*Nil*	p ...	6 3	do ...	do ...	250 0 0	411¼	0 9 8
		do Cook-room ...	do ...	...	... do ...	...	p ...	1 0	p ...	10 0	do ...	do ...	1,500 0 0	2,419	0 9 11
		do stable	do ...	...	... do ...	...	*Nil*	*Nil*	p ...	11 9	do ...	do ...	350 0 0	658¾	0 8 6
		Burial ground wall ...	...	...	... ...	...	...	...	p ...	...	...	...	1,000 0 0	855	1 2 8
		Post Office, 4th class ...	single ...	...	0 6 p ...	1 6	p ...	1 6	p ...	10 0	terraced ...	tiled ...	3,664 0 0	1,248¼	1 14 9
		Out-offices in compound ...	...	...	... ...	...	...	...	k p ...	...	do ...	terraced ...		287	
		Clerks' quarters... ...	single ...	...	0 6 p ...	1 6	p ...	1 6	k p ...	10 0	do ...	do ...		368	
		Church	do ...	...	1 0 p ...	2 0	p ...	2 0	p ...	16 9	tiled ...	ter and tiled	7,300 0 0	1,848	3 15 2
		4th class Post Office ...	do ...	*Nil*	*Nil* p ...	2 0	p ...	1 6	p ...	14 0	terraced ...	ter and kunkur.	3,260 0 0	1,972½	1 3 11
		Record Room	do ...	*Nil*	*Nil* p ...	2 0	p ...	1 6	p ...	14 0	do ...	do ...		272¼	
		Out-offices	do ...	*Nil*	*Nil* ...	2 0	...	0 6	k p ...	10 0	do ...	do ...		368	
		Shally Inspection Bungalow...	...	...	... ...	...	...	...	p ...	...	do ...	terraced ...	1,604 0 0	1,105	1 7 2
		Judge's Court-House ...	double ...	...	not known ...	...	p ...	2 0	p ...	29 0	flat ...	do ...	4,231 0 0	5,320	0 12 8
		Judge's and Magistrate's Record Room.	single ...	...	... do ...	...	p ...	1 0	p ...	12 0	arched ...	stone ...	680 0 0	5,360½	0 2 0
		Moonsiff's Court... ...	...	...	... ...	...	...	...	p ...	...	flat ...	terraced ...	7,189 0 0	11,664	0 9 10
		Magistrate's and Collector's Court.	single ...	...	not known ...	...	p ...	1 0	p ...	mean 14 0	do ...	stone ...	2,000 0 0	5,885	0 5 5
		Guards cook-room ...	...	...	... ...	...	...	...	p ...	...	do ...	mud ...	450 0 0	646¼	0 11 2
	Bancoora (Station).	Deputy Collector's Court ...	single ...	...	not known ...	...	p ...	2 0	p ...	mean 14 0	tiled ...	stone ...	1,700 0 0	3,245	0 8 4
		Record Room	do ...	...	... do ...	...	p ...	1 0	p ...	12 3	arched ...	terraced ..	800 0 0	2,416	0 5 3
		Treasury	do ...	...	... do ...	...	p ...	1 0	p ...	mean 14 0	flat ...	do ...	1,071 0 0	590¼	1 13 0
		Sub-Registrar's Court ...	do ...	...	... do ...	...	p ...	2 0	p ...	14 0	do ...	do ...	0 0 0	3,432	0 0 0
		Treasury Guard House ...	...	...	... ...	...	...	...	p ...	...	do ...	do ...	550 0 0	805	0 10 11
		Civil and Criminal Jail ...	double ...	...	... p ...	2 0	p ...	1 0	p ...	32 6	arched ...	stone ...	16,692 0 0	12,500	1 5 4
		Hindoo and Mahomedan Cook-room.	...	..	... ...	...	...	...	p ...	...	sloped ...	...	1,658 0 0	1,968	0 13 6
		Jailor's quarters... ...	upper story	*Nil*	*Nil* p ...	2 0	p ...	1 0	p ...	13 6	flat ...	terraced ...	...	1,464	...
		Guard Room	single ...	*Nil*	*Nil* p ...	2 0	p ...	1 0	p ...	12 3	do ...	stone ...	1,711 0 0	1,316	1 4 9
		Jail entrance and warders Room.	lower story	*Nil*	*Nil* p ...	2 0	p ...	1 0	p ...	12 3	do ...	do ...	4,279 0 0	1,543½	2 12 4

Executive Division.	Locality.	Name of building.	Description and Height of Walls.												Cost.	Area.	Rate per superficial foot.
			Single or double storied.	Foundation. Concrete.		Foundation. Masonry.	Average.	Plinth.	Average.	Walls (to top of wall-plate).		Roof.	Floor.				
							Ft. In.		Ft. In.		Ft. In.				Rs. A. P.		Rs. A. P.
Burdwan ...	Bancoora (Station).	Jail Hospital and female ward	single ...	*Nil*	...	not known ...		p ...	3 0	p ...	15 6	flat ...	stone ...		5,688 0 0	6,846	0 13 3
		Female Jail Hospital ...	do ...	...	not	known ...	...	p ...	4 1	p ...	10 11	thatched ...	mud ...		...	1,172½	...
		Proposed Jail guard-room ...	...	...	...	...	...	...	...	...	...	flat ...	stone ...		1,700 0 0	5,100	0 5 4
		Undertrial Jail	single ...	...	not	known ...	...	p ...	1 0	p ...	10 9	do ...	do ...		5,500 0 0	2,813	1 15 3
		Jail Superintendent's Office ...	double ...	*Nil*	p ...	...	2 0	p ...	1 0	p ...	25 9	do ...	terraced ...		...	4,860	...
		School	single ...	...	not	known ...	...	p ...	2 6	p ...	17 3	flat ...	do ...		2,233 0 0	7,854	0 4 6
		Head Master's quarters ...	do ...	...	...	do ...	...	p ...	2 0	p ...	10 0	do ...	do ...		1,182 0 0	4,914	0 3 10
		Out-offices	do ...	...	...	do ...	...	...	...	p ...	9 0	do ...	do ...		0 0 0	528	...
		Boarding house	do ...	...	...	do ...	...	p ...	2 0	p ...	9 9	do ...	do ...		1,900 0 0	1,100	1 11 8
		Circuit house	do ...	...	...	do ...	...	p ...	2 0	p ...	mean 14 1½	do ...	do ...		8,500 0 0	9,405	0 14 5
		Cook-house and servants' house.	do ...	...	...	do ...	...	p ...	1 0	p ...	9 9	do ...	do ...		...	2,124	...
		Stable	do ...	...	...	do ...	...	k ...	...	k ...	6 3	thatched ...	mud ...		780 0 0	1,562	0 8 0
		Watchman's house ...	...	...	...	...	...	...	...	...	...	terraced ...	terraced ...		...	143	...

L. ROBERTS, C. E.,

Executive Engineer, Burdwan Division.

Statement of construction, cost, and length of bridges exceeding 50 lineal feet in the Bengal Presidency.

Executive Division.	Name of bridge, or of river or nullah, and situation.	Date of completion.	Description of bridge.	Kind and depth of foundation.	No. and size of spans.	Width of roadway between parapets or railings.		Height of roadway above foundations or river bed.		Total length of bridge.		Total cost.	Cost per 100 feet of length.	Remarks.
						Ft.	In.	Ft.	In.	Ft.	In.			
Burdwan Division.	Poijoll Bridge ... ... Do Nullah in 25th mile on Calcutta and Jessore Road.	not known...	iron girder supported on two lime masonry piers. Roadway wooden.	lime masonry brick work. Depth of foundation unknown.	3 spans 21′ 6″ each.	20	6	13	3	74	6	Not known	Not known	
	Gyeghatta Boat-bridge in 37th mile, Calcutta and Jessore Road.	do ...	bridge-of-boats ...	unknown	7 openings, 10′ each.	12	0	17	0	145	0	do ...	do	
	Pullerghat Bridge over Mooktarsari River on 4th mile of Jessore and Bongong Road.	do ...	masonry bridge ...	... ...	2 spans of 6′ ...	18	0	18	9	92 r. ft.		...	do	
	Jhingergacha Bridge over Coboduck River on 10th mile, Jessore and Bongong Road.	do ...	iron suspension bridge ...	... ...	3 spans two sides, one 39′ and middle one 168′	9	0	26	0	385	0	...	do	
	Jadubpore Bridge over Betwa River, 12th mile.	do ...	masonry bridge ...	... ...	3 spans of 16 each.	17	6	21	0	116½	0	...	do	
	Jointipore Bridge over Hautkur River, 25th mile.	do ...	iron girder bridge on iron piles.	... ...	5 spans of 30′ each.	15	11	23	6	152	0	...	do	
	Hurrydaspore Bridge over Nabegunj River, 26th mile.	do ...	Iron girder bridge on wooden piles.	... ...	6 spans of 23¼′ each.	16	0	22	0	144	0	Not known	do	
	Bongong boat-bridge over Echamuty River, 28th mile.	do ...	iron pontoon ...	... ...	22 boats. They are placed 12′ apart.	11	0	This floats. The roadway above surface of water is 4′		442	0	do ...	do	

L. ROBERTS, C. E.,

Executive Engineer, Burdwan Division.

Statement of construction, cost and length of bridges exceeding 50 lineal feet in the Bengal Presidency.

1	2	3	4	5	5	7	8	9	10	11	12
Executive Division.	Name of bridge or of river or nullah and situation.	Date of completion.	Description of bridge.	Kind and depth of foundation.	No. and size of spans.	Width of roadway between parapets or railings.	Height of roadway above foundations or river bed.	Total length of bridge.	Total cost.	Cost per 100 feet of length.	REMARKS.
						Ft. In.	Ft. In.	Ft. In.	Rs.	Rs. A. P.	
Burdwan ...	Salle Bridge between Raneegunge and Bancoora between 12th and 13th mile stones on 19th mile of Raneegunge and Midnapore Road.	1858 ...	wooden	rubble masonry ...	4 spans of 31½′	12 4	23 0	141 0	3,500	2,482 4 4	...
	Grand Trunk Road.										
	Ballee Bridge between 6th and 7th miles.	not known	iron suspension ...	not known	1 span, 240′	16 0	35 0	250 0	30,000	12,000 0 0	...
	Bangur Khall between 11th and 12th mile stones, Old Grand Trunk Road.	do ...	pucca brick masonry ...	do	1 span 10 4″	21 0	14 10	71 9	1,000	1,393 11 4	...
	Bandel between 27th and 28th mile stones.	do ...	do ...	do	1 span, 30′	16 0	22 0	260 0	10,000	3,846 2 6	...
	Chenne between 58th and 59th mile stones.	1835 ...	do ...	do ...	3 spans, 8′	17 0	9 0	56 0	1,256	2,242 13 9	...
	Khargram Shaikpore between 61st and 62nd mile stones.	1850 ...	do ...	do	3 spans, 36′	22 0	22 0	227 6	10,945	4,811 0 0	...
	Khargram between 62nd and 63rd mile stones.	1849 ...	do ...	do	3 spans, 20′	22 0	17½ 0	150 0	4,724	3,149 5 4	...
	Burdwan Banka Bridge between 71st and 72nd mile stones.	1838 ...	do ...	do	5 spans— 4 of 22′ 6″; 1 of 33′	18 6	19 6	420 0	37,333	8,888 13 0	...
	Bagajorah between 121st and 122nd mile stones.	1849 ...	pucca brick and rubble stone masonry.	do	4 spans, 15′	22 3	17 0	72 0	8,512	11,822 3 7	...
	Singurran River between 122nd and 123rd mile stones.	not known	iron suspension ...	do	3 spans— 1′ 142″; 2′ 59¼″	16 0	29 0	286 0	28,043	9,804 3 2	Recently dismantled.
	Kundollah between 132nd and 133rd mile stones.	1861 ...	pucca rubble stone masonry.	do	2 spans, 20′	22 3	16 8	54 0	5,153	9,542 9 6	...
	Bagaband between 134th and 135th mile stones.	1849 ...	do ...	do	3 spans, 15′	21 6	11 0	63 0	2,426	3,850 12 8	...
	Nooniah between 134th and 135th mile stones.	1849 ...	iron suspension ...	do	3 spans— 1′ 142″; 2′ 59¼″	16 0	36 0	286 0	27,354	9,564 5 4	Recently dismantled.
	Satgong	not known	do ...	do	1 span, 82′	12 0	26 0	98 0	Not known	...	To be dismantled.
	Mugrah	do ...	wooden	wooden posts ...	9 spans— 8 14′ 3″; 1 20′ 9″	9 10	22 0	140 0	Do ...	...	Temporary bridge.
	Tomlah between 117th and 118th mile stones.	48–49 ...	iron suspension ...	masonry	3 spans— 1 85′ 0″; 2 23′ 9″	14 0	20 0	210 0	14,185	6,754 12 2	Recently dismantled.
	Burrakur 149th mile ...	not known	iron girder	masonry wells ...	9 spans, 133′	21 0	30 0	2,620 0	Not known	...	No records in this Division.

No. 391, P, W. D. Press—10-12-81—900.

W. P. MILNE, C. E., Assistant Engineer,
for Executive Engineer, Burdwan Division.

Enclosure to Circular No. XXIV Public Works.

Statement of Construction, Cost and Length of Bridges exceeding 50 lineal feet in the Bengal Presidency.

Executive Division.	Name of bridge, or of river or nullah, and situation.	Date of completion.	Description of bridge.	Kind and depth of foundation.	No. and size of spans.	Width of roadway between parapets or railings.	Height of roadway above foundations or river-bed.	Total length of bridge.	Total cost.	Cost per 100 feet of length.	REMARKS.
									Rs.	Rs.	
CIRCULAR AND EASTERN CANALS DIVISION.	*Bridges over Tollys Nullah.*										
	Hastings Bridge	1875-76...	Lattice girder ...	Masonry on concrete, and depth 20 feet.	1 span of 162 feet	24 feet, with 2 footpaths of 5 feet each.	Above foundation 16 feet.	174	1,46,264	84,000	
	Kidderpore do	1869-70...	Do ...	Do and depth 19′ 9″ ...	Do of 130 do.	24 feet, and 2 footpaths of 5 feet each.	Do 16 feet 6 inches.	140	1,17,343	83,800	
	Zeerut do	1856 ...	Warrens girder ...	Unknown ...	Do of 120 do.	19 feet ...	Do 14 feet	126′ 9″	Unknown	...	
	Allipore do	1862-63...	Plate girder on screw pile piers.	Do ...	3 spans; Centre... 74 6; End ... 53 3; Do ... 54 3; 182 0; 2 piers 10 0; 192 0	20 „ ...	34 feet above lowest bed.	199	56,739	28,512	
	Kally Ghat do	1823 ...	Suspension foot bridge	Masonry on piles 8½ feet depth.	1 span of 138 feet	8 „ ...	18½ feet above foundation.	141*	16,800	12,000	* Between points of suspension.
	Tallygunge do	1827 ...	Do bridge ...	Do 12 feet ..	Do of 101 do	14 „ ..	16 do	111†	24,300	21,900	† Do do
	Gurreah do	1828 ...	Do do ...	Do do ...	Do of 105 do	14 „ ...	14 do ...	114	17,596	15,435	
	Bridges over Circular Canal.										
	Chitpore Bridge	1834 ...	Suspension bridge ...	Not known ...	1 span of 99 feet	22 feet ...	34 feet above lock floor.	99	29,344	29,640	
	Barrackpore do	1870 ...	Lattice girder do ...	Do ...	1 do of 92′ 3″	20 feet, with 2 foot paths of 4 feet each.	18 feet above foundation.	99	52,869	53,403	
	Dum-Dum do	1831	Suspension do ...	Do ...	1 do of 100′	23 feet ...	15 feet do.	100	20,598	20,598	
	Ultadanga do	1842 ...	Do do	Do ...	1 do of 100′	18 „ ...	17 feet 9 inches do.	102	17,000	16,666	
	Manicktulla do	1830 ...	Do do ...	Do ...	1 do of 100′	18 „ ...	17 feet do.	100	15,576	15,576	
	Narkeldanga do	1830 ...	Do do ...	Do ...	1 do of 100′	18 „ ...	17 feet 9 inches do.	100	17,125	17,125	
	Balliaghatta do	1860 ...	Warren girder do ...	Do ...	1 do of 93′	18 „ ...	19 feet do.	104	33,399	32,114	
	Bridge over new canal.										
	New cut bridge	1859-60...	Warren girder bridge ...	Not known ...	1 span of 121′	18 feet ...	15 feet 9 inches above foundation.	134	44,187	32,975	

No. 391, P. W. D. Press—10-12-81—900.

H. JOLL,
Executive Engineer,
Circular and Eastern Canals Division.

PUBLIC WORKS DEPARTMENT, BENGAL.

Statement of Construction, Areas and Cost of Principal Buildings in the Bengal Presidency.

Abbreviations.—p, pucca; k p, kutcha pucca; p k p, pucca and kutcha pucca; d w, daub and wattle; cor, corrugated; d, dressed; ter, terraced; b l, brick-in-lime; b m, brick-in-mud; r, rubble; c r, coursed rubble; d s, dry stone; c, concrete; p s t, pent single tiled; p d t, pent double tiled; t, thatched; b f, brick flat; fl, flagged; in, inner; o, outer; u, upper; gr, ground.

Executive Division.	Locality.	Name of building.	Description and Height of Walls.													Cost.	Area.	Rate per superficial foot.
			Single or double storied.	Foundation. Concrete.		Foundation. Masonry.		Plinth.		Walls (to top of wall-plate). Ground.		Walls (to top of wall-plate). 1st floor.		Walls (to top of wall-plate). 2nd floor.		Roof.	Floor.			
																		Rs.		Rs.
1st Calcutta Division. 3rd Sub-Division.		*Imperial.*																		
		Paper Currency ...	three ...	unknown	Ft. In. unknown	unknown	Average. Ft. In. unknown	p	Average. Ft. In. 4 0	Ft. In. 22 0		Ft. In. 18 0		Ft. In. 22 0		arched ...	costic tiles and marble stone.	2,69,088	11,212	24
		do Hall ...	single ...	...	...	...	...	...	...	...		...		35 0		...	...	1,24,448	7,778	16
		Old Opium Godown ...	do ..	...	...	...	...	...	1 0			...		16 0		ter ...	bk-on-edge ..	unknown	84,187-6	
		University Main Building ...	do ...	...	3 0	...	10 6	...	4 10	40 0		...		...		do ...	stone ...	4,18,128	24,408	@ 17
Ditto ... 4th Sub-Division		Government House consisting of—																		
		South-East and South-West wings.	three ...	...	...	...	...	...	1 10½	14 5½		21 0½		22 5¼		do ...	ter ...	..	5,925	
		do corridors ...	...	...	...	...	...	...	1 8½	14 5¼		21 0		22 5½		...	...	...	849	
		North-East and North-West wings.	...	...	...	...	...	...	1 10	14 5½		21 0¾		22 5¼		...	...	...	4,720	
		do corridors	...	...	...	...	...	...	1 9	14 5½		21 0¼		22 5		...	...	...	849	
		Four staircase rooms ...	...	...	...	...	...	...	varying from 1-6 to 1-10	15 0		22 2¾		23 0		...	...	...	900	
		Centre portion ...	...	...	...	...	...	...	1-4 to 1-9	14 0		21 1		22 6		...	..	...	18,462	
		North Verandah ...	...	...	...	...	...	...	1 7	15 0		...		43 6		...	...	...	1,656	
		South do ...	...	...	...		...	...	1 8	14 9		...		43 0¾		...	...	14,17,522	1,440	
		Two hot water houses ...	...	...	...	...	...	...	mean 0 5	10 0		...		...		...	...	...	341	
		Malley's and Engineer's Godown No. 2.	single ...	...		...	...	...	1 6	13 10		...		...		...	...	...	205	
		Governor General's Body-guard house.	double ...	...	...	...	...	...	1 3	13 5		varying from 15 to 20½		...		...	bk-on-edge...	...	9,450	ground floor bk edge and 1 floor tiled.
		do Kitchen and Servants' quarters and coach-house.	do ...	...	...	...	...	...	0 6	varying from 14-6 to 18-9		10-0 to 15-0		...		...	do asphalted and tiled.	...	27,767	
		do Stable	do ...	...	...	...	...	...	1 0	do do 1st floor 16 to 21 & 13 gr floor		15 0		...		...	bk-on-edge...	...	2,270	
		General Treasury ...	...	...	...	...	...	...	Average 3 0	18 0		17 0		15 6		ter ...	ter, asphalted and stone.	97,371	6,388 9,879 3,440 946	
		Latrine for Europeans ...	...	...	...	...	...	...	0 6	10 1		...		...		...	ter ...	...	215	
		do for Natives ...	...	...	...	...	...	...	0 6	9 9		...		...		...	...	...	342	
		Legislative Council ...	...	...	...	...	...	...	2 0	15 6		20 9		11 9						
		Latrine	...	...	...	...	...	...	dismantled											
		Record rooms ...	...	..	...	...	...	...	1 6	15 7		11 9								
	Calcutta ...	Stable and coach-house ...	...	...	...	...	...	...	0 11	14 2		...		...						
		Loudon's Buildings— ...	three ...																	
		Home Office	...	...	...	...	...	...	2 9	15 6		17 5		14 6		ter	ter ...	...	5,140 2,408	
		Public Works Department...	...	...	...	...	...	...	3 0	14 2		17 3		14 2		...	...	...	14,417	
		Agriculture, Commerce and Revenue.	...	...	...	...	...	...	2 9	15 6		17 5		14 6		...	...	...	7,364	
		Coach-house and stable, &c., Public Works Department, Native Latrine.	single ...	...	...	...	...	...	0 6	11 9		...		...		...	bk-on-edge	...	mean. 3,393	one story used by P. W. Home and Agricultural Departments.
2nd Sub-Division.		South-West Latrine and Tiffin room.	do ...	...	...	...	...	...	0 6	varying from 11-9 to 12-9		...		...		...	ter ...	1,00,000 ...	1,046-6	
		Out-office, Public Works Department. do, Central, for the Home Office. do, Agricultural Department.	one block	...	...	...	...	...	2 0	14 9		...		...		...	...	...	9,006	
		North-West Latrine ...	...	...	...	...	...	...	0 6	11 9		...		...		...	...	...	792	
		Foreign Secretariat ...	three ...	...	...	...	...	...	1 9	15 1		20½		14 1½		ter ...	ter ...	...	6,288	
		Record Office	single ...	...	...	...	...	...	1 3	15 3		...		...		...	...	...	4,355-8	
		Coach-house	do ...	...	...	...	...	...	0 6	16 3		...		...		...	bk-on-edge...	...	496-7	
		Printing Office, Centre ...	do ...	...	...	...	...	...	1 6	varying from 14-5 to 15-3		...		...		...	ter ...	...	1,348-6	
		do East ...	do ...	...	...	...	...	...	1 6	14 10		...		...		...	...	...	1,277-10	
		do do ...	do ...	...	...	...	...	...	1 6	14 9		...		...		...	asphalted and ter.	...	2,093-5	
		Library	double ...	...	...	...	...	...	0 6	9 10		18¼		...		...	...	99,600	799-6	
		Durwan's room ...	single ...	...	...	...	...	...	1 3	16 6		...		...		...	...	...	178-4	
		Persian Library ...	double ...	...	...	...	...	...	1 6	9 6		12 10		...		...	...	...	561-1	
		Cook-room	single ...	...	...	...	...	...	1 3	14 9		...		...		ter ...	asphalted and ter.	...	897-8	
		Stables	do ...	...	...	...	...	...	...	9 6		...		...		...	bk-on-edge	...	480-1	
		Latrines	do ...	...	...	...	...	...	1 3	13 7		...		...		...	cement ...	...	1,080	
		Toshakhannah	double ...	...	...	...	...	...	1 9	9 9		16 9		...		...	ter ...	...	1,455-8	
		do	do ...	...	...	...	...	...	1 9	9 3		10 0		...		...	...	...	1,214-9	
		New Opium Godown ...	single ...	...	...	...	...	...	2 0	28 3		...		...		ter ...	bk and ter...	1,77,010	49,675-6	
		New Post Office Main Building.	...	...	...	...	...	...	3 6	22 9		26½		...		...	ter and stone	...	32,026	
		do do ...	...	...	...	...	...	...	3 6	23 2		25 9		...		...	...	...	3,375	
		do do ...	...	...	...	...	...	...	3 6	23 3		25 11		...		...	...	...	20,662-6	
		Main gates	...	...	...	...	...	...	...	mean 15 9		...		...		...	...	...	325-6	
		do	...	...	...	...	...	...	...	mean 16 10		...		...		...	...	...	243-3	
		Range of out-houses for servants.	...	...	...	...	...	...	1 6	13 6		...		...		...	ter ...	6,30,510	3,703-2	
		Vans, Stables and Banghy Department.	...	...	...	...	...	...	1 5	average 12 9		...		...		...	do and bk-on-edge		3,566-3	
		Latrines and Vans and Store room.	...	...	...	...	...	...	1 6	average 12 10		...		...		...	...	...	3,744-11	
		do do ...	...	...	...	...	...	...	1 5	average 12 9		...		...		...	bk-on-edge...	...	2,953-6	
		do do ...	...	...	...	...	...	...	1 6	average 13 3		...		...		...	...	...	2,303	
		do do ...	...	...	...	...	...	...	1 5	12 10		...		...		...	...	...	384	
		New Telegraph Building ...	three ...	...	...	...	...	...	4 6	21 2		24 6		18 0		ter ...	patent stone tiles, and asphalted over terrace.	7,23,566	27,958	

Executive Division.	Locality.	Name of Building.	Description and Height of Walls. Single or double-storied.	Foundation. Concrete.	Foundation. Masonry.	Plinth.	Wall (to top of wall plate).	Roof.	Floor.	Cost.	Area.	Rate per superficial foot.
				Ft In.	Ft. In.	Ft. In.	Ft. In.			Rs.		
1st Calcutta Division. 5th Sub-Division.	*Imperial*—continued. Barrackpore	Government House	double ...	...	... p ...	2 3 p ...	1 3 p ...	36 6 ter ...	ter and cement	..	31,525	
		House No. 1	single ...	...	... p ...	4 0 p ...	1 10 p ...	17 7 do ...	do ...	...	10,031	
		do No. 2	do ...	...	... p ...	4 0 p ...	1 10 p ...	17 7 do ...	do ...	...	10,031	
		do No. 3	do ...	...	... p k p ...	3 0 p k p ...	1 6 p k p ...	15 9 do ...	ter, cement and asphalte.	...	7,785	
		Kitchen	do ...	...	... p ...	4 0 p ...	0 7 p ...	16 9 do ...	ter and stone	...	4,843	
		Flag staff house	do ...	...	... p k p ...	2 0 p k p ...	2 6 p k p ...	18 9 do ...	ter ...	...	10,253	
		Band Master's house	do ..	...	.. p ...	2 4 p ...	2 6 p ...	18 3 do ...	do and cement	...	2,602	
		Cenatoph	do ...	...	0 3 p ...	4 0 p ...	5 0 p ...	20 0 Stone ...	vaulted ...	...	3,667	
		Survey Tower	four	...	... p ...	3 10 p ...	1 0 p ...	59 2 ter ...	brick-on-edge	...	415	
		Band Barrack	double ...	...	0 4 p ...	3 1 p ...	4 4 p ...	29 10 do ...	stone and tiled	...	5,260	
		Park Superintendent's house ...	single ...	...	... k p ...	2 0 k p ...	2 8 k p ...	13 10 do ...	ter, asphalte and cement.	...	3,096	
		Dhobee house	do ...	...	... k p ...	2 8 k p ...	1 11 k p ...	13 3 do ...	tiled ...	...	1,899	
		Coachman's house	do ...	...	0 4 p ...	2 8 p ...	2 7 p ...	17 3 do ...	ter and cement	...	1,799	
		Old Menagerie	do ...	...	... p ...	4 0 p ...	... p ...	10 0 do ...	tiled ...	...	3,864	
		New "	do ...	...	... p ...	2 1 p ...	0 11 p ...	9 0 do ...	do ...	...	4,294	
		Old Aviary	do ...	...	... p ...	3 10 p ...	.. p ...	14 8 do ...	do and tiled	..	3,965	
		New do	do ...	...	... p ...	2 4 p ...	0 6 p ..	12 3 do ...	tiled ...	...	7,870	
		Stable No. 1	do ...	...	... p ...	2 10 p ...	... p ...	16 8 do ...	b l ..	...	9,840	
		do No. 2	do ...	...	... p ...	0 11 p ..	1 1 p ...	14 11 do ...	do ...	..	1,622	
		do No. 3	do ...	...	0 6 p ...	1 0 ...	... p ...	7 3 t ...	mud ...	...	4,530	
		do No. 4	do ...	...	... p ...	1 6 ...	... p ...	6 6 p s t ...	brick and mud	...	2,252	
		Seed house ...	...	...	... p ..	2 6 p ...	4 3 p ...	13 5 ter ...	ter and tiled...	...	3,541	
	Belgurriah ...	Stable at Belgurriah	...	...	... p ...	3 3 p ..	... p ...	13 3 do ...	b l ...	...	4,893	
		do bungalow at do	...	..	... p ...	3 3 p ...	... p ...	13 0 do ...	ter ...	...	1,750	

W. H. NIGHTINGALE, C. E.,

Executive Engineer, 1st Calcutta Division.

Executive Division.	Locality.	Name of building.	Description and Height of Walls. Single or double storied.	Foundation. Concrete.	Foundation. Masonry.	Plinth.	Walls (to top of wall-plate). 2nd.	Walls (to top of wall-plate). 1st.	Walls (to top of wall-plate). Ground.	Roof.	Floor.	Cost.	Area.	Rate per superfical foot.
1st Calcutta Division.		*Provincial.*			Average.	Average.								
				Ft. In.	Ft. In.	Ft. In.	Ft. In.	Ft. In.	Ft. In.			Rs.		Rs. A. P.
3rd Sub-Division.		Police Lock-up ...	double ...	unknown	unknown unknown	unknown p ...	3 0 ...	16 0	16 0	flat ter ...	ter, p c and bk-edge.	41,160	5,880	@ 7 0 0
		do Magistrate's Court ...	three ...	...	... ...	... ...	... 19 0	18 0	8 0	ter ...	ter, tiled, boarded and p c.	unknown	10,814	
		St. Andrew's Church ...	single ...	...	... ...	... ...	... 5 0	...	...	34 0	do ...	arched and marble.	1,02,915	11,435	9 0 0
		Economic Museum ...	do ...	...	... ...	... ...	... 3 0	.	...	19 0	do ...	bk-on-edge	13,779	2,716	5 0 0
		Custom House	double ...	...	... ...	... ...	... 1 0	...	19 0	21 0	do ...	stone, ter and bk edge.	1,55,250	17,250	9 0 0
		do Double range	single ...	...	... ...	... ...	... 1 6	...	...	18 0	do ...	bk-on-edge...	92,796	15,466	6 0 0
		N godown ...	...	...	... ...	... ...	... 1 0	...	...	15 0	do ...	do	41,485	8,297	5 0 0
		W of D R Godown ...	...	...	... ...	... ...	... 1 0	...	...	14 0	do & iron	do ...	49,350	9,870	5 0 0
		West shed ...	...	...	... ...	... ...	... 1 0	...	...	11 6	ter ...	do ...	62,940	15,735	4 0 0
		Assistant Collector's residence	double ...	...	... ...	... ...	... 1 9	...	15 0	14 0	do ...	ter ...	39,057	5,978	6 8 0
		East of above	...	...	... ...	... ...	... 1 0	...	...	14 0	...	bk-on-edge...	83,860	16,772	5 0 0
		W of Main Building ...	...	...	... ...	... ...	... 1 0	...	...	14 0	...	...	11,890	2,378	5 0 0
		W of A C's residence ...	...	...	... ...	... ...	... 1 0	...	..	11 0	...	...	46,880	11,720	4 0 0
		S of E shed No. 1 ...	...	...	... ...	... ...	... 1 0		...	11 0	...	...	50,464	12,616	4 0 0
		Writers' Building ...	three ...	...	... ...	... ...	... 1 6	15 0	17 0	16 0	...	ter ...	3,62,880	22,680	16 0 0
		do New No. 1	do ...	...	... ...	... ...	... 2 6	15 0	17 0	16 0	...	stone and sills patent tiles.	unknown	15,336	
	Calcutta ...	do do No. 2	...	...	... ...	... ...	...	...	...	...	...	...	...	11,557
		do do No. 3	...	...	... ...	... ...	...	...	...	...	...	...	...	10,414
		Medical College, consisting of residence of Principal.	partly three	...	... ...	... ...	... 0 6	13 8	16 6	14 3	ter ...	ter ...	36,590	3,659-8	10 0 0
		Student's quarter ...	double ...	...	... ...	... ...	... 2 0	12 0	16 6	...	do ...	do and tiled	1,992	332-5	6 0 0
		do Superintendent's quarters.	do ...	...	... ...	... ...	... 2 0	12 0	16 6	...	do ...	do ...	13,272	2,272-3	6 0 0
		Staff Surgeon's quarter ...	do ..	...	... ...	... ...	... 2 0	12 0	16 6	...	do ...	do ...	10,074	1,679-3	6 0 0
		N. Students' quarters .	single ...	...	... ...	... ...	... 2 0	12 0	...	...	do ...	do ...	22,109	7,491-6	3 0 0
4th Sub-Division.		Office Building Library ...	double ...	...	... ...	... ...	... 2 0	12 0	16 9	...	do ...	do ..	65,736	10,906-11	6 0 0
		Museum Building ...	single ...	...	... ...	... ...	... 4 6	18 0	...	...	do ...	do ...	40,520	8,104-11	5 0 0
		Resident Surgeon's and Purveyor's quarter.	double ...	...	... ...	2 0 ...	1 6	13 3	14 3	...	do ...	do ...	15,588	2,598-7	6 0 0
		Resident Physician and Apothecaries' quarter.	do ...	...	... ...	2 0 ...	1 6	13 3	14 3		do ...	do ...	22,800	3,800	6 0 0
		Medical College Hospital Main Building.	three ...	...	... ...	unknown ...	3 0	7 9	22 6	23 6	do ...	do and stone	1,54,448	9,653	16 0 0
		Chooney Lall Seal's Dispensary.	single ...	...	... ...	2 4 ...	1 8	16 6	...	...	do ...	ter ...	23,255	4,650-9	5 0 0
		Presidency College old Main Building.	double ...	...	... ...	... ...	3 8	16 3	19 9	...	do ...	cemented ...	...	12,000	unknown.
		East wing of do ...	single ...	...	... ...	... ...	4 0	22 0	...	...	do ...	do ...	1,852	6,240	3 0 0
		West wing of do ...	do ...	...	... ...	... ...	4 0	22 0	...	...	do ...	do ...	1,852	6,240	3 0 0

Executive Division.	Locality.	Name of building.	Description and Height of Walls. Single or double storied.	Foundation. Concrete.	Foundation. Concrete. Ft. In.	Foundation. Masonry.	Foundation. Average. Ft. In.	Plinth.	Plinth. Average. Ft. In.	Walls (to top of wall-plate). Ft. In.	Walls (to top of wall-plate). Ft. In.	Walls (to top of wall-plate). Ft. In.	Roof.	Floor.	Cost. Rs.	Area.	Rate per superficial foot. Rs. A. P.
1st Calcutta Division—contd.		*Provincial*—contd.															
	Calcutta	Presidency College—*contd.*											ter ...	cemented ...	11,010	3,870	@ 3 0 0
		East detached wing ...	single ...	unknown	unknown	unknown	unknown	p ...	2 0	20 0	...	...	do ...	do ...	11,010	3,870	3 0 0
		West do ...	do ...	...	...	...	...	...	2 0	20 0	...	16 0	do ...	stone ...	3,26,805	34,638	9 0 0
		Presidency College, New ...	three ...	...	...	...	...	...	2 8	18 6	18 6	...	do ...	cemented ...	22,707	75,693-3	3 0 0
		Old Hare School ...	single ...	...	...	...	...	...	2 6	11 6	...	...	do ...	stone ...	1,08,098	12,469	9 0 0
		Colootolah Branch School ...	double ...	...	3 0	...	10 0	...	1 6	18 0	20 6	...	do ...	ter and cemented.	30,632	6,640	6 0 0
		Bethune School ...	single ...	...	...	...	2 0	...	7 6	22 0	...	...	do ...	do ...	19,292	4,189	6 0 0
		Lady Superintendent's House	double ...	...	...	...	unknown	...	4 6	14 9	15 0	...	do ...	ter ...	34,400	5,630	7 0 0
		Small Cause Court ...	do ...	...	...	...	...	...	4 0	12 3	14 9	...	do ...	tiled ...	27,400	3,751-6	9 0 0
		Resident of the Superintendent of Campbell Hospital.	do ...	...	...	...	...	...	5 3	13 6	16 0	...	do ...	ter ...	31,698	4,538-6	8 0 0
		Police Court ...	do ...	...	...	...	...	...	4 9	13 0	16 0	...	do ...	do ...	17,513	2,621	8 0 0
		Lock Hospital ...	do ...	...	...	...	...	...	2 3	12 9	15 0	...	do ...	do ...	16,115	6,863	3 0 0
	Sealdah	Deputy Superintendent's quarter, Campbell Hospital.	single ...	...	...	...	...	...	2 9	12 6	...	...	cor ...	bk-on-edge and stone.	66,136	16,534	4 0 0
		Campbell Medical School ...	do ...	...	...	...	2 6	...	2 3	28 0	...	...	do ...	ter ...	5,200	1,325	4 0 0
		Lecture Theatre, No. 1 ...	do ...	...	...	...	2 0	...	2 0	11 0	...	...	do ...	do ...	26,500	2,650	10 0 0
		od No. 2 ...	do ...	...	2 0	...	6 3	...	3 6	31 0	...	...	vaulted ...	do ...	19,352	4,838	4 0 0
		Small Pox Hospital for Natives.	do ...	...	2 0	...	2 6	...	3 0	15 0	...	...	do ...	do ...	7,812	1,302	6 0 0
		do for Europeans ...	double ...	...	unknown	unknown	unknown	...	...	13 6	14 0	...	ter ...	ter ...	6,080	760	8 0 0
4th Sub-Division—*contd.*	Manicktolah	Manicktollah Distillery Ento	do ...	...	...	...	...	...	2 3	11 3	12 0	...	do ...	do and boarded.	...	10,731-4	
		Revenue Board Office ...	three ...	...	...	...	...	...	1 11	18 0	19 9	18 6		bk-on-edge...	...	1,295-11	
		Stables, North side ...	...	...	...	...	...	...	1 3	13 0	...	...	...	...	...	1,779-10	
		Privy and Urinals ...	...	...	...	...	...	...	2 6	13 3	...	...	...	...	...	740-9	
		Coach-house and Servants' room and Tiffin room.	single ...	...	...	...	...	...	...	13 1	...	...	...	...	1,85,172	3,986-7	
		Record-keeper's godown, coach-house.	do ...	...	...	...	...	...	...	13 0	...	...	...	...	...	2,342-8	
		Durwan's Lodge ...	do ...	...	...	...	...	...	1 3	13 0	...	...	...	...	...	156-3	
		do do ...	do ...	...	...	...	...	...	0 9	13 0	...	...	...	...	...	156-3	
		New High Court ...	...	...	...	...	...	...	3 0	25 3	29½ 0	20 0	pent roof of cor iron.	stone paving	17,99,114	1,02,000	
		Northern out-offices to do ...	...	...	...	...	...	...	3 0	10 3	...	...	flat ter ...	bk-on-edge and paving.	7,866	2,128	
		Western do ...	...	...	...	...	...	...	3 0	14 0	...	...	...	...	9,187	2,415	
		Latrines to do ...	...	...	...	...	...	...	1 3	10 3	...	...	...	...	3,977	960	
		New Court of Small Causes	...	...	...	...	...	...	3 0	16 6	23 9	25 3	ter on iron girders and joists.	stone in public room, asphalte in Offices on beaten ter on iron girder and T joists.	...	17,168	This does not include a flight of steps to entrance.

Executive Division.	Locality.	Name of building.	Single or double storied.	Foundation. Concrete.	Foundation. Concrete. Ft. In.	Foundation. Masonry.	Foundation. Average. Ft. In.	Plinth.	Plinth. Average. Ft. In.	Walls (to top of wall-plate). Ft. In.	Walls (to top of wall-plate). Ft. In.	Walls (to top of wall-plate). Ft. In.	Roof.	Floor.	Cost. Rs.	Area.	Rate per superficial foot. Rs. A. P.
2nd Sub-Division.	Calcutta	Coach-house and stables ...	...	...	...	...	...	...	...	15 4½	...	...	ter on wooden beams	bk-on-edge .	3,17,200	1,960	
		Sale rooms, godown, &c. ...	...	...		...	...	...	2 0	13-5 to 14-0	...	...	...	tiles and asphalted.	...	7,420	
		Privies and urinals ...	...	...	...	...	...	...	0 11	14 7	mean ..	...	...	bk-on-edge...	...	1,460	
		Stamp Office, Main Building	...	...	...	...	...	...	1 6	16 9	17 0	14 3	ter ...	do ...		2,131-4	
		do do ...	...	...	...	...	...	...	...	...	...	...	...	...		4,503	
		do do ...	...	...	...	...	...	...	...	...	...	...	...	ter ...		319-4	
		do do ...	...	...	...	...	...	...	...	...	...	...	...	boarded ...		8,097-2	
		do do ...	...	...	...	...	...	...	...	...	...	...	...	asphalted ...		142-1	
		North ranges, east ...	...	...	...	...	...	...	1 6	12 6	19½	...	...	do ...		7,951-6	
		do west ...	...	...	...	...	...	...	0 6	11 0	13 11	...		do ...		1,909-6	
		Servants' house and urinals...	...	...	...	...	...	...	0 6	10 0	...	...	...	ter and bk-on-edge.		801-10	
		Duftrys' room ...	...	...	...	...	...	...	1 6	11 6	...	...	...	ter	3,49,570	1,073-6	
		Godown, west ...	...	...	...	...	...	...	0 6	14 3	...	...	...	do ...		2,254-6	
		do ...	...	...	...	...	...	...	0 6	14 3	...	...	...	do ...		293-8	
		Babus' Tiffin room ...	...	...	...	...	...	...	...	10 0	...	...	tiled ...	rubbish ...		425-7	
		Coach house and stables ...	...	...	...	...	...	...	...	12 3	...	...	khoa ..	do ..		1,436-10	
		do ...		...	...	...	...	...	...	12 3	...	...	...	do ...		181-3	
		Store Godown, No. 1 ...	...	...	...	...	...	...	0 6	12 3	15 2	...	...	bk-on-edge...		4,550	
		do do 2 ...	...	...	...	...	...	...	0 6	12 3	15 2	...	...	do ...		2,961	
		do do 3 ...	...	...	...	...	...	...	0 6	12 3	15 1	...	...	do ...		1,119-8	
		do do 4 ...	...	...	...	...	...	...	0 6	12 3	15 7	...	...	do ...		913-6	
		do do 5 ...	...	...	...	...	...	...	0 6	12 3	15 7	...	...	do ...		403	
		Calcutta Collectorate, Main Building.	...	...	...	...	...	...	1 0	16 9	17 0	14 3	ter ...	partly ter and asphalted.	...	2,161	
		do do ...	...	...	...	...	...	...	1 0	16 9	17 0	14 3	...	cemented ...	...	2,001	
		do do ...	...	...	...	...	...	...	1 0	16 9	17 0	14 3	...	do ...	...	1,368	
		St. John's Church, Main Building.	...	...	...	...	...	...	4 9	14 0	21 3	...	ter ...	ter, stone and marbled.		12,080	
		do N. S. verandah	...	...		...	...	...	4 9	36 3	...	...		do ...		1,752-9	
		West portico ...	...	...	...		...	...	4 9	20 6	...	...	...	do ...		1,396-6	
		East godown ...	...	...	...	...	...	...	4 9	...	...	...	...	khoa ...	1,95,946	1,207	
		West „ ...	...	...	...	...	...	...	4 9	13 0	22¼	...					
		Palki shed ...	...	...	...	...	...	...	1 3	10 9	...						
		Iron and wooden rail on compound wall with gateway ...	...	...	...	...	...	...	2 9	7 9 / 10 0	... / ...	... / ..	ter ...	ter ...		2,373	
		House No. 3, Koilah Ghaut Street.	...	...	...	...	...	...	0 6	13 2	17 0	...	do ...	do ...	...	4,401	
5th Sub-Division.	Barrackpore	Government School ...	...	...	...	p ...	2 3	p .	2 0	p ...	p ...	15 7	do ...	ter and cement.	...	2,940	
		Magistrate's Court ...	...	...	...	p k p...	5 1	p k p...	0 7	p k p ...	p k p ...	16 10	do ...	stone and asphalt.	...	5,064	
		Police Building ...	...	...	...	k p ...	1 11	k p ...	3 8	k p ...	k p ...	12 9	do ...	ter ...	...	1,798	

W. H. NIGHTINGALE, C. E.,

Executive Engineer, 1st Calcutta Division.

Statement of Construction, Cost, and Length of Bridges exceeding 50 lineal feet in the Bengal Presidency.

Executive Division.	Name of bridge, or of river or nullah, and situation.	Date of completion.	Description of bridge.	Kind and depth of foundation.	No. and size of spans.	Width of roadway between parapets or railings.	Height of roadway above foundations or river-bed.	Total length of bridge.	Total cost.	Cost per 100 feet of length.	REMARKS.
1st Calcutta Division.	*Nil*	*Nil*	*Nil*	*Nil*	*Nil*	*Nil*	*Nil*	*Nil*	*Nil*	*Nil*	*Nil*

W. H. NIGHTINGALE, C. E.,

Executive Engineer, 1st Calcutta Division.

Executive Division.	Locality.	Name of building.	Description and Height of Walls.													Cost.	Area.	Rate per superficial foot.
			Single or double storied.	Foundation.				Plinth.		Walls (to top of wall-plate).				Roof.	Floor.			
				Concrete.		Masonry.												
					Ft. In.		Average Ft. In.		Average. Ft. In.	Ft. In.		Ft. In.	Ft. In.			Rs.		Rs. A. P.
		Orphan Asylum School.																
2nd Calcutta Division.	Khidderpore	Main Building ...	three ...	...	...	...	...	p ...	0 9	8 0		19 3	18 9	terraced ...	terraced ...	1,18,142	12,436	9 8 0
		Secretary's House ...	double ...	...	...	p ...	2 0	p ...	1 10	15 0		17 0	...	do ...	tiled ...	35,259	5,825	6 1 0
		Hospital	do ...	...	...	...	...	p ...	1 0	12 0		11 0	...	do ...	terraced ...	22,380	4,476	5 0 0
		Telegraph store yard.																
	Alipore ...	Cable machinery shed ...	single ...	...	...	...	...	p ...	1 0	15 0		...	...	do ...	bk-on-edge ...	16,090	1,462	10 15 0
		Instrument room ...	double ...	...	...	...	...	p ...	2 9	14 3		12 9	...	do ...	asphalte ...	18,936	2,066	9 3 0
		Blacksmith's shop ...	single ...	...	...	...	...	p ...	*Nil* ...	10 9		...	...	do ...	earth ...	17,446	8,845	1 13 9
		Workshop godown and Carpenter's Shop.	do ...	...	...	...	...	p ...	0 6	9 9		...	...	do ...	terraced ...	18,332	4,807	3 13 0
		Belvedere House.																
		New West Wing, Main Building.	partly 3 and partly 2.	...	...	...	...	p ...	8 6	19 6		16 9	...	do ...	ter and cement	84,232	6,250	13 10 3
		South-west do do ...	double ...	...	...	...	...	p ...	0 9	10 6		19 6	...	do ...	ter and marble	39,789	4,422	9 0 0
		do east do do ...	do .	..	...	...	...	p ...	0 9	10 6		21 3	...	do ...	do ...	32,940	3,660	9 0 0
		Centre Block do ...	do ...	...	...	...	...	p ...	...	8 0		24 0	.	do ...	ornamental tile, slate and marble.	59,730	5,973	10 0 0
		East Wing do ...	three ...	...	...	...	...	p ...	...	8 0		20 0	16 9	do ...	ter, stone and cement.	71,503	6,600	10 13 3
		Alipore Jail.																
		Jail wards, south ..	double ...	...	...	...	...	p ...	1 0	12 0		13 9	...	do .	terraced ...	1,21,016	13,722	8 1 6
		do west ...	do ...	...	...	...	...	p ...	1 0	12 0		13 9	...	do ..	do ...	86,744	13,878	6 4 0
		do north ...	do ...	...	..	.	...	p ..	1 0	12 0		13 9	...	do ...	do ...	1,21,016	13,722	8 1 6
		Jailor's quarters and Superintendent's Office.	do ...	...	...	...	...	p ...	1 0	11 10		13 8	...	do ...	tiled and ter ...	66,330	6,384	10 6 3
		Jute Factory	single ...	brick ...	1 0	p ...	4 0	p ...	3 0	17 0		...	...	do ...	stone ...	69,568	26,160	2 10 6
		Superintendent's dwelling house.	double ..		...	...	...	p ...	4 0	15 3		16 6	...	do ...	terraced ...	75,180	7,839	9 9 6
		Reformatory School ...	single ...	*Nil* ...	...	p ...	2 6	p ...	2 0	12 0		...	...	do ...	bk-on-edge ...	35,357	12,857	2 12 0
		Body Guard stable, Cavalry line.	do .	*Nil* ...	...	p ...	2 0	p ...	2 0	14 1		...	...	do ...	do ...	43,164	10,792	4 0 0
		Meteorological Observatory, Main Building.	partly two	*Nil* ...	...	p ...	3 4½	p ...	4 0	16 6 up to spring		16 0 soffit	...	do ...	terraced ...	26,157	4,291	6 1 6
	Russa ...	Jail Building	single ...	...	...	..	...	p ...	1 3	11 9		13 9	...	vaulted ...	bk-on-edge ...	55,484	14,075	3 15 0
		Bridges over 50 feet in length, &c.	...	...	...	*Nil* ...	...	...	...	*Nil.*								

W. H. NIGHTINGALE, C. E.,

Offg. Executive Engineer, 2nd Calcutta Division.

Executive Division.	Locality.	Name of building.	Description and Height of Walls. Single or double storied.	Foundation. Concrete.	Foundation. Masonry.	Plinth.	Walls (to top of wall-plate). 1st floor.	Walls (to top of wall-plate). 2nd.	Walls (to top of wall-plate). 3rd.	Roof.	Floor.	Cost.	Area.	Rate per superficial foot.
					Ft. In. / Average. Ft. In.	Average. Ft. In.	Ft. In.	Ft. In.	Ft. In.			Rs.		Rs. A. P.
2nd Calcutta	Calcutta Chowringhee.	Imperial Museum ...	double ...	brick ...	2 0 / p / 3 0	p / 8 0	26 0	33 2	...	ter on girders and joists.	stone and cement	10,27,162	84,159	12 3 3
		Bengal Secretariat. General Department ...	three ...	...	... / p / unknown	p / 0 6	9 0	15 0	18 6	ter on beams and burgahs.	ter and stone	1,99,508	14,345	13 14 6
		do Printing Department ...	single ...	...	... / p / ...	p / 3 0	18 9	...	...	do ...	terraced ...	52,250	13,238	3 15 0
	Calcutta Sudder Street.	do Main building ...	three ...	...	... / p / ...	p / 2 10	12 2	19 4	12 9	do ...	ter and stone	2,14,900	21,282	10 1 9
	do Brijeetalao	Lord Bishop's Palace ...	do ...	...	... / p / ...	p / 2 10	13 6	20 6	15 0	do ...	ter, stone and incostic tiled.	64,890	9,270	7 0 0
	do Maidan	*Presidency Jail Main buildings.*	do ...	*Nil*	... / p / 5 0	p / 2 0	10 5	15 4	18 11	terraced ...	ter, tile and bk-on-edge.	1,09,106	13,225	8 4 0
		do Native Doctor's quarters	double ...	...	... / p / 2 6	p / 3 0	8 3	12 6	...	do ...	tiled and ter and bk-on-edge.	22,048	2,756	8 0 0
		do Superintendent's do ...	do ...	*Nil*	... / p / 5 3	p / 2 0	14 0	17 0	...	do ...	tiled and ter...	36,099	5,157	7 0 0
		do Native Corridors (3) ...	do	*Nil*	... / p / 2 0	p / 3 0	12 3	14 9	...	do ...	do ...	66,000	13,200	5 0 0
		do Printing Office and Book Binder's Department.	partly 2 and partly 1 ...	...	... / p / p / 4 6	p / p / 3 0	9 3 / 10 2	9 9 / 15 3	... / ...	do ...	brick-on-edge and ter.	25,875	5,175	5 0 0
	Collinga ...	Madrasa College ...	do ...	*Nil*	... / p / 2 6	p / 1 10½	12 4	17 3	...	do ...	tiled and ter...	94,564	9,216	10 4 2
	Lower Circular Road.	St. James' Church ...	single ...	...	... / p / 2 6	p / 1 6	43 0	...	...	corrugated ...	ter and stone...	2,25,824	12,599	17 14 9
		do Parsonage ...	double ..	...	... / p / 2 6	p / 3 0	17 3	17 6	...	terraced ...	terraced ...	30,985	3,510	8 13 3
	Calcutta Park Street.	Mathematical Instrument Department.	do ...	...	... / p / 2 6	p / 2 9	16 0	17 9	...	do ...	stone, tiled and ter.	1,01,282	12,135	8 5 6
	Dhullundah	Native Lunatic Asylum, north Extension.	do ...	*Nil*	*Nil* / p / 3 0	p / 2 0	12 6	14 0	...	do ...	down story asphalted, 2nd story ter.	63,357	17,375	3 10 3
		General Hospital. Central building ...	double ...	*Nil*	*Nil* / p / 4 0	p / 1 6	15 9	20 3	...	do ...	stone ...	1,22,265	14,024	8 11 6
		Western do ...	three ..	*Nil*	*Nil* / p / 4 0	p / 1 0	8 3	12 0	14 0	do ...	ter, tile, tile ...	83,640	13,302	6 4 6
		Eastern do ...	do ...	*Nil*	*Nil* / p / 4 0	p / 1 0	8 6	11 9	14 0	do ...	tiled, ter, ter...	86,609	13,302	6 8 3
		Apothecary's quarter ...	single ...	...	... / ... / ...	p / 2 9	12 0	...	...	do ...	tiled ...	30,015	12,006	2 8 0
		Medical Officer's do ...	double ...	...	... / p / 3 6	p / 3 9	12 6	17 3	...	do ...	terraced ...	1,12,290	18,715	6 0 0
		Nurse's do ...	do ...	...	... / ... / ...	p / 3 0	14 0	14 0	...	do ...	do ...	30,000	4,200	7 2 3
		Female Hospital ...	single ...	...	... / ... / ...	p / 4 3	17 0	...	...	do ...	stone ...	19,744	5,101	3 14 0
	Bhowanipore...	European Lunatic Asylum Superintendent's quarter.	double ...	...	... / p / 2 0	p / 1 6	14 9	17 6	...	do ...	do ...	30,150	6,672	4 8 3
	Khidderpore	St. Stephen's Church ...	single ...	...	... / ... / ...	p / 4 0	25 0	...	...	sloped terraced on trusses.	ter and marble	60,460	7,140	8 7 0
		do Parsonage ...	double ...	...	... / ... / ...	p / 1 6	12 3	13 6	...	terraced ...	tiled and ter ...	22,119	4,883	4 8 6

W. H. NIGHTINGALE, C. E.,

Offg. Executive Engineer, 2nd Calcutta Division.

Executive Division.	Locality.	Name of building.	Description and Height of Walls. Single or double storied.	Foundation. Concrete.	Foundation. Masonry.	Plinth.	Walls (to top of wall-plate). Ground floor.	Walls (to top of wall-plate). 1st floor.	Roof.	Floor.	Cost.	Area.	Rate per superficial foot.
					Ft. In. / Average. Ft. In.	Average. Ft. In.	Ft. In.	Ft. In.			Rs.		Rs. A. P.
2nd Calcutta	Alipore ...	Judges' Cutcherry ...	double ...	...	*Nil* / unknown / unknown	p ... / 3 6	14 0	18 3	terraced ...	tiled ...	62,614	11,581	5 6 6
		Moonsiff's Court ...	single ...	*Nil*	*Nil* / p ... / 2 0	p ... / 3 0	varying from 12′ up to	18′, 15′ and spring soffit.	do ...	stone ...	26,526	6,237	4 4 0
		Collectorate	do ...	*Nil*	*Nil* / p ... / 2 0	p ... / 3 0	12 0	24 0	vaulted ...	tiled ...	36,748	10,160	3 9 9
		Magistrate's Court ...	do ...	*Nil*	*Nil* / p ... / 2 0	p ... / 3 0	11 0 / 9 0	19 0 / 15 0	a block verrandah do.	do ...	64,972	16,422	3 15 3
		Municipal Office and Sunderbund Commissioner's Office, &c.	do	*Nil*	*Nil* / p ... / 2 0	p ... / 2 6	12 0	24 0	do ...	do ...	53,248	13,265	4 0 3
		Sub-Registry Office and District Engineer's Office.	do ...	*Nil*	*Nil* / p ... / 3 0	p ... / 2 6	16 0	...	terraced ...	do ...	24,421	5,868	4 2 6
	Diamond Harbour.	Moonsiff's Court ...	double ...	*Nil*	*Nil* / p ... / 3 0	p ... / 2 0	11 9	13 9	do ...	terrace ...	15,935	2,013	7 14 6
		Custom House	do ...	*Nil*	*Nil* / p ... / 3 0	p ... / 1 6	7 9	14 0	do ...	planked ...	32,256	6,868	4 10 9
		Telegraph Office ...	do ..	*Nil*	*Nil* / p ... / ...	p ... / ...	11 9	18 0	do ...	terraced ...	10,000	3,135	3 3 0
		Post Office	double ...	p ...	0 6 / p ... / 2 0	p ... / 2 0	10 6	10 0	do ...	do ...	7,817	994	7 13 9
		Lock-up	single ...	*Nil*	*Nil* / p ... / ...	p ... / 1 3	17 0	...	pantile on trusses.	do ...	unknown ...	616	...
		Sub-Divisional Building ...	double ..	*Nil*	*Nil* / p ... / 3 0	p ... / 0 3	8 9	16 6	terraced ...	do and tiled	44,136	4,950	8 14 9
		do Cutcherry	single ...	*Nil*	*Nil* / p ... / 2 0	p ... / 3 0	16 0	...	do ..	do ...	9,660	3,533	2 11 9
	Barripore ...	do do	do ...	*Nil*	*Nil* / p ... / 1 6	p ... / 2 3	13 3	...	thatched ...	do ...	6,066	3,240	1 14 0
	Port Canning	Police Building ...	double ...	*Nil*	*Nil* / unknown / unknown	p ... / 3 9	14 3	16 6	terraced ...	tiled ...	unknown ...	2,528	...
	Atcheepore ...	Telegraph Office ...	2 or partly 3.	*Nil*	*Nil* / p ... / 4 0	p ... / 3 0	8 6	16 0	do ...	terraced ...	13,332	1,924	6 14 9
	Hoogly Point	do do ...	double ...	*Nil*	*Nil* / p ... / 2 0	p ... / ...	8 6	16 0	do ...	do ...	10,086	1,681	6 0 0
	Mudpoint ...	do do ...	do ...	*Nil*	*Nil* / p ... / 2 0	p ... / ...	8 6	16 0	do ...	do ...	10,086	1,681	6 0 0
		do do ...	do ...	*Nil*	*Nil* / p ... / 2 0	p ... / 4 0	14 6	13 6	do ...	do ...	32,936	1,530	21 8 3
	Saugore Island.	Lighthouse	single ...	*Nil*	*Nil* / p ... / 8 0	p ... / 7 0	...	72 0	vaulted, all iron, boarded.	do ...	unknown	1,600	...
		Superintendent's dwelling ...	double ..	...	... / p ... / 4 0	p ... / 6 0	7 6	14 6	terraced ...	boarded ...	do ...	1,230	...

W. H. NIGHTINGALE, C. E.,

Executive Engineer, 2nd Calcutta Division.

Statement of Construction, Cost and Length of Bridges exceeding 50 lineal feet in the Bengal Presidency.

Executive Division.	Name of bridge, or of river or nullah, and situation.	Date of completion.	Description of bridge.	Kind and depth of foundation.	No. and size of spans.	Width of roadway between parapets or railings.	Height of roadway above foundations or river-bed.	Total length of bridge.	Total cost.	Cost per 100 feet of length.	REMARKS.
							Ft. In.				
2nd Calcutta	Churial, over the Churial khal. River 15 miles, Budge Budge road.	Not known	Pucca masonry with six arches ...	Pucca, depth not known ...	Six arches, 15 ft. 3 in. each.	25 ft.	22 6	110	Not known	Not known.	

W. H. NIGHTINGALE, C. E.,

Executive Engineer, 2nd Calcutta Division.

Executive Division.	Locality.	Names of buildings.	Description and lengths of walls.										Cost.	Area.	Rate per superficial foot.
			Single or double-storied.	Foundation.				Plinth.		Wall to top of wall-plate.	Roof.	Floor.			
				Concrete.		Masonry.									
									Average.				Rs.		Rs. A. P.
Calcutta Workshop Division.	Sheebpore	Eastern block, Engineering College.	double ...	unknown	...	p ...	unknown	p m ...	2′6″ × 2′6″	no wall-plate, the thickness of the wall in ground floor 2 feet, 1st floor 1′-6″. Total length from plinth 35 feet.	terraced ...	ter, chunar stone and asphalting.	44,625	5,250 s. ft. 150 × 35	8 8 0
		Central block ...	do ...	do	...	p ...	do	do	2′6″ × 2′6″	do do ...	do ...	do ...	44,625	5,250	8 8 0
		South-western block ...	... ...	...	...	...	...	...	2′6″ × 2′6″	... ...	... ...	... ...	44,625	5,250	8 8 0
		St. Peter's Church & Library	double, only one room in 3rd story.	unknown	unknown	p m ...	unknown	p m ...	3′ × 3′	no wall-plate in the library; portion of the building under the beams, but in the Church portion there are two wall-plates. The thickness of the wall in the ground floor is 2′ 9″, and in 1st floor 2′ 6″; height from plinth 38′ 9″	ter, cor iron roof with iron trusses, ornamental ceiling.	ter, chunar stone and marble.	69,745	5,365 153 × 35	13 0 0
		Principal's block ...	... ...	...	...	...	...	...	3′ × 3′	no wall-plate; thickness of the wall ground floor 2′ 6″, and 1st floor 2 feet, height of building from plinth 38′ 9″	terraced ...	ter, chunar stone.	59,015	5,365 153 × 35	11 0 0
		Cook house, Coach house and Stable.	single ...	unknown	unknown	p m ...	unknown	p m ...	1′ × 2′	no wall-plate under the beams; thickness of wall 1′ 6″; length of building from plinth 13′ 6″.	do ...	tiled ter and cement plastering.	21,385	8,556	2 8 0
		Superintendent's house without office.	double ...	do	do ..	...	...	...	4′ × 2′ 6″	do do, thickness of the wall— 1st floor 1′ 9″ 2nd do 1′ 6″ height of building from plinth 36′	ter and sloped	flood ter; chunar stone and asphalting.	28,285	3,600 s. ft. 60 × 60	8 0 0
		Cook house attached to Superintendent's quarter.	single ...	...	...	...	...	...	2′ × 2′	do do, thickness of the wall 1′ 6″, height from plinth 12′	terraced ...	tiled and ter with cement plaster.	4,680	18,720 52 × 36	2 8 0
		Drawing Office for Engineering College.	do ...	unknown	unknown	p m ...	...	p m ...	3′ 6″ × 2″	no wall-plate under the beams; thickness of the wall 1′ 6″; height from plinth 20′.	do ...	flood and tiled	18,000	4,000 80 × 50	4 8 0
		Small house for the use of Assistant Surgeon.	... ...	...	...	...	...	...	1′ 6″ × 2¼″	do do thickness of the wall 1′ 8″, height from plinth 12′	do ...	tiled and cement plastering.	5,555	2,226 53 × 42	2 8 0
		Coock house attached to do do.	... ...	...	...	...	...	...	6′ × 1′ 3″	do do thickness of the wall 12″; height from plinth 9′	do ...	mud ...	525	262-6 25 × 10½	2 0 0

Executive Division.	Locality.	Names of buildings.	Description and lengths of walls.										Cost.	Area.	Rate per superficial foot.
			Single or double-storied.	Foundation. Concrete.		Foundation. Masonry.		Plinth.		Wall to top of wall-plate.		Roof.	Floor.			
							Average.		Average.					Rs.		Rs. A. P.
Calcutta Workshop Division.—contd.	Sheebpore—contd.	Octagonal Bungalow No. 1...	single, upper thatch roof.	...	...	p m ...	...	p m ...	2′6″ × 1′10″	no wall-plate under the beams; thickness of the wall— ground floor 1′ 4″ upper floor 1′ 3″.	ter and thatched with ceiling cloth.	flood and chunar stone with cement plastering.	6,048	1,728	3 8 0
		Bungalow No. 2...	thatch roof ...	...	...	...	...	...	...	thatched roof ...	thatch with ceiling cloth.	flood, tiled and cement plaster.	2,736	1,824 s. ft.	1 8 0
		do No. 3...	...	...	...	...	...	...	...	...	...	...	2,736	1,824 do	1 8 0
		do 4...	...	...	...	...	...	...	...	...	...	...	2,736	1,824 do	1 8 0
		do 5...	...	*Nil*	*Nil*	...	1′ × 1′3″	...	3′1½″ × 1¼″	wattle and daub wall ...	...	ter with cement plaster.	2,062	3,000 do	0 11 0
		do 6...	...	...	...	...	1′ × 10″	...	3′ × 10″	... ...	...	do with asphalting.	2,165	3,000	0 11 6
		do 7...	...	...	...	...	1′ × 1′3″	...	3′ × 1′ 3″	... ...	...	mud ...	1,500	3,000 s. ft.	0 8 0
		do 8...	...	...	...	...	1′ × 10′¼″	...	5′3″ × 10′ ½″	... ...	...	...	1,500	3,000 do	0 8 0
		Temporary Hospital and Dispensary.	shed ...	*Nil*	*Nil*	p ...	bollen of posts 2′6″ × 6″	p ...	2′ × 3′	double durmah mat walling	thatched ...	Rustic, with 1½″ daub.	986	73 × 21	0 10 3½
		Temporary Lavatory ...	...	...	...	p ...	1′3″ × 1′	p ...	1′ 3″ × 1′	do do ...	...	tiled, bedded on mud.	250	31 × 16	0 8 1
		Durwan's lodge near North-east gate.	single ...	unknown	unknown	...	...	...	1′ 6″ × 2′	no wall-plate under the beams, 1′ 6″ thick wall, 10′ height.	ter, sloped ...	terraced ...	460	176 s. ft.	2 8 0
		Do do river bank near ghât	do ...	...	...	...	...	...	1′ 6″ × 2′	do do plate, 1′ 6″ thick, 10′ height.	do ...	do ...	460	176 do	2 8 0
		Sentry box, North side ...	do ...	unknown	unknown	p ...	...	p ...	1′ × 3″	no wall-plate under the beams, 1′ thick wall, 11′ height.	terraced ...	tiled ...	140	70 do	2 0 0
		Cook room for the use of Native students.	do ...	do ...	do ...	p ...	...	...	6′ × 2′	do do under the beams, 1′ 6″ thick wall, 12′ height.	do ...	do ...	903	361 do	2 8 0
		Temple of Ease for the use of European students.	...	...	...	...	...	...	2′ × 2′	no wall-plate under the beams, 1′ 6″ wall, 14′ height.	do ...	do ..	672	224	3 0 0
		Temporary privy for the use of Native students, Engineering College.	*Nil*	*Nil*	...	...	4′ × 1′	p ...	4′ × 1′	p ... *Nil.*	*Nil.*	cement plastering.	108	144 s. ft.	0 12 0
		Workshop building ...	single, only 2 rooms in 2nd floor.	*Nil*	*Nil*	p ...	3′ 11½″ 5′ × 2′6″ / 2	p ...	2′ × 6″	p ... no wall-plate, 1′ 8″ thick wall, 22′ height.	terraced ...	mud ...	1,54,615	31,775 400 × 65 50 × 46 50 × 46 50 × 23′6″	4 13 10

CHAS. FOURACRES,
Supdt., Calcutta Workshop Division.

Executive Division.	Locality.	Name of building.	Description and Height of Walls.										Cost.	Area.	Rate per superficial foot.
			Single or double storied.	Foundation. Concrete.		Foundation. Masonry.		Plinth.		Walls (to top of wall-plate).		Roof.	Floor.		
				Ft.	In.		Average. Ft. In.		Average. Ft. In.		Ft. In.			Rs.	Rs. A. P.
Darjeeling	Darjeeling...	Shrubbery old portion ...	double ...	*Nil*		r l ...	6 6	r l ...	0 6	r l ...	14 6	cor ...	planked ...	98,702	5,250 / 5,244	9 6 0
		New portion with portico ...	do ...	.....		r l ...	6 6	r l ...	2 0	r l ...	14 6	shingled ...	do ...			
		Mount Pleasant with portico	do ...	no concrete ...		c r ...	2 0	p ...	0 6	lower story / upper „	7 6 / 13 0	cor ...	lower do ... / upper ...	24,291	8,107	3 0 0
		Deputy Commissioner's Cutcherry.	do ...	owing to drains all round, foundation taken in the front plinth.		p and c r	2 0	p ...	0 12	p ...	15 6	do ...	planked ...	26,820	12,000	2 4 0
		Additional building to Bhootia Boarding School.	do ...	.....		c r ...	1 6	c r ...	0 6	p ...	16 0	shingled ...	do ...	7,957	2,684	3 0 0
		Old Post Office or Bhootia Boarding School.	single ...	upon hard soil ...		c r ...	0 9	p ...	0 9	p ...	12 0	do ...	do ...	6,000	2,720	2 4 0
		Post and Telegraph Office ...	do ...	no concrete ...		c r ...	2 0	c r ...	1 9	p ...	12 0	cor ...	do ...	9,085	2,856	3 2 0
		Police Hospital ...	do ...	do ...		c r ...	0 12	p ...	1 6	p ...	10 0	do ...	do ...	10,684	4,266	2 8 0
		Circuit house ...	do ...	do ...		c r and p	2 6	p ...	0 9	p ...	13 6	do ...	do ...	7,036	2,976	2 8 0
		Church ...	gable ...		0 6	c r ...	2 6	p ...	2 1	p ...	17 9	do ...	do ...	29,815	2,850	10 8 0
		Zillah School ...	single ...	no concrete ...		c r ...	2 0	c r ...	5 6	c r ...	13 3	shingled ...	do & c ...	10,661	4,140	2 8 0
		Thorn Cottage ...	double ...	do ...		c r ...	2 9	c r ...	1 9	k & p ...	18 0	cor & shingled	planked ...	12,493	4,935	2 8 0
	Dowhill ...	Circuit house ...	single ...	do ...		r s l ..	2 6	r s l ...	2 6	r s l ...	15 0	do ...	do ...	19,765	4,070	4 12 0
		Boarding School ...	do ...	do ...		r s l ...	2 6	r s l ..	2 0	r s m ...	14 0	cor ...	do ...	28,574	7,390	3 13 0
	Kurseong ...	Dâk bungalow	do ...	do ...		r s m ...	1 6	r s m ...	2 0	r s m ...	12 0	do ...	do ...	14,257	3,419	4 2 0
		Constantia or Sub-divisional cutcherry.	do ...	do ...		r s m ...	2 0	r s m ...	3 6	b m ...	12 0	do ...	do ...	not known	6,277	not known
		Jail.														
	Darjeeling...	New jail wards ...	single ...	Cannot be known.		r ...	3 0	b l ...	2 0	b l ...	12 6	cor ...	planked ...	...	2,994	6 12 0
		Hajut ward and cells ...	do ...	...		r ...	2 0	b l ...	1 6	b l ...	12 6	do ...	do ...	...	1,028	
		Female ward and cells ...	do ...	...		r ...	2 0	b l ...	1 6	b l ...	12 6	do ...	do ...	...	1,020	
		Civil jail, now hospital ...	do ...	...		r ...	2 0	b l ...	1 6	b l ...	12 6	do ...	do ...	...	309	
		Insane wards and hospital, now godown.	do ...	...		r ...	2 6	b l ...	1 6	b l ...	12 0	do ...	do ...	...	515	
		do do, now civil jail ...	do ...	...		r ...	2 6	b l ...	1 6	b l ...	12 0	do ...	do ...	...	371	
		Store-rooms with passage	do ...	...		r ...	2 6	b l ...	1 6	b l ...	8 6	planked ..	do ...	95,845	664	
		Upper-story or Office ..	...	...		...	...	...	...	b l ...	12 0	cor ...	do ...	...	640	
		Cook-house, now wheat grinding-shed.	single ...	...		r ...	2 0	b l ...	1 6	b l ...	7 9	do ...	ter ...	...	230	
		do do ...	do ...	...		r ...	2 0	b l ...	1 6	b l ...	7 9	do ...	do ...	...	230	
		Cook-house ...	do ...	...		r ...	2 0	b l ...	1 6	b l ...	8 0	do ...	do ...	...	126	
		Guards' room with cook-house	do ...	...		r ...	2 0	b l ...	1 6	b l ...	10 av.	do ...	planked ...	...	247	
		do do ...	do ...	...		r ...	2 0	b l ...	1 6	b l ...	10 0	do ...	do ...	...	247	

Executive Division.	Locality.	Name of building.	Single or double storied.	Foundation. Concrete. Ft. In.	Foundation. Masonry.	Masonry Average. Ft. In.	Plinth.	Plinth Average. Ft. In.	Walls (to top of wall-plate).	Walls Ft. In.	Roof.	Floor.	Cost.	Area.	Rate per superfical foot.
				DESCRIPTION AND HEIGHT OF WALLS.									Rs.		Rs. A. P.
Darjeeling...	Darjeeling...	Work-shed, now wheat granary	single ...	Cannot be known. ...	r ...	2 6	b l ...	1 6	b l ...	8 6	cor ...	planked ...	95,845	364	6 12 0
		do do sifting-shed ...	do ...	...	r ...	2 0	b l ...	1 6	b l ...	8 6	do ...	do ...		364	
		Cook-house for prisoners ...	do ...	...	r ...	2 0	b l ...	1 6	b l ...	7 9	do ...	ter ...		185	
		Privy ...	do ...	...	r ...	2 0	b l ...	1 6	b l ...	7 av. 0	do ...	do ...		102	
		do ...	do ...	...	r ...	2 0	b l ...	1 6	b l ...	7 0	do ...	do ...		102	
		Cook-house, now blacksmith's shop.	do ...	...	r ...	2 0	b l ...	1 6	b l ...	8 0	do ...	mud floor...		185	
		Jail bakery, now jailor's quarters.	do ...	...	r ...	2 0	b l ...	1 6	b l ...	9 6	do ...	planked ...		1,401	
		New jail bakery ...	do ...	c 0 12	r ...	7 6	c r ...	2 8	c r ...	7 0	do ...	ter ...		2,626	
		Compound wall ...	...	cannot be known	r ...	5 0	b l ...	2 0	b l ...	13 6 av.	*Nil.*	*Nil.*		...	
		do (inside) ...	...		r ...	2 6	b l ...	1 6	b l ...	6 3	*Nil.*	*Nil.*		...	

W. B. CHRISTIE,
Executive Engineer, Darjeeling Division.

Statement of construction, cost, and length of bridges exceeding 50 lineal feet in the Bengal Presidency.

Executive Division.	Name of bridge, or of river or nullah, and situation.	Date of completion.	Description of bridge.	Kind and depth of foundation.	No. and size of spans.	Width of roadway between parapets or railings. Ft. In.	Height of roadway above foundations or river-bed.	Total length of bridge. Ft. In.	Total cost. Rs.	Cost per 100 feet of length. Rs.	REMARKS.
Darjeeling...	Punchani Bridge over Mattigurah Diversion road.	Mar 1880 ...	Wooden-bridge on piles ...	Piles of sal bullas 12 feet in depth.	20 spans of 18 feet average.	8 0	12 to 4 feet above river bed.	360 0	5,834	1,620	
	Champta Bridge over Mattigurah Diversion road.	do ...	do do	do do ...	10 spans of 18 feet average.	8 0	12 to 6 feet do	180 0	4,104	2,280	
	Old Mohanuddy Bridge over road from Silligoree to Mattigurah.	...	do do ...	do do believed to be 12 feet.	48 spans, 20 feet average.	9 0	9 to 2 „ do	972 0	not known...	...	Being dismantled under a sanctioned estimate, No. 1121 of 1880-81, Superintending Engineer's Office.
	Old Champta Bridge on road from Silligoree to Mattigurah.	...	do do ...	do do 10 feet ...	17 spans, 11 feet average.	8 3	4 to 1 „	196 0	...	...	
	Pathariaghatta Bridge on road from Mattigurah to Bisserbatty.	...	do do ...	do do 7 „ ...	15 spans, each 9 feet 6 inches.	7 7	10 to 4 „	150 0	...	...	
	Khuprail Bridge on road from Mattigurah to Bisserbatty.	...	do do ...	do do 8 to 9 „ ...	15 spans of 19 feet 6 inches.	8 0	7 to 8 „	303 0	...	...	
	Pugla Jhora Bridge on road from Mattigurah to Bisserbatty.	...	do do ...	do do 7 to 8 „ ...	7 spans of 13 feet.	8 6	8′ 6″ to 11 feet	98 0			
	Ruktee Bridge on road from Mattigurah to Bisserbatty.	...	do do ...	do do 7 to 8 „ ..	15 spans of 20 feet.	8 0	6 to 12′ 6″	319 0			
	Garudara Bridge on road from Mattigurah to Bisserbatty.	...	do do ...	do do 9 „ ...	6 spans of 19 feet 6 inches.	8 0	8 to 11 feet	119 0			

W. B. CHRISTIE,
Executive Engineer, Darjeeling Division.

Executive Division.	Locality.	Name of Building.	Description and Height of Walls. Single or double storied.	Foundation. Concrete. Ft. In.	Foundation. Masonry.	Average. Ft. In.	Plinth.	Average. Ft. In.	Walls (to top of wall-plate).	Ft. In.	Roof.	Floor.	Cost. Rs.	Area.	Rate per superficial foot. Rs. A. P.
Burdwan Division.	Dum Dum	Lock-up	single	...	p	2 0	p	2 6	p	16 3	n tiled	tiled	...	4,260	
		Police Building	double	...	p	1 3	p	1 6	k p	19 9	terraced	do	...	2,408	
		Hajut Ward	do	...	p	1 3	p	1 6	p	19 9	n tiled	do	...	753	
	Baraset	Cutcherry	do	...	p	2 0	p	1 6	p	25 9	terraced	ter	30,000	3,501	
		Residence	do	...	p	2 0	p	1 6	p	33 9	do	do	40,000	5,819	
		School	do	...	p	2 0	p	...	p	30 3	do	do	10,000	2,707	
		Hostel	do	...	p	...	p	3 0	p	...	do	do	1,716	1,178	
		Jail Building	single	...	p	2 0	k p	3 0	k p	35 3	do	tiled	59,000	6,294	
	Chougda	Inspection Bungalow	3 storied...	...	p	2 0	k p	1 6	k p	10 6	do	ter	...	956	
		Inspection Bungalow	single	...	p	...	p	2 0	mat	14 3	thatched	do	...	...	
	Bongong	Cutcherry	do	...	k p	0 6	p	2 0	p	16 9	terraced	tiled	8,000	2,241	
		Residence	do	...	...	...	p	2 6	p	17 0	do	ter	11,000	3,510	
		Lock-up	do	...	p	1 6	p	1 0	p	15 6	tiled	do	5,225	3,619	
		Dâk Bungalow	do	...	p	2 0	p	5 0	p	12 0	vaulted	do	...	3,595	
	Jessore	Collectorate	do	...	p	1 6	p	2 6	p	16 0	arched and ter	tile and ter	27,484	16,093	
		Judge's and Magistrate's Court	do	...	p	3 0	p	2 0	p	17 0	do	do	38,011	42,607	
		Small Cause Court	do	...	p	1 0	p	5 0	k p	14 6	ter and tiled	terraced	2,696	3,599	
		Registry Office	do	...	p	2 6	p	2 0	p	15 9	terraced	tiled	7,724	2,094	
		Circuit House	do	...	p	1 3	p	2 0	p	15 6	do	terraced	9,936	5,406	
		School	do	...	p	3 0	p	1 0	p	16 0	do	tiled	6,856	7,361	
		Distillery at Mohungunge	do	...	p	2 6	p	3 0	p	12 0	do	mud and ter	3,539	2,310	
		Burial ground	do	...	p	2 6	k p	1 6	k p	5 9	...	...	1,721	3,672	
		Dâk Bungalow	do	...	p	3 0	p	3 9	p	16 6	thatched	tiled	...	2,344	
		Post Office	double	c 1 0	p	3 0	p	2 0	p	10 0	terraced	terraced	3,624	934	
		Jailor's House	do	...	p	2 6	p	1 0	p	s 12 6 / d 12 6	do	do	15,391	2,575	
		Wards for mail convicts	single	...	p	3 0	p	3 0	p	d 14 0 / s 13 2	do and arched.	do	...	17,797	
		Civil Ward	do	...	p	2 0	p	2 0	p	9 6	terraced	tiled	...	400	
		Powder Magazine	double	...	p	1 0	p	5 0	mat	15 0	vaulted	terraced	1,876	485	
		Police Barrack	single	...	p	3 0	p	1 0	p	12 0	thatched	tiled	2,897	3,990	
		Hospital	do	...	p	2 0	p	2 3	p	15 0	terraced	terraced	64,639	163	
		Mad Cell	do	...	p	3 0	p	1 6	p	10 6	arched	do	...	190	
	Narail	Sub-Divisional dwelling-house	do	...	p	1 0	p	2 0	p	s 14 3 / d 17 4	terraced	tiled	15,034	2,718	
		Lock-up	single	...	p	2 6	p	1 6	p	15 6	tiled	terraced	5,225	7,267	
	Magoorah	Cutcherry	do	...	p	1 0	p	2 0	p	16 0	terraced	ter and tiled	29,844	5,231	
		Lock-up	do	...	p	3 0	p	3 0	p	12 0	thatched	terraced	5,000	14,673	
	Jenidah	Sub-Divisional dwelling-house	do	...	p	2 0	p	2 0	p	16 0	terraced	tiled	...	3,456	
		Cutcherry	do	...	p	1 6	p	2 0	p	16 0	do	do	29,411	3,249	
		Small Cause Court	do	...	p	2 0	p	2 0	p	16 0	do	do	...	2,473	
		Lock-up	do	...	p	1 6	p	1 10	p m	16 0	tiled	do	5,000	7,182	
		Circuit House	do	...	p	1 6	p	3 9	p	15 0	terraced	terraced	10,900	5,885	
		Collector's Cutcherry	do	...	p	1 6	p	7 3	p	20 0	...	do	30,000	9,921	
		College	do	...	p m	2 3				21 6	terraced	stone	96,000	30,800	
		Small Cause and Moonsiff's Court.	do	...	p	3 0	p m	2 6	p	20 0	do	tiled	10,990	4,875	
	Kishnaghur	P W Godown	do	...	p m	2 0	p m	2 0	p m	9 0	do	terraced	2,000	255	
		Judge's Cutcherry	do	...	p m	2 0	p m	3 0	p m	12 3	do	do	30,283	15,750	
		Joint Magistrate and Deputy Collector's Court and Treasury.	do	...	p m	2 0	p m	2 9	p m	10 0	do	do	...	9,060	
		Post Office	do	...	k p	2 5	k p	1 3	k p	7 10	thatched	do	3,624	1,845	
		Jail Ward	do at two ends double	...	p m	1 7	p m	2 3	p	13 6	arched and ter	stone tiled	5,311	17,448	
		Jail Hospital and Female Ward	single	...	p m	2 3	p m	2 2	p	11 6	terraced	terraced	13,257	4,299	
		Jailor's residence	do	...	k p	2 0	k p	3 5	k p	10 0	thatched	do	1,700	1,508	
		Cemetery	...	...	...	...	...	...	p	...	Nil	Nil	2,000	64,505	
		Sub-Registry Office	single	...	p m	1 7	p m	3 0	p	14 0	terraced	terraced	5,011	1,837	
		Physical Science Lecture Building.	do	...	p	2 3	p	4 0	p	16 0	do	do	11,137	2,252	
	Meherpore	Cutcherry	do	...	p m	2 0	p m	2 0	p	15 0	do	tiled	10,823	3,781	
		Lock-up	do	...	p m	2 0	p m	2 0	p	15 0	tiled	terraced	5,000	623	
		Dwelling-house	do	...	p m	2 0	p m	1 3	p	15 6	terraced	tiled	11,000	3,443	
	Kooshteah	Cutcherry	do	...	p	3 0	p	5 0	p	20 0	do	terraced do	32,257	8,566	
		Lock-up	do	...	p	3 6	p	5 0	p	16 0	tiled	do	5,000	2,221	
		Dwelling-house	do	...	p	2 0	p	5 0	p	16 0	thatched	do	13,057	2,849	
	Koomercolly	Burial ground	...	...	p	1 0	...	...	p	6 0	Nil	Nil	1,018	5,313	
	Chooadanga	Cutcherry	single	...	p	1 6	p	2 0	p	16 0	terraced	tiled	11,000	3,396	
		Lock-up	do	...	p	2 0	p	2 0	p	16 0	tiled	terraced	5,000	598	
		Dwelling-house	do	...	p	2 0	p	2 0	p	16 0	terraced	tiled	11,689	2,382	
	Ranaghat	Cutcherry	do	...	p m	2 0	p m	1 6	p	...	do	do	10,454	3,327	
		Lock-up	do	...	p	2 0	p	2 0	p	16 0	tiled	bk-on-edge	5,000	632	
		Dwelling-house	do	...	p m	2 0	p m	1 8	p	16 6	terraced	tiled	11,000	3,445	
	Kanchraparah	Post Office	...	...	k p	1 6	k p	1 0	k p	11 0	thatched	do	1,999	1,513	
Burdwan	Hooghly (Station.)	Post Office	single	not	known	...	...	1 6	k p	10 6	ter and tiles	asphalte, tiles and ter.	1,577	1,192½	1 5 2
		Out-offices	do	...	do	...	...	1 0	k p	11 0	do	terraced	100	410	0 3 10
		Judge's Court	do	...	do	...	...	4 0	k p	18 0	do	do	40,525	10,360	3 14 2
		Stables	do	...	do	...	...	0 6	k p	11 6	do	do	300	660	0 7 3
		Privy	do	...	do	...	Nil	Nil	k p	8 0	do	do	174	148½	1 2 9
		Magistrate's Court	do	...	do	...	...	2 0	k p	15 9	do	do	12,914	5,544	2 5 3
		Hajut Guard	do	...	do	...	...	...	p	mean 11 3	do	tiled	3,876	693½	5 9 5
		Coach house	do	...	do	...	Nil	Nil	p	10 6	do	bk-on-edge	273	324	0 13 5
		Range of out-offices	do	...	do	...	Nil	Nil	p	11 9	tiled	k	285	1,183	0 3 10
		Guard Room	...	...	do	...	...	...	k p	9 8	flat	tiled	830	1,6 3	0 7 10
		River side ghat	single	...	do	...	Nil	Nil	k p	18 0	do	do	14,000	9,590 covered 2,056	1 4 7
		Collector's Court	double	Nil	Nil	p 2 0	Nil	Nil	p	34 0	ter and tile	terraced	7,124	10,080	
		Out-offices	single	not	known	...	p	0 9	p	9 0	terraced	plank and tiles.		768	0 9 6
		do	do	...	do	...	Nil	Nil	p	10 2	do	terraced		1,092	...
		Enclosure wall	...	...	...	...	...	...	rails	...	...	...		...	...
		Branch School	single	Nil	Nil	p 3 0	p	3 0	p	17 0	terraced	asphalte	3,909	5,695¼	0 11 0
		Out-offices	do	...	not	known	...	p	p	mean 8 6	ter and thatch	do	...	1,016	...
		Privy	do	...	...	do	Nil	Nil	p	6 0	terraced	terraced	...	140	...
		Durwan's house	do	...	...	do	Nil	Nil	p	8 6	do	do	...	315	...
		Enclosure wall	...	...	...	...	...	...	balustrade	...	...	...	...	...	...
		Distillery	single	...	not	known	...	Nil	Nil	p	mean 7 0	tiled	terraced	...	4,921	...

Executive Division.	Locality.	Name of Building.	Description and Height of Walls. Single or double storied.	Foundations. Concrete.	Foundations. Masonry.	Foundations. Average.	Plinth.	Plinth. Average.	Walls (to top of wall-plate).	Walls (to top of wall-plate). Average.	Roof.	Floor.	Cost.	Area.	Rate per superficial foot.
				Ft. In.		Ft. In.		Ft. In.		Ft. In.			Rs.		Rs. A. P.
	Hooghly (Station).	Out-offices	single ...	...	...	...	...	...	p ...	...	thatched ...	mud ...	...	104	...
		Criminal Jail	do ...	...	not	known ...	...			mean					
		Compound wall	...	...	...	...	...	p ... 1 0	p ...	14 6	terraced ...	terraced ...	43,798	21,907	1 15 11
		Cook-rooms	single ...	..	not	known ...	...	... ...	p ...	16 0	...	...	...	...	...
		Hospital	do ...	*Nil*	*Nil*	p ...	2 6	*Nil* *Nil*	p ...	5 0	flat ...	k ...	...	1,240	...
		Cooking shed	do ...	...	not	known ...	...	p ... 2 0	p ...	17 9	do ..	p ...	7,842	5,880	1 5 4
		Out-offices	do ...	*Nil*	*Nil*	p ...	2 6	*Nil* *Nil*	p ...	8 6	tiled ...	k ...	720	972	0 11 10
		Dead-house	do ...	*Nil*	*Nil*	p ...	2 6	p ... 2 0	p ...	10 0	pitched ...	terraced	2,326	640	3 10 1
		Hospital compound wall ...	..	...	...	...	...	p ... 2 0	p ...	12 9	terraced ...	do ...	...	400	...
		Dewany Jail	single ...	...	not	known ...	...	... ...	p ...	14 0	...	...	...	...	...
		Ditto enclosure wall ...	...	...	...	...	...	p ... 1 0	p ...	12 0	flat ...	terraced ...	12,082	3,150	3 13 4
		Female Jail with four solitary cells.	single ...	*Nil*	*Nil*	p ...	2 0	... ...	p ...	16 0	...	...	...	...	...
		Two additional rooms ...	...	...	...	...	...	*Nil* *Nil*	p ...	13 0	terraced ...	terraced ...	4,610	1,110	4 2 5
		Enclosure wall ...	...	...	...	...	...	... ...	p ...	...	do ...	do ...	565	900	0 10 0
		Jailor's quarters ...	double ...	...	not	known ...	...	... ...	p ...	...	...	...	...	...	...
								p ... 1 0	p ...	26 6	flat ...	terraced ...	3,176	2,128	1 7 10
		Godown	single ...	*Nil*	*Nil*	p ...	2 0	*Nil* *Nil*	p ...	mean 7 0	do ...	do ...	...	1,296	...
		Six solitary cells ...	do ...	*Nil*	*Nil*	p ...	2 0	p ... 1 6	p ...	11 6	terraced ...	do ...	4,231	1,829¾	2 5 0
		Guard-room	do ...	...	not	known ...		p ... 0 6	p ...	10 0	sloping ...	do ...	...	1,751	...
		Four Sentry boxes ...	...	...	...	...	...	... ...	p ...	...	flat ...	do ...	...	1,600	...
		Hajut	...	...	not	known ...	...	p ... 2 0	p ...	11 0	terraced ...	...	...	1,253	...
		Record Office	single ...	...	....	do ...	...	p ... 3 0	p ...	mean 14 6	do ...	terraced ...	8,484	7,700	1 1 7
		Sub-Registrar's Office ...	do ...	...	1 0	p ...	3 0	p ... 2 0	p ...	18 0	do ...	do ...	4,588	1,284½	3 9 2
	Bandel (Station).	Commissioner's Office ...	double ...	...	not	known ...	...	p ... 1 0	p ...	31 6	tiles and ter	do ...	...	9,984	...
		Range of out-offices ...	single ...	...	...	do ...	...	*Nil* *Nil*	p ...	11 10	do ...	do ...	...	5,320	...
		do of stables ...	do ...	...	...	do ...	...	*Nil* *Nil*	p ...	10 6	do ...	stone ...		867	...
		Boarding House ...	double ...	...	...	do ...	...	... 2 0	k p ...	27 0	ter and tiles	ter marble and tiles.	36,048	30,625	1 2 10
		Out-offices	single ...	*Nil*	*Nil*	*Nil*	2 0	... 1 0	k p ...	9 11	tiled ...	tiled ...	580	1,170	0 7 11
		Compound wall	...	...	...	...	...	... ...	k p ...	...	...	...	...	...	...
		Cook-room	...	...		...	...	... ...	p ...	9 11	terraced ...	flag stones...	2,483	1,048	2 5 10
		Latrine	double ...	*Nil*	*Nil*	p ...	3 0	*Nil* *Nil*	p ...	19 0	do ...	asphalt ...	1,777	323¼	5 10 0
		Chinsurah Reserve Police Barracks.	single ...	...	not	known ...	...	... 1 6	...	10 6	...	...	...	...	...
	Chinsurah (Station).	College of Mohamed Moshin	double ...	...	...	do ...	...	p ... 1 6	p ...	mean 46 6	flat ...	terraced ...	48,480	33,288	1 7 3¼
		Range of out-offices ...	single ...	...	...	do ...	...	p ... 2 0	p ...	12 6	do ...	do ...		3,225¾	
		Two Darwans' houses ...	do ...	...	...	do ...	...	p ... 1 5	p ...	9 0	do ...	do ...	6,652	181¼	1 12 10
		Store-room	...	...	...	...	...	... ...	p ...	9 6	do ...	do ...		282¾	
		Pucca ghat	...	...	...	...	...	...	p ...	24 0	...	...	2,827	2,940	0 15 4
		Compound wall... ...	...	...	...	...	...	... ...	p ...	...	...	...	...	...	...
		Public drain	...	...	...	...	...	... ...	...	...	...	...	3,476	1,820	1 14 6
		New privy	single ...	...	0 6	p ...	1 6	p .. 4 0	p ...	10 0	flat ...	terraced ...	1,766	520¼	3 6 4
		Laboratory, Chinsurah College	do ...	...	1 0	p ...	2 9	p ... 2 0	p ...	20 0	terraced ...	do ...	7,253	2,212¾	3 4 5
		Protestant Church Cemetery	...	...	...	...	...	... ...	p ...	...	flat ...	do ...	16,000	5,760	2 12 5
Burdwan ...		Magistrate's dwelling ...	single ...	...	not	known ...	...	... 3 0	k p ...	21 6	flat ...	terraced ...	16,000	11,875	1 5
		Stable No. 1, &c. ...	do ...	...	..	do ...		... ...	k p ...	11 0	do ...	do ...	...	...	...
		Pucca ghat	...	...	...	...	...	... ...	k p ...	...	...	...	...	...	...
		Jugul Addy's Ghat ...	single ...	...	not	known ...	...	... 0 6	k p ...	12 0	terraced ...	...	6,000	covered part 1,188 4,420	1 1 1
		Court-house	do ...	...	...	do ...	...	... 1 6	k p ...	mean 16 0	flat ...	terraced ...	3,000	2,900	1 0 6
		Out-offices	do ...	...	...	do ...	...	... 1 6	k p ...	7 6	do ...	do ...	...	1,487½	...
		Jail	do ...	*Nil*	*Nil*	...	3 0	... 2 0	k p ...	11 9	do ...	do ...	4,500	714	6 4 10
		Criminal Hazut	do ...	*Nil*	*Nil*	...	3 0	... 2 0	k p ...	12 0	do ...	do ...	4,000	697	5 11 9
		Cook-room	...	...	...	...	...	... ...	k p ...	0 0	do ...	do ...	...	310½	...
	Serampore (Station).	Solitary cells	...	...	...	...	...	... ...	k p ...	0 0	do ...	do ...	2,000	483	4 2 3
		Female ward	single ...	...	not	known ...	...	... 1 9	k p ...	9 3	do ...	do ...	1,000	1,540	0 10 4
		Hospital	do ...	*Nil*	*Nil*	p ...	3 0	p ... 2 0	p ...	11 9	terraced ...	do ...		402¼	
		Cook-room to do ...	do ...		not	known ...	...	p ... 1 9	p ...	7 3	do ...	do ...	7,966	305½	8 15 2
		European ward	do ...	*Nil*	*Nil*	p ...	3 0	p ... 2 0	p ...	11 9	do ...	do ...		182	
		Cook-house of Dewany Jail...	do ...	*Nil*	*Nil*	p ...	3 0	... 2 0	k p ...	11 9	flat ...	mud ...	2,000	471½	4 3 11
		Do for female ward ...	do ...	*Nil*	*Nil*	not known	...	... 1 9	k p ...	7 3	sloped ...	do ...	...	1,149½	...
		Jailor's room	do ...	...	...	do ...	...	... 1 9	k p ...	9 3	flat ...	p ...	...	271¼	...
		Constable's cook-room ...	do ...	...	...	do ...	...	... 1 9	k p ...	9 3	do ...	p ...		603¾	...
		Post Office	do ...	...	...	do ...	...	p ... 2 4	p ...	12 0	do ...	p ...	...	1,369½	...
		Church	do ...	...	...	do ...	...	... 2 0	k p ...	23 6	do ...	p ...	8,181	5,040	1 9 11
		Out-offices	...	...	...	...	...	... ...	...	...	...	...	..	800	...
		Flag staff ghat	...	...	...	...	...	... ...	p ...	12 0	...	...	3,600	1,890	1 14 6
		Kutcherry or godown ghat ...	...	...	...	...	...	... ...	p ...	12 0	terraced ...	terraced ...	5,050	1,619¼	3 1 10
	Mahesh (Station).	Distillery	single ...	*Nil*	*Nil*	p ...	1 6	p ... 1 6	p ...	mean 9 0	flat and sloped	...		6,889	
		Darogah's house... ...	do ...	*Nil*	*Nil*	p ...	1 6	p ... 2 0	p ...	10 0	terraced ...	terraced ...	3,500	682½	0 5 8
		Spirit godown	do ...	...	not	known ...	...	... ...	p ...	10 3	tiled ...	do ...		259½	
		Toll House at Mugrah ...	...	..		do ...	...	... ...	...	...	terraced ...	terraced ...		1,512	
		Cook-room	...	—	...	...	...	... ...	p ...	...	thatch ...	do ..	3,500	225	1 14 0
	Grand Trunk Road.	Privy	..	...	...	...	...	... ...	p ...	...	do ...	do ...		126	
		Post Office	single ...	...	not	known ...	..	... ...	k p	13 6	thatched ...	do ...	1,661	2,829¾	0 9 4
		Out-offices	do ...	...	..	do ...	...	...	k p ...	8 9	do ..	do ...	346	1,326	0 4 2
		Road Chowkee at Pundooah...	do ...	...	...	do ...	...	k p ... 1 0	k p ...	14 0	terraced ...	do ...	854	522¾	1 10 1
		Stable	...	...	...	...	...	... ...	k p ...	...	thatched ...	bk-on-edge...	...	517	...
	Bansberriah (Station).	Police building	single ...	*Nil*	*Nil*	...	2 0	... 1 6	k p ...	mean 10 0	tiled ...	terraced ...		987	
		Cook-room	do ...	*Nil*	*Nil*	...	2 0	... 1 6	k p ...	mean 10 0	do ...	do ...	1,996	192½	1 0 6
		Constables' barrack and cook-room.	do ...	*Nil*	*Nil*	...	2 0	... 1 6	k p ...	mean 10 0	do ...	do ...		756	
	Ooterparah (Station).	Government School ...	double ...	...	not	known ..	.	p ... 2 6	p ...	31 0	terraced ...	do ...	10,966	3,920	2 12 9
		Out-office	single ...	...	...	do	...	p ... 0 9	p ...	8 9	do	do ...	...	611½	...
		Post Office	do ...	*Nil*	*Nil*	p ..	1 6	p ... 1 6	p ...	14 0	thatched ...	do ...	2,000	2,790	0 11 5
		Salt Golahs Nos. 1 and 6 ...	do ...	*Nil*	*Nil*	p ...	2 0	p ... 1 0	p ...	19 9	terraced ...	mud ...		7,040	
		do Nos. 2 and 7 ...	...	...	...	...	...	... ...	p ...	...	do ...	do ...		9,309	
		do Nos. 3 and 8 ...	...	...	...	...	...	... ...	p ...	...	do ...	do ...		9,309	
		do Nos. 4 and 9 ...	...	...	...	...	...	... ...	p ...	...	do ...	do ...		9,309	
		do No. 5 ...		...	...	...	...	... ...	p ...	...	do ...	do ...	6,48,446	4,815	1 7 8
	Salkea (Station).	do Nos. 10 and 15 ..	...	...	...	...	...	... ...	p ...	...	do ...	do ...		9,309	
		do Nos. 11 to 19 ..	...	...	...	...	...	... ...	p ...	...	do ...	do ...		38,520	
		do Nos. 20, 25, 30...	...	...	...	...	...	... ...	p ...	...	do ...	do ...		15,768	
		do Nos. 21 to 24, 26 to 29, and 31 and 32.	...	...	...	...	...	... ...	p ...	...	do ...	do ...		48,150	

Executive Division.	Locality.	Name of Building.	Description and Height of Walls. Single or double storied.	Foundation. Concrete.	Foundation. Masonry.	Plinth.	Walls (to top of wall-plate).	Roof.	Floor.	Cost.	Area.	Rate per superficial foot.
				Ft. In.	Average. Ft. In.	Average. Ft. In.	Ft. In.			Rs. A. P.		Rs. A. P.
Burdwan...	Salkea (Station).	Salt Golahs, Nos. 33, 36, 39...	...	... ...	... ...	... ...	p	terraced ...	mud ...		15,836	
		do Nos. 34, 37, 40...	...	... ...	... ...	... ...	p	do ...	do ...		15,836	
		do No. 41 ...	...	... ...	... ...	... ...	p	do ...	do ...		6,105	
		do Nos. 35 and 38...	...	... ...	... ...	... ...	p	do ...	do ...		9,416	
		do Nos. 42, 45, 49 ..	...	... ...	... ...	... ...	p	do ...	do ...		13,910	
		do Nos. 43, 46, 50...	...	... ...	... ...	... ...	p	do ...	do ...		13,910	
		do Nos. 44, 47, 51...	...	... ...	... ...	... ...	p	do ...	do ...		13,910	
		do No. 48 ...	...	... ...	... ...	... ...	p	do ...	do ...		3,195	
		do Nos. 52, 54, 59...	...	... ...	... ...	... ...	p	do ...	do ...		13,910	
		do Nos. 53, 55, 60...	...	... ...	... ...	... ...	p	do ...	do ...		11,700	
		do Nos. 56, 57 ...	...	... ...	... ...	... ...	p	do ...	do ...		9,630	
		do Nos. 61, 66 and 71; 52, 67, 72; 58, 63, 68; 64, 69, 74; 65, 70, 75.	...	... ...	... ...	... ...	p	do ...	do ..	6,48,446 0 0	69,550	1 7 8
		do No. 79 ...	...	... ...	... ...	... ...	p	do ...	do ...		4,815	
		do Nos. 73 and 78...	...	... ...	... ...	... ...	p	do ...	do ...		9,309	
		do Nos. 76, 80, 82, 77, 81, 83.	...	... ...	... ...	... ...	p	do ...	do ...		27,820	
		do E. G. I. and M....	...	... ...	... ...	... ...	p	do ...	do ...		21,300	
		Office of Superintendent ...	single ...	... not	known	p ... 1 0	p ... 15 6	do ...	stone		4,760	
		Out-office ...	do ...	... ...	do	*Nil* *Nil*	p ... 10 6	do ...	terraced ...		1,586	
		S. shed on verandah ...	...	... ...	... ...	... ...	p	terraced ...	mud ...		8,400	
		Middle do ...	...	... ...	... ...	... ...	p	do ..	do ...		8,400	
		Weigh godown ...	...	... ...	... ...	... ...	p	do ...	terraced ...		650	
		Main Guard house ...	...	... ...	... ...	... ...	p	do ...	stone ...		5,166	
		do do small ...	...	... ...	... ...	... ...	p	do ...	terraced ...		925	
		Out-office	...	... ...	... ...	... ...	p	do ..	do ...		610	
		Distillery godown ...	single ...	... *Nil*	p ... 2 0	p ... 1 6	p ... 10 0	tiled ...	do ...	...	600	
		Guard house	...	... ...	... ...	... ...	durmah mats. ...	thatched ...	mud	335 0 0	450	0 4 5
		Magistrate's Court ...	double, and part 3 storied.	... *Nil*	p ... 3 0	p ... 3 0	p ... 39 6	terraced ...	tiled and ter	1,42,284 0 0	17,750	8 0 3
		2 Servants and cook-room east side.	...	... no	sections ...	... ...	p	do ...	terraced ...	2,379 0 0	793	3 0 0
		do west side ...	...	... ...	do	... ...	p	do ...	do ...	2,457 0 0	819	3 0 0
		Latrine	...	... ...	do	.. ...	p	do ...	do ...	1,383 0 0	735	1 14 1
		Magistrate's residence ...	double ...	... *Nil*	p .. 3 0	p ... 5 3	p . 34 0	do ...	do ...		6,138	
		Out-office, south side ...	...	... no	sections ...	... ...	p	do ...	do ...		1,365	
		do west do ...	...	... ...	do	... ...	p	do ...	do ...	52,174 0 0	832	4 12 5
		do north do ...	...	... ...	do	... ...	p	do ...	do ...		1,365	
		do east do ...	...	... ...	do	... ...	p	do	do ...		923	
		Durwan's room ...	...	... ...	do	... ...	p	tiled ..	do ...		297	
		Jail.										
		Ward, Nos. 1 and 2 ...	No. 1 single	... *Nil*	p ... 2 0	p ... 2 0	p ... 10 6	terraced ...	terraced ...	740 0 0	3,920	0 3 0
			No. 2 do	... *Nil*	p ... 3 0	p ... 2 0	... 12 0	vaulted ...	...	...	...	...
	Howrah (Station).	Ward No. 3	single ...	... *Nil*	p ... 2 0	p ... 1 0	p ... 10 6	vaulted ...	terraced ...		1,012	
		do No. 4	do ...	... *Nil*	p ... 2 0	p ... 1 0	p ... 10 6	do ...	do ...		989	
		do No. 5	do ..	... *Nil*	p ... 2 0	p .. 1 6	p ... 9 9	do ..	do ...		616	
		do No. 6	do ...	... *Nil*	p ... 2 0	*Nil* *Nil*	p ... 10 0	do ...	do ...	15,697 0 0	476	3 3 8
		Condemned cell... ...		... ...	... ...	... ...	p	do ...	do ...		168	
		Guard-room	single ...	... *Nil*	p ... 2 0	*Nil* *Nil*	p ... 7 6	do ...	do ...		715	
		Privy	...	... ...	... ...	... ...	p	do ...	do ...		170	
		Jailor's office and cook-room ..	single ...	... *Nil*	p 2 0	*Nil* *Nil*	p ... 10 0	terraced ...	do		715	
		St. Thomas' Church	do ...	... not	known	p .. 3 0	p .. 20 0	do ...	ter marble flags.		5,474	
		Servant's Pantry room ...	...	.. ...	... ...	... ...	p ..	do ...	terraced ...	10,448 0 0	299	1 12 7
		do Goomty ...	...	... ...	... ...	... ...	p	do ...	do ...		64	
		New Burial Ground ...	single ...	.. not	known ...	p ... 2 0	p ... 12 6	tiled ...	do ...	13,121 0 0	1,098	11 15 2
		School	do ...	.. *Nil*	p ... 2 0	p ... 4 0	p ... 10 0	terraced ...	do ...	19,380 0 0	4,845	4 0 0
		do additional room ...	do ...	... *Nil*	p ... 2 0	p ... 4 0	p ... 16 0	...	...	...	...	...
		Urinal attached to School ...	...	.. ...	... ...	... ...	p	terraced ...	tiled ...	...	451	...
		Old Post Office	single ...	.. not	known	p ... 3 3	p .. 12 0	do ...	asphalt ...	1,576 0 0	818	1 14 9
		New do	do ...	.. *Nil*	p 2 6	p ... 2 6	p .. 16 6	do ...	terraced ..	9,880 0 0	2,628	3 2 9
		Out-office	do ...	... *Nil*	p ... 2 0	p ... 1 3	p ... 10 0	do ...	do ...		483	
		Botanical Gardens.										
		Superintendent's house ...	double ...	... not	known	... ...	p ... 35 9	do ...	do ..	59,136 0 0	7,392	8 0 0
		Out-office ...	single ...	... ...	... p ...	1 6	p ... 12 0	do ...	do ...	17,100 0 0	11,400	1 8 0
		Head nursery man's house ...	...	... ...	.. ...	..	p	do ..	do ...	1,914 0 0	1,033½	1 13 8
		Out-office for do ...	...	... ...	... ...	... ...	k p	do ...	do ...	304 0 0	607¼	0 8 0
		Seed-house	double ...	... *Nil*	p ... 1 6	p ... 3 0	p ... 29 0	ter and cor iron.	ter and as-phalt.	22,400 0 0	4,480	5 0 0
		Tool-house	single ...	... *Nil*	p ... 1 3	p ... 0 9	p ... 10 0	tiled ...	brick on edge	267 0 0	357	0 12 0
		Gardener's store... ...	do ...	... *Nil*	p ... 2 0	p ... 2 0	p ... 10 0	do ...	do ...	810 0 0	1,080	0 12 0
	Seebpore (Station).	Assistant Overseers' house ...	do ...	... *Nil*	p ... 2 0	p ... 3 0	p ... average 14 ½	terraced ...	ter and tiles	11,280 0 0	2,900	3 14 3
		Cook-room and godown ...	do ...	... *Nil*	p ... 2 0	p ... 2 0	p ... 10 0	do ...	do ...	2,044 0 0	954	2 2 3
		Propagatory shed ...	do ...	... ...	... ...	... ...	p	tiled ...	brick on edge	587 0 0	1,175	0 8 0
		Conservatory No. 1 ...	do ...	... *Nil*	p ... 2 0	*Nil* *Nil*	do on posts 10 6	covered by creeper.	mud ...	1,158 0 0	3,090	0 6 0
		do Nos. 2, 3 ...	do ...	... *Nil*	p ... 2 0	*Nil* *Nil*	do ... 10 6	thatched ...	do ...	1,027 0 0	2,733¾	0 6 0
		do No. 4 ...	do ...	... *Nil*	p ... 2 0	*Nil* *Nil*	do ... 10 6	covered by creeper.	do ...	1,334 0 0	3,414	0 6 3
		Kids' Monument ...	...	... ...	... ...	... ...	p	domed ...	terraced ...	882 0 0	441	2 0 0
		Pucca Ghat	...	... ...	... ...	... ...	p	...	...	2,772 0 0	924	2 5 11
		Curators' house	double ..	... 2 0	p ... 2 0	p ... 2 6	p ... 26 8	terraced ...	Pucca ...	11,467 0 0	1,498	6 4 6
		Out office	single ...	... 1 6	p ... 1 6	p ... 1 3	p ... 9 9	do ...	do ...		327	
		Curators' servant's house ...	do ...	... 1 6	p ... 1 6	... 2 9	k p ... 9 8½	do ...	terraced ..	1,061 0 0	507½	2 1 5
		2nd Gardener's residence ...	do ...	... *Nil*	p ... 2 0	p ... 3 0	p ... 16 0	do ...	do ...	8,639 0 0	2,341¼	3 11 0
	Juggutbul-lubpore (Station).	Police Station	double ...	... not	known	p ... 1 0	p ... 24 6	do ...	do ...	5,323 0 0	1,950	2 11 8
	Chinsurah (Station).	Barracks, I, I, I, ...	single ...	...	do	p ... 1 6	p ... 10 6 mean	tiled ...	tiled ...		9,393	
		do I	do ...	...	do	p ... 1 6	p ... 12 6	ter and tiles	terraced...	42,073 0 0	3,570	2 13 1
		do I	do ...	...	do	p .. 1 6	p ... 13 6	do ...	do ...		1,960	
		Criminal Jail.										
	Burdwan (Station).	Male ward ...	single ..	... not	known	p ... 1 3	p ... 12 0	vaulted ...	terraced ...	57,000 0 0	18,550	3 1 2
		Jailor's house ...	do ...	... upper	floor only ...	... ...	p ... 16 0	terraced ...	do ...	6,551 0 0	2,123½	3 1 4
		Cook-shed ...	do ...	... not	known	*Nil* *Nil*	p ... 10 0	do ...	mud ...	1,330 10 10	2,266	0 9 4
		do ...	do ...	... ...	do	*Nil* *Nil*	terraced ... 10 0	do ..	do ...	...	252	...
		Hospital ...	do ...	... ...	do	p ... 2 3	p ... 16 0	do ...	terraced ...	8,600 0 0	3,627	2 5 11
		do cook-shed ...	do ...	... ...	do	*Nil* *Nil*	p ... 7 4	do ...	mud ...	200 0 0	654½	0 4 10
		Female ward ...	do ...	... ...	do	p ... 1 3	p ... 12 0	do ...	terraced ...	...	1,128	...

Executive Division.	Locality.	Name of building.	Single or double-storied.	Description and Height of Walls. — Foundation. — Concrete.	Concrete Ft. In.	Masonry.	Masonry Average. Ft. In.	Plinth.	Plinth Average Ft. In.	Walls (to top of wall-plate).	Walls Ft. In.	Roof.	Floor.	Cost. Rs. A. P.	Area.	Rate per superficial foot. Rs. A. P.
	Burdwan (Station).	Guard-room	single	...	not	known	...	p	2 0	p	12 6	terraced	terraced	5,000 0 0	1,642¼	3 0 8
		do godown	do	...	...	do	...	p	1 9	p	12 3	do	do	...	4,557	...
		do	do	...	...	do	...	p	1 9	p	12 3	do	do	...	2,394	...
		Six solitary cells	do	Nil	Nil	p	2 0	p	1 0	p	13 0	do	kunkur and ter.	3,369 4 9	2,445	1 6 0
		Tank and ghat	...	...	...	...	...	...	...	p	...	...	...	3,600 0 0	10,800	0 5 4
		Compound wall	...	...	...	...	...	...	...	p	...	...	...	...	3,827½	...
		Judge's Court house	single	...	not	known	...	p	2 0	p	17 6	vaulted	terraced	27,763 4 3	14,028¾	1 15 8
		N. side attached	do	...	...	do	...	p	2 0	p	15 0	terraced	do	5,369 14 4	1,162	4 9 11
		Sub-Judge's Court house	do	...	...	do	...	p	2 0	p	18 0	thatched and ter.	do	5,750 0 0	58,742	0 15 8
		Judge's English Office	do	...	...	do	...	p	2 0	p	17 6	terraced	do	...	1,890	...
		do attached parches	...	...	...	...	...	...	...	p	...	do	do	...	212	...
		do	...	...	...	...	...	...	...	p	...	do	do	...	185¼	...
		Malkhana	single	...	not	known	...	p	1 0	p	9 9	do	do	1,231 2 1	877½	1 6 5
		Municipal Commissioner's Office	do	Nil	Nil	p	3 0	p	3 0	p	17 0 side walls 11 feet.	sloping ter...	do	2,125 0 0	2,573½	0 13 2
		Magistrate's and Collector's Cutchery.	do	...	Nil	p	3 0	p	4 0	p	20 0	sloping ter	do	1,28,918 7 9	17,353½	7 2 8 (for this and the next line)
		Attached Treasury	do	...	not	known	...	p	4 0	p	15 0	terraced	do	...	631½	
		Guard-room	do	...	Nil	p	4 0	p	5 0	p	10 0	do	do	unknown	1,620	
		Stable	do	...	not	known	...	Nil	Nil	p	12 0	do	mud	100 0 0	665	0 2 4
		Cook shed	do	...	Nil	p	4 0	p	5 0	p	10 0	sloping ter...	do	179 4 1	236¼	0 12 1
		Joint Magistrate's and Police Court.	do	...	Nil	p	3 0	p	4 9	p	17 9	terraced	terraced	12,309 9 9	7,776	1 9 3
		Out-offices	do	...	not	known	...	p	1 0	p	9 10	do	do	659 6 2	1,145½	0 9 2
		do	do	...	...	do	...	p	1 0	k p	9 0	thatched	tiled	100 0 0	1,239½	0 1 3
		Circuit house	do	...	...	do	...	p	2 9	p	15 6	vaulted and ter.	terraced	16,500 0 0	8,616¼	1 14 7
		Out-offices	do	...	...	do	...	Nil	Nil	p	9 6	terraced	do	3,208 3 10	2,838	1 2 1
		Charitable Hospital	do	...	...	do	...	p	2 0	p	10 0	vaulted	do	9,500 0 0	7,370	1 4 7
		Compound wall	...	...	...	...	...	...	...	p	...	.	...	...	1,032	
		Tank and Ghat	..	...	...	...	...	...	...	p	...	...	...	1,200 0 0	18,000	0 1 1
		Grave-yard wall	...	...	...	...	...	...	...	p	...	...	...	1,700 0 0	106½	1 9 8
		Burdwan Store Godown	single	...	Nil	p	3 0	p	1 0	p	9 6	vaulted and ter.	terraced	unknown	1,866	
		Post Office	do	...	Nil	p	2 0	p	1 0	p	11 6	thatched, vaulted and ter.	do	3,415 5 11	4,482	0 12 2
		Out-office	do	...	not	known	...	p	1 0	p	9 0	vaulted and thatched.	do	300 0 0	1,586	0 3 0
		Compound wall	...	...	...	...	...	...	...	p	...	...	...	150 0 0		
		Telegraph Office	p	...	Nil	p	3 0	p	3 0	p	14 0	terraced	terraced	7,293 12 8 including out-houses. (for this and the next line)	3,422¼	1 [illegible] 10 (for this and the next line)
		Range of out-offices	p	...	Nil	p	3 0	Nil	Nil	p	7 6	thatched	do		1,061¾	
Burdwan		Godown	single	Nil	Nil	p	2 0	p	1 0	p	9 6	terraced	terraced	7,293 12 8 (for this and the next two lines)	282	1 6 10 (for this and the next two lines)
		Cook-room	do	Nil	Nil	p	2 0	p	1 0	p	8 6	do	do		232½	
		Wall	...	...	...	...	...	...	...	p	...	...	...		2,827	
		Sub-Registrar's Office	single	...	not	known	...	...	...	p	14 0	terraced	terraced	5,191 8 8	1,7[illegible]5¼	2 14 6
	Cutwa (Station).	Deputy Magistrate's dwelling-house.	do	...	...	do	...	p	2 0	p	16 6	do	do	unknown	3,599	
		Cook-house	do	...	...	do	...	Nil	Nil	k	9 0	thatched	mud	...	620	
		Stable	do	...	...	do	...	Nil	Nil	k	8 0	do	do	...	551	
		New Court-house	do	...	2 0	p	3 0	p	2 0	p	16 0	terraced	terraced	5,104 3 3	1,593	3 3 3
		Lock-up	do	...	not	known	...	p	1 6	p	15 0	do	do	unknown	1,033	
		Cook-house	do	...	...	do	...	p	0 9	p	10 0	do	do	...	107½	
		Compound wall	...	...	...	...	...	...	...	p	...	...	...	...	770	
		Cook shed	single	...	...	do	...	p	0 9	p	10 0	terraced	terraced	...	192	
	Culnah (Station).	Deputy Magistrate's dwelling-house.	do	Nil	Nil	p	2 6	p	3 0	p	16 6	do	do	5,900 0 0	11,524	0 7 0 (for this and the next two lines)
		Out-offices	do	Nil	Nil	Nil	Nil	...	...	p	5 6	do	do	...	640	
		do	do	Nil	Nil	Nil	Nil	...	...	p	8 6	do	do	...	1,287	
		Court-house	do	Nil	Nil	p	2 0	p	2 0	p	16 0	do	do	unknown	3,850	
		Out-offices	do	...	...	...	...	...	...	p	...	do	do	...	240¼	
		Lock-up	do	...	Nil	p	3 0	p	3 0	p	14 6	do	do	...	1,010½	
		Cook-house	do	...	not	known	...	p	3 0	p	14 6	do	do	...	183¾	
		do	do	...	...	do	...	p	3 0	p	14 6	do	do	...	99¾	
		Compound wall	...	...	...	...	...	...	...	p	...	...	..	...	736	
	Jehanabad (Station).	Deputy Magistrate's Court house.	single	Nil	Nil	p	1 6	p	2 0	p	16 0	terraced	terraced	231 0 6	1,883¾	0 1 11
		Do dwelling-house	p	...	not	known	...	not	known	p	13 6	do	do	unknown	7,216	...
		Compound wall	...	...	...	...	...	...	...	p	...	...	...	...	408	...
		Lock-up	single	...	Nil	...	...	p	3 0	p	15 0	terraced	terraced	8,468 0 0 (for this and the next three lines)	1,045	4 8 11 (for this and the next three lines)
		Out-houses	do	...	not	known	...	p	1 9	p	9 0	do	do		162¾	
		do	do	...	...	do	...	p	1 9	p	9 0	do	do		99¾	
		Compound wall	...	...	...	...	...	...	...	p	...	...	...		549	
		Charitable Hospital	single	...	Nil	p	2 0	p	1 0	p	12 0	terraced	terraced	2,163 9 0	1,194	1 13 0
	Grand Trunk Road.	Gopalpore Inspection Bungalow.	do	...	Nil	...	2 0	...	1 0	k p	8 0	thatched	do	673 4 1¼	1,056¼	0 10 2
		Out-offices	do	...	Nil	...	1 6	Nil	Nil	k p	8 0	do	mud	255 0 0	520	0 7 10
		Mohunpore Inspection Bungalow.	do	...	Nil	p	3 0	p	2 0	r	12 6	terraced	terraced	1,164 0 0	1,105	1 0 10
		Out-offices	...	...	...	...	...	...	...	r	...	do	do	217 12 7	809¼	0 4 3
	Bood Bood (Station).	Deputy Magistrate's Court and dwelling-house.	single	...	not	known	...	p	2 3	p	15 6	thatched	do	2,358 12 10 (for this and the next three lines)	4,647½	0 6 3 (for this and the next three lines)
		Cook-room	do	...	...	do	...	...	1 0	k p	8 0	do	do		240	
		Stable	do	...	...	do	...	Nil	Nil	k p	8 0	do	mud		720	
		Servants' houses	do	...	...	do	...	...	0 6	k p	7 6	do	do		396	
		Treasury room	do	...	Nil	p	2 0	p	1 0	p	12 0	terraced	terraced	504 10 6	149	3 6 2
		Lock-up (male ward and hazut).	do	...	Nil	p	2 0	p	2 0	p	12 0	do	do	5,806 8 8 (for this and the next seven lines)	2,880	0 12 8 (for this and the next seven lines)
		Female ward	do	...	Nil	p	2 0	p	2 0	p	12 0	do	do		704	
		Hospital	do	...	Nil	p	2 0	p	2 0	p	12 0	do	do		1,056¼	
		Cook shed female ward	do	...	Nil	p	2 0	p	2 0	p	12 0	do	do		192	
		do Male ward	do	...	Nil	p	2 0	p	2 0	p	12 0	do	do		348	
		do Hospital	do	...	Nil	p	2 0	p	2 0	p	12 0	do	do		200	
		Guards' room	do	...	Nil	p	2 0	p	2 0	p	12 0	do	do		1,276	
		Dispensary	do	...	Nil	p	2 0	p	2 0	p	12 0	do	do		533½	
		Moonsiffs' cutcherry	do	...	Nil	p	2 0	k p	3 0	k p	14 6	thatched	tiled	1,338 1 6	1,800	0 11 10

Executive Division.	Locality.	Name of Building.	Single or double storied.	Foundation. Concrete.	Concrete Ft. In.	Foundation. Masonry.	Masonry Average. Ft. In.	Plinth.	Plinth Average. Ft. In.	Walls (to top of wall-plates).	Walls Ft. In.	Roof.	Floor.	Cost. Rs. A. P.	Area.	Rate per superficial foot. Rs. A. P.
	Bood Bood (Station).	Police Station and out-houses	single ...	Nil	Nil	...	2 0	...	1 0	k p ...	12 0	terraced ...	terraced ...	1,657 0 0	1,769¼	0 15 0
		Bood Bood Inspection Bungalow.	do ...	Nil	Nil	p ...	2 0	p ...	1 0	k p ...	8 0	thatched ...	do ...	712 0 0	1,056¼	0 10 9
		Out-offices ...	...	...	...	...	...	...	...	k p ...	...	do ...	do ...	187 0 0	809¼	0 3 7
		Magistrate's dwelling-house	single ...	...	not	known ...	...	p ...	3 0	p ...	16 0	terraced ...	do ...	6,680 0 0	6,440	1 0 7
		Out-offices ...	do ...	Nil	Nil	p ...	4 0	Nil ...	Nil	p ...	10 0	do ...	do ...	496 0 0	715	0 11 1
		Stable ...	do ...	Nil	Nil	p ...	1 6	p ...	1 0	p ...	11 6	do ...	do ...	296 0 0	500¼	0 9 5
		Court-House ...	do ...	...	not	known ...	...	p ...	0 6	p ...	mean 14 0	do ...	do ...	6,387 0 0	4,125¼	1 8 9
		Cook-room ...	do ...	Nil	Nil	p ...	4 0	p ...	0 6	p ...	7 9	do ...	do ...	303 0 0	466¾	0 10 4
		Stable ...	do ...	Nil	Nil	p ...	4 0	p ...	1 0	p ...	11 9	do ...	do ...	565 0 0	500¼	1 2 0
		Jail Building ...	...	...	...	...	...	...	...	p ...	...	do ...	do ...	9,258 0 0	6,053	1 8 5
		Cook shed and ...	do ...	Nil	Nil	p ...	3 0	Nil	Nil	p ...	7 0	do ...	do ...			
		Wards, &c. ...	do ...	Nil	Nil	p ...	3 0	Nil	Nil	...	7 0	do ...	do ...			
	Raneegunge (Station).	Police Station Building ...	do ...	Nil	Nil	p ...	5 0	Nil	Nil	p ...	average 15 0	do ...	do ...	3,697 0 0	2,349	1 9 1
		Inspection Bungalow ...	...	...	...	...	...	...	...	p ...	...	thatched ...	do ...	2,150 0 0	2,196	0 12 2
		and Out-houses ...	...	...	...	...	...	...	...	p ...	...	do ...	do ...		...	
		Godown ...	...	...	...	...	...	...	...	k p ...	...	do ...	do ...		629	
		Church ...	single ...	Nil	Nil	p ...	2 6	p ...	4 0	p ...	15 0	terraced ...	do ...	18,142 0 0	3,168	5 11 7
		Servants' house ...	do ...	Nil	Nil	p ...	2 0	p ...	1 0	p ...	8 0	do ...	do ...	1,189 0 0	275	1 3 0
		Graveyard wall ...	...	...	...	...	...	...	...	p ...	...	...	...		723	
		Military graveyard wall ...	...	...	...	...	...	...	...	p ...	...	...	...	1,268 0 0	1,302	0 15 6
		Post Office ...	single ...	Nil	Nil	p ...	2 6	p ...	1 0	p ...	12 6	terraced ...	terraced ...	2,297 0 0	1,457¼	1 4 10
		Cook-room ...	do ...	Nil	Nil	p ...	2 6	p ...	1 0	p ...	9 9	do ...	do ...		190	
		Enclosure wall and privy ...	...	...	...	...	...	...	...	p ...	...	do ...	do ...		117	
		Telegraph Office... ...	single ...	Nil	Nil	p ...	2 6	p ...	2 0	p ...	14 0	do ...	do ...	8,632 0 0	5,841	1 7 7
		Godown ...	do ...	Nil	Nil	p ...	1 0	p ...	1 0	p ...	9 6	do ...	do ...	1,808 0 0	308¾	0 11 0
		Privy ...	do ...	...	not	known ...	...	p ...	1 0	p ...	6 6	do ...	do ...		76½	
		Servants' house ...	do ...	Nil	Nil	p ...	2 0	Nil	Nil	p ...	8 6	do ...	do ...		851¾	
		Cook-room ...	do ...	Nil	Nil	p ...	2 0	Nil	Nil	p ...	8 6	do ...	do ...		232½	
		do houses ...	do ...	Nil	Nil	...	2 0	Nil	Nil	k ...	8 6	thatched ...	earth ...		1,042½	
		Well ...	...	...	...	...	...	...	...	p ...	...	...	...		113	
	Burrakur (Station.)	Pucca buildings ...	single ...	...	not	known ...	...	...	...	r ...	13 0	terraced ...	terraced ...	2,000 0 0	2,252½	0 14 2
		Out-houses ...	...	...	...	...	...	...	3 0	k ...	...	thatched ...	earth ...	50 0 0	630	0 1 3
		Toll house ...	single ...	...	...	...	...	...	...	r ...	13 0	ter and cor iron	terraced ...	2,337 0 0	1,444	1 9 10
		Out do ...		...	not	known ...	...	r	2 0	k	...	thatched	mud ...	89 0 0	600	0 2 4
		Large Dâk Bungalow ...	do ...	...	not	known ...	...	...	2 0	r (in mud)	16 0	do ...	terraced ...	2,000 0 0	6,075	0 5 3
		Out-house ...	do ...	...	...	do ...	...	...	1 6	do ...	7 0	tiles and grass	do and b l ...	200 0 0	1,627½	0 1 11
		do ...	do ...	...	...	do ...	...	...	1 6	do ...	8 3	thatched ...	earth ...	100 0 0	892½	0 1 9
		Overseer's bungalow ...	do ...	...	...	do ...	...	...	1 6	do ...	14 0	do ...	terraced ...	625 0 0	652	0 15 4
		Out-house ...	...	...	...	...	...	...	...	do ...	...	do ...	earth ...	20 0 0	340	0 1 0
		Post Office ...	do ...	...	not	known ...	...	...	2 0	do ...	11 0	terraced ...	terraced ...	1,000 0 0	1,776	0 9 6
	Assensole (Station.)	5th Class Post Office with enclosure wall.	do ...	Nil	Nil	...	3 0	...	2 0	r ...	11 0	do ...	ter and kunkur.	2,351 0 0	1,557½	1 4 6
		Out-offices ...	do ...	Nil	Nil	...	2 0	...	2 0	r ...	9 0	do ...	mud ...		275	

Executive Division.	Locality.	Name of Building.	Single or double storied.	Foundation. Concrete.	Concrete Ft. In.	Foundation. Masonry.	Masonry Average. Ft. In.	Plinth.	Plinth Average. Ft. In.	Walls (to top of wall-plates).	Walls Ft. In.	Roof.	Floor.	Cost. Rs. A. P.	Area.	Rate per superficial foot. Rs. A. P.
Burdwan ...	Beerbhoom (Station).	Collector's Court ...	do ...	Nil	Nil	p ...	1 6	p ...	4 0	p ...	mean. 19 0	flat ...	stone and tiles	45,154 0 0	21,925¾	2 0 11
		do Guard Room ...	do ...	...	not	known ...	...	p ...	1 0	p ...	15 0	do ...	terrace ...	1,500 0 0	2,040	0 11 9
		Magistrate's Cutcherry ...	do ...	...	...	do ...	...	p ...	2 0	p ...	20 4	thatched ...	do ...	12,000 0 0	7,385¾	1 9 11
		do Record Room ...	do ...	...	...	do ...	...	p ...	1 0	p ...	12 6	vaulted ...	do ...	500 0 0	3,435	0 2 3
		Judge's new Cutcherry ...	do ...	Nil	Nil	p ...	4 0	p ...	4 0	p ...	20 0	flat ...	stone and tiles	47,687 0 0	16,666¼	2 13 9
		School house	do ...	...	not	known ...	...	p ...	1 3	p ...	15 10	do ...	terraced ...	7,500 0 0	7,070	1 0 11
		do residence	do ...	Nil	Nil	p ...	2 0	Nil	Nil	k ...	11 9	thatched and tiled.	do ...	1,698 0 0	1,708¼	0 15 10
		do do out-office ...	do ...	...	not	known ...	...	Nil	Nil	p ...	9 0	flat ...	do ...	96 0 0	727¾	0 2 1
		School godown No. 1 ...	...	...	...	...	...	...	...	k ...	...	thatched ...	mud ...	100 0 0	459	0 3 5
		do do No. 2 ...	single ...	Nil	Nil	...	1 0	Nil	Nil	k ...	9 6	do ...	do ...	75 0 0	566¾	0 2 1
		Jailor's quarters ...	double ...	...	not	known ...	...	p ...	1 0	p ...	22 0	terraced ...	terraced ...	400 0 0	717¾	0 9 0
		Jail ward	single ...	...	...	do ...	...	p ...	3 0	p ...	13 9	vaulted ...	do ...	66,740 0 0	17,728½	3 12 2
		Hajut cell in jail ...	do ...	Nil	Nil	p ...	2 0	p ...	1 6	p ...	10 6	flat ...	do ...	3,150 0 0	906¾	3 7 6
		Jail out-office	do ...	...	not	known ...	...	...	...	p ...	mean 8 0	terraced ...	mud ...	500 0 0	480¼	0 3 3
		do do								p ...		do ...	do ...		500	
		do do								p ...		do ...	do ...		464	
		do do								p ...		do ...	do ...		975	
		Jail Hospital	do ...	...	...	do ...	...	p ...	3 0	p ...	13 9	do ...	tiled ...	5,275 0 0	1,514¾	3 7 8
		Guard Room	do ...	...	...	do ...	...	p ...	3 0	p ...	13 9	do ...	terraced ...	500 0 0	4,071	0 2 0
		Jail tank ghat	...	...	...	...	...	...	...	p ...	...	...	...	740 0 0	1,051¼	0 11 3
		Old solitary cells ...	...	...	...	...	...	...	...	p ...	...	flat ...	terraced ...	276 0 0	298	0 13 10
		Circuit house	single ...	...	not	known ...	...	p ...	1 6	p ...	15 6	terraced ...	do ...	16,000 0 0	9,487¾	1 10 11
		do godown	do ...	...	...	do ...	...	Nil	Nil	p ...	6 3	do ...	do ...	250 0 0	411¾	0 9 8
		do Cook-room ...	do ...	...	...	do ...	...	p ...	1 0	p ...	10 0	do ...	do ...	1,500 0 0	2,419	0 9 11
		do stable	do ...	...	...	do ...	...	Nil	Nil	p ...	11 9	do ...	do ...	350 0 0	658¾	0 8 6
		Burial ground wall ...	...	...	...	...	...	...	...	p ...	...	...	...	1,000 0 0	855	1 2 8
		Post Office, 4th class ...	single ...	...	0 6	p ...	1 6	p ...	1 6	p ...	10 0	terraced ...	tiled ...	3,664 0 0	1,248¼	1 14 9
		Out-offices in compound ...	...	...	...	...	...	...	...	k p ...	...	do ...	terraced ...		287	
		Clerks' quarters... ...	single ...	...	0 6	p ...	1 6	p ...	1 6	k p ...	10 0	do ...	do ...		368	
		Church	do ...	...	1 0	p ...	2 0	p ...	2 0	p ...	16 9	tiled ...	ter and tiled	7,300 0 0	1,848	3 15 2
	Bancoora (Station).	4th class Post Office ...	do ...	Nil	Nil	p ...	2 0	p ...	1 6	p ...	14 0	terraced ...	ter and kunkur.	3,260 0 0	1,972½	1 3 11
		Record Room	do ...	Nil	Nil	p ...	2 0	p ...	1 6	p ...	14 0	do ...	do ...		272¼	
		Out-offices	do ...	Nil	Nil	...	2 0	...	0 6	k p ...	10 0	do ...	do ...		368	
		Shally Inspection Bungalow...	...	...	...	...	...	...	...	p ...	...	do ...	terraced ...	1,604 0 0	1,105	1 7 2
		Judge's Court-House ...	double ...	...	not	known ...	...	p ...	2 0	p ...	29 0	flat ...	do ...	4,231 0 0	5,320	0 12 8
		Judge's and Magistrate's Record Room.	single ...	...	...	do ...	...	p ...	1 0	p ...	12 0	arched ...	stone ...	680 0 0	5,360½	0 2 0
		Moonsiff's Court... ...	...	...	...	...	...	...	...	p ...	...	flat ...	terraced ...	7,189 0 0	11,664	0 9 10
		Magistrate's and Collector's Court.	single ...	...	not	known ...	...	p ...	1 0	p ...	mean 14 0	do ...	stone ...	2,000 0 0	5,885	0 5 5
		Guards cook-room ...	...	...	...	...	...	...	...	p ...	...	do ...	mud ...	450 0 0	646¼	0 11 2
		Deputy Collector's Court ...	single ...	...	not	known ...	...	p ...	2 0	p ...	mean 14 0	tiled ...	stone ...	1,700 0 0	3,245	0 8 4
		Record Room	do ...	...	...	do ...	...	p ...	1 0	p ...	12 3	arched ...	terraced ..	800 0 0	2,416	0 5 3
		Treasury	do ...	...	...	do ...	...	p ...	1 0	p ...	mean 14 0	flat ...	do ...	1,071 0 0	590½	1 13 0
		Sub-Registrar's Court ...	do ...	...	...	do ...	...	p ...	2 0	p ...	14 0	do ...	do ...	0 0 0	3,432	0 0 0
		Treasury Guard House ...	...	...	...	...	...	...	...	p ...	...	do ...	do ...	550 0 0	805	0 10 11
		Civil and Criminal Jail ...	double ...	...	...	p ...	2 0	p ...	1 0	p ...	32 6	arched ...	stone ...	16,692 0 0	12,500	1 5 4
		Hindoo and Mahomedan Cook-room.	...	..	...	...	...	...	...	p ...	...	sloped ...	...	1,658 0 0	1,968	0 13 6
		Jailor's quarters... ...	upper story	Nil	Nil	p ...	2 0	p ...	1 0	p ...	13 6	flat ...	terraced ...	...	1,464	...
		Guard Room	single ...	Nil	Nil	p ...	2 0	p ...	1 0	p ...	12 3	do ...	stone ...	1,711 0 0	1,316	1 4 9
		Jail entrance and warders Room.	lower story	Nil	Nil	p ...	2 0	p ...	1 0	p ...	12 3	do ...	do ...	4,279 0 0	1,543½	2 12 4

Executive Division.	Locality.	Name of building.	Description and Height of Walls.												Cost.	Area.	Rate per superficial foot.
			Single or double storied.	Foundation.				Plinth.		Walls (to top of wall-plate).		Roof.	Floor.				
				Concrete.		Masonry.											
							Average.		Average.								
							Ft. In.		Ft. In.		Ft. In.				Rs. A. P.		Rs. A. P.
Burdwan ...	Bancoora (Station).	Jail Hospital and female ward	single ...	*Nil*	...	not	known ...	p ...	3 0	p ...	15 6	flat ...	stone ...		5,688 0 0	6,846	0 13 3
		Female Jail Hospital ...	do ...	...	not	known ...	...	p ...	4 1	p ...	10 11	thatched ...	mud ...		...	1,172¼	...
		Proposed Jail guard-room ...	...	...	...	...	...	...	...	...	...	flat ...	stone ...		1,700 0 0	5,100	0 5 4
		Undertrial Jail	single ...	...	not	known ...	...	p ...	1 0	p ...	10 9	do ...	do ...		5,500 0 0	2,813	1 15 3
		Jail Superintendent's Office ...	double ...	*Nil*	p ...	...	2 0	p ...	1 0	p ...	25 9	do ...	terraced ...		...	4,860	...
		School	single ...	...	not	known ...	...	p ...	2 6	p ...	17 3	flat ...	do ...		2,233 0 0	7,854	0 4 6
		Head Master's quarters ...	do ...	...	...	do ...	...	p ...	2 0	p ...	10 0	do ...	do ...		1,182 0 0	4,914	0 3 10
		Out-offices	do ...	...	...	do ...	...	...	...	p ...	9 0	do ...	do ...		0 0 0	528	...
		Boarding house	do ...	...	...	do ...	...	p ...	2 0	p ...	9 9	do ...	do ...		1,900 0 0	1,100	1 11 8
											mean						
		Circuit house	do ...	...	...	do ...	...	p ...	2 0	p ...	14 1½	do ...	do ...		8,500 0 0	9,405	0 14 5
		Cook-house and servants' house.	do ...	...	...	do ...	...	p ...	1 0	p ...	9 9	do ...	do ...		...	2,124	...
		Stable	do ...	...	...	do ...	...	k ...	...	k ...	6 3	thatched ...	mud ...		780 0 0	1,562	0 8 0
		Watchman's house ...	...	...	...	...	...	...	...	...	...	terraced ...	terraced ...		...	143	...

L. ROBERTS, C. E.,

Executive Engineer, Burdwan Division.

Statement of construction, cost, and length of bridges exceeding 50 lineal feet in the Bengal Presidency.

Executive Division.	Name of bridge, or of river or nullah, and situation.	Date of completion.	Description of bridge.	Kind and depth of foundation.	No. and size of spans.	Width of roadway between parapets or railings.	Height of roadway above foundations or river bed.	Total length of bridge.	Total cost.	Cost per 100 feet of length.	Remarks.
						Ft. In.	Ft. In.	Ft. In.			
Burdwan Division.	Poijoll Bridge ... ... Do Nullah in 25th mile on Calcutta and Jessore Road.	not known...	iron girder supported on two lime masonry piers. Roadway wooden.	lime masonry brick work. Depth of foundation unknown.	3 spans 21′ 6″ each.	20 6	13 3	74 6	Not known	Not known	
	Gyeghatta Boat-bridge in 37th mile, Calcutta and Jessore Road.	do ...	bridge-of-boats ...	unknown	7 openings, 10′ each.	12 0	17 0	145 0	do ...	do	
	Pullerghat Bridge over Mooktarsari River on 4th mile of Jessore and Bongong Road.	do ...	masonry bridge ...	... ...	2 spans of 6′ ...	18 0	18 9	92 r. ft.	...	do	
	Jhingergacha Bridge over Coboduck River on 10th mile, Jessore and Bongong Road.	do ...	iron suspension bridge ...	... ...	3 spans two sides, one 39′ and middle one 168′	9 0	26 0	385 0	...	do	
	Jadubpore Bridge over Betwa River, 12th mile.	do ...	masonry bridge ...	... ...	3 spans of 16 each.	17 6	21 0	116½ 0	...	do	
	Jointipore Bridge over Hautkur River, 25th mile.	do ...	iron girder bridge on iron piles.	... ...	5 spans of 30′ each.	15 11	23 6	152 0	...	do	
	Hurrydaspore Bridge over Nabegunj River, 26th mile.	do ...	Iron girder bridge on wooden piles.	... ...	6 spans of 23½′ each.	16 0	22 0	144 0	Not known	do	
	Bongong boat-bridge over Echamuty River, 28th mile.	do ...	iron pontoon ...	... ...	22 boats. They are placed 12′ apart.	11 0	This floats. The roadway above surface of water is 4′	442 0	do ...	do	

L. ROBERTS, C. E.,

Executive Engineer, Burdwan Division.

Statement of construction, cost and length of bridges exceeding 50 lineal feet in the Bengal Presidency.

1	2	3	4	5	6	7	8	9	10	11	12
Executive Division.	Name of bridge or of river or nullah and situation.	Date of completion.	Description of bridge.	Kind and depth of foundation.	No. and size of spans.	Width of roadway between parapets or railings.	Height of roadway above foundations or river bed.	Total length of bridge.	Total cost.	Cost per 100 feet of length.	REMARKS.
						Ft. In.	Ft. In.	Ft. In.	Rs.	Rs. A. P.	
Burdwan ...	Salle Bridge between Raneegunge and Bancoora between 12th and 13th mile stones on 14th mile of Raneegunge and Midnapore Road.	1858 ...	wooden ...	rubble masonry ...	4 spans of 31¼′				3,500	2,482 4 4	...
	Grand Trunk Road.										
	Ballee Bridge between 6th and 7th miles.	not known	iron suspension	not known ...	1 span, 240′	16 0	35 0	250 0	30,000	12,000 0 0	...
	Bangur Khall between 11th and 12th mile stones, Old Grand Trunk Road.	do ...	pucca brick masonry	do ...	1 span 10 4″	21 0	14 10	71 9	1,000	1,393 11 4	...
	Bandel between 27th and 28th mile stones.	do ...	do	do ...	1 span, 30′	16 0	22 0	260 0	10,000	3,846 2 6	...
	Cheune between 58th and 59th mile stones.	1835 ...	do	do ...	3 spans, 8′	17 0	9 0	56 0	1,256	2,242 13 9	...
	Khargram Shaikpore between 61st and 62nd mile stones.	1850 ...	do	do ...	3 spans, 36′	22 0	22 0	227 6	10,945	4,811 0 0	...
	Khargram between 62nd and 63rd mile stones.	1849 ...	do	do ...	3 spans, 20′	22 0	17¼ 0	150 0	4,724	3,149 5 4	...
	Burdwan Banka Bridge between 71st and 72nd mile stones.	1838 ...	do	do ...	5 spans— 4 of 22′ 6″ 1 of 33′	18 6	19 6	420 0	37,333	8,888 13 0	...
	Bagajorah between 121st and 122nd mile stones.	1849 ...	pucca brick and rubble stone masonry.	do ...	4 spans, 15′	22 3	17 0	72 0	8,512	11,822 3 7	...
	Singurrun River between 122nd and 123rd mile stones.	not known	iron suspension	do ...	3 spans— 1′ 142″ 2′ 59¼″	16 0	29 0	286 0	28,043	9,804 3 2	Recently dismantled.
	Kundollah between 132nd and 133rd mile stones.	1861 ...	pucca rubble stone masonry.	do ...	2 spans, 20′	22 3	16 8	54 0	5,153	9,542 9 6	...
	Bagaband between 134th and 135th mile stones.	1849 ...	do	do ...	3 spans, 15′	21 6	11 0	63 0	2,426	3,850 12 8	...
	Noniah between 134th and 135th mile stones.	1849 ...	iron suspension	do ...	3 spans— 1′ 142″ 2′ 59¼″	16 0	36 0	286 0	27,354	9,564 5 4	Recently dismantled.
	Satgong ...	not known	do	do ...	1 span, 82′	12 0	26 0	98 0	Not known	...	To be dismantled.
	Mugrah ...	do ...	wooden ...	wooden posts ...	9 spans— 8 14′ 3″ 1 20′ 9″	9 10	22 0	140 0	Do ...	...	Temporary bridge.
	Tomlah between 117th and 118th mile stones.	48-49 ...	iron suspension	masonry ...	3 spans— 1 85′ 0″ 2 23′ 9″	14 0	20 0	210 0	14,185	6,754 12 2	Recently dismantled.
	Burrakur 149th mile ...	not known	iron girder ...	masonry wells ...	9 spans, 133′	21 0	30 0	2,620 0	Not known	...	No records in this Division.

W. P. MILNE, C. E., Assistant Engineer,
for Executive Engineer, Burdwan Division.

No. 391, P. W. D. Press—10-12-81—900.

Heads of Departments.

Circular No. XXIV Public Works.

GOVERNMENT OF INDIA.

PUBLIC WORKS DEPARTMENT.

CIVIL WORKS.

Miscellaneous.

To

THE GOVERNMENTS OF MADRAS, BOMBAY, BENGAL, THE NORTH WESTERN PROVINCES AND OUDH, AND THE PUNJAB, IN THE PUBLIC WORKS DEPARTMENT.

THE CHIEF COMMISSIONERS OF THE CENTRAL PROVINCES, BRITISH BURMA, ASSAM AND COORG.

THE RESIDENT AT HYDERABAD.

THE AGENTS TO THE GOVERNOR GENERAL FOR CENTRAL INDIA, RAJPUTANA AND BELUCHISTAN.

THE ACCOUNTANT GENERAL, PUBLIC WORKS DEPARTMENT.

THE INSPECTOR GENERAL OF MILITARY WORKS.

THE DIRECTOR GENERAL OF RAILWAYS.

THE FOREIGN DEPARTMENT, FOR COMMUNICATION TO RESIDENT AT MYSORE.

Fort William, December 8, 1881.

SIR,

In continuation of Circular No. VI P. W., dated the 19th April 1881, I am directed to forward, for information, statements of areas and cost of buildings, and memorandum of construction and cost of bridges exceeding 50 feet in length, in the several Divisions* of the Central, late Presidency, Circle in Bengal.

* Circular and Eastern Canals.
1st Calcutta.
2nd ,,
Calcutta Workshops.
Burdwan.
Darjeeling.

I have the honor to be,

SIR,

Your most obedient Servant,

Major, R. E.,

Offg. Asst. Secy. to the Govt. of India.

P. W. 1881. Dept
No 76 to 84

GOVERNMENT OF INDIA.

PUBLIC WORKS DEPARTMENT.

CIVIL WORKS.

Miscellaneous.

To

Circular No. XXIV Public Works.

Dated December 8, 1881.

Received 27 Dec 1

B/ No 89 Wd/ 12th January/82

Communicated to the offices of the Public Works Dept. in continuation of G.O. 1217 W. d/ 14 May 81.

27.12.81

B. No. 89 Wd/ 12th January/82

Statements of areas and cost of buildings and memo. of construction and cost of bridges, &c., in the several Divisions of the Central, late Presidency, Circle in Bengal.

No. 391, P. W. D. Press—10-12-81—900.

S. E.
C. E. for S.
C. E. for I.
C. E. for Rys.
Secy. Supt. Surv. & Do.