(1) Number of pages 16

(2) Date of repair Aug 1987

(3) Initials of the Referencer Lavan

# TAMIL NADU ARCHIVES

## GOVERNMENT OF TAMIL NADU

Public Works DEPARTMENT

| G.O. No. / B.P. No. | 1895 — W | Press. / Mis. |
|---|---|---|
| Dated | 12-5-1883 | 193 . |

*Not to be folded or roughly handled.*

Archives — 1 10,006-9 89

1395

GOVERNMENT OF MADRAS.

PUBLIC WORKS DEPARTMENT.

Buildings and Roads.
Civil Works.

Read—the following papers :—

No. 265 T.J.

Note by the Superintending Engineer, Sixth Circle, on the estimate for constructing a Sub-Magistrate's Cutcherry at Negapatam.

The estimate is prepared with reference to G.O., No. 3121 W., of 27th November 1882. Provision is made for constructing a Cutcherry and a first-class Police station combined.

1 Plan.
1 Site Plan.
1 Estimate.
1 Duplicate Abstract Estimate.

The Cutcherry and the Station-house are to be constructed under the same roof; provision is made in the estimate to remove the present compound wall, to close up the well close by, and to divert the road at either ends of the proposed building as shown in red dotted in the accompanying site plan.

No compensation is allowed in the estimate for the land which belonging to the Municipality the Commissioners waive any claims they may have on it.

Trichinopoly,
4th May 1883.

(Signed) H. R. MEAD, Lieut.-Colonel, R.E.,
Superintending Engineer, Sixth Circle.

To the Chief Engineer, Public Works Department.

MEMORANDUM.

The plans and estimate are submitted for the sanction of Government.

2. It appears to the Chief Engineer, however, that a reconsideration of the estimated provision for roof timbers is necessary before the work is carried out, and that stone slabs under the purlins on top of cross walls seem desirable as well as under the trusses.

3. The air-holes in the lock-up and police room might with advantage be converted into barred ventilators, and it is thought that there should be a door from the guard-room into the back verandah as well as the two in front. Also that the windows of the record-room should have iron bars.

4. Out-offices of some sort seem necessary, but it is presumed there are places available, or provision would have been made for them in the estimate.

Chepauk,
11th May 1883.

(Signed) R. H. SANKEY, Colonel, R.E.,
Chief Engineer, P.W.D.

Order—dated 12th May 1883, No. 1395 W., Public Works.

The estimate, amounting to Rs. 6,420, for constructing a Sub-Magistrate's Cutcherry and Police station at Negapatam, is sanctioned.

2. A sum of Rs. 5,000 is provided for the work in the current year's Provincial Budget.

3. The attention of the Superintending Engineer is called to the remarks in the Chief Engineer's memorandum above recorded.

4. This sanction has been registered as Provincial No. 28 W. of 1883-84 and classified as Civil Buildings, Original Works.

(True Extract.)

Major, R.E.,
Under Secy. to Govt., P.W.D.

To the Superintending Engineer, Sixth Circle, with six Enclosures.
" Examiner, Public Works Accounts, with duplicate Abstract Estimate.
" Judicial Department.

Exd. C. Howarth.
Spare Copies

BUILDINGS AND ROADS.
CIVIL WORKS.

# Govt. of {1883} Madras.

PUBLIC WORKS.

*Dated May, 12th.*

*Read.* *Encl.*

**G.O., 12th May 1883, No. 1395 W.**

**MAY.**

**Sub-Magistrate's Cutcherry and Police Station at Negapatam**

*The estimate for constructing a* —, sanctioned.

Note

It seems to me with reference to T's para 3 that neither pankas nor punkah pole are required in "Jail wards" or "Lock-ups".
Further the lengths given in Estimate for punkahs & wall punkahs seem to me incorrect. How do I think all the scantlings of roof timbers correct. However altering them would affect the Estimate but very slightly & on the whole they are quite adequate.
In drafting order & sanction it might be said that re consideration of Estimate provision for roof timbers & masonry piers carrying out the ends, and that returns shds under the punkahs on E/F of cross walls seem necessary as well as under the trusses.—
I agree with T that the air holes had better be converted into barred ventilators.
I rather think there might be a door from Guard Room into the back verandah as well as the two in front, and I am inclined to think the circular Record Room should have iron bars.
Architect of course best can measure, but it is presumed there are plans & that a panka is really required.

CS
7/5.

Public Works Department, 188 8.

3/1395

Current No. 3830
Letter No. 205 TJ
Dated the 2nd May 83
From the Engr Expr & Circle

Note of Remarks.

1. Recommends plans and estimate, Rs. 9,420, for the construction of Sub Mag's & Taluk cutcherry and police station at Negapatam — passed.
2. The plans now sent correspond, so far as court house, receiving room, clerks and record rooms are concerned, with the standard; but the arrangements for the police and prisoners differ from those laid down in the standard.
3. The arrangement of the roof timbers over 'Jail wards' is somewhat confused, judging from the estimate there provision is made for 'Queen posts' but scantlings of the other roof timbers are

correct.

4. It would be an improvement if all the 'div. tables' as now provided in the lock-up and police were transformed into ventilators of the same dimensions as those at the end face of the lock-up.

5. It is to be noted no outoffices have been provided.

6. The estimate has been countersigned by the Collector.

8th May/83

Dgs

Forwarded.

Cr

8/5

C. No. 3836

4/1395 P. W. Secretariat.

**Note by Budget Section.**

Work Construction of a Civil Magistrate's cutchery and police station at Negapatam

Remarks and References.

Fund Provincial

Service Head Civil Buildings

Departmental Head Original Works

| | | |
|---|---|---|
| Amount of Estimate ... ... ... ... | Rs. | 6420 |
| Expenditure in previous year ... ... | " | " |
| Allotment in current year ... ... ... | " | " |
| Balance required to complete ... ... | " | 6420 |
| Total Rs. | | |

Note of available funds.

Rs 6000 provided in provincial budget for 1883-84 for constructing a new Civil Magistrate Cutchery at Negapatam

10/5

Budget Clerk.

No: 265 T.J

5/1395

Note by the Superintending Engineer Circle on the estimate for Constructing a Sub-Magistrates Kutcherry at Negapatam.

Index 3+1=4
1 Plan
1 Site plan
1 Estimate
3
1 Duplicate abstract Estimate

The estimate is prepared with reference to G.O. No 512 W of 27th November 1882. Provision is made for Constructing a Kutcherry and a first class Police Station Combined.

The Kutcherry and the Station house are to be constructed under the same roof; provision is made in the estimate to remove the present Compound wall, to close up the well close by, and to divert the road at either ends of the proposed building as shown in red dotted in the accompanying site plan.

No Compensation is allowed in the estimate for the land which belonging to the Municipality the Commissioners waive any claims they may have on it.

Trichinopoly
11th May 1883.

Dy Engineer, Circle.

P.W.C. No 3836

From.

The Supt. Engineer
6th Circle

To.

The Chief Engineer
P. W. D.

No 265 T.T.

Dated 4th May 1883.

Rec'd 7th " 2 Class
G.O. 1395 Wdg 12-5-83

Sub. Magistrate's Kutcheri & Police Station at Negapatam.

Submits for sanction an Estimate of Rs 6,420 for constructing a-

6/1395 Ga P.W.D.

Memorandum by the Chief Engineer.

The plans and estimate are submitted for the sanction of Government.

2. It appears to the Chief Engineer however that a reconsideration of the estimated provision for roof timbers is necessary before the work is carried out, and that stone slabs under the purlins on top of cross walls seem desirable as well as under the trusses.

3. The air-holes in the back wall of police rooms might with advantage be converted into barred ventilators, and it is thought that there should be a door from the guard room into the

the back verandah as well as the two in front. Also that the windows of the record room should have iron bars.

4. Out offices of some sort seem necessary but it is presumed there are places available, or provision would have been made for them in the estimate.

A. Lawley Colonel R.E.
Chief Engineer, P.W.D.

Chepauk
11th May 1883

A/

13 & 14

7/1395 No. 1395W PUBLIC WORKS DEPARTMENT.

## PROCEEDINGS OF THE MADRAS GOVERNMENT.

UNDER date the 12th May 83.

READ the following

From,
The Supt. Engineer 6th Circle (No. 765 J.J. 24th May 83)

Memo. by the Chief Engineer P.W. Dept. (" " — " 11th do)

The estimate amounting to Rs 6,420 for constructing a Sub-magistrates Cutcherry and police station at Negapatam, is sanctioned.

2. A sum of Rs 5,000 is provided for the work in the current year's Provincial Budget.

3. The attention of the Superintending Engineer is called to the remarks in the Chief Engineer's memo;

Memo: above recorded.

4-. This sanction has been registered as Provincial Sch. 28 Yr of 1883-84 and classified as Civil Buildings, Original Book No.

Cir / Cy. 1115.

13950

Supt Engineer, Lucknow Circle with 6 encls:
Exec. Engr. Accts with duplicate abstract Contl. Judicial Departt. -7
Dep. Secy
18/5

25/5/97

3834

# Govt. of [1883] Madras.

PUBLIC WORKS.

Dated 15/5

Read 12th May 1883 Rec'd. No. 1397 Sto

G. O., 17 ~~April~~ 1883, No. 1305 W

Nos.

Sub Magistrate Cuttack and Police Station at Nepapalam.

Re Criminal Jurisdiction over Ranetik.

H S
5

Entered in Record Register