

(1) Number of pages 20 C/O Shree
(2) Date of repair 12/11/87
(3) Initials of the Referencer lona

TAMIL NADU ARCHIVES

GOVERNMENT OF TAMIL NADU

P. W.

DEPARTMENT

G.O. No.	2261	— W	Press.
B.P. No.			Mis.
Dated	14-8-1882		198

Not to be folded or roughly handled

2261
1

GOVERNMENT OF MADRAS.

PUBLIC WORKS DEPARTMENT.

Buildings and Roads.
Civil Works.

READ—the following papers:—

No. 216 M.D.

Report by the Superintending Engineer, Sixth Circle, on estimate for improving stables and godowns attached to the Sub-Collector's bungalow at Dindigul, Rs. 2,233.

The estimate was called for in G.O., No. 630 W., dated 27th February 1883.

1 Abstract Estimate.
1 Plan.

2. The roof of the building is carried on on Malabar trusses, several of which are bent and have sagged. All the rafters,

purlins and wall-plates, as also uprights and horizontal pieces of trusses, are decayed by dry-rot, &c., and the roof has in consequence sagged to such an extent as to make the buildings very unsafe. It is therefore necessary to remove and re-roof it with an ordinary couple roof with palmyra rafters and junglewood reepers.

3. The walls are to be whitewashed, repaired, and raised where necessary to allow a slope of $1\frac{1}{2}$ to 1.

4. Several of the doors are in a very bad state; they are to be replaced by new ones with jambs and soffits built in brick in mortar to a length of $1\frac{1}{2}$ feet.

5. The portions enclosed by A, B, C, D, in plan being in excess of the requirements, it is to be demolished and the site cleared.

6. The estimate has the approval of the Collector, and is recommended for sanction.

7. The Superintending Engineer regrets much the great delay in the submission of this estimate; it ought to have been submitted at least three months ago, sickness and changes of officers and subordinates is the reason of the delay.

KODAIKANAL,
30th July 1883.

(Signed) H. R. MEAD, Lieut.-Colonel, R.E.,
Superintending Engineer, Sixth Circle.

From Lieutenant-Colonel H. R. MEAD, R.E., Superintending Engineer, Sixth Circle, to the Chief Engineer, Public Works Department, dated Kodaikanal, 4th August 1883, No. 224 M.D.

With reference to your No. 1414 C., dated 31st ultimo, directing me to execute, with the least possible delay, the necessary repairs to the out-buildings in the compound of the Sub-Collector's bungalow at Dindigul, I have the honor to report that an estimate for improving stables, &c., was submitted for the sanction of Government with my No. 216 M.D., dated 30th ultimo.

2. An application for funds is also being submitted for sanction.
3. As the work is emergent, I have instructed the Executive Engineer, Madura Division, to commence it in anticipation of sanction to the estimate.

ORDER—dated 14th August 1883, No. 2261 W., Public Works.

The estimate, amounting to Rs. 2,233, for improvements to the out-buildings of the Sub-Collector's bungalow at Dindigul, is sanctioned.

2. No funds being immediately available, the Superintending Engineer will propose a redistribution of budget credits in view to the early execution of the work.

3. This sanction has been registered as Provincial No. 90 W. of 1883-84 and classified as Civil Buildings, Original Works.

(True Extract.)

(Signed) R. H. SANKEY, Major-General, R.E.,
Secretary to Govt., P.W.D.

To the Superintending Engineer, Sixth Circle, with two Enclosures.
" Examiner, Public Works Accounts.
" Revenue Department.

2261
2

BUILDINGS AND ROADS.
CIVIL WORKS.

Govt. of (1883) Madras.

PUBLIC WORKS.

Dated August, 14th.

Recd.

Encl.

G.O., 14th Aug. 1883, No. 2261 W.

AUGUST.

Sub-Collector's Bungalow,
Dindigul

Estimate for improvements to the out-build-
ings of the —, sanctioned.

2261
3

4TH JUNE 1883, No. 1548 W., PUBLIC WORKS.

GOVERNMENT OF MADRAS.

PUBLIC WORKS DEPARTMENT.

General.
Establishment.

READ—the following letter from Lieutenant-Colonel H. R. MEAD, R.E., Superintending Engineer, Sixth Circle, to the Chief Engineer, Public Works Department, dated Trichinopoly, 23rd May 1883, No. 97 M.D. :—

I have the honor to bring to your notice that, under paragraph 1229 of the Code, I fixed the rent to be paid by the Sub-Collector at Dindigul at Rs. 65 a-month and informed the Collector I had done so.

2. I am now in the receipt of G.O., No. 1466 W., of 21st May, forwarding G.O., No. 1937, dated 11th May, in the Revenue Department, on Proceedings from the Board of Revenue sanctioning their request that the rent of Rs. 65 (said to be proposed by me) should be sanctioned.

3. I venture to point out that this order was not necessary; the Code lays on me the disagreeable duty of fixing these rents, which in this case I have done, and therefore no further order was required under the Code.

4. I request to be informed if, in future, I am to fix rents as laid down in the Code, or if I am only to propose them for the approval of the Board of Revenue or any other Department and for the sanction of Government.

5. I submit that it would be best for the Code ruling to be adopted, viz., for me to fix the rents finally; of course, should any officer consider himself aggrieved, he will be at liberty to appeal to Government.

ORDER—dated 4th June 1883, No. 1548 W., Public Works.

The views expressed by the Superintending Engineer are generally correct, but the Government consider that no special ruling on the subject is required. The attention of the Superintending Engineer is called to the first sentence of Code, paragraph 1229, which states that the rent to be recovered, when not fixed by a particular order of Government, shall in each case be fixed by the Superintending Engineer of the Circle.

2. In the particular case in point, however, the rent having already been fixed by the Superintending Engineer, it is considered in the Public Works Department that the sanction given in Revenue Department Order, No. 1937, dated 11th May 1883, was not necessary.

(True Extract.)

(Signed) R. H. SANKEY, Colonel, R.E.,
Secretary to Govt., P.W.D.

To the Superintending Engineer, Sixth Circle.
" Other Superintending Engineers.
" Examiner, Public Works Accounts.
" Revenue Department.
" Board of Revenue.

Exd. C. Howarth,
Spare Copies

GENERAL
ESTABLISHMENT.

Govt. of (1883) Madras.

PUBLIC WORKS.

Dated June, 4th.

Recd.

Encl.

G.O., 4th June 1883, No. 1548 W.

JUNE.

Rent of Buildings

Passing orders on letter from the Superin-
tending Engineer, Sixth Circle, regarding
fixing the —.

226/

Public Works Department, 1883-84.

Current No. 6589

Letter No. 216-M.D.

Dated the 30th July 1883

From the Supg Engr 6th Circle

NOTE OF REMARKS.

1. The accompanying plan and estimate, Rs 2,233, provide for repairing and improving the stables attached to the sub-Collector's bungalow at Dindigul.
2. It would be safer if the scantlings of rafters were 3"x6" and not as now 3"x5"
3. The estimate has been countersigned by the ag. collector

4th August/83
RSTH

For orders

Cu
24/8

I don't know how piling ra-
fters are affected as to electricity. I
fear of both the scantling 3"x5" is
as shown in section A.B. would be
insufficient. — It is not stated
how far apart and to center the
rafters are spaced & another point
is that flat tiles are not to be used.
From this I infer that S.E. is
satisfied that the dimensions are
correct — so sanction without
comment

CP
6/9

C. No. 6564

226/5

P. W. Secretariat.

Note by Budget Section.

Work

Remarks and References.

Improving the Stables
attached to the Sub. Collector's
bungalow at Dindigul in
the Madurai Division.

Fund Provincial

Service Head Civil Buildings

Departmental Head Principal Works

Amount of Estimate Rs. 2238

Expenditure in previous year "

Allotment in current year "

Balance required to complete 2238

Total Rs. _____

Note of available funds.

The Minor Works or Revenue grant is
only Rs. 355, deducting the transfer of Rs. 1500 from
the current Civil Budget allotment.

Supy. Eng. may be asked to prepare
a distribution of the budget credit.

M. S. S.
Budget Clerk.

Note by Budget Section.

W. 216 M. 15. 226/

Report by the Superintending Engineer, to include an Estimate for Improving Stables & Godowns attached to the Sub. Collector's Bungalow at Dindigul Rs 2233.

Encls: 2.

1. abstract estimate plan.

The Estimate was called for in G.O. No 630W dated 27 February 1883.

2. The roof of the building is carried on, on Malabar Smoores several of which are bent and have sagged. All the rafters, purlins and wall plates as also uprights & horizontal pieces of Smoores are decayed by dry-rot &c and the roof has in consequence sagged to such an extent as to make the buildings very unsafe. It is therefore necessary to remove and re-roof it with an ordinary couple roof with palm-leaf rafters and junglewood rafters.

3. The walls are to be white washed, repaired and raised where necessary to allow a slope of $1\frac{1}{2}$ to 1.

4.

4. Several of the doors are in a very bad state they are to be replaced by new ones with jambs and soffits built in Bricks in mortar to a length of $1\frac{1}{2}$ feet.

5. The portions enclosed by A. B. C. D. no plan being in excess of the requirements it is to be demolished and the site cleared.

6. The estimate has the approval of the collector and is recommended for sanction.

7. The Superintending Engineer regrets much the great delay in the submission of this estimate, it ought to have been submitted at least 3 months ago. Sickness & changes of officers & subordinates is the reason of the delay.

MM Hunt Lt Col 1096

Sup^r Engineer, Bridge.

2261

N^o 1645630 W. 27.2.83
a 362 W. 1.2.83
u 235 C. 22.1.83
G.O. 2957 W. 9.11.82.

W.C. No. 6569

From,

The Sup^r Engineer
b: Circle

To,

The Chief Engineer
P. W. D.

No. 216 M.D.

Dated 30th July 1883.

Re: 216 M.D.

Encls: 2

Stables & attached
to the Sub Collector's
bungalow at Dindigul —

Forwarded for
sanction are estimate
of Rs 2233 for im-
proving the —

No. 224 M.D. Sup^r Engineer's office, Circle.
226/8
From Rodaikanal. 4th August 1883.

The Superintending Engineer
b: Circle.

To,

The Chief Engineer
P. W. D.

Sir,

With reference to your No. 1414C dated
31st Ultimo directing me to execute with
the least possible delay the necessary repairs
to the out buildings in the compound of
the sub. collector's Bungalow at Dindigul
I have the honor to report that an estimate
for improving stables &c was submitted
for the sanction of Government with my
No. 216 M.D. dated 30th Ultimo.

2. An application for funds is also
being submitted for sanction.

3. As the work is urgent I have
instructed the Executive Engineer Madurai
to commence it in anticipation of sanction
to the estimate.

I have &c.

M. M. M. Kbe
Sup^r Engineer, Circle.

02513.8
copy 9/8 M.D. 13/8

B. 1466-41.5-83
A. 1548-41.6-13
1413-14C 31.7.83

Dr. C. M. 6720

From,

The Super Engineer
6: Circle

To,

The Chief Engineer
P. W. D.

No. 224 M.D.

Dated 14 August/83.

Out-houses in the
compound of the
Sub Collector's
bungalow at
Dindigul —

States that an
estimate for im-
proving the — was
submitted on the 30th
ultimo —

2261

No. 2261 W

PUBLIC WORKS DEPARTMENT.

PROCEEDINGS OF THE MADRAS GOVERNMENT.

Under date the 14 Aug/83

Read the following

From the Suply. Engineer

6th Circle

M.E. No. 216. M.D. 30th July/83

80

224 M.D. 4 Aug/83

The estimate
amounting to Rs. 2233, for improvements
to the outbuildings of
the Sub Collector's banga-
low at Dindigul, is
sanctioned.

2. No funds being
immediately available,
the Superintending Engineer
will propose a redistribu-
tion of budget credits
in view to the early
execution of the work.

3. This sanction
has been registered as

as Provincial N^o 40 a
of 1883-84, and classified
as Civil Buildings
original works

W/

W/

11/1/83

- 82574 sub

Input

14/11

Ch 6700020

for this paper

+ 82574 13/8

10/8

To
The Suply. Engr. Sixth Lrd
with 2 enclosed

By and P. P. W. Acct.

Revenue Department

21/8

2261
10

6569
6720

Govt. of (1883) Ind. Is.

PUBLIC WORKS.

Dated

Recd.

Encl.

G. O., 14 August 1883, No. 2251

Nos.

Sub. Charles Brangton,
Diadigul

Estimate for improvements
to the outbuilding of the
Sanctuary

Sanctuary in Rept. Register