

(1) Number of pages 12
(2) Date of repair 3 7 87
(3) Initials of the Referencer lana ✓

TAMIL NADU ARCHIVES

GOVERNMENT OF TAMIL NADU

*P*UBLIC WORKS DEPARTMENT

G.O. No.	2316 W	Press.
B.P. No.		Mis.
Dated	17. 8. 1883	198

Not to be folded or roughly handled

Archives I--10,006 I -80.

GOVERNMENT OF MADRAS.

PUBLIC WORKS DEPARTMENT.

Buildings and Roads.
Civil Works.

READ—the following paper :—

No. 328.

Report to accompany the estimates for constructing quarters for Sub-Registrars and their Clerks at Vayitri and Gúdalúr, in the Nilgiri Division.

The estimates, amounting to Rs. 2,200 each, were prepared on the accompanying design as ordered in G.O., No. 1672 W., dated 3rd July 1882, to provide house accommodation for the Sub-Registrars and their Clerks at Vayitri and Gúdalúr.

2 Site Plans. | 2 Abstracts.
1 Plan. | 2 Specifications.

2. The proposed accommodation for each station will consist of a room measuring 12 feet by 10 feet for the Sub-Registrar, and another 10 feet square for his Clerk, with kitchen 5 feet wide in rear, and a verandah 4 feet wide in front, of the building; the roof to be of couples and collar beams and covered with mission tiles, with $\frac{3}{4}$ inch thick planking nailed to the lower side of the couples.

3. The plans and estimates have been approved of and countersigned by the Inspector-General of Registration.

4. Site plans for the erection of these buildings are also herewith sent.

5. If the estimates be sanctioned at an early date, the works may be carried out before the end of the current official year.

COIMBATORE,
8th August 1883.

(Signed) J. BEATTY, Colonel, R.E.,
Superintending Engineer, Fourth Circle.

ORDER—dated 17th August 1883, No. 2316 W., Public Works.

The undermentioned estimates, for constructing quarters for Sub-Registrars and their Clerks at the following stations, in the Nilgiri Division, are sanctioned for execution when funds are available :—

	Amount of Estimate.	Register No.
	RS.	
Vayitri	2,200	No. 92 W. of 1883-84.
Gúdalúr	2,200	No. 93 W. of 1883-84.

2. These sanctions have been registered as Provincial Nos. 92 and 93 W. of 1883-84 and classified as Civil Buildings, Original Works.

(True Extract.)

Major, R.E.,
Under Secy. to Govt., P.W.D.

To the Superintending Engineer, Fourth Circle, with five Enclosures.
" Examiner, Public Works Accounts.
" Judicial Department.
" Inspector-General of Registration.
Ed. A. F. Goodall.
Spare Copies

BUILDINGS AND ROADS.
CIVIL WORKS.

Gobt. of (1883) Madras.
PUBLIC WORKS.

Dated August, 17th.

Recd.

Encl.

G.O., 17th Aug. 1883, No. 2316 W.

AUGUST.

Quarters

Estimates for constructing — for Sub-Registrars and their Clerks at Vayitri and Gúdalúr, Nílgi Division, sanctioned.

N^o 328

Supg Engineer's Office 4th Circle
Bombay, 8th August 1883

2316

Report to accompany the estimates for constructing Quarters for Sub-Registrars and their clerks at Vythori and Gúdalúr in the Nílgi Division.

The estimates amounting to Rs. 2,200 each were prepared on the accompanying design as ordered in G.O. N^o 1672 dated 3rd July 1882, to provide house accommodations for the Sub-Registrars and their clerks at Vythori and Gúdalúr.

2 The proposed accommodation for each station will consist of a room measuring 12 feet by 10 feet for the Sub-Registrar, and another 10 feet square for his clerk, with kitchen 5 feet wide in rear, and a verandah 14 feet wide in front of the building; the roof to be of couples and collar beams and covered with mission tiles, with $\frac{3}{4}$ inch thick plankings nailed to the lower side of the couples.

3 The plans and estimates have been approved of and countersigned by the Inspector General of Registration.

4. Site plans for the erection of these buildings are also herewith sent.

5 If the estimates be sanctioned at an early date the works may be carried out before the end of the current official year.

L. Seatty - Col. R. E.
Superintending Engineer
4th Circle.

2316
3

B 1672 ~ 3.7.82

PWC No. 6806
From
The Supg. Engineer,
Fourth Circle.

Dated 8th
Sept. 9th } August/83.
Recd 10

No: 328

Inc: 4. (3 plans)

Quarters for sub. Registrars
and their Clerks at Tago-
theri and Gudalur:-

Report to accom-
pany the 2 Estimates
of Rs: 2200 each for con-
struction —

12/25/8
13/8 12/8 12/8

12/25/8

Public Works Department, 1883-84

Current No. 6806
Letter No. 328
Dated the 8th August/83
From the Supg. Engr. 4th Circle

NOTE OF REMARKS.

1. The accompanying estimate and plan provide for the construction of quarters for a sub Registrar and his clerk at Tago-theri at a cost of Rs. 2200. A similar building is to be erected at Gudalur at the same cost.
2. The foundations are to be of rough stone in chunnam, the rest of the masonry being of brick in chunnam.
3. Plan and estimate have been countersigned by the Insp. Genl of Registration.

11th August/83
RTH

B

2316
4

No 2316 W

PUBLIC WORKS DEPARTMENT.

2316
5

PROCEEDINGS OF THE MADRAS GOVERNMENT.

UNDER date the

17th Aug 1883

Read the following

Letter from the Supt. Engrs
to the Govt.

N.O. No 328 of 8th August 1883

The undersigned
submits for consideration
grants for Sub Engineers
and their clerks at the
following stations, in the
Mylapore Division are some-
times for recreation when
funds are available.

	Amount of Estimate	Grants to
Mythore	2200	No 92 W of 1883. 84
Indalur	2200	No 93 W of 1882. 84

2. These sometimes have
been registered as Provincial
Nos 92 and 93 W of 1882-
84, and classified as Civil
Engineering. Original Grants.

The Supt. Engrs. to the Govt., with
- Accounts P.M. Accounts
- Individual Engrs
- in separate form of Departmental
- 10/8

13/8
14/8

12-11-83 6800

Govt. of (1883) Madras.

PUBLIC WORKS.

Dated

Recd.

Encl.

G. O., 19th Aug 1883, No. 2316

Nos.

Quotations

Estimates for Construction

for sub. Registrars &
their clerks at
Vythiri & Gudalur,
Nilgiri Division, S. Can.

At Registrar