29/93/56/93

102/93

(1) Number of pages 10.

(2) Date of repair 13.7.87

(3) Initials of the Referencer

TAMIL NADU ARCHIVES

GOVERNMENT OF TAMIL NADU

Public Works DEPARTMENT

G.O. No. 2620 W. Press.
B.P. No. Mis.

Dated 17-9-1883. 198 .

S.C.N.

Not to be folded or roughly handled.

Archives —1 10,006-9 88

No 1146 T.V. 2620/1

Report by the Superintending Engineer VI Circle on the Estimate for Constructing a Sub-Registrar's Office at Vellum in Tanjore District Rs 2,240.

Encls: 1 Estimate.

This Estimate is prepared in accordance with instructions contained in G.O No 1176 W of 9th May 1881, and Countersigned by the Inspector General of Registration.

2 The Plan is based on the Standard design Sheet No 21 that accompanied G.O No 120 W of 14th January 1882.

3 The Site selected for the Contemplated Building has been approved of both by the Collector and the Inspector General of Registration. A Compensation of Rs 180 is allowed in the Estimate. The soil of the Ground is reported to be soft red Earth mixed with Gravel, the depth of the foundation viz 1 foot Concrete and 3 ft Masonry is considered sufficient.

1.

4 Weather boards have been provided to side Windows of Clerks & Sub-Registrars room.

5 The work can probably be Completed in 9 months after Sanction and allotment of funds.

W W Burn Lieut Col R.E.
Superintending Engineer 6th Circle
Kodaikanal.
8th September 1883.

2620/7

A. 1176 W 9.5.81
A. 120 W 14.1.82

Pw.Ch.7838

From

The Supt. Engineer
6 circle.

To

The Chief Engineer
Pw.D

No 1146 T.J
Dated 8th } September/83.
Rec'd.
Ex 6 (1 plan)

Sub. Registrar's office
at Vallam:—

Forwards for sanction an Estimate for Constn of the —

J/

Pr 15-9
Wks 13/9 Retd 17/9

Public Works Department, 1883-84.

Current No. 7838
Letter No. 1146 T.J
Dated the 8th Sept/83
From the Supt. Engr. 6th Circle

2620/3

Note of Remarks.

1. The enclosed is an estimate for the construction of a Sub-Registrar's office at Vallam Tanjore. The estimate amounts to Rs. 2,240.
2. With the exception of certain necessary alterations in the basement and foundations, the estimate conforms with the Standard Land sanctioned under G.O. No. 120 PW of 14/1/82.— Rs 150 are allowed for land compensation and Rs. 25 for 2 weather boards
3. The estimate has been countersigned by the Inspr. Genl. of Registration.

13th Sept/83
PWK

2620/3

PJ

Rs 2620 W

PUBLIC WORKS DEPARTMENT.

PROCEEDINGS OF THE MADRAS GOVERNMENT.

2629/4

UNDER date the 17th Sept 83.

READ the following

Letter from the Supt. Engr. Sixth Circle, No. 2.P. No 1140 T.T. of 8th Sept 1883

The estimate amounting to Rs 2240, for constructing a Sub Registrar's office at Vallam, on the Tanjore Division is sanctioned for execution, for which funds are available.

This sanction has been registered as Provincial No 116 of 1883-84, under class V. Civil Buildings, Provincial Works.

Dno 22/9

The Supt Engr Sixth Circle with Drawings.
" Examiner P.W. Accounts
" Inspector General of Registration
" Judicial Department
Survey Dept

22/5

3710 D.

Govt. of 1883 Madras.

PUBLIC WORKS.

Dated

Rec^d Entd.

G.O. 17 September 1883, No. 2620

Nos.

Sub-Registry Office

Transmitting for Sanctioning

a — at Valkum

in Tanjore District!

Sanctioned.

5/4

/5

Entd in Rect Register