

(1) Number of pages 10

SH. (2) Date of repair _____

(3) Initials of the Referencer SH ✓

TAMIL NADU ARCHIVES

GOVERNMENT OF TAMIL NADU

F.W.D. DEPARTMENT

G.O. No.
B.P. No.

1290

Press.
Mis.

Dated

23. 5. 1884 197 .

Not to be folded or roughly handled

BSH

60
23RD MAY 1884, No. 1290 W., PUBLIC WORKS.

GOVERNMENT OF MADRAS.

PUBLIC WORKS DEPARTMENT.

Buildings and Roads,
Civil Works.

READ—the following paper:—

No. 7 C.

Report by the Superintending Engineer, VI Circle, on the estimate for reconstructing a portion of road No. XI, from Vasudavanallur to Srivilliputtur taluk limits, in the Tinnevely district, Rs. 35,600.

The portion of road is 9 miles and 293 yards long and crossed by 46 streams and channels. The estimate provides for raising the road where necessary, metalling and constructing masonry works across 42 minor streams, leaving 4 of the large ones unbridged for the present. The surface of the road to be 18 feet wide of which 9 feet are to be metalled 6 inches thick and gravelled over $1\frac{1}{2}$ inches thick.

- 3 Plans.
- 1 Index map.
- 1 Report.
- 2 Detailed estimates.
- 2 Abstract do.
- 1 General abstract.
- 1 Copy of Local Fund Board's proceedings, dated 16th April 1884.
- 1 President's letter, No. 55, of 16th April 1884.

2. It is observed from the papers that the Local Fund Engineer has thoroughly

examined the work and satisfied himself as to the sufficiency of water-way and the depth of foundations allowed for the culverts, and the plans for the work are very carefully prepared.

3. The rates are fair and the estimate is recommended for sanction.

4. As the amount of the estimate exceeds Rs. 10,000, the President's letter to the Board of Revenue, the estimate, &c., are sent to the Chief Engineer for his approval.

KODAIKANAL,
3rd May 1884.

(Signed) H. R. MEAD, Lieut.-Col., R.E.,
Superintending Engineer, VI Circle.

ORDER—dated 23rd May 1884, No. 1290 W., Public Works.

The estimate, amounting to Rs. 35,600, for reconstructing a portion of road XI, from Vasudavanallur to the limit of the Srivilliputtur taluk, in the Tinnevely district, is sanctioned, and registered as Local No. 9 W. of 1884-85.

(True Extract.)

Major, R.E.,
Under Secy. to Govt., P.W.D.

To the Board of Revenue, with thirteen enclosures.
„ Superintending Engineer, VI Circle.
„ Financial Department.

Exd. E. Fernandez.
Spare Copies

BUILDINGS AND ROADS.
CIVIL WORKS.

Govt. of (1884) Madras.

PUBLIC WORKS.

Dated May, 23rd.

Recd.

Encl.

G.O., 23rd May 1884, No. 1290 W.

MAY.

Road

Estimate of Rs. 35,600 for reconstructing a portion of — No. XI, from Vasudavanullur to the limit of the Srivilliputtur taluk, Tinnevely district, sanctioned.

W. J. C.

1290/2

Report by the Superintending Engineer to be made on the estimate for reconstructing a portion of Road No. XI from Vasudavanullur to Srivilliputtur Taluk limits in the Tinnevely District Rs. 35,600.

Encls. 12

3 Plans sent separately.

1 Index map.

1 Report

2 Detailed sketch by H. B. streams and channels.

2 abstracts —

1 G. O. abstract

1 Copy of L. J.

B. O. Pro. of

16th April 1884

1 President's

letter No. 55

16th April 1884

The portion of Road is 9 miles + 293 yards long and crossing 46 streams and channels. The estimate provides for raising the Road where necessary, metalling and constructing masonry works across 42 minor streams, leaving 4 of the large ones unbridged for the present. The surface of the road to be 18 feet wide of which 9 feet is to be metalled 6 inches thick and gravelled over 1½ inches thick. It is observed from the papers that the Local Fund Engineer

has thoroughly examined the work and satisfied himself as to the sufficiency of water-way and the depth of foundations allowed for the culverts and the plans for the work are very carefully prepared.

3. The rates are fair and the estimate is recommended for sanction.

4. As the amount of the estimate exceeds Rs 10,000, the President's letter to the Board of Revenue, the estimate &c are sent to the Chief Engineer for his approval.

 Lieut. Col. R.B.

Superintending Engineer
b. Circle

Koduvakaval
3rd May 1884.

1290
3

From, (2)
The Sup^r Engineer
P. W. D.

To,
The Chief Engineer
P. W. D.

No 7 C

Dated 3rd May 1884.
Encls 12.

No 1290 of 23rd May/84

Portion of Road No.
XI from Vasudava-
nallur to Strivilliputhur

Forwarded for
approval estimates
for reconstructing
a —

PUBLIC WORKS DEPARTMENT.

PROCEEDINGS OF THE MADRAS GOVERNMENT.

Under date the 23rd May/84
Read the following

From the Suptg. Engr^g VI Circle } H. G. No 7 C of 3rd May 1884.

The estimate amounting
to Rs 35,600, for reconstructing
a portion of Road XI from
Vasudavanallur to the limit
of the Strivilliputhur taluk,
in the Tinnavelly District, is
sanctioned and registered as
Local No 9. W of 1884-85.

Board of Rev. with 13 encls:

S. E. VI Circle

Encl. Dept.

(Ch. Secy. for Comtee initials)

Cy.
15-5-84

W
17-5-84

FW
19/5/84

Cy

Govt. of (1884) Madras.

PUBLIC WORKS.

(5)

27/5/14

Dated

Read

By

G.O. 23 Aug 1884, No. 1290

Road

Estimate of Rs 35,600
 for reconstructing
 portion of
 No 11 from Vasudavara
 = nullur to the limit
 of the Srivilliputhur
 taluk, Tiruvellu District
 situated

60
/5

S. S. S. S. S.