

(1) Number of pages 22
(2) Date of repair Oct 1987
(3) Initials of the Referencer low ✓

TAMIL NADU ARCHIVES

GOVERNMENT OF TAMIL NADU

DEPARTMENT

PW

G.O. No.	2254 W	Press.
B.P. No.		Mis.
Dated	28.9.1885	198 .

Not to be folded or roughly handled

28TH SEPTEMBER 1885, No. 2254 W., PUBLIC WORKS.

GOVERNMENT OF MADRAS.

PUBLIC WORKS DEPARTMENT.

Buildings and Roads.
Civil Works.

READ—the following letter from Colonel H. D. CLOETE, Inspector-General of Police, to the Chief Secretary to Government, dated Madras, 24th August 1885, No. 4980:—

I have the honor to forward for sanction Public Works Department site-plan and estimates, &c., amounting to Rs. 1,340, for the construction on the standard design of four huts at Virudupati, Tinnevely district.

2. The site for the work has been secured.

No. 1577, Judicial.

Approved and transferred to the Public Works Department.

OOTACAMUND,
5th September 1885.

(By Order.)

(Signed) A. G. CARDEW,
Acting Assistant Secretary.

ORDER—dated 28th September 1885, No. 2254 W., Public Works.

The estimate, amounting to Rs. 1,340, for constructing four police huts at Virudupati, in the Tinnevely district, is sanctioned for execution when funds are available.

2. This sanction has been registered as Provincial No. 126 W. of 1885-86, and classified as Civil Buildings, Original Works.

(True Extract.)

Lieut.-Col., R.E.,
Offg. Under Secy. to Govt., P.W.D.

To the Superintending Engineer, VI Circle, with three enclosures.

„ Examiner, Public Works Accounts, with the estimate

for note and return to Superintending Engineer, VI Circle.

„ Judicial Department.

Ed. J. Henricus.
Spare Copies

BUILDINGS AND ROADS.
CIVIL WORKS.

Govt. of Madras

PUBLIC WORKS.

Dated September, 28th.

Recd.

Encl.

G.O., 28th Sept. 1885, No. 2254 W.

SEPTEMBER.

Police Huts at Virudupati,
Tinnevely District

Estimate for —, sanctioned.

2254
2

GOVERNMENT OF MADRAS.

PUBLIC WORKS DEPARTMENT.

14th January 1880, No. 93 W.

Buildings and Roads.
Civil Works.

Read the following papers:—

- No. 21. From the Consulting Architect, dated 12th December 1879, No. 558.
No. 21-A. " Inspector-General of Police, dated 23rd December 1879,
No. 5,817.

No. 22. ORDER THEREON, 14th January 1880, No. 93 W.

THE Government approve the standard designs for Police huts submitted by the Consulting Architect, and direct their adoption in supersession of all previous designs for such buildings.

2. The designs will be lithographed and the specification and estimate of quantities printed, and circulated for the information of the Department.

(True Extract.)

(Signed) R. H. SANKEY, Colonel, R.E.,
Secretary to Govt., P.W.D.

To all Superintending Engineers.
To the Consulting Architect.
" Judicial Department.

End. A. F. Goodall.
Spare Copies

BUILDINGS AND ROADS.
CIVIL WORKS.

Govt. of (1880) Madras.
PUBLIC WORKS.

To

ALL SUPERINTENDING ENGINEERS.

Ac., &c., &c.

Dated January 14th.

Issued

Recd.

Encl.

G. O., 14th January 1880, No. 93 W.





JANUARY.
Nos. 21-22.

Standard Designs for Police Huts.—
Approves the —, and directs their adoption
in supersession of all previous designs for
such buildings.

5/50

GENERAL DESIGN FOR POLICE HUTS

BUILT OF BURNT BRICK IN MUD AND TILED



PLAN

G.O. No 93 W dated 14 January 1880

Chief Office of the Insp. Genl of Police
Madras 23rd December 1879

(Signed) T. K. Ganthir. Major
By Insp. Genl of Police
for Insp. Genl of Police

(Signed) B. F. Chelvan
Cons. District Government

Th. P. S.
Major R. E.
By Chief Engineer P.W.D.

STANDARD DESIGN FOR POLICE HUTS.

DESIGN No. 2.

2254
4

General Specification of Works to be performed in erecting one pair of Police huts with walls of burnt brick laid in mud and tiled roofing.

Excavation.—Excavate the trenches to the various depths shown on the drawing and well ram and pun the beds.

Bricklayer.—Ram in 6 inches of concrete and bring to a sound, well consolidated state and an even upper surface.


Build the walls in bricks cast from a mould $10" \times 5" \times 3"$ well burnt and laid in fine worked slip. Fix all wood-work during the execution of the masonry. Build in English bond. After the roof is on rake out all the joints to the extent of $\frac{3}{4}$ of an inch from the face and point in good mortar composed of one part fresh slacked lime, two parts pounded brick.

Wash the interior and exterior with a wash composed of 30 lime, 1 yellow ochre.


Carpenter.—Provide jungle-wood posts, doors, window frames, and breastsummers.

Provide and fix jungle-wood or palm tree couples and rafters. Each rafter will be


smoothed by an adze
crosses another.




where it joins or



The rafters and upper end of king piece will be spiked with a half inch spike; the lower end of the king piece and the tie in two pieces will also



be spiked. The ties will rest on the wall and the rafters project.



Roofer.—Finish the roof with well-burnt pantiles laid on a bamboo frame in the usual manner. Protect the end and over the division wall with chunam bands.

(Signed) R. F. CHISHOLM,
Consulting Architect to Government.

ESTIMATE for constructing two Police huts with walls of burnt brick in mud and tiled roofing according to Standard Design No. 2, dated 9th December 1879.

Detailed Quantities.

Particulars of Work.	No.	Length.	Breadth.	Depth.	Contents.	Total.
<i>Excavation for foundations.</i>						
		FT. IN.	FT. IN.	FT. IN.		
Longitudinal walls	8	11 4	1 6	1 6	204	
Transverse walls	3	18 4	1 6	1 6	124	
Compound walls	3	14 4	1 6	1 6	97	
Do.	1	27 2	1 6	1 6	61	
Latrine walls	2	6 7	1 6	1 6	30	
Cubic feet					516	
Cubic yards						19
<i>Concrete 6" thick.</i>						
One-third of excavation ... C. feet...					172	
<i>Burnt brick in mud.</i>						
Longitudinal walls	4	12 0	0 10	9 0	300	
Do. in side of cook-room	4	12 0	0 10	9 0	50	
Transverse walls	2	6 0	0 10	5 0	50	
Do.	3	9 8	0 10	9 0	218	
Gables	6	4 0	0 10	8 0	160	
Fire places	3	8 10	0 10	1 6	33	
Compound wall	2	3 2	1 0	1 0	6	
Do.	3	15 0	0 10	6 0	225	
Latrine wall	1	26 6	0 10	6 0	153	
Do.	2	6 7	0 10	6 0	66	1,331
<i>Deductions.</i>						
Doorways	4	2 3	0 10	5 9	43	
Do.	2	2 3	0 10	5 0	19	
Windows	2	1 9	0 10	3 9	11	73
Cubic feet						1,358
<i>Flooring with mud.</i>						
Rooms	2	12 0	8 0	1 0	192	
Verandahs	4	12 0	3 2	1 0	152	
Cubic feet						344
<i>Single wood wrought and put up.</i>						
Posts	6	0 4 1/2	0 4 1/2	7 0	6	
Breastsummers	4	14 0	0 4	0 3	8	
Rafters	36	10 9	0 3	0 4	32	
Collar pieces (4 for each room)	8	10 6	0 3	0 3	5	
Uprights	8	3 0	0 3	0 3	2	
Lintels over doors	4	3 9	0 9	0 1 1/2	2	
Do. windows	2	3 3	0 9	0 1 1/2	1	
Cubic feet						56

Detailed Quantities—cont.

Particulars of Work.	No.	Length.	Breadth.	Depth.	Contents.	Total.
		FT. IN.	FT. IN.	FT. IN.		
<i>Batten doors and windows with frames.</i>						
Doors	4	2 3	...	5 9	52	
Do.	2	2 3	...	5 0	23	
Windows	2	1 9	...	3 9	13	
Square feet					88	
<i>Pointing with chunam.</i>						
Interior walls	2	40 0	...	7 0	560	
Gables	4	8 0	...	1 4 1/2	44	
Verandahs	4	12 0	...	7 0	336	
Do.	8	4 0	...	6 0	192	
Do.	2	6 0	...	5 4	64	
Exterior walls	2	6 0	...	6 0	72	
Do.	3	0 10	...	6 0	15	
Do.	2	17 8	...	8 6	300	
Compound walls	3	15 0	...	10 6	473	
Do.	1	25 3	...	10 6	265	
Latrine walls	2	6 7	...	10 6	138	
Door jambs	4	13 9	...	0 10	46	
Do.	2	10 0	...	0 10	17	
Window jambs	2	11 0	...	0 10	18	2,540
<i>Deductions.</i>						
Doors	2 x 4	2 3	...	5 9	104	
Do.	2 x 2	2 3	...	5 0	45	
Windows	2 x 2	1 9	...	3 9	26	175
Square feet					2,365	
Squares					23 65	
<i>Whitewashing.</i>						
Interior and exterior ... Squares ...					23 65	
<i>Tarring wood-work.</i>						
Doors and windows	2	88 0	...	...	176	
Posts	6	7 0	...	1 3	53	
Breastsummers	4	14 0	...	1 6	84	
Rafters	36	10 9	...	1 2	452	
Collar pieces	8	10 6	...	1 0	84	
Uprights	8	3 0	...	1 0	24	
Lintels over doors	4	3 9	...	1 9	26	
Do. windows	2	3 3	...	1 9	11	
Square feet					910	
Squares					9 10	
<i>Roofing with pantiles over bamboo reapers.</i>						
Roofing with pantiles over bamboo reapers. ...		28 0	...	22 0	616	Sq. ft.
Squares						6 16

ESTIMATE for constructing two Police huts with walls of burnt brick in mud and tiled roofing according to Standard Design No. 2, dated 9th December 1879.

Abstract.

Quantity.	Item.	Rate.	Per	Amount.
		RS. A. P.		RS. A. P.
19 C. yds.	Excavation for foundations			
172 C. feet.	Concrete			
1,258 "	Burnt brick in mud			
344 "	Flooring with mud			
56 "	Jungle-wood wrought and put up.			
88 Sq. feet.	Batten doors and windows with frames.			
23 65 Squares.	Pointing with chunam			
23 65 "	Whitewashing			
9 10 "	Tarring wood-work			
6 16 "	Roofing with pantiles over bamboo reapers.			
	Contingencies at 5 per cent.			
	Cost of two huts			
	For one			

MADRAS,
23rd December 1879.

(Signed) R. F. CHISHOLM,
Consulting Architect to Government.

(Signed) T. K. GUTHRIE, Major,
Ag. Asst. Inspector-General,
for Inspector-General of Police.

Public Works Department, 1885-86.

Current No. 2254
9026

Letter No. 1577

Dated the 5th Sept. 85

From the Secy to Govt. and Secy to P.W.D.

NOTE OF REMARKS.

1. The accompanying is an estimate for constructing four Police huts at Tirudur in the Tirunelveli district, and amounts to Rs. 1340.

2. Except that the foundations are to be 1 foot deeper as the soil is black cotton the design now submitted accords in all particulars with the standard design for Police huts sanctioned in G.O. No. 93W. of the 14th Jan'y. 80.

3. A site plan is submitted. Rs. 42 are allowed for land compensation.

4. The estimate has been countersigned by the Insp. Genl. of Police - also the site plan. The estimate is approved in the order of the Secy to P.W.D.

18th Sept. 85

W.T.
19.85

22/9/85

Report by the Deputy Engineer 6th
 Circle on the Estimate for Constructing 4
 Police huts at Virudupatti in Saver Taluk
 Tirunelveli District. P. 1340

enclos 2
 1 Estimate
 1 Site plan.

The Superintendent of Police,
 in his letter No 13 dated 15th March/84 to
 the address of the Executive Engineer, called
 for an estimate for 8 huts at this station
 but subsequently in his letter No 39 of
 24th July/84 stated that only 4 huts
 are required as the other 4 have been made
 by the conversion of the old station house.
 This estimate for 4 huts is accordingly
 prepared in conformity with the standard
 design approved of by G. O. No 93 W of
 14th January/880.

2 — Sites marked X, Y, and Z
 in the plan accompanying were selected
 and forwarded for the approval of the
 Superintendent of Police who has approved
 the site marked X as being adjacent.

to the old station house which was
altered into Police huts vide his letter
No. 17 Dated 30th March/85. The site of
being a private land a Compensation
of Rs 42 is allowed in the Estimate as
per land statement attached.

The soil is said to be black
Cotton and the foundation allowed by
6 inches Concrete and 2 ft masonry is
considered sufficient. The site is also
approved of by the collector.

3— The rates are fair and the
Estimate is forwarded to the Superinten-
dent of Police for submission to Govt
for their sanction in the Judicial Dept
vide para 1168 A of the P.W. Code.

M. M. M. Co. R.
Superintending Engineer, B.P.C.
Trichinopoly
1st August 1885

2254

By 10.8.85

11/557 18/85
10/8
From,
The Sup^r Engineer
6th Circle.
To,
The Supt^t of Police
Sinnerelly.

No 259 T.N
Dated 7th August 1885
Encl 2

Report on the estimate
for constructing four
Police huts at Viru-
dupatti in the Sather
Taluk, Sinnerelly Dist.

Subd. 30/8/85
2

Hutting and Building
General Department

No. 4980.

Chief Office of the Inspector General of Police,
Madras, 24th August 1885.

From
Colonel H. D. Clote
Inspector General of Police,
To
The Chief Secretary
Government
Madras

Sir,

Enclosures 6

- 1. Schedules and
- 1. Site plan
- 1. Detailed estimate
- 1. Abstract estimate
- 1. Report of the
Execution Engineer
- 1. B.C. Sanctioning B.C.
- 6 Enclosures

I have the honor to forward
for sanction I.P. W. Site plan and
estimates to amounting to Rs 10,000
for the construction on the standard
design of 4 huts at Virudupatti,
Sinnerelly District.

2. The site for the work has
been secured.

I have the honor to be
Sir
Your most obedient servant
H. D. Clote
Inspector General of Police

Recd H.D. Clote
20/8/85

G.O. No 934. 14-1-80.

Judicial (1885)

DEPARTMENT

CURRENT NO 306

From

Lt. H. I. Clute

Inspector General

of Police,

Dated 21st

August 1885.

Received

No. 4980

SUBJECT.

Memorandum for sanction
G.P.W. Site plan & estimate
for Rs 1340 for the construction
of 4 huts at Virudupatti
Kinnemully District.

Oct. 22/85

H. 31/8

11/29

Resubmitted to G.O. No 22983. 17/4/85

PUBLIC WORKS DEPARTMENT.

No. 2254 W.

PROCEEDINGS OF THE MADRAS GOVERNMENT.

Under date the 28th September 1885.

Read the following

From the Inspector General of Police. H. No. 4980 of 21st August 1885.
Condorcement by the Judicial Deptt. H. No. 1577 of 5th September 1885.

The estimate amounting to
Rs. 1,340, for constructing four police huts
at Virudupatti in the Kinnemully
District, is sanctioned for execution
when funds are available.

2. This sanction has been regis-
tered as Provincial No. 126 W of 1885-86,
and classified as Civil Buildings,
Original Works.

Recd
6/10/85

Sept. 21. 1885

The Supt. Genl. III circle with the
" Examines of P.W. Secty with the
estimate for note and return to L.C. III.
Judicial Department

23-9-85

2254
11

7902

Govt. of (1885) Madras.

PUBLIC WORKS.

Dated

Recd

Encl.

G.O. 28 Sep 1885; No. 71-44

Police huts at Virudu-
kudi, Quinqually St.
Set for - sanctioned.

18397

60

30/9