

(1) Number of pages 16
(2) Date of repair 24.8.87
(3) Initials of the Referencer lms.

TAMIL NADU ARCHIVES

GOVERNMENT OF TAMIL NADU

P.W. DEPARTMENT.

G.O. No.	588 - W	Press.
B.P. No.		Mis.
Dated	12.3.1885	198

Not to be folded or roughly handled.

12TH MARCH 1885, No. 588 W., PUBLIC WORKS.

GOVERNMENT OF MADRAS.

PUBLIC WORKS DEPARTMENT.

Buildings and Roads.
Civil Works.

READ—the following letter from Colonel J. BEATTY, R.E., Superintending Engineer, IV Circle, to the Chief Engineer, Public Works Department, dated Coimbatore, 6th February 1885, No. 55 E.W. :—

I have the honor to submit, herewith, a revised estimate for the Bhavani sub-registrar's office. The original sanction, in G.O., No. 1790 W., of 14th July 1882, amounted to Rs. 2,040, and the revised estimate now submitted amounts to Rs. 2,334.

2. The cause of excess is that deeper foundations and a higher basement than provided in the sanctioned estimate have been found necessary. The subordinate who reported on the trial pits pronounced the soil to be "hard gravel," while it proved to be of a "variable" but "stony" character; and he failed to bring to notice that the surface of ground at the site was below M.F.L. in the Bhavani river hard by. It was, however, the only site available and the extra work became unavoidable.

ORDER—dated 12th March 1885, No. 588 W., Public Works.

The revised estimate, amounting to Rs. 2,334, for constructing a sub-registrar's office at Bhavani, in the Coimbatore district, is sanctioned in supersession of the estimate referred to in G.O., No. 1790 W., dated 14th July 1882.

2. A sum of Rs. 2,040 is provided for the work in the current year's budget.

3. This sanction has been registered as Provincial No. 268 W. of 1884-85, and classified as Civil Buildings, Original Works.

(True Extract.)

Major, R.E.,
Under Secy. to Govt., P.W.D.

To the Superintending Engineer, IV Circle, with three enclosures.
" Examiner, Public Works Accounts.
" Judicial Department.

Exd. E. Fernandez.
Spare Copies

BUILDINGS AND ROADS.
CIVIL WORKS.

Gobt. of (1885) Madras.
PUBLIC WORKS.

Dated March, 12th.

Recd.

Encl.

G.O., 12th March 1885, No. 588 W.

MARCH.

Sub-Registrar's office at
Bhavani, Coimbatore District

Revised estimate for —, sanctioned.

14TH JULY 1882, No. 1790 W., PUBLIC WORKS.

GOVERNMENT OF MADRAS.

PUBLIC WORKS DEPARTMENT.

Buildings and Roads.
Civil Works.

No. 97.

READ—the following paper :—

No. 240.

Report on Estimates for new Offices for the Registration Department in Coimbatore District.

In G.Os., Nos. 1976 W., dated 10th August 1881, 1176 W., dated 9th May 1881, 2440 W., dated 4th October 1881,

Six Site Plans. 1872 W., dated 29th July 1881, and
Eight Abstract Estimates. 2684 W., dated 1st November 1881, plans

and estimates were called for; they are now submitted as follows :—

	RS.
Registrar's Office at Coimbatore	3,920
Sub-Registrar's Office at Aravakurhi	2,120
Do. at Satyamangalam	2,120
Do. at Karur	2,120
Do. at Bhavani	2,040
Do. at Kollegal	2,630

They have been prepared according to the standard plans, &c., circulated in G.O., No. 120 W., dated 14th January 1882, and terraced roofs are provided for it, being considered most suitable to Coimbatore District. The sites have been selected in communication with Sub-Registrars, and are approved of by the Inspector-General. The plans and estimates have been examined in this office and have been approved of. The works would probably take eight months to complete after sanction and allotment of funds. There are no public buildings available at the places where it is proposed to build the new offices except at Bhavani, where the lower rooms of the Bhavani bungalow could, at a cost of Rs. 250, be made suitable for the Sub-Registrar's Office. This proposal, however, is not approved of by the Registration Department, who naturally prefer new buildings to be built for their offices.

COIMBATORE.
26th June 1882.

(Signed) H. R. MEAD, Lieut.-Col., R.E.,
Superintending Engineer, Fourth Circle.

No. 98.

ORDER—dated 14th July 1882, No. 1790 W., Public Works.

The undermentioned estimates are sanctioned :—

(1) Constructing a Registrar's Office at Coimbatore	Rs. 3,920.	Register No. 55 W. of 1882-83.
(2) Do. Sub-Registrar's Office at Aravakurhi	2,120.	56 W.
(3) Do. do. at Satyamangalam	2,120.	57 W.
(4) Do. do. at Karur	2,120.	58 W.
(5) Do. do. at Bhavani	2,040.	59 W.
(6) Do. do. at Kollegal	2,630.	60 W.

2. The balance available under the lump sum provision, Budget Item No. 46, for Registration Offices, after providing for incomplete works of the last official year, is Rs. 8,967, and funds from this source are appropriated to the extent of Rs. 8,160 for the first three works above mentioned. The remaining works will be executed when funds are available.

3. These sanctions have been registered as Provincial Nos. 55, 56, 57, 58, 59, 60 W. of 1882-83 and classified as Civil Buildings, Original Works.

(True Extract.)

(Signed) R. H. SANKEY, Colonel, R.E.,
Secretary to Govt., P.W.D.

To the Superintending Engineer, Fourth Circle, with twelve Enclosures.
" Examiner of Public Works Accounts, with two duplicate Abstract Estimates.
" Inspector-General of Registration.
" Judicial Department.

BUILDINGS AND ROADS.
CIVIL WORKS.

Govt. of 1882 Madras.
PUBLIC WORKS.

Dated July, 14th.

Recd.

Encl.

G.O., 14th July 1882, No. 1790 W.

JULY.
Nos. 97-98.

Registrar's Office.

Estimates for the construction of a — at
Coimbatore and Sub-Registrar's Offices at
certain places, sanctioned.

N^o 55
9/7

Superintending Engineer's Office, 4th Fl.
Coimbatore 6th February 1885.

From

The Superintending Engineer
4th Fl.

To,

The Chief Engineer
Public Works Department.

Sir,

Enclosures 3.

1 Estimate with
Abstract
1 Report
1 Comparative
Statement.

I have the honor to submit
herewith a revised estimate for the
Bharavari Sub-Registrar's office. The
original sanction in G.O. No. 1790 W.
of 14th July 1882 amounted to Rs. 2,334.
and the revised estimate now sub-
mitted amounts to Rs. 2,334.

2. The cause of excess is that
deeper foundations and a higher
basement than provided in the
sanctioned estimate have been
found necessary. The subordinate
who reported on the trial pits pro-
mised the soil to be "hard gravel",
while it proved to be of a "variable"
but

our strong character, and he failed
to bring to notice that the surface
of ground at the site was below
M.F.L. in the Bhavani river hard
ly. It was however the only site
available and the extra work became
unavoidable.

I have the honor to be
Sir,

Your most obt. Servt.

Colonel. H. G.
Superintending Engineer. S. P. S. S. S.

24

S. 1790/1882

From
The Superintending
Fourth Circle.



Dated 6th Feb. 1885

N^o 55
9/11

Enc: 3

Sub Registrar's Office
Baran:

Submits a revised
estimate for the — a —
amounting to Rs. 2334.

Sanction,

CC.

19.2.85

Public Works Department, 188-85.

6/18
5/8

Current No. 1132

Letter No. 55

Dated the 6th February 1885

From the S.E. IV Circle

NOTE OF REMARKS.

1. This is a revised estimate
for constructing a Sub-
Registrar's Office at Baran
in the Coimbatore
District. It amounts to
Rs. 2334 — being Rs. 294 in
excess of the original esti-
-mate, Rs. 2040, sanctioned
in G.O. No. 1790 of the 14th July
1882.

2. The necessity for the revision
is due chiefly to the
original estimate having
been prepared on incorrect
and insufficient information
regarding the site
of the proposed office — as
has been found necessary
to increase the foundation
of the office by a sub-
-stems of concrete 1 1/2 feet thick.

and to increase the height of the basement from 2 ft. to 3 feet. - The item 'Petty supervision' has been introduced into the revised estimate, it is stated to have been omitted from the original by an oversight. 3. The revised estimate has not been countersigned by the Insp. Genl. of Registration, but, subject to approval, there is no necessity for submitting it to him.

21 Feb/85. 1
BH

(88W)

PUBLIC WORKS DEPARTMENT.

PROCEEDINGS OF THE MADRAS GOVERNMENT.

Under date the

Read the following

From the Suptg. Engineer IV Circle. H. G. No. 55 G. W. d/6 February 1885.

The revised estimate amounting to Rs 2,334, for constructing a Sub. Registrar's office at Bhavanur in the Coimbatore District, is sanctioned, in supersession of the estimate referred to in G. O. No. 1790 W dated 14th July 1882.

2. A sum of Rs 2,040 is provided for the work in the current year's Budget.

3. This sanction has been registered as Provincial No. 268 W of 1884-85, and classified as Public Buildings, Original Works.

To the Suptg. Engr. IV Circle with 3 copies
" Examiners P. W. Works
" Judicial Department
Maj (Ch. Secy for Coimbatore District)

Cd.
21-2-85

Cu

21-2-85

6-3-85



5/54

1134

Govt. of (1885) Madras.

PUBLIC WORKS.

1885, No. 5004

at Bhavani, Crim.
before S.

Revised Report
Sanctioned

60
4

13/3/33