

70
13TH MARCH 1885, No. 594 W., PUBLIC WORKS.

GOVERNMENT OF MADRAS.

PUBLIC WORKS DEPARTMENT.

Buildings and Roads.
Civil Works.

READ—the following paper :—

Proceedings of the Board of Revenue, dated 21st February 1885, No. 586.

ORDER—dated 13th March 1885, No. 594 W., Public Works.

The estimate, amounting to Rs. 24,080, for completing the Ongole-Kottapatam road, in the Nellore district, is sanctioned, and registered as Local No. 56 W. of 1884-85.

2. The Revenue Board's proceedings No. 6553, dated 20th December 1884, do not appear to have been communicated to the Public Works Department.

(True Extract.)

Major, R.E.,
Under Secy. to Govt., P.W.D.

To the Board of Revenue, with one enclosure.
" Superintending Engineer, II Circle.
" Financial Department.

Exd. E. Fernandez.
Spare Copies

BUILDINGS AND ROADS.
CIVIL WORKS.

Gobt. of (1885) Madras.
PUBLIC WORKS.

Dated March, 13th.

Recd.

Encl.

G.O., 13th March 1885, No. 594 W.

MARCH.

Ongole-Kottapatam Road,
Nellore District

Estimate for completing the —, sanctioned.

BOARD OF REVENUE, 21st FEBRUARY 1885, No. 586.

PROCEEDINGS OF THE BOARD OF REVENUE.

READ—the following letter from J. GROSE, Esq., President, Local Fund Board, Nellore, to the Secretary to the Board of Revenue, dated 7th February 1885, No. 64-Eng. :—

I have the honor to submit an estimate for completing the Ongole-Kottapatam Road at a cost of Rs. 24,080.

2. This is the estimate referred to in Board's Proceedings, dated 20th December 1884, No. 6553, Routine. It has been duly countersigned by the Superintending Engineer, but he has omitted to forward it to the Board of Revenue as required by Board's Proceedings, dated 4th September 1884, No. 2085.

RESOLUTION—dated 21st February 1885, No. 586.

Submitted for the sanction of Government.

2. The order quoted at the end of paragraph 2 is that of Government and not the Board's.

3. It is requested that the President's original letter submitted to Government with Board's Proceedings, Routine Series, No. 6553, dated 20th December 1884, may be returned to this office.

(A true Copy and Extract.)

W. M. S. S. S.
Acting Sub-Secretary.

To the Secretary to Government, Public Works Department, with estimate.
" Chief Secretary to Government, Financial Department.
" President, Local Fund Board, Nellore.
" Accountant-General.

Exd. A. Raitt.

PUBLIC WORKS DEPARTMENT.
1885.

Board of Revenue,
MADRAS.

Printed February st.

Proceedings, 21st February 1885, No. 586.

Submitting, for sanction of Government, estimate for completing the Ongole-Kottapatam Road, at a cost of Rs. 24,080, and requesting that the President's original letter submitted to Government with Board's Proceedings, Routine Series, No. 6553, dated 20th December 1884, may be returned to Board's office.

Sanction -

Cd.

11.3.85

Public Works Department, 1884-85.

Current No. 1918

Letter No. 586

Dated the 21st February 1885

From the Board of Revenue

NOTE OF REMARKS.

1. The accompanying estimate provides for completing the Ongole-Kottapatam Road in the Nellore District at a cost of Rs. 24,080.
2. The length of road to be completed is 11 miles, and the work consists in the spreading of metal and gravel, turfing, and earthwork. Where metal is being laid for the first time, or rather, if none exists on the road surface, it will be spread in two layers, each 4 inches thick - the lower layer to consist of 2" gauge pieces of metal, and the upper, of 1 1/2" gauge pieces. Where metal is being simply renewed the

594

1 1/2" gauge pieces only are to be employed. Over the metal a blinding of gravel 1 inch thick is to be spread.

The road is to be 20 feet wide - the center 12 feet being metalled with a turfed earth berm, 4 feet wide, on either side. -

The width allowed to the gravelling is 12 feet, and to the turfing 3 feet. -

The transverse slope of road surface to be adopted is 1 in 36 (1 inch in 3 ft.).

3. The report and detail estimate are at variance as to the thickness to be allowed to metal where it is being renewed, the report sets it at 3 inches, the detail estimate at 6 inches. - of course the latter must be accepted.

4. The estimate has been countersigned by S.E.II., and by the President of the L.F. Board.

11th March/85

Yes - the previous sum paid by

X 5

B. J. R. I. works

N^o 594. W

PUBLIC WORKS DEPARTMENT.

PROCEEDINGS OF THE MADRAS GOVERNMENT.

UNDER date the 13th March/85

READ the following

Proceedings of the Board of Rev. H. E. N^o 586 of 21st Decy/85

The estimate amounting to Rs 240.80, for completing the Ougole-Kottapattam road, in the Villore District is sanctioned, and registered as Local N^o 56 W of 1884-85.

2. The Revenue Board's Proceedings N^o 6553 dated 20th December 1884, do not appear to have been communicated to the P. W. Department.

7. The Board of Rev with 1 encl. " Supg: Engr II Circle " Financial Department.

Recd 19-3-85

CJ. 12.3.85

Cu

12.3.85

J-814
B₁₂
1413

su
u

PUBLIC WORKS.

Encl.

$$\frac{70}{4}$$


Dated 20th December 1884.

No. 6553 Routine

READ

READ Application for transfer of fund from the
President Local Fund Board & Tellore dated
17 November 1884 no 49.

Resolution

Submitted for the sanction of Government as the proposals involve transfer of funds from one major head to another in the Road Fund Budget.

2. The Board presume that the estimate for completing the Ongole-Kottapattanam road, which has been sanctioned by the circle Board in their Resolution no. 146 has been forwarded to the Superintending Engineer.

3. The President is requested to submit a copy of the Circle Board's Resolution no 430 of 1884, sanctioning the estimate for the repairs of the Dornal Road.

(True Extract,
Signed) E. F. McCarty
for Dr. MacKenzie
Ag. Subsecy.

To The Chief Secy to Govt &c
" President L. J. McMillen
" Accountant General.

(True Copy)

Copy, Manufacture
Agrib Secretary

Int

8. 9. 10. 11. 12. 13. 14. 15. 16. 17. 18.

Encls. in Bd's Pro. of 26th March
1885 No 2934 Dis to the Secy to Govt P.W.D.

P.W. Secy
28/3/85

No 49

Application for TRANSFER of Funds approved by the Local Fund Board, *Nellore* Circle, *Nellore* District.

| From | | | | To | | | References to previous correspondence. | |
|---|--------------------------------|--------------------------|---|---|--------------------------|------------------------------------|---|---|
| Particulars of the item with the Major and Minor heads of the Budget specified. | Amount provided in the Budget. | Amount already expended. | Amount available for transfer after providing for probable outlay to the end of the year. | Particulars of the item with the Major and Minor heads of the Budget specified. | Amount already allotted. | Amount required to be transferred. | | |
| 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 |
| <u>Part I New works</u> | | | | | | | | |
| 8. Podalakur Repair Road | 4,000 | nil | 2,000 | | | | | |
| 9. Gudur Tekkavaram | 3,000 | 240 | 1,500 | | | | | |
| 10. Naidupet Vankatagiri | 5,000 | nil | 2,000 | | | | | |
| 11. Naidupet Duparagapattam | 5,000 | 30 | 2,000 | Repairs of Communication | | | | |
| <u>Part II Repairs</u> | | | | | | | | |
| 22. Naidupet Vankatagiri | 1,100 | 55 | 500 | Repairs of Gornal Road. | nil | 9300 | | |
| 18. Nellore Someswaram | 2,700 | 230 | 500 | | | | | |
| <u>Appendix to Part II</u> | | | | | | | | |
| 13. Podalakur Sangam | 700 | nil | 300 | | | | | |
| 19. Vankatavellam Choultry to Vankatavellam | 700 | 10 | 300 | | | | | |
| 20. Naidupet to Podalakur | 800 | 50 | 200 | | | | | |
| | | | | | | | * This is one of the most in this District. It is to be connected with the Project as well as the to Cuddalore and made in the Budget says that this allocation required. Vide Part The estimate was sanctioned (Vide | |

* This is one of the most important roads in this District. It is traversed by traffic in connection with the works of the Sangam Project as well as through traffic to Cuddapah and no provision is made in the Budget. The Engineer says that this allotment is necessarily required. Vide Res. No 1259/1884-85. The estimate was sanctioned by the circle Board (Vide Res. No 139/1884).

(Signature)

Director of the Local Fund Board,

Circle

District

April 1885.

(True Copy)

President Local Fund Board,
District

Sub-Committee



Proceedings of the Board of Revenue.

Dated 26th March 1885.

No. 2934 *mis*

READ G.O. 13th March 1885, no. 594 W. Public Works.

Resolution:-

Communicated to the President,
Local Fund Board, Nellore.

2. The Board's Proceedings referred to in para 2 of the G.O. were not communicated to the Public Works Department as they related only to the transfer of funds required for the work for which the estimate is now sanctioned and to another work. A copy is, however, now sent for information.

(See Extract)

Ag Subsecretary.

To,
The President, L. F. B. Nellore

Secretary to Govt. P. W. D

with a copy of Bd's Pro: dated
20th Decr 1884, no. 6553 Rontua

594 W 7/13/3/85

J.M.C. No 2867

1885.

Board of Revenue,
MADRAS.

B. No 808. W of 31st March 85.

To *Secy*

Recorded.
Recorded

C.S.

31.3.85

W.S.
31.3.85

Recd. 27.3.85



The Secretary to Govt.
Public Works Department

B. No 808. W of 31st March 85.

Proceedings, dated 26th March 1885,
No. 2954 *mis*

Subject. *to President, L.F. B. 2nd*

Communicating *to* *secretary*
estimate for completing the
Ongole - Kottapattam Road; and
forwarding for information, a copy
of *Pro.* dated 20 Decr '84, no 6553.

B W
7/4

Id
1974 85

With order
W