

13TH MARCH 1885, No. 607 W., PUBLIC WORKS.

GOVERNMENT OF MADRAS.

PUBLIC WORKS DEPARTMENT.

Buildings and Roads.
Civil Works.

READ—the following papers:—

From Major J. L. L. MORANT, R.E., Officiating Consulting Architect to Government, to the Chief Engineer, Public Works Department, dated Chepâk, 7th January 1884, No. 1338.

In compliance with G.O. No. 3457 W., dated 3rd December 1883, Public Works Department, I have the honor to submit detailed plans and estimates for constructing a Collector's cutcherry at Nellore.

2. The estimated cost, according to current rates at Madras, will be Rs. 39,484. The approximate estimate given in Mr. Vincent's letter No. 210, dated 22nd May 1883, was Rs. 30,200. The difference is caused by the enlargement of the Collector's court, which has necessitated wrought-iron girders of great span, and by the addition of a bigger retiring-room for the Collector. Additional ventilation has also been provided in some of the larger rooms.

3. The specification has been drawn up as fully as possible, but is necessarily of a suggestive nature as the officer on the spot can alone be the best judge of what is usually done. It should be carefully perused by the Executive Engineer, Nellore, before submitting his final estimate for the work, in order that he may fully realise what the design proposes to effect.

No. 108 C., Public Works.

Forwarded to the Superintending Engineer, II Circle, who will revise the estimate to accord with rates prevailing at Nellore.

2. Attention should be paid to the remarks in paragraph 3 of the Consulting Architect's letter, as regards the specification.

3. Provision should also be made for such out-offices as the Collector may consider absolutely necessary.

4. The return of the papers now transmitted is requested.

16th January 1884.

(Signed) C. BOWEN, Major, R.E.,
Under Secy. to Govt., P.W.D.

From J. W. RUNDALL, Esq., Superintending Engineer, II Circle, to the Chief Engineer, Public Works Department, dated Masulipatam, 10th October 1884, No. 605 N.L. :—

I have the honor to forward, herewith, an estimate, amounting to Rs. 43,820, for constructing a new Collector's cutcherry at Nellore, based on the designs and list of quantities received with your memorandum, No. 108 C., of the 15th January last.

2. It would be advisable to indent for and get the rolled girders direct from England.

3. The Consulting Architect should be requested to furnish complete working drawings for the stair cases. As far as I am able to judge, the estimate rate will suffice for their construction, but complete drawings are necessary. I cannot quite make out how the back (called angle) stair case is worked in, as they are merely sketched in plan in the design.

4. I have allowed a high rate for mouldings and similar works, as we shall have to obtain workmen from Madras trained to do the work.

5. The cutcherry has been entered in the budget for 1885-86 recently sent to you, and Rs. 15,000 have been asked for.

P.S.—The Consulting Architect's letter received with your memorandum under reply was not received back from the Nellore division, but will be obtained and forwarded shortly.

From J. W. RUNDALL, Esq., Superintending Engineer, II Circle, to the Chief Engineer, Public Works Department, dated Masulipatam, 29th January 1885, No. 842 N.L.

I have the honor to forward, herewith, an estimate, amounting to Rs. 50,250, for the Collector's new cutcherry at Nellore, in supersession of that for Rs. 43,820 transmitted with my No. 605 N.L. of the 10th October.

1 Tracing.
1 Site plan.
1 Abstract estimate in duplicate.
1 Detailed estimate.
1 Abstract estimate for stable.
1 General abstract.
1 Specification.

1 Executive Engineer's report.
1 Superintending Engineers' report.
1 Superintending Engineer's original letter, No. 605 N.L., dated 10th October 1884.

2. Provision for the removal of the existing building, for a compound-wall, and for new stables, has now been made.

3. The design is the Consulting Architect's, and the details of the estimate

are explained in the accompanying reports by the Executive Engineer and myself.

4. The estimate has been signed by the Collector; the rates are suitable, and I beg to recommend its sanction.

ORDER—dated 13th March 1885, No. 607 W., Public Works.

The estimate, amounting to Rs. 50,250, for constructing a cutcherry for the Collector at Nellore, is sanctioned.

2. A sum of Rs. 15,000 has been provided for the work in the Provincial budget for 1885-86.

3. This sanction has been registered as Provincial No. 270 W. of 1884-85, and classified as Civil Buildings, Original Works.

(True Extract.)

(Signed) J. SHAW-STEWART, Colonel, R.E.,
Secretary to Govt., P.W.D.

To the Superintending Engineer, II Circle, with nine enclosures.
„ Examiner, Public Works Accounts, with general abstract estimate.
„ Consulting Architect to Government.
„ Revenue Department.

Exd. E. Fernandez.
Spare Copies

*With sanction since
order to the construction
of 29-5-85.
10*

BUILDINGS AND ROADS.
CIVIL WORKS.

Govt. of 1885 Madras.

PUBLIC WORKS.

Dated March, 13th.

Recd.

Encl.

G.O., 13th March 1885, No. 607 W.

MARCH.

Cutcherry for the Collector at
Nellore

Estimate for —, sanctioned.

[Form No. viii.]

GOVT.
OF MADRAS.

1885.

{ P. W.
DEPT.

EXAMINER, P. W. ACCOUNTS.

Madras, 31st MARCH 1885.

OFFICE NOTE No. 987

To

W.



Encls: 1

IN RETURNING THE ABSTRACT
ESTIMATE FOR 'COLLECTOR'S CUTCHERRY
AT NELLORE' FURNISHED WITH G.O. NO.
607 W. DATED 13TH MARCH 1885, I HAVE
THE HONOUR TO POINT OUT THAT THE
ESTIMATE PROVIDES FOR 'VERANDAH
BLINDS' AND 'RATTAN MATS' THIS AP-
PEARS TO BE OPPOSED TO CODE PARAS
1156 AND 1158, AS INTERPRETED BY G.O.
NO. 680 W. DATED 13TH MARCH 1885.

DCJ
C.

89
3/3

Bill 30

1858 May 9 April 13

B

Provision for blinds
(Re. 469) and mats (Re.
1326) will accordingly
be struck out of the
estimate, which will
then be reduced to
Re. 148,455.

1858/4/15
2-1

2. Such articles, must
in accordance with
P.W. Code rules, be
supplied by the accu-
pying Department.

B. 1858 May 9 April

CD

2.4.45

111
2.4.45
B

S.E. II Circle
Exe: P.W. Accs with photo. L.H.
Rev: Deptt
10/14/34
11/1/35

with the