

GOVERNMENT OF MADRAS.

JUDICIAL DEPARTMENT.

READ—the following paper :—

Note by the Chief Engineer, Public Works Department.

The estimate prepared by the Superintendent of the District Jail at Calicut, for the erection of accommodation for twelve lunatics, is defective in the following respects :—

- (a) The nature of soil is not stated.
- (b) The foundation should be of brick or laterite in chunam ; not laterite in mud, as proposed.
- (c) The depth and breadth allowed for the foundations appear to be insufficient.
- (d) The omission of flooring of any description. Either asphalt or cement floor should be put down, to admit of the wards being washed daily.
- (e) The partition walls should be of brick or laterite in chunam ; not of sun-dried bricks in mud, as proposed.
- (f) The description of tiles to be used is not stated, nor is the scantling of the rafters given.
- (g) The slope given to the roof appears insufficient, when the heavy rainfall is taken into consideration.
- (h) The ventilators should be placed higher, and reduced in depth from 2 to $1\frac{1}{2}$ feet. They should also be provided with weather-boards.
- (i) It is suggested that, to secure proper ventilation, the doors should be half-pannelled and half-railed (iron bars being used), instead of being made entirely of planks.
- (j) The pillars appear to be unnecessarily large for the height, and too close together.
- (k) The laying of the bressummers should be on edge, not flat, as shown in section.
- (l) The amount of estimate should apparently be Rs. 1,842, not Rs. 1,800 as stated.

2. It is suggested that a revised estimate be prepared by the local public works officers, and that the work be undertaken by the Public Works Department. The revised estimate would supersede that sanctioned in G.O., No. 926 W., dated 18th April 1885.

13th July 1886.

(Signed) J. SHAW-STEWART, Col., R.E.,
Chief Engineer, P.W.D.

No. 400-D.

MEMORANDUM.

Copy of the foregoing note by the Chief Engineer is forwarded to the Judicial Department, with reference to G.O., No. 1585, dated 16th June 1886.

2. The Government in this department concur in the Chief Engineer's remarks.

3. The estimate received with the Government order quoted above is herewith returned to the Judicial Department.

OOTACAMUND,
14th July 1886.

(Signed) J. SHAW-STEWART, Col., R.E.,
Secretary to Govt., P.W.D.

To the Judicial Department, with four enclosures.

ORDER—dated 22nd July 1886, No. 1932, Judicial.

Communicated to the Inspector-General of Jails in continuation of G.O., 16th June 1886, No. 1585. He will inform the Superintendent of the District Jail, Calicut, that the Government await his report regarding the site for the new cells.

2. The plan and estimate will be returned to the Public Works Department in view to the cells being constructed by that department.

(True Extract.)

E. F. WEBSTER,
Chief Secretary.

To the Inspector-General of Jails.
,, Public Works Department, with plan and estimate.

Govt. of {1886} Madras.

JUDICIAL.

Issued

Recd.

Encl.

G.O., 22nd July 1886, No. 1932.

JULY.

Jails.

Communicating to the Inspector-General of Jails memorandum from the Public Works Department regarding the erection of cells for lunatics in the district jail, Calicut, and requesting him to inform the Superintendent that Government await his report regarding the site of the new cells.

22ND JULY 1886, No. 1932, JUDICIAL.

GOVERNMENT OF MADRAS.

JUDICIAL DEPARTMENT.

READ—the following paper :—

Note by the Chief Engineer, Public Works Department.

The estimate prepared by the Superintendent of the District Jail at Calicut, for the erection of accommodation for twelve lunatics, is defective in the following respects :—

- (a) The nature of soil is not stated.
- (b) The foundation should be of brick or laterite in chunam; not laterite in mud, as proposed.
- (c) The depth and breadth allowed for the foundations appear to be insufficient.
- (d) The omission of flooring of any description. Either asphalt or cement floor should be put down, to admit of the wards being washed daily.
- (e) The partition walls should be of brick or laterite in chunam; not of sun-dried bricks in mud, as proposed.
- (f) The description of tiles to be used is not stated, nor is the scantling of the rafters given.
- (g) The slope given to the roof appears insufficient, when the heavy rainfall is taken into consideration.
- (h) The ventilators should be placed higher, and reduced in depth from 2 to $1\frac{1}{2}$ feet. They should also be provided with weather-boards.
- (i) It is suggested that, to secure proper ventilation, the doors should be half-pannelled and half-railed (iron bars being used), instead of being made entirely of planks.
- (j) The pillars appear to be unnecessarily large for the height, and too close together.
- (k) The laying of the bressummers should be on edge, not flat, as shown in section.
- (l) The amount of estimate should apparently be Rs. 1,842, not Rs. 1,800 as stated.

2. It is suggested that a revised estimate be prepared by the local public works officers, and that the work be undertaken by the Public Works Department. The revised estimate would supersede that sanctioned in G.O., No. 926 W., dated 18th April 1885.

13th July 1886.

(Signed) J. SHAW-STEWART, Col., R.E.,
Chief Engineer, P.W.D.

No. 400-D.

MEMORANDUM.

Copy of the foregoing note by the Chief Engineer is forwarded to the Judicial Department, with reference to G.O., No. 1585, dated 16th June 1886.

2. The Government in this department concur in the Chief Engineer's remarks.

3. The estimate received with the Government order quoted above is herewith returned to the Judicial Department.

Ootacamund,
14th July 1886.

(Signed) J. SHAW-STEWART, Col., R.E.,
Secretary to Govt., P.W.D.

To the Judicial Department, with four enclosures.

ORDER—dated 22nd July 1886, No. 1932, Judicial.

Communicated to the Inspector-General of Jails in continuation of G.O., 16th June 1886, No. 1585. He will inform the Superintendent of the District Jail, Calicut, that the Government await his report regarding the site for the new cells.

2. The plan and estimate will be returned to the Public Works Department in view to the cells being constructed by that department.

(True Extract.)

E. F. WEBSTER,
Chief Secretary.

To the Inspector-General of Jails.

„ Public Works Department, with plan and estimate.

C No 2030 W a/13th August/86

Communicated, with a
copy of Pros. d/16th June
1886, No 1585 Judicial
to the Suptg Engr. IV
Circle, who will submit
revised plans and
estimates based on the
Chief Engineer's note
of 13th July 1886.

sd/ JSS
W

Sd. IV Circle
with 4 enclos
Judicial Dept

Govt. of (1886) Madras.

JUDICIAL.

Issued

Recd.

Encl.

G.O., 22nd July 1886, No. 1932.

JULY.

Jails.

Communicating to the Inspector-General of
Jails memorandum from the Public Works De-
partment regarding the erection of cells for luna-
tics in the district jail, Calicut, and requesting
him to inform the Superintendent that Govern-
ment await his report regarding the site of the
new cells.

With order

22ND JULY 1886, No. 1932, JUDICIAL.

GOVERNMENT OF MADRAS.

JUDICIAL DEPARTMENT.

READ—the following paper :—

Note by the Chief Engineer, Public Works Department.

The estimate prepared by the Superintendent of the District Jail at Calicut, for the
erection of accommodation for twelve lunatics, is defective in the following respects :—

- (a) The nature of soil is not stated.
- (b) The foundation should be of brick or laterite in chunam; not laterite in
mud, as proposed.
- (c) The depth and breadth allowed for the foundations appear to be insufficient.
- (d) The omission of flooring of any description. Either asphalt or cement
floor should be put down, to admit of the wards being washed daily.
- (e) The partition walls should be of brick or laterite in chunam; not of sun-dried
bricks in mud, as proposed.
- (f) The description of tiles to be used is not stated, nor is the scantling of the
rafters given.
- (g) The slope given to the roof appears insufficient, when the heavy rainfall is
taken into consideration.
- (h) The ventilators should be placed higher, and reduced in depth from 2 to
1½ feet. They should also be provided with weather-boards.
- (i) It is suggested that, to secure proper ventilation, the doors should be half-
pannelled and half-railed (iron bars being used), instead of being made
entirely of planks.
- (j) The pillars appear to be unnecessarily large for the height, and too close
together.
- (k) The laying of the bressummers should be on edge, not flat, as shown in
section.
- (l) The amount of estimate should apparently be Rs. 1,842, not Rs. 1,800 as
stated.

2. It is suggested that a revised estimate be prepared by the local public works
officers, and that the work be undertaken by the Public Works Department. The
revised estimate would supersede that sanctioned in G.O., No. 926 W., dated 18th
April 1885.

(Signed) J. SHAW-STEWART, Col., R.E.,
13th July 1886. Chief Engineer, P.W.D.

No. 400-D.

MEMORANDUM.

Copy of the foregoing note by the Chief Engineer is forwarded to the Judicial
Department, with reference to G.O., No. 1585, dated 16th June 1886.

2. The Government in this department concur in the Chief Engineer's remarks.

3. The estimate received with the Government order quoted above is herewith
returned to the Judicial Department.

Ootacamund, (Signed) J. SHAW-STEWART, Col., R.E.,
14th July 1886. Secretary to Govt., P.W.D.

To the Judicial Department, with four enclosures.

ORDER—dated 22nd July 1886, No. 1932, Judicial.

Communicated to the Inspector-General of Jails in continuation of G.O., 16th June 1886, No. 1585. He will inform the Superintendent of the District Jail, Calicut, that the Government await his report regarding the site for the new cells.

2. The plan and estimate will be returned to the Public Works Department in view to the cells being constructed by that department.

(True Extract.)

E. F. WEBSTER,
Chief Secretary.

To the Inspector-General of Jails.

„ Public Works Department, with plan and estimate.

1/2 2030 Wa/13th August 1886

Communicated with
a copy of Pros: of
16th June 1886, No. 1585
Judicial, to the S. E.
IV file, who will
submit revised plans
and estimates based
on the Chief Engineer's
note of 13th July 1886.

1/24 Iss
W

S. E. IV f
with 4 enclos
Judl Dept

Govt. of 1886 Madras.

JUDICIAL.

Issued

Recd.

Encl.

G.O., 22nd July 1886, No. 1932.

JULY.

Jails.

Communicating to the Inspector-General of
Jails memorandum from the Public Works De-
partment regarding the erection of cells for luna-
tics in the district jail, Calicut, and requesting
him to inform the Superintendent that Govern-
ment await his report regarding the site of the
new cells.

With order