

(1) Number of pages 10
(2) Date of repair 9.11.87
(3) Initials of the Referencer lcw ✓

TAMIL NADU ARCHIVES

GOVERNMENT OF TAMIL NADU

p.w. DEPARTMENT

G.O. No. 212 W
B.P. No.

Press.
Mis.

212 W
Dated 26.1.1886

198

Not to be folded or roughly handled

P. W. D.

W Consulting Architect's Office,
Chopauli, Madras,
15th January 1886.
No. 1460

From

The Consulting Architect to the Government of Madras,

To

The Chief Engineer

In,

Public Works Dept.

I have the honor to submit
to herewith for your consideration
and approval an Estimate for
continuing ^{the} Western boundary
dwarf wall of the Beach Road
from Pycroft's Road to the Hindoo
burning ground a distance of
1575 feet.

The Estimate amounts to Rs 11,834.
A sum of Rs 4,000 - - - is entered
for this work in the Provincial
services Budget Estimate page 21
under the head of Miscellaneous

public improvements extending
"the dwarf wall up to the Hindu
"Cemetery". This I regret to say
is an error. It should have
been entered "extending the
dwarf wall up to St. Thome
the same as the promenade
extension item 37.

I have the honor to be

sir

your most obedt. servant

W. H. Wilson

Consy. Mch. to Govt.

Palup 29/9/10

7-12-85 file

38

16/1/10

2/212

From


THE CONSULTING ARCHITECT

TO THE GOVERNMENT OF MADRAS,

To

The Chief Engineer

Public Works Dept



No.

Dated 15th January 1886.

Received

No. of ENCLOSURES.

Subject.

Submits an Estimate amounting to Rs 11,834 for providing a stone boundary wall on the west side of the South Beach.

Current No.

Letter No.

Dated the

From the

NOTE OF REMARKS.

This estimate is submitted for the construction of a stone boundary wall on the west side of the South Beach, Madras, from George's Road to the Marine Grounds, a distance of 575 feet. The estimate amounts to Rs. 11,834.

The estimate is for a stone boundary wall with best stone and will stand 2 1/2 feet high. The foundation is to be of brick and mortar, 2 feet deep, resting on a concrete bed 1 foot deep. The stone piers are to be in the cut. Stone down wall at regular intervals. The rates are correct.

15 January 1886
B.P.

For orders -

The work is entered
under Class B. without
allotment, in the
Annual Budget
for 1886-87, item 36,
para 20-21.

Cu
19.1.86

The estimate for the
work is Rs. 11834/-
and is available.

The Government
has sanctioned the
work as available.

W
25.1.86

PROCEEDINGS OF THE MADRAS GOVERNMENT.

Under date the

From the Consulting Architect
to Government

Read the following

A. E. & Co. Memo of 15th January 1886.

The estimate amounting
to Rs. 11834/- for continuing the
~~western boundary~~ wall of
along the western side of
the Beach Road. Madras
from Poyet's Road to the
Hindoo Burial Ground is
sanctioned for execution
when funds are available.

2. This sanction has
been registered as Provincial
No. 199 W of 1885-86, and
classified as miscellaneous
Public Improvements, original
work.

25/1/86

The Engr. Archt to Govt with 2 copies.

Exam. P. W. Secy with duplicate
abstract estimate.

Financial Department

Cu

W
25.1.86

Govt of 1886

PUBLIC WORKS

1886

1886

1886

1886

1886

1886