Number of Pages :- 30.

Date of Repair - 17.12.1987

Initials of the Repairman

8/4

Tamil Nadu Archives.

Government of Tamilnadu

Public works Department

G.O. No.:- 3085

Dated - 16.11.1886

A&B

1/3025

16th November 1886, No. 3025 W., Public Works.

GOVERNMENT OF MADRAS.

PUBLIC WORKS DEPARTMENT.

Buildings and Roads.
Civil Works.

Read—the following letter from Major A. C. SMITH, R.E., Superintending Engineer, III Circle, to the Chief Engineer, Public Works Department, dated Bellary, 3rd November 1886, No. 1535:—

I have the honor to submit, for sanction of Government, revised estimates, aggregating Rs. 17,354, for completing the famine road from Koilkuntla to Nosam, in the Kurnool district, in supersession of the estimate of Rs. 20,559 sanctioned for this work in G.O., No. 700 W., dated 17th March 1882.

2. The original estimate, it would appear, was framed by an incompetent subordinate, who allowed unnecessarily large masonry works for small jungle streams; but the work was not then carried out for want of funds. The revised estimate provides for masonry works actually necessary and for other description of work as particularised below:—

		RS.
1.	Repairing the road by gravelling and metalling	6,184
7.	Masonry tunnels	2,740
39.	Road-dams of different dimensions	7,645
	Raising the road on the 1st and 19th miles	785
	Total ...	17,354

3. The road, when completed, will be very useful to the people of the Koilkuntla taluk, and it will act as a feeder to the Moodanoor station on the Madras Railway, *viâ* Jammalamadugu, a town of importance in the Cuddapah district.

Note by the Chief Engineer, Public Works Department.

The estimate is recommended for sanction with the following remarks:—

1. A comparative statement should have been submitted.
2. The rough stone revetment in the fourth mile should have a backing of gravel.

(Signed) J. O. HASTED, Col., R.E.,
Chief Engineer, P.W.D.

13th November 1886.

Order—dated 16th November 1886, No. 3025 W., Public Works.

The revised estimate, amounting to Rs. 17,354, for completing the road from Koilkuntla to Nosam, in the Kurnool district, is sanctioned in supersession of the estimate of Rs. 20,559 sanctioned in G.O., No. 700 W., dated 17th March 1882.

2. Attention is drawn to the note by the Chief Engineer, Public Works Department, above recorded.

3. This sanction has been registered as Local No. 31 W. of 1886-87.

(True Extract.)

Captain, R.E.,
Under Secy. to Govt., P.W.D.

To the Superintending Engineer, III Circle.
" Examiner, Public Works Accounts.
" Financial Department (L.F.), with thirty-eight enclosures.

Exd. L. Passaigue.
Spare Copies

2/3025

BUILDINGS AND ROADS.
CIVIL WORKS.

Govt. of 1886 Madras.

PUBLIC WORKS.

Dated November, 16th.

Encl.

Recd.

G.O., 16th Nov. 1886, No. 3025 W.

NOVEMBER.

Road

Revised estimate of Rs. 17,354, for completing the — from Koilkuntla to Nosam, in the Kurnool district, sanctioned.

3/25
24

GOVERNMENT OF MADRAS.

PUBLIC WORKS DEPARTMENT.

17th March 1882, No. 700 W.

Buildings and Roads.
Civil Works.

Read the following paper:—

No. 116. Proceedings of the Board of Revenue, dated 8th March 1882, No. 1234, Routine.

Read letter from the President, Local Fund Board, Kurnool, dated 4th February 1882, No. 94.

Completion of road from Koilkuntla to Nossam.

THE estimate amounting to Rs. 20,559, for the work marginally noted, is submitted for the sanction of Government through the Deputy Chief Engineer, Public Works Department.

2. The work appears as Item No. 3 in Part I of the current year's budget of the Kurnool Circle with an allotment of Rs. 1,500.

3. The President's attention is drawn to No. 30 of the Local Fund Rules, according to which the total amount of an estimate should be in round numbers.

(True Extract.)

(Signed) F. GIBSON,
Acting Sub-Secretary.

No. 117. ORDER THEREON, 17th March 1882, No. 700 W.

THE estimate amounting to Rs. 20,559, for completing the road from Koilkuntla to Nossam in the Kurnool District, is sanctioned.

2. This sanction has been registered as Local No. 60 W. of 1881-82.

(True Extract.)

Lieut.-Col., R.E.,
Ag. Under Secy. to Govt., P.W.D.

To the Board of Revenue, with five enclosures.
" Accountant-General.
" Financial Department.

Exd. S. T. Austin.
Spare Copies

BUILDINGS AND ROADS.
CIVIL WORKS.

Govt. of (1882) Madras.

PUBLIC WORKS.

To

THE BOARD OF REVENUE,
&c., &c.,

Dated March, 17th.

Issued

Recd. *Encl.*

G.O., 17th March 1882, No. 700 W.

MARCH.

Nos. 116-117.

Road from Koilkuntla to Nossam in the Kurnool District.—Estimate amounting to Rs. 20,559 for completing the —, sanctioned.

Proceedings of the ~~Court~~ Board of ~~Wards~~ Revenue,

Dated 8th March 1882.

No. 1234 ~~Miscellaneous~~ Routine.

READ letter from the President Local Fund Board Kurnool dated 4th February 1882 No. 94.

Completion of road from Koilkuntla to Nossum.

The estimate amounting to Rupees 20,559, for the work marginally noted, is submitted for the sanction of Government through the Dy. Chief Engineer P.W.D.

2. The work appears as item No. 3 in Part I of the current year's budget of the Kurnool Circle with an allotment of Rs. 1500.

3. The President's attention is drawn to No. 30 of the Local Fund Rules.

according to which, the total amount of an Estimate should be in round numbers.

(True Extract)

D. Gibbs

Asst Sub Secretary

To

The Secretary to Govt. P.W.D.
through the Dy Chief Engineer,
with the President's letter and
its 4 enclosures in original
to be returned.

Despd A. C. Mogg

1882.

Board of Revenue,

MADRAS.

P. W. C. No 1553

To

The Secretary to Govt.
P.W.D.
thro' the Dy Chief Engineer.

E-5 (1st of 24 [illegible]

Recd 9 March 82

~~Miscellaneous~~ Proceedings, dated 8th March 1882, No. 1234 Routine

Subject.

Submitting for the sanction of Govt. Estimate for completing road from Koilkuntla to Nossam in the Kurnool Dt.

6/325

P. W. DEPARTMENT—1881-82.

~~MEMORANDUM~~

Current No. 1553

Proceedings of the Board of Revenue
~~Letter~~ Number 1234

dated the 8th March 1882

from the ~~Supg. Engineer of~~ Board of Revenue Madras

Note of Remarks

703 W

The Estimate with plan, sections and Specification for Completion of Road from Koilkuntla to Nossam in the Kurnool Division, a distance of about 20 miles amounts to Rupees 20,559.

The whole length of the roadway requires clearing of Bushes filling the fissures forming Banks on the sides, and gravelling over the roadway 3 inches thick for a breadth of 5 yards of which 4 yards to be metalled 6 inches thick and will be watered and rammed. all streams are to be provided with Road Dams and Tunnels.

Tho

No. Buildings & [illegible]
Civil Works

PUBLIC WORKS DEPARTMENT.

MADRAS GOVERNMENT.

UNDER date the 17th March 1882

Read the following :—

P. E. No 1234 d/8th March /82

The estimate amounting to Rs 20,559 for completing the road from Koilkuntla to Nossam in the Kurnool district is sanctioned.

2. This sanction has been registered as Local No. 60 W of 1881-82.

13.3.82

13.3.82

The Rates more or less agree with the District sche

The estimate has been approved of and Countersigned by the President Local Fund Board.

11-3-82

No. 700 W. No. Buildings & Roads
Civil Works

PUBLIC WORKS DEPARTMENT.

A
[illegible]

PROCEEDINGS OF THE MADRAS GOVERNMENT.

UNDER date the 17th March 1882

Read the following :—

Proceedings of the Board of Revenue — A.E. No. 1234 d/8 March /82

[illegible]

The estimate amounting to Rs 20,559 for completing the road from Koilkuntla to Nossam in the Kurnool district is sanctioned.

2. This sanction has been registered as Local No. 60 W of 1881-82.

13.3.82

13.3.82

Board of Rev: with 5 enclos: ✓

Acct. Genl. ✓

Finl. Dept. ✓

28/3/82

1553

F.C.
C.P. 8578 of 86

Govt. of (1882) Madras.
PUBLIC WORKS.

To

Dated 17/3/82

Issued

Recd. Encl.

G. O. 17th March 1882, No. 700 W.

Nos.

Road from Koilkuntla to Nossam in the Kurnool District

Estimate amounting to Rs 20,559 for completing the — . Sanctioned

---

9/32

Road from Koilkuntla to Nossam Rs 17,354

W

A comparative statement should have been submitted

— There are 7 Tunnels provided for instead of 2 as entered in the S.E. letter and the amounts under each head should be as entered in pencil

— Would it not be advisable to place a backing of metal & clay & gravel under the stone revetment of the embankment in the 4th Mile, reported to as having been eaten away by a channel

---

Public Works Department.

Current No. 8578

Letter No. 1535

Dated the 3rd November 86

From the S.E. III Circle

CS 13/11/86

9.11.86

NOTE OF REMARKS.

The accompanying revised estimate with survey and plans provides for completing the road from Koil-kuntla to Nossam in the Kurnool district. The revised estimate amounts to Rs 17,354 — being Rs 3,205 less than the original estimate, Rs 20,559, sanctioned in G.O. No. 700 W. dated 17th March '82. The revised estimate is divided as follows:— Metalling and gravelling — Rs 6184; Tunnels — Rs 2,740; road dams — Rs 7,645; and raising causeways in the 1st and 19th miles — Rs 785.

2. The necessity for the present revision is stated to arise from the original estimate having been prepared by an incompetent subordinate who provided masonry works unnecessarily large and expensive for the various small streams the road crosses in its course—

FC
CRC-8578 of 86

Note

The Estimate is recommended for Sanction with the following remarks.

A comparative statement should have been submitted.

The Rough stone contract for the 2nd mile should have a backing of gravel -.

Sanction accordingly.

11/11/86

Public Works Department.

CS 13.11.86

Current No. 8578

Letter No. 1535

Dated the 3rd November 86

From the S.E. III Circle

9.11.86

NOTE OF REMARKS.

The accompanying revised estimate with survey and plans, provided for [illegible] road from [illegible] -kuntlam to Noorkan in the [illegible] district. — The revised estimate amounts to Rs. 17,354 — being Rs. 3,205 less than the original estimate, Rs. 20,559, sanctioned in G.O. No. 700 W. of the 17th March '82. — The revised estimate is divided as follows:— Metalling and gravelling — Rs. 6184; [illegible] — Rs. 2,740; road dams — Rs. 7,645; and raising the road in the 1st and 19th [illegible] — Rs. 785.

2. The necessity for the present revision is stated to arise from the original estimate having been prepared by an incompetent subordinate who provided masonry works unnecessarily large and expensive for the various small streams the road crosses in its course—

the tunnels and road dams of the present revised estimate are thought fully to meet all requirements.

3. A comparative statement is not submitted, and the reason assigned for its non-submission is not sound. It is said that:- "The rates allowed in the accompanying revised estimate being about the same as those in the original estimate, a comparative statement is not necessary." - and this would seem to imply that in cases where the revision is due to proposed differences in the quantities or qualities of the materials to be employed, or to a change in form of construction, the comparative statement may be regarded as superfluous.

4. The rates seem fair. - The revised estimate, survey and plans have been countersigned by the Vice President of the district L. F. Board.

314
5/11/86

11/322

Superintending Engineer's Office,
3rd Circle

No. 1535

Bellary 3rd Novr. 1886.

From,
Major A. C. Smith R.E.
SUPERINTENDING ENGINEER,
IIIrd CIRCLE.

To,
THE Chief Engineer
P. W. D.
Madras

4/11/86

Sir,

I have the honor to submit for sanction of Government revised estimates aggregating Rs 17,354 for completing the famine road from Koilkuntla to Nossam in the Kurnool District in supersession of the estimate of Rs 20,559 sanctioned for this work in G. O. No. 700 W dated 17th March 1882.

2. The original estimate, it would appear, was framed by an incompetent subordinate who allowed unnecessarily large masonry works for small jungle streams; but the work

Enclosures. 38×
1 Survey.
10 Long. Sections &c.
1 Plan of masonry work.
1 Detd. & Abst. estimate for earth work.
18 Detd. & Abst. estimates for masonry works.
2 Specifications
2 Data
1 Gl. Abstract
1 Detd. & Abst. estimate for road work
1 Report.

× Were forwarded by parcel post

was not then carried out for want of funds. The revised estimate provides for masonry works actually necessary and for other description of work as particularised below.

1. Repairing the road by gravelling and metalling ——— Rs 6184.

2. Masonry tunnels ——— 995

39. Road dams of different dimensions ——— 9390

Raising the road on the 1st and 19th miles ——— 785.

Total Rs. 17354

3. The road when completed will be very useful to the people of the Koilakuntla Taluq, and it will act as a feeder to the Moodanoor station on the Madras Railway via Jammalamadugu a town of importance in the Cuddapah District.

I have the honor to be
Sir
Your most obedt Servant
A. L. Smith. Major R.E.
Suptg Engineer 3rd Circle

12/325
2

P.W. No. 8578

From,
The Superintending Engineer,
IIIrd Circle.

To,
The Chief Engineer
P. W. D
Madras

No. 700 W d/ 17.3.82

Dated 3 } November 1886.
Received 4 }

Enclosures. +38.
(+12 plans)

No. 1535

Famine road from Koilkuntla to Nossam in the Kurnool District.

Submitting for sanction of Govt. revised estimates aggregating Rs 17,354 for completing the └┘.

Note by the Chief Engineer, P. W. Department.

The estimate is recommended for sanction with the following remarks:-

1. A comparative statement should have been submitted.

2. The rough stone revetment in the fourth mile should have a backing of gravel.

13/11/86 E. W.

13.11.86

B & R
Works

19/3

PUBLIC WORKS DEPARTMENT.

A

No 3025

PROCEEDINGS OF THE MADRAS GOVERNMENT.

READ the following

From the Supdg. Engineer III Circle. H. E. No: 1535 d/ 3rd November 1886.
Note by the Chief Engineer P. W. Department d/ 13th " "

The revised estimate amounting to Rs 17,354, for completing the road from Koilkuntla to Nosam in the Kurnool District, is sanctioned in supersession of the estimate of Rs. 20,559 sanctioned in G. O. No: 700 W dated 17th March 1882.

2. Attention is drawn to the note by the Chief Engineer P. W. Department above recorded.

3. This sanction has been registered as Local No: 31 W of 1886-87.

D
24/11/86

13.11.86

To
The Supdg. Engr. III Circle ✓
" Examiner of P. W. Accts ✓
" Financial Department (L. F.)
with 38 enclosures

(To The Chief Secy for favor of counter initials)

Jon
13/11/86

W
13/11

85/0

Govt. of (1886) Madras.

PUBLIC WORKS.

17/11

Recd 18/11 - 9 am

Dated

Recd

Encl.

G.O., 16th Novr 1886, No 3025 W

Road

Revised Estimate of Rs 17,354 for completing the —— from Koilkuntla to Nosam in the Kurnool district, Sanctioned.

60/4

P 7/11 eve 10/11

✓