(1) Number of pages 40

(2) Date of repair 18-1-88

(3) Initials of the Referencer

TAMIL NADU ARCHIVES

GOVERNMENT OF TAMIL NADU

Public Works DEPARTMENT

G.O. No. 1098 Press.
~~B.P. No.~~ ~~Mis.~~

Dated 21-4-1887 198.

Not to be folded or roughly handled

Archives I--10,006 1-80.

1098/1

21st April 1887, No. 1098 W., Public Works.

GOVERNMENT OF MADRAS.

PUBLIC WORKS DEPARTMENT.

Buildings and Roads.
Civil Works.

Read—the following papers:—

From the Consulting Architect to Government, dated 4th February 1887, No. 1327.

From J. W. BRASSINGTON, Esq., Officiating Consulting Architect to the Government of Madras, to the Chief Engineer, Public Works Department, dated Chepâk, 12th March 1887, No. 1530.

I have the honor to submit a revised plan, with schedule of quantities, for a Sub-Judge or District Munsif's court.

2. This design will supersede the design circulated with G.O., No. 505 W., dated the 6th March 1885.

3. The revised design and quantities for Tahsildars' cutcherries will follow.

No. 970 C.

Forwarded for the approval of Government in the Judicial Department.

2. The design has already been approved in Committee by the Honorable Members and Secretaries to Government.

(Signed) J. O. HASTED, Colonel, R.E.,
Secretary to Govt., P.W.D.

15th March 1887.

Approved and transferred to the Public Works Department.

(By Order.)

(Signed) H. A. STUART,
Under Secy., J.D.

Ootacamund,
12th April 1887.

Order—dated 21st April 1887, No. 1098 W., Public Works.

The revised type design, with schedule of quantities and descriptive specification, for a Sub-Judge's or District Munsif's court-house with tiled roof, will be circulated to officers of the Public Works Department, for information and guidance, in supersession of the design circulated with G.O., No. 505 W., dated 6th March 1885.

2. The Consulting Architect will, as early as practicable, submit a type design affording the same accommodation for a court-house with a terraced roof.

3. The submission of a revised type design for taluk offices is awaited.

(True Extract.)

(Signed) J. O. HASTED, Colonel, R.E.,
Secretary to Govt., P.W.D.

To Superintending Engineers.
,, the Consulting Architect to Government.
,, the Judicial Department.

Exd. P. L. Pereira.

Spare Copies.

BUILDINGS AND ROADS.
CIVIL WORKS.

Govt. of | 1887 | Madras.

PUBLIC WORKS.

Dated April, 21st

Recd. *Encl.*

G.O., 21st April 1887, No. 1098 W.

APRIL.

Sub-Judge's or District Munsif's Court-house

A revised type design for a — with tiled roof, circulated to officers of the Pub Works Department.

1098/2

SUB-JUDGE OR DISTRICT MUNSIF'S COURT-HOUSE.

Descriptive Specification.

Foundation.—A depth of 5 feet is provided in the quantities, but this should be settled locally in accordance with the nature of the soil.

Brickwork.—The walls should be carried up in English bond-walls of central portion being 2½ bricks thick, ends 2 bricks thick, partitions 1½ bricks thick, verandah retaining walls 1 brick thick, except under posts, which will be half a brick thicker.

Where good bricks are obtainable the exterior of the building should be pointed.

Woodwork.—The verandah posts, trusses, doors and windows should be of teakwood, the rafters and other minor roof timbers may be of approved country wood.

Tiled roofing.—The roof will be covered with flat and pantiles; if the quality of these are good the usual unsightly "chunam bands" might be dispensed with.

All valleys should be protected with sheet lead.

Stonework.—Stone slabs 12″ × 12″ × 6″ with mortice holes 2 inches square and 2 inches deep cut into them into which the verandah posts will rest. Slabs will also be placed under the bearings of trusses. The steps may also be of stone if procurable without great expense.

Flooring.—The floor may be of square bricks or stone slabs if the latter are easily procurable.

Interior finishing.—The interior will be fine plastered with shell lime or plastered and washed.

Finials.—The finials may be of copper, iron or wood.

The different kinds of work to be done will be executed in conformity with the standard specification of the Public Works Department.

(Signed) J. W. BRASSINGTON,
Offg Consulting Architect to Government.

Estimate Form—Detail Measurements.

Detail of work.	No.	Measurements in Feet.			Area or contents.	Total quantity of each description of work.
		Length.	Breadth.	Depth.		
EXCAVATION FOR FOUNDATIONS.						
Court-house, record and property room.						
Outer walls	...	151 3	4 10½	5 0	4,052	
Partition	1	15 0	4 10½	5 0		
Do.	1	19 0	4 1½	5 0	392	
Gumastah's, Head Clerk's, Judge's retiring room, &c.						
Outer walls	2	99 6	4 6	5 0	4,478	
Partitions	3	12 0	4 1½	5 0	743	
Verandah	...	261 9	3 9	5 0	4,908	
Extra for posts	28	4 0	0 3	5 0	146	
Do. at corners	8	0 3	0 3	5 0		
Do. next to walls	4	0 9	0 3	5 0		
Steps	1	14 0	3 0	1 6	252	
Do.	4	10 6	3 0	1 6		
Total, Cubic Feet ...	...	...	...	...	...	14,971
CONCRETE.						
Court-house, record and property room.						
Outer walls	...	151 3	4 10½	1 6	1,216	
Partition	1	15 0	4 10½	1 6		
Do.	1	19 0	4 1½	1 6	118	

Estimate Form—Detail Measurements—*cont.*

Detail of work.	No.	Measurements in Feet.			Area or contents.	Total quantity of each description of work.
		Length.	Breadth.	Depth.		
Gumastah's, Head Clerk's, Judge's retiring room, &c.						
Outer walls	2	99 6	4 6	1 6	1,343	
Partitions	3	12 0	4 1½	1 6	223	
Verandah	...	261 9	3 9	1 6	1,472	
Extra for posts	28	4 0	0 3	1 6	} 44	
Do. at corners	8	0 3	0 3	1 6		
Do. next to walls	4	0 9	0 3	1 6		
Steps	1	14 0	3 0	1 6	} 252	
Do.	4	10 6	3 0	1 6		
Total, Cubic Feet ...	...	...	...	...	...	4,668
BRICKWORK IN FOUNDATIONS.						
Footings.						
Court-house, record and property room.						
Outer walls	...	151 3	2 10½	1 6	} 726	
Partitions	1	17 0	2 10½	1 6		
Do.	1	21 0	2 1½	1 6	67	
Gumastah's, Head Clerk's, Judge's retiring room, &c.						
Outer walls	2	101 6	2 6	1 6	} 919	
Partitions	3	14 0	2 6	1 6		
Verandah	...	267 9	1 9	1 6	703	
Extra for posts	28	2 0	0 3	1 6	} 23	
Do. at corners	8	0 3	0 3	1 6		
Do. next to walls	4	0 9	0 3	1 6		
Above footings to ground level.						
Court-house, record and property room.						
Outer walls	...	151 3	1 10½	2 0	567	
Extra thickness for plinth in rear wall and ends	...	43 0	0 3	2 0	22	
Partition	1	18 0	1 10½	2 0	68	
Do.	1	22 0	1 1½	2 0	50	
Gumastah's, Head Clerk's, Judge's retiring room, &c.						
Outer walls	2	102 6	1 6	2 0	615	
Extra thickness for plinth at ends ...	2	18 0	0 3	2 0	18	
Partitions	3	15 0	1 1½	2 0	101	
Verandah	...	270 9	0 9	2 0	406	
Extra for posts	28	1 0	0 3	2 0	} 17	
Do. at corners	8	0 3	0 3	2 0		
Do. next to walls	4	0 9	0 3	2 0		
Total, Cubic Feet ...	...	...	...	...	...	4,302
BRICKWORK IN BASEMENT.						
Court-house, record and property room.						
Outer walls	...	151 3	1 10½	2 0	567	
Extra thickness for plinth in rear and ends	...	43 0	0 3	2 0	22	
Partition	1	18 0	1 10½	2 0	68	
Do.	1	22 0	1 1½	2 0	50	

Estimate Form—Detail Measurements—*cont.*

Detail of work.	No.	Measurements in Feet.			Area or contents.	Total quantity of each description of work.
		Length.	Breadth.	Depth.		
Gumastah's, Head Clerk's, Judge's retiring room, &c.						
Outer walls	2	102 6	1 6	2 0	615	
Extra thickness for plinth at ends ...	2	18 0	0 3	2 0	18	
Partitions	3	15 0	1 1½	2 0	101	
Verandah	...	270 9	0 9	2 0	406	
Extra for posts	28	1 0	0 3	2 0	} 17	
Do. at corners	8	0 3	0 3	2 0		
Do. next to walls	4	0 9	0 3	2 0		
Steps	1	12 3	2 0	1 6	} 139	
Do.	4	8 6	2 0	1 6		2,003
Deductions—						
Stone under-posts and for steps ...	...	...	...	...	...	105
Total, Cubic Feet ...	...	...	...	...	...	1,898
BRICKWORK IN SUPERSTRUCTURE.						
Court-house, record and property room.						
Outer wall	...	151 3	1 10½	18 6	} 5,871	
Partition	1	18 0	1 10½	18 6		
Gable	1	18 0	1 10½	3 0	101	
Partition	1	22 0	1 1½	24 6	606	
Gumastah's, Head Clerk's, Judge's retiring room, &c.						
Outer walls	2	102 6	1 6	13 5	4,126	
Partitions	3	15 0	1 1½	13 5	} 806	
Gables	3	15 0	1 1½	2 6		
Dais wall	...	23 6	0 9	1 0	18	11,528
Deductions—						
At hip from partition in record and property room	1	9 0	1 1½	3 0	30	
Doors	9	4 0	1 10½	8 0	540	
Do.	12	4 0	1 6	8 0	576	
Do.	2	4 0	1 1½	8 0	72	
Windows	2	4 0	1 10½	6 0	90	
Do.	2	4 0	1 6	6 0	72	
Ventilators	9	4 0	1 10½	2 9	186	
Archwork as per details	...	...	...	...	247	1,813
Total, Cubic Feet ...	...	...	...	...	...	9,715
Archwork.						
Over doors and windows	11	5 0	1 10½	1 1½	116	
Do. do.	14	5 0	1 6	1 1½	118	
Do. do.	2	5 0	1 1½	1 1½	13	
Total, Cubic Feet ...	...	...	...	...	...	247
Cut-stonework.						
Under-posts	40	1 0	1 0	0 6	20	
Steps	...	169 0	1 0	0 6	85	
Slabs under trusses	4	2 0	1 10½	0 4	5	
Do. do.	10	1 6	1 6	0 4	8	
Total, Cubic Feet ...	...	...	...	...	...	118

Detail of work.	No.	Measurements in Feet.			Area or contents.	Total quantity of each description of work.
		Length.	Breadth.	Depth.		
Filling in basement.						
Court-house	1	30 0	18 0	1 6	810	
Court dais	1	7 6	7 3	1 0	54	
Record and property room	2	22 0	8 5¼	1 6	557	
Gumastah's, head clerk's, judge's retiring room, &c.	...	81 1½	15 0	1 6	1,825	
Verandahs	...	218 3	8 3	1 6	2,701	
Total, Cubic Feet ...	...	...	...	...	...	5,947
Teakwood wrought and put up.						
Court-house, record and property room.						
2 Trusses to span 18 feet. Tie beams	2	21 9	0 4	0 7	8	
Principal rafters ...	4	11 9	0 4	0 6	8	
Struts	4	5 9	0 4	0 4	3	
Purlins allowing for halving ...	2	47 0	0 5	0 6	20	
Do. over wall do. ...	2	58 6	0 4	0 4	18	
Do. do. ...	2	22 0	0 4	0 4		
Ridge	1	38 0	0 3	0 9	7	
Principal rafters in record and property room	2	11 9	0 4	0 6	4	
Hip rafters	4	19 6	0 4	0 5	11	
Common rafters (18 inches centre to centre)	46	14 6	0 3	0 5	130	
Do. do. ...	6	13 0	0 3	0 5		
		Average length.				
Jack rafters	56	9 0	0 3	0 5		
Gumastah's, Head Clerk's, Judge's retiring room.						
5 Trusses to span 15 feet. Tie beams	5	18 0	0 4	0 6	15	
Principal rafters ...	10	9 9	0 4	0 5	14	
Struts	10	4 9	0 4	0 4	5	
Purlins allowing for halving ...	4	41 0	0 4	0 5	23	
Do. over wall	4	45 0	0 3	0 4	18	
Do. do.	2	18 0	0 3	0 4		
Ridge	2	37 0	0 2½	0 7	9	
Hip rafters	4	16 6	0 4	0 4	7	
Common rafters (18 inches centre to centre)	98	11 3	0 3	0 4	112	
		Average length.				
Jack rafters	40	6 0	0 3	0 4		
Verandahs.						
Posts	40	0 6	0 6	7 6	75	
Breastsummers allowing for halving.	...	282 0	0 6	0 6	71	
Ridge for entrance to court ...	1	11 0	0 3	0 6	1	
Ridge for end gables of verandah ...	4	5 6	0 2½	0 6	2	
Hip rafters	8	17 0	0 4	0 5	19	
Hip for gable at entrance	2	11 6	0 3	0 5	256	
Hip do. at ends	4	8 6	0 3	0 5		
Common rafters	110	13 3	0 3	0 5		
Jack rafters at entrance gable ...	9	9 6	0 3	0 5		
Do. at corners	72	9 3	0 3	0 5		
Do. at end gables	8	8 0	0 3	0 5		
Do. do.	24	5 6	0 3	0 5		
Wall plate at front and ends of court.	...	62 0	0 4	0 3	5	

1098/4

Detail of work.	No.	Measurements in Feet.			Area or contents.	Total quantity of each description of work.
		Length.	Breadth.	Depth.		
Verandahs—cont.						
Barge board at entrance gable ...	2	8 6	0 1½	0 8	1	
Do. do. do. ...	2	3 0	0 1½	1 0	1	
Do. do. knobs ...	2	0 6	0 6	0 9	1	
Collar piece	1	6 6	0 4	0 3	1	
Do. plank	1	5 0	0 1½	1 9	1	
Barge boards at ends	8	6 6	0 1	0 7	3	
Collar pieces	4	5 6	0 2	0 3	1	
Plank	4	1 0	0 2	1 6	1	
Total, Cubic Feet ...	...	...	...	...	...	851
Venetian and panel doors with frames.						
Outer doors	17	4 0	...	8 0	544	
Total, Square Feet ...	...	...	...	...	...	544
Panelled doors with frames.						
Inner doors, and for record and property room	6	4 0	...	8 0	192	
Total, Square Feet ...	...	...	...	...	...	192
Venetian windows with glazed shutters and iron bars	4	4 0	...	6 0	...	
Total, Square Feet ...	...	...	...	...	...	96
Ventilators.						
For court, record and property room.	9	4 0	...	2 9	...	
Total, Square Feet ...	...	...	...	...	...	99
Wrought Iron work in trusses.						
1" diar. kingrods for 18 feet trusses.	2	8 0	=16 0	× 2·62	= 41·92	
1" hex. nut and bolt heads for do.	6	...	...	× 1·10	= 6·60	
3" diar. ½" thick washers for do.	4	...	...	0·32	= 1·28	
1½" × ½" heel straps for do.	4	2 9	=11 0	× 2·50	= 27·50	
1½" × ½" bearing plates for do.	4	0 6¾	= 2 3	× 2·50	= 5·62	
⅝" hex. nuts for do.	8	...	...	× ·267	= 2·13	
Caps of ⅜" plates 6" wide	2	2 0	= 4 0	× 7·51	= 30·04	
⅞" diar. kingrods for 15 feet trusses.	5	6 7½	=33 1½	× 2·01	= 66·58	
⅞" hex. nut and bolt heads for do.	15	...	...	× 0·73	= 10·95	
3" diar. ½" thick washers for do.	10	...	...	× 0·32	= 3·20	
1½" × ⅜" heel straps for do.	10	2 3	=22 6	× 1·87	= 42·07	
1½" × ⅜" bearing plates for do.	10	0 6¾	= 5 7½	× 1·87	= 10·51	
⅝" hex. nuts for do.	20	...	...	·267	= 5·34	
Caps of ⅜" plate 6" wide	5	1 6	= 7 6	× 7·51	= 56·32	
Total, lb. ...	...	...	...	...	...	310
Tiled roofing with flat and pan tiles.						
Court-house, &c.	1	61 0	...	30 0	1,830	
Gumastah's, head clerk's and judge's retiring room, &c.	2	46 0	...	25 0	2,300	
Verandahs	...	160 0	...	11 0	1,760	
Do.	...	80 0	...	12 6	1,000	
Square Feet ...	...	...	...	...	6,890	
Total, Squares ...	...	...	...	...	...	70

Estimate Form—Detail Measurements—*cont.*

Detail of work.	No.	Measurements in Feet.			Area or contents.	Total quantity of each description of work.
		Length.	Breadth.	Depth.		
Flooring with 8 inches square pavement bricks.						
Court-house	1	30 0	...	18 0	540	
Record and property room	2	8 5¼	...	22 0	371	
Gumastah's, head clerk's, judge's retiring room, &c.	...	81 1½	...	15 0	1,217	
Verandahs	...	237 9	...	9 0	2,140	
Square Feet ...	...	...	...	...	4,268	
Total, Squares ...	...	...	...	...	...	43
Plastering interior (2 coats).						
Court-house	...	96 0	...	18 6	1,776	
Court gables	1	18 0	...	3 0	54	
Dais sides	2	8 0	...	1 0	16	
Record and property rooms	2	60 10½	...	18 6	2,252	
Additional height to partition ...	2	17 6	...	6 0	210	
Gable	1	16 10½	...	6 0	101	
Door and window jambs	11	20 0	...	1 10½	413	
Ventilator jambs	9	9 6	...	1 10½	160	
Gumastah's, head clerk's rooms, &c.		302 3	...	13 5	4,055	
Door and window jambs	14	20 0	...	1 6	420	
Do. do.	2	20 0	...	1 1½	45	9,502
Deductions—						
Doors	27	4 0	...	8 0	864	
Windows	4	4 0	...	6 0	96	
Ventilators	9	4 0	...	2 9	99	1,059
						8,443
Square Feet ...	...	...	...	...	...	
Total, Squares ...	...	...	...	...	...	85
Pointing exterior.						
Basement all round	...	352 9	...	2 0	706	
Court-house, &c.	...	118 9	...	18 6	2,197	
Gumastah's rooms, &c.	2	105 6	...	13 5	2,831	5,734
Deductions—						
Doors	19	4 0	...	8 0	608	
Windows	4	4 0	...	6 0	96	
Ventilators	9	4 0	...	2 9	99	803
Square Feet ...	...	...	...	...	...	4,931
Total, Squares ...	...	...	...	...	...	50
Lead sheeting for valleys	...	96 0	1 6	=144 0	× 5	720 lb.
Mouldings over windows (exterior).	4	5 3	...	...	21	L. ft.
Railings for dais	...	...	...	...	25	L. ft.
Finials over court room	...	...	...	2 in number.		
Finials over Gumastah's and Nazarat establishment	...	...	...	2 in number.		
Finials for verandahs	...	...	...	5 in number.		

1028
5

Estimate Form—Detail Measurements—*cont.*

Detail of work.	No.	Measurements in Feet.			Area or contents.	Total quantity of each description of work.
		Length.	Breadth.	Depth.		
Painting with 3 coats of Carson's paint.						
Venetian and panel doors	3	544 0	...	...	1,632	
Panelled doors	2	192 0	...	...	384	
Venetian and glazed windows ...	5	96 0	...	...	480	
Ventilators	2	99 0	...	...	198	2,694
Roof timbers including reepers and verandah posts	...	...	...	...	..	11,800
Square Feet ...	...	...	...	...	...	14,494
Total, Squares ...	...	...	...	...	...	145
Punkah.						
Over dais	1	10 0	...	...	10	L. ft.

ESTIMATE FORM—Abstract.

Quantity.	Description of work.	Rate.	Per	Amount.	Total.
		RS		RS.	RS.
14,971 C. feet ...	Excavation for foundations (rate to include refilling of trenches) ...	...	1,000 C. feet.		
4,668 „ ...	Concrete in foundations	...	100 „		
4,302 „ ...	Brickwork in foundations	...	„		
1,898 „ ...	Do. in basement	...	„		
9,715 „ ...	Do. in superstructure	...	„		
247 „ ...	Archwork	...	„		
118 „ ...	Cut stonework	..	C. feet.		
5,947 „ ...	Filling in basement	...	1,000 C. feet.		
851 „ ...	Teakwood wrought and put up ...	...	C. feet.		
544 Sq. feet ..	Venetian and panel doors with frames complete	...	Sq. feet.		
192 „ ..	Panelled doors with frames complete ...	...	„		
96 „ ...	Venetian windows with glazed shutters and iron bars complete	...	„		
99 „ ...	Ventilators	...	„		
310 lb. ...	Wrought ironwork in trusses ...	...	lb.		
70 Squares ..	Tiled roofing with flat and pantiles including teak reepers	...	Square.		
43 „ ...	Flooring with 8-inch square pavement bricks	...	„		
85 „ ...	Plastering interior (two coats) ...	...	„		
50 „ ...	Pointing exterior	...	„		
720 lb. ...	Lead sheeting for roof valleys ...	...	lb.		
21 L. feet. ...	Moulding over windows	...	L. feet.		
25 „ ...	Hand railing for dais	...	„		
2 in No. ...	Finials over court room	...	Each.		
2 „ ...	Do. at ends	...	„		
5 „ ...	Do. for verandah	...	„		
145 Squares ...	Painting with 3 coats of Carson's paint.	...	Square.		
5 in No. ...	Add extra for finishing barge boards ...	...	Each.		
1 „ ...	Punkah 10 feet long	...	„		
	Petty supervision				
	Contingencies				

(Signed) J. W. BRASSINGTON,
Offg. Consulting Architect to Government.

MADRAS,
12th March 1887.

Sub Judge or District Munsif's Court-House

Descriptive Specification

Foundation — A depth of 5 ft. is provided in the quantities but this should be settled locally in accordance with the nature of the soil.

Brickwork — The walls should be carried up in English bond. Walls of central portion being 2½ bricks thick, ends 2 bricks thick, partitions 1½ bricks thick, verandah retaining walls 1 brick thick except under post which will be half a brick thicker. Where good bricks are obtainable the exterior of the building should be pointed.

Woodwork — The verandah posts, Trusses, Doors & windows should be of Teakwood, the rafters, and other minor roof timbers may be of approved country wood.

Tiled roofing — The roof will be covered with flat & pan tiles, if the quality of these are good the usual unsightly "Chunam bands" might be dispensed with.

All valleys should be protected with sheet lead.

Stonework — Stone slabs 12" × 12" × 6" with mortice holes 2" square and 2" deep cut into them into which the verandah posts will rest. Slabs will also be

placed.

placed under the bearings of trusses. The steps may also be of stone if procurable without great expense.

Flooring ——— The floor may be of square bricks or stone slabs if the latter are easily procurable

Interior Finishing ——— The interior will be fine plastered with shell lime or plastered & washed

Finals ——— The finals may be of copper, Iron or wood.

The different kinds of work to be done will be executed in conformity with the standard Specification of the Public Works Department.

J W Brassington

Offg. Consulting Architect
to Government

pud 1245/87

(P. W. D. Code.—Paras.)

P. W. D. Form.
No. M 204.

1088 2

ESTIMATE FORM.—Detail Measurements.

Detail of Work.	Number.	Measurements in Feet. Length.	Breadth.	Depth.	Area or Contents.	Total Quantity of each description of Work.
Excavation for Foundations						
Court House, Record & property room						
Outer walls	—	151. 3	4. 10½	5. 0	4052	
Partition	1	15. 0	4. 10½	5. 0		
do	1	19. 0	4. 1½	5. 0	392	
Gumastahs, Head Clerks Judges retiring room &c						
Outer walls	2	99. 6	4. 6	5. 0	4478	
Partitions	3	12. 0	4. 1½	5. 0	743	
Verandah	—	261. 9	3. 9	5. 0	4908	
Extra for posts	28	4. 0	0. 3	5. 0	146	
do at corners	8	0. 3	0. 3	5. 0		
do next to walls	4	0. 9	0. 3	5. 0		
Steps	1	14. 0	3. 0	1. 6	252	
do	4	10. 6	3. 0	1. 6		
Total Cubic feet						14971
Concrete.						
Court House, Record & property room						
Outer walls	—	151. 3	4. 10½	1. 6	1216	
Partition	1	15. 0	4. 10½	1. 6		
do	1	19. 0	4. 1½	1. 6	118	
Carried over Cubic feet					1334	

20,000—10-11-86.

ESTIMATE FORM.—Detail Measurements.

Detail of Work.	Number.	Measurements in Feet.			Area or Contents.	Total Quantity of each description of Work.
		Length.	Breadth.	Depth.		
Brought forward Cubic ft					1334	
Gumastahs, Head Clerks, Judges retiring room &c						
Outer walls	2	99. 6	4. 6	1. 6	1343	
Partitions	3	12. 0	4. 1½	1. 6	223	
Verandah	—	261. 9	3. 9	1. 6	1472	
Extra for posts	28	4. 0	0. 3	1. 6	44	
do at Corners	8	0. 3	0. 3	1. 6		
do next to walls	4	0. 9	0. 3	1. 6		
Steps	1	14. 0	3. 0	1. 6	252	
do	4	10. 6	3. 0	1. 6		
Total Cubic feet						4,668
Brickwork in foundations Footings						
Court House, Record & property room						
Outer walls	—	151. 3	2. 10½	1. 6	726	
Partitions	1	17. 0	2. 10½	1. 6		
do	1	21. 0	2. 1½	1. 6	67	
Gumastahs, Head Clerks, Judges retiring room &c						
Outer walls	2	101. 6	2. 6	1. 6	919	
Partitions	3	14. 0	2. 6	1. 6		
Verandah		267. 9	1. 9	1. 6	703	
Carried over Cubic feet					2415	

1088/5

[P. W. D. Code.—Paras.]

P. W. D. Form.
No. M 204.

ESTIMATE FORM.—Detail Measurements.

16

Detail of Work.	Number.	Measurements in Feet.			Area or Contents.	Total Quantity of each description of Work.
		Length.	Breadth.	Depth.		
Brought forward Cubic feet					2415	
Extra for posts	28	2. 0	0. 3	1. 6	23	
do at Corners	8	0. 3	0. 3	1. 6		
do next to walls	4	0. 9	0. 3	1. 6		
Above footings to ground level						
Court House, Record & property room						
Outer walls	—	151. 3	1. 10½	2. 0	567	
Extra thickness for plinth in rear wall & ends	—	43. 0	0. 3	2. 0	22	
Partition	1	18. 0	1. 10½	2. 0	68	
do	1	22. 0	1. 1½	2. 0	50	
Gumastahs, Head Clerks, Judges retiring room &c						
Outer walls	2	102. 6	1. 6	2. 0	615	
Extra thickness for plinth at ends	2	18. 0	0. 3	2. 0	18	
Partitions	3	15. 0	1. 1½	2. 0	101	
Verandah	—	270. 9	0. 9	2. 0	406	
Extra for posts	28	1. 0	0. 3	2. 0	17	
do at Corners	8	0. 3	0. 3	2. 0		
do next to Walls	4	0. 9	0. 3	2. 0		
Total Cubic feet						4,302

ESTIMATE FORM.—Detail Measurements.

Detail of Work.	Number.	Measurements in Feet. Length.	Breadth.	Depth.	Area or Contents.	Total Quantity of each description of Work.
Brickwork in basement.						
Court House, Record & property room						
Outer walls	–	151. 3	1. 10½	2. 0	567	
Extra thickness for plinth in rear rooms	–	43. 0	0. 3	2. 1	22	
Partition	1	18. 0	1. 10½	2. 0	68	
do	1	22. 0	1. 1½	2. 0	50	
Gumastahs, Head Clerks, Judges retiring room &c						
Outer walls	2	102. 6	1. 6	2. 0	615	
Extra thickness for plinth at ends	2	18. 0	0. 3	2. 0	18	
Partitions	2	15. 0	1. 1½	2. 0	101	
Verandah	–	270. 9	0. 9	2. 0	406	
Extra for posts	28	1. 0	0. 3	2. 0	17	
do at Corners	8	0. 3	0. 3	2. 0		
do next to walls	4	0. 9	0. 3	2. 0		
Steps	1	12. 3	2. 0	1. 6	139	
do	4	8. 6	2. 0	1. 6		
						2,003
Deductions						
Stone under posts and for steps						105
Total Cubic feet						1898

[P. W. D. Code.—Paras.]

P. W. D. Form.
No. M 204.

1098/9

ESTIMATE FORM.—Detail Measurements.

Detail of Work.	Number.	Measurements in Feet. Length.	Breadth.	Depth.	Area or Contents.	Total Quantity of each description of Work.
Brickwork in Superstructure						
Court House, Record & property room						
Outer wall	–	151. 3	1. 10½	18. 6	5,871	
Partition	1	18. 0	1. 10½	18. 6		
Gable	1	18. 0	1. 10½	3. 0	101	
Partition	1	22. 0	1. 1½	24. 6	606	
Gumastahs, Head Clerks, Judges retiring room &c						
Outer walls	2	102. 6	1. 6	13. 5	4,126	
Partitions	3	15. 0	1. 1½	13. 5	806	
Gables	3	15. 0	1. 1½	2. 6		
Dais wall	–	23. 6	0. 9	1. 0	18	11,528
Deductions						
At hips from partition in Record and property room	1	9. 0	1. 1½	3. 0	30	
Doors	9	4. 0	1. 10½	8. 0	540	
Do	12	4. 0	1. 6	8. 0	576	
Do	2	4. 0	1. 1½	8. 0	72	
Windows	2	4. 0	1. 10½	6. 0	90	
Do	2	4. 0	1. 6	6. 0	72	
Ventilators	9	4. 0	1. 10½	2. 9	186	
Archwork as per details					247	1,813
Total Cubic feet						9715

20,000—10-11-86.

6

ESTIMATE FORM.—Detail Measurements.

Detail of Work.	Number.	Measurements in Feet. Length.	Breadth.	Depth.	Area or Contents.	Total Quantity of each description of Work.
Archwork						
Over doors & windows	11	5. 0	1. 10½	1. 1½	116	
Do	14	5. 0	1. 6	1. 1½	118	
Do	2	5. 0	1. 1½	1. 1½	13	
Total Cubic feet						247
Cut Stonework						
Under posts	40	1. 0	1. 0	0. 6	20	
Steps		169. 0	1. 0	0. 6	85	
Slabs under trusses	4	2. 0	1. 10½	0. 4	5	
do	10	1. 6	1. 6	0. 4	8	
Total Cubic feet						118
Filling in basement						
Court House	1	30. 0	18. 0	1. 6	810	
Do Dais	1	7. 6	7. 3	1. 0	54	
Record & property room	2	22. 0	8. 5¾	1. 6	557	
Gumastahs, Head Clerks, judges retiring room &c	–	81. 1½	15. 0	1. 6	1825	
Verandahs	–	218. 3	8. 3	1. 6	2701	
Total Cubic feet						5,947

[P. W. D. Code.—Paras.]

P. W. D. Form. No. M 204

1098
10

ESTIMATE FORM.—Detail Measurements.

Detail of Work.	Number.	Measurements in Feet. Length.	Breadth.	Depth.	Area or Contents.	Total Quantity of each description of Work.
Teakwood wrought & put up						
Court House, Record & property room.						
2 Trusses to span 18 ft — Tie beams	2	21. 9	0. 4	0. 7	8	
Principal rafters	4	11. 9	0. 4	0. 6	8	
Struts	4	5. 9	0. 4	0. 4	3	
Purlins, allowing for halving	2	47. 0	0. 5	0. 6	20	
Do over wall do	2	58. 6	0. 4	0. 4	18	
Do do	2	22. 0	0. 4	0. 4		
Ridge	1	32. 0	0. 3	0. 9	7	
Principal rafters in record & property room	2	11. 9	0. 4	0. 6	4	
Hip rafters	4	19. 6	0. 4	0. 5	11	
Common rafters (18" centre to centre)	46	14. 6	0. 3	0. 5	130	
do	6	13. 0	0. 3	0. 5		
Jack rafters	56	average length 9. 0	0. 3	0. 5		
Gumastahs, Head clerks, judges retiring room						
5 Trusses to span 15 ft. — Tie beams	5	18. 0	0. 4	0. 6	15	
Principal rafters	10	9. 9	0. 4	0. 5	14	
Struts	10	4. 9	0. 4	0. 4	5	
Purlins, allowing for halving	4	41. 0	0. 4	0. 5	23	
Carried over Cubic feet					266	

20,000—10-11-86.

ESTIMATE FORM.—Detail Measurements.

Detail of Work.	Number.	Measurements in Feet. Length.	Breadth.	Depth.	Area or Contents.	Total Quantity of each description of Work.
Archwork						
Over doors & windows	11	5. 0	1. 10½	1 1½	116	
Do	14	5. 0	1. 6	1. 1½	118	
Do	2	5. 0	1 1½	1. 1½	13	
		Total Cubic feet				247
Cut Stonework						
Under posts	40	1 0	1. 0	0 6	20	
Steps		169. 0	1. 0	0 6	85	
Slabs under trusses	4	2. 0	1. 10½	0 4	5	
do	10	1. 6	1. 6	0 4	8	
		Total Cubic feet				118
Filling in basement						
Court House	1	30. 0	18. 0	1. 6	810	
Do Dais	1	7 6	7. 3	1. 0	54	
Record & property room	2	22. 0	8. 5¼	1. 6	557	
Gumastahs, Head Clerks, Judge's retiring room &c	–	51. 1½	15. 0	1. 6	1825	
Verandahs	–	218. 3	8. 3	1. 6	2701	
		Total Cubic feet				5,947

P. W. D. Form.
No. M 204.

1098/10

ESTIMATE FORM.—Detail Measurements.

Detail of Work.	Number.	Measurements in Feet. Length.	Breadth.	Depth.	Area or Contents.	Total Quantity of each description of Work.
Teakwood wrought & put up						
Court House, Record & property room						
2 Trusses to span 18 ft — Tie beams	2	21. 9	0. 4	0. 7	8	
Principal rafters	4	11. 9	0. 4	0. 6	8	
Struts	4	5. 9	0. 4	0. 4	3	
Purlins, allowing for halving	2	47. 0	0. 5	0 6	20	
Do over wall do	2	58. 6	0. 4	0 4	18	
Do do	2	22. 0	0. 4	0 4		
Ridge	1	38. 0	0. 3	0. 9	7	
Principal rafters in record & property room	2	11. 9	0 4	0. 6	4	
Hip rafters	4	19 6	0 4	0 5	11	
Common rafters (18" centre to centre)	46	14. 6	0. 3	0 5	130	
do	6	13 0	0 3	0 5		
Jack rafters	56	average length 9 0	0. 3	0 5		
Gumastahs, Head clerks, judges retiring room						
5 Trusses to span 15 ft. — Tie beams	5	18. 0	0. 4	0. 6	15	
Principal rafters	10	9 9	0 4	0 5	14	
Struts	10	4. 9	0 4	0 4	5	
Purlins, allowing for halving	4	41. 0	0 4	0 5	23	
					266	

Carried over Cubic feet

20,000—10-11-86.

ESTIMATE FORM.—Detail Measurements.

Detail of Work.	Number.	Length.	Breadth.	Depth.	Area or Contents.	Total Quantity of each description of Work.
Wrought Iron work in Trusses						
1" diar: king rods for 18 feet trusses	2	8. 0	= 16 ×	2.62	= 41.92	
1" hex nut & bolt heads for do	6		×	1.10	= 6.60	
3" diar: 1/8" thick washers for do	4			0.32	= 1.28	
1½ × ½ heel straps for do	4	2.9	= 11 ×	2.30	= 27.50	
1½" × ½" bearing plates for do	4	0.6¾	= 2.3 ×	2.50	= 5.62	
5/8 hex nuts for do	8		×	.267	= 2.13	
Caps of 3/8" plates 6" wide	2	2.0	= 4.0 ×	7.51	= 30.04	
7/8" diar: king rods for 15 feet trusses	5	6.7½	= 33-1½ ×	2.01	= 66.58	
7/8" hex nut & bolt heads for do	15		×	0.73	= 10.95	
3" diar 1/8" thick washers for do	10		×	0.32	= 3.20	
1½ × 3/8" heel straps for do	10	2-3	= 22-6 ×	1.87	= 42.07	
1½" × 3/8" bearing plates for do	10	0.6¾	= 5-7½ ×	1.87	= 10.51	
5/8" hex nuts for do	20			.267	= 5.34	
Caps of 3/8" plate 6" wide	5	1-6	= 7-6 ×	7.51	= 56.32	
		Total lbs				310

[P. W. D. Code.—Paras.]

P. W. D. Form.
No. M 204.

1095/12

ESTIMATE FORM.—Detail Measurements.

Detail of Work.	Number.	Length.	Breadth.	Depth.	Area or Contents.	Total Quantity of each description of Work.
1	3	4	4	4	4	5
Tiled roofing with flat & pan tiles						
Court House &c	1	61. 0		30. 0	1830	
Gumastahs, Head Clerks & Judges retiring room &c	2	46. 0		25. 0	2300	
Verandahs	–	160. 0		11. 0	1760	
do	–	80. 0		12. 6	1000	
				Square feet	6890	
				Total Squares		70
Flooring with 8" square pavement bricks						
Court House	1	30. 0		18. 0	540	
Record & property room	2	8. 5¼		22. 0	371	
Gumastahs Head Clerks. Judges retiring room &c	–	81. 1½		15. 0	1217	
Verandahs	–	237. 9		9. 0	2140	
		Square feet			4268	
				Total Squares		43

20,000—10-11-86.

ESTIMATE FORM.—Detail Measurements.

Detail of Work.	Number.	Length.	Breadth.	Depth.	Area or Contents.	Total Quantity of each description of Work.
Plastering interior (2 coat)						
Court House	–	96. 0		11. 6	1776	
do Gables	1	18. 0		3. 0	54	
Dais sides	2	8. 0		1. 0	16	
Record & property rooms	2	60. 10½		18. 6	2252	
Additional height to partition	2	17. 6		6. 0	210	
Gable	1	16. 10½		6. 0	101	
Door & window jambs	11	20. 0		1. 10½	413	
Ventilator do	9	9. 6		1. 10½	160	
Gumastahs, Head Clerks rooms &c	–	302. 3		13. 5	4055	
Door & window jambs	14	20. 0		1. 6	420	
Do	2	20. 0		1. 1½	45	9,502
Deductions						
Doors	27	4. 0		8. 0	864	
Windows	4	4. 0		6. 0	96	
Ventilators	9	4. 0		2. 9	99	1,059
		Square feet				8,443
		Total Squares				85

[P. W. D. Code.—Paras.]

P. W. D. Form.
No. M 204.

ESTIMATE FORM.—Detail Measurements.

Detail of Work.	Number.	Length.	Breadth.	Depth.	Area or Contents.	Total Quantity of each description of Work.
Pointing Exterior						
Basement all round		352. 9		2. 0	706	
Court House &c		118. 9		18. 6	2197	
Gumastah's rooms &c	2	105. 6		13. 5	2831	5,734
Deductions						
Doors	19	4. 0		8. 0	608	
Windows	4	4. 0		6. 0	96	
Ventilators	9	4. 0		2. 9	99	803
				Square feet		4,931
				Total Squares		50
Lead sheeting for valleys		96. 0	1. 6.		144 × 5	720 lbs
Mouldings over windows (exterior)	4	5. 3				21 Lineal feet
Railings for dais						25 Lineal feet
Finials over Court room						2 in Numbers
Finials over Gumastahs & Nazarat Establishment						2 in Numbers

ESTIMATE FORM.—Detail Measurements.

Detail of Work.	Number.	Measurements in Feet. Length.	Breadth.	Depth.	Area or Contents.	Total Quantity of each description of Work.
Finials for Verandahs			5 in Numbers			
Painting with 3 Coats of Carson's paint						
Venetian & panel doors	3	544			1,632	
Panelled doors	2	192			384	
Venetian & glazed windows	5	96			480	
Ventilators	2	99			198	2,694
Roof timbers including reepers & Verandah posts						11,800
			Square feet			14494
			Total Squares			145
Punkah						
Over Dais	1	10			10 Lineal feet.	

ESTIMATE FORM.—Abstract.

Quantity.	Description of Work.	Rate.	Per	Amount.	Total.
		RS.		RS.	RS.
14,971 Cub. ft	Excavation for foundations (rate to include refilling of trenches)		1000 cub. ft		
4,668 "	Concrete in foundations		100 cub. ft		
4,302 "	Brickwork in foundations		"		
1898 "	Do. in basement		"		
9,715 "	Do. in Superstructure		"		
247 "	Archwork		"		
118 "	Cut stonework		Cub. ft.		
5,947 "	Filling in basement		1000 cub. ft.		
851 "	Teakwood wrought & put up		Cub. ft		
544 Sq. ft	Venetian & panel doors with frames complete		Sq. ft		
192 "	Panelled doors with frames complete		"		
96 "	Venetian windows with glazed shutters & Iron bars complete.		" "		
99 "	Ventilators.		lb		
310 lbs	Wrought Ironwork in trusses				
70 Squares	Tiled roofing with flat & pan tiles including teak reepers		Square		
43 "	Flooring with 8" Square pavement bricks		" "		
85 "	Plastering interior (two coats)		"		
50 "	Pointing exterior		lb.		
720 lbs	Lead sheeting for roof valleys		L. ft		
21 Lineal feet	Moulding over windows				

Grand Total of Estimate ..

Executive Engineer.

Station }
Dated }

ESTIMATE FORM.—Detail Measurements.

Detail of Work.	Number.	Measurements in Feet. Length.	Measurements in Feet. Breadth.	Measurements in Feet. Depth.	Area or Contents.	Total Quantity of each description of Work.
Finials for Verandahs			5 in Numbers			
Painting with 3 coats of Carson's paint						
Venetian & panel doors	3	544			1632	
Panelled doors	2	192			384	
Venetian & glazed windows	5	96			480	
Ventilators	2	99			198	2,694
Roof timbers including reepers & Verandah posts						11,800
		Square feet				14494
		Total Squares				145
Punkah						
Over Dais	1	10	"		10 Lineal feet.	

ESTIMATE FORM.—Abstract.

Quantity.	Description of Work.	Rate.	Per	Amount.	Total.
		RS.		RS.	RS.
14,971 Cub. ft	Excavation for foundations (rate to include refilling of trenches)		100 cub. ft		
4668 "	Concrete in foundation		100 cub. ft		
4302 "	Brickwork in foundations		"		
1898 "	Do. in basement		"		
9,715 "	Do. in Superstructure		"		
247 "	Archwork		"		
118 "	Cut stonework		Cub. ft.		
5,947 "	Filling in basement		100 cub. ft.		
851 "	Teakwood wrought & put up		Cub. ft		
544 Sq. ft	Venetian & panel doors with frames complete		Sq. ft		
192 "	Panelled doors with frames complete		"		
96 "	Venetian windows with glazed shutters & Iron bars complete		"		
99 "	Ventilators		"		
310 lbs	Wrought Ironwork in trusses		lb		
70 Squares	Tiled roofing with flat & pan tiles including teak reepers		Square		
43 "	Flooring with 8" Square pavement bricks		"		
85 "	Plastering interior (two coats)		"		
50 "	Pointing exterior		"		
720 lbs	Lead sheeting for roof valleys		lb.		
21 Lineal feet	Moulding over windows		L. ft		

Grand Total of Estimate ..

Station }

Dated

Executive Engineer.

Reference to Madras P. W. D. Code.

Paras. 1074, 1075, 1086, 1087, 1091 to 1094, 1108,
1111 to 1114, 1130 and 1145 to 1147.

P. W. D. Form.
No. M 207.

Circle—

Division—

ESTIMATE FORM.—Abstract.

(To accompany the Detailed Estimate No.
of 188 -8 for * .)

* Here enter the name and description of work in full.

ESTIMATE FORM.—Abstract.

Quantity.	Description of Work.	Rate.	Per	Amount.	Total.
		RS.		RS.	RS.
25 Lineal feet	Handrailing for dais		L: ft:		
2 in No	Finials over court room		Each		
2 "	Do. at Ends		"		
5 "	Do. for Verandah		"		
11.5 Squares	Painting with 3 Coats of Carson's paint		Sqre:		
5 in No.	Add Extra for finishing Barge boards		Each		
1 "	Punkah 10 feet long		"		
	Petty Supervision				
	Contingencies				
	Grand Total of Estimate ..				

Station Madras
Dated 12 March 1887

~~Executive Engineer.~~

Offg Consulting Archt.
to Government

Reference to Madras P. W. D. Code.

Paras. 1074, 1075, 1086, 1087, 1091 to 1094, 1108, 1111 to 1114, 1130 and 1145 to 1147.

P. W. D. Form.
No. M 207.

Circle—

Division—

ESTIMATE FORM.—Abstract.

(To accompany the Detailed Estimate No. __________ of 188 -8 for * __________.)

Constructing a Sub judges or District Munsifs Cour at ....

* Here enter the name and description of work in full.

No 1245/87
2

---

p2

1098/16

P. W. D

Consulting Architect's Office,
Chepauk, Madras,
12th March 1887

No 1530

From J. W. Brassington Esqr
Offg. The Consulting Architect
to the Government of Madras,

To

The Chief Engineer
Public Works Department

Sir,

Enclosure.
7 Drawings
1 Schedule of Quantities.

I have the honor to submit a Revised plan with Schedule of quantities for a Sub judge or District Munsifs Court.

2. This Design will supersede the Design circulated with G. O. No 505 W dated the 6th March 1885.

3. The Revised design & quantities for Tahsildars Cutcheries will follow.

I have the honor to be
Sir
Your Most Obedient Servant
J W Brassington
Offg Consulting Architect

Inst 1245/87
2

2.1
P.W.C. No 2029

Public Works Department.

2928/87

No 3

No 970 C of 15th March 1887

Forwarded for the approval of Govt in the Judicial Dept.

2. The design has already been approved in Committee by the Hon'ble members & Secretaries to Govt.

(Sd.) [illegible] Colonel R.E.
Secy to Govt. P.W.D.

From

THE CONSULTING ARCHITECT
TO THE GOVERNMENT OF MADRAS,

To

The Chief Engineer
P. W. D.

PUBLIC WORKS DEPARTMENT
12 MAR 7

No. 1530

Dated 12th March 1887
Received 12 " "

No. of Enclosures. 2.4
(+1 tracing)

Subject.

Sub-judges or District Munsifs' Court-House -
Submits Revised standard Design with Schedule of quantities and descriptive specifications for -

[illegible]

J. G.O. No 3252 - 10-12-86 - Irri
—— 921 — 8-4-85 —
—— 3282 - 18-12-84 —
—— 2170 - [illegible] 84 —
- 1640 d/ 4-7-86 Irri
- 3195 d/ 1-12-86 Irri
- 3170 d/ 29-11-86 Irri
Judl Refce in C. No 109 of 1887

H.M. Ootacamund
12th April /87.

Approved and
transferred to the
Public Works' Department.
(By order)
H A Stuart
Under Secretary

505 " 6.3.85.
2854 " 15.11.84
1841 " 29.7.84
1837 " 29.7.84
2909 " 15.10.83.
2045 " 30.8.80.
2294 " 6.9.79.
3929 " 9.10.78.
786. 7.3.77.
2204 : 21.8.76.
642. 13.3.76.
2093. 23.7.75.
1986. 13.7.75
1314 : 8.5.75
1871. 13.7.74
1340. 20.5.74
1014. 20.4.74
795. 23.3.74
2865. 28.11.73.
38. 6.11.73
2869. 2.9.69.
1436. 1.5.69

Resubmitted W.C. 15-4-87
29/3

P.W. No 2928 CURRENT NO. 1245

1887.

Public Works Department.

No. 970 C
Dated 15th March /87
Despatched 16th March /87
Received 17/15-4-87

CHIEF SECRETARY
17 MAR 87

Encl: 5
(+1 plan)

SUBJECT.

Forwarding for approval revised standard design with schedule of quantities and descriptive specification for Sub-Judges or District Munsifs Court house.

With order

No. 1098 W

B & R
~~Civil~~ Works.

PUBLIC WORKS DEPARTMENT.

1098/13

PROCEEDINGS OF THE MADRAS GOVERNMENT.

UNDER date the 21 April 1887

READ the following

From the C.A. to Govt. A.S. No 1327 d/ 4.2.87
" " —— do —— " " ~~1520~~ 1530 d/ 12.3.87
Endt to the Judl Dept " " 970 C d/ 15.3.87
" from —— do —— " " —— d/ 12.4.87.

Designs to be lithographed

5

The revised type design, with schedule of quantities and descriptive specification, for a sub judge's or district munsif's Court house with tiled roof, will be circulated to officers of the P. W. Dept for information and guidance, in supersession of the design circulated with G.O. No 505 W of 6th March 1883.

2. The Consg. Architect will, as early as practicable, submit a type design affording the same accommodation for a Court house with a terraced roof.

3. The submission of a revised type design for taluk offices is awaited.

Jdu
19/4/87

WW
21.4.87

Return of file [illegible]
apparently by letter [illegible]
[illegible] – 16-4-87

Typist [illegible]
to [illegible]
[illegible]
[illegible]

Cn
19-4-87

J – [illegible]
21-4-87

KB W
21/4

To supply Engrs
C.A. to Govt.
Judl Dept.

J Dec
16/5

Cn

R. 21-4-87

23-2-09.

$\frac{2920}{862}$

Govt. of (1887) Madras.

PUBLIC WORKS.

Urgent

Please
Rend. [illegible]
20/4/87

Dated

Recd. Encl.

G.O. 21 april 1887. No. 1098 W

Sub-judge's ~~Do~~ or district munsif's court house

A revised type design for a —— with tiled roof, circulated to officers of the P.W. Dept

220/10

Cir 22/4

REFERENCE TO MADRAS P. W. D. CODE.

PARAS. 1074, 1075, 1086, 1087, 1091 TO 1094, 1108, 1111 TO 1114, 1130 AND 1145 TO 1147.

P. W. D. FORM.
No. M 207.

CIRCLE—

DIVISION—

ESTIMATE FORM.—Abstract.

(To accompany the Detailed Estimate No. ________)
of 188 -8 for * ________

* Here enter the name and description of work in full.

10

1098/15

ESTIMATE FORM.—Abstract.

Quantity.	Description of Work.	Rate.	Per	Amount.	TOTAL.
		RS.		RS.	RS.
25 Lineal feet	Handrailing for dais		L: ft:		
2 in No	Finials over Court room		Each		
7 "	Do. at Ends		"		
5 "	Do. for Verandah		"		
14.5 Squares	Painting with 3 coats of Carson's paint		Sqre:		
5 in No:	Add Extra for finishing Barge boards		Each		
1 "	Punkah 10 feet long		"		
	Petty Supervision				
	Contingencies				

Grand Total of Estimate ..

STATION Madras }
Dated 12 March 1887 }

~~Executive Engineer.~~

Offg Consulting Archt.
to Government

Reference to Madras P. W. D. Code.

Paras. 1074, 1075, 1086, 1087, 1091 to 1094, 1108, 1111 to 1114, 1130 and 1145 to 1147.

P. W. D. Form.
No. M 207.

Circle—

Division—

ESTIMATE FORM.—Abstract.

(To accompany the Detailed Estimate No. of 188 -8 for * Constructing a Sub judges or District Munsifs' Cour at ....)

* Here enter the name and description of work in full.

No 1245/87
2

P. W. D

Consulting Architect's Office,
Chepauk, Madras,
12th March 188~~6~~7

1691/11

No 1530

From J. W. Brassington Esq.
Offg. The Consulting Architect
to the Government of Madras,

To

The Chief Engineer
Public Works Department

Enclosure.
7 Drawings
1 Schedule of quantities.

Sir,

I have the honor to submit a Revised plan with Schedule of quantities for a Sub judge or District Munsifs Court.

2. This Design will supersede the Design circulated with G. O. No. 505 W dated the 6th March 1885.

3. The Revised design & quantities for Tahsildars Cutcheries will follow.

I have the honor to be
Sir
Your Most Obedient Servant
J. W. Brassington
Offg. Consulting Architect

~~P.W.C. No 2029~~ 2:1

P. 3

Public Works Department.

2928/87

From

The Consulting Architect
to the Government of Madras,

To

The Chief Engineer
P. W. D

PUBLIC WORKS DEPARTMENT
12 MAR 87

No. 1530

Dated 12th March 1887

Received 12 – "

No. of Enclosures. 2.4
(+1 tracing)

Subject.

Sub-judges or District Munsifs' Court House – Submits Revised standard Design with Schedule of quantities and descriptive specifications for –

[illegible]

No. 970 C of 15th March 1887

Forwarded for the approval of Govt in the Judicial Dept.

2. The design has already been approved in Committee by the Hon'ble members & Secretaries to Govt.

Jo. Hasted Colonel R.E.
Secy to Govt. P.W.D.

J. Works No 3252 - 10-12-86 - No
—— 921 — 8 . 4 - 85 —
—— 3282 - 18 . 12 - 84 —
—— 2870 - [illegible] - 84 —
- 1640 d/ 4-7- 86 No
- 3198 d/ 1-12-86 No
- 3170 d/ 29-11-86 No
Jud Refer in C No 109 of 1887

H.M. Ootacamund
12th April/87.

Approved and transferred to the Public Works' Department.

(By order)

HAS H A Stuart
Under Secretary

505 d 6.3.85.
2854 d 15.11.84
1841 d 29.7.84
1837 d 29.7.84
2909 d 15.10.83.
2045 d 30.8.80.
2294 d 6.9.79.
3929 d 9.10.78.
786. 7.3.77.
2204. 21.8.76.
642. 13.3.76.
2093. 23.7.75.
1906. 13.7.75.
1314. 8.5.75.
1871. 13.7.74
1340. 20.5.74
1014. 20.5.74.
795. 23.3.74
2865. 28.11.73.
38. 6.11.73.
2069. 2.9.69.
1436. 1.5.69

Resubmitted W.C. 15.4.87 M 19.4
29/3

P.W. ~~No 2928~~ CURRENT NO. ~~1245~~

1887.

Public Works Department.

No. 970C
Dated 15th } March/87
Despatched 16th } March/87
Received 17/15.4.87

GOVT SECRETARY 17 MAR 87

En: 5 (+1 plan)

SUBJECT.

Forwarding for approval revised standard design with schedule of quantities and descriptive specification for Sub-Judge's or District Munsif's Court house.

Write order

No. 1098 W

B & O ~~[illegible]~~ Works

PUBLIC WORKS DEPARTMENT.

1098/19

PROCEEDINGS OF THE MADRAS GOVERNMENT,

UNDER date the 21 April 1887

READ the following

From the C.A. to Govt. A.S. No 1327 d/ 4.2.87
" " —— do —— " " ~~1520~~ 1530 d/ 12.3.87
" " —— do —— " " 970 C d/ 15.3.87
Endt. to the Judl. Dept " " —— d/ 12.4.87.
" from —— do —— " "

Designs to be lithographed

5

The revised type design, with schedule of quantities and descriptive specification, for a sub judge's or district munsif's Court house with tiled roof, will be circulated to officers of the P.W. Dept for information and guidance, in supersession of the design circulated with G.O. No 505 W of 6th March 1885.

2. The Consg. Architect will, as early as practicable, submit a type design affording the same accommodation for a Court house with a terraced roof.

3. The submission of a revised type design for taluk offices is awaited.

19/4/07

21.4.07

Return of file [illegible] apparently by ~~letter~~ [illegible]

~~[illegible]~~ 16-11-07

[illegible] as requested

Cu

19-11-07

J - 21-11-07

B W 21/4

To supply copy of C.A. to Govt. Judl Dept.

Done

15/5

Cu

R. 21.4.07

W.L.S 21/4/07

23-2-09.

2928/862

Govt. of (1887) Madras,

PUBLIC WORKS.

Urgent

Please send back 20/4/87

Dated

Recd. Encl.

G.O., 21 April 1887, No. 1098 W

Sub-judge's ~~Do~~ or district munsif's court house

A revised type design for a —— with tiled roof, circulated to officers of the P.W. Dept.

820/10

Ew 22/4