

(1) Number of pages 14
(2) Date of repair March 88
(3) Initials of the Referencer lms ✓

TAMIL NADU ARCHIVES

GOVERNMENT OF TAMIL NADU

P.W.D. DEPARTMENT

G.O. No.	<i>2439. IV.</i>	Press.
B.P. No.		Mis.
Dated	<i>9.9.1887</i>	<i>198</i>

Not to be folded or roughly handled.

9TH SEPTEMBER 1887, No. 2439 W., PUBLIC WORKS.

2439
1

GOVERNMENT OF MADRAS.
PUBLIC WORKS DEPARTMENT.

Buildings and Roads.
Civil Works.

READ—the following letter from Colonel J. BEATTY, R.E., Superintending Engineer, IV Circle, to the Chief Engineer, Public Works Department, dated Dhárápuram, 24th August 1887, No. 354 E.W.:—

I have the honor to submit, for sanction of Government and provision of funds, a plan and estimate, amounting to Rs. 4,500, for extending the coach-house at Government House, Ootacamund, together with a specification and duplicate abstract of the estimate.

2. This estimate has been prepared and the work commenced at the request of His Excellency the Governor, and the Military Secretary to His Excellency the Governor has informed the Executive Engineer that the charge may be met from the savings of Rs. 6,015 on item No. 3 of the completion estimate of Government House which is "Constructing New Government House."

ORDER—dated 9th September 1887, No. 2439 W., Public Works.

The plan and estimate, amounting to Rs. 4,500, for extending the coach-house at Government House, Ootacamund, are sanctioned against the saving on item No. 3 of the completion estimate for Government House, referred to in G.O., No. 1915 W., dated 9th July 1883.

2. The Superintending Engineer's attention is drawn to G.O., No. 2402 W., dated 6th September 1887, with reference to which he will propose a transfer of funds required for the work.

3. This sanction has been registered as Provincial, No. 87 W. of 1887-88, and classified as Civil Buildings, Original Works.

(True Extract.)

(Signed) J. O. HASTED, Colonel, R.E.,
Secretary to Govt., P.W.D.

To the Superintending Engineer, IV Circle, with four enclosures.
" Examiner, Public Works Accounts, with the duplicate abstract estimate.
" Military Secretary to His Excellency the Governor.

Exd. J. Moses.
Spair Copies.

BUILDINGS AND ROADS.
CIVIL WORKS.

Govt. of (1887) Madras.
PUBLIC WORKS.

Dated September, 9th.

Recd.

Encl.

G.O., 9th Sept. 1887, No. 2439 W

SEPTEMBER.

Government House,
Ootacamund

Coach-house.—Plan and estimate of Rs.
4,500 for extending the — at —, sanctioned
with remarks.

No. 354
W.

Superintending Engineer's Office 4th Circle.
Camp Sharapuram, 24th Augt 1887.

From

Colonel J. Beatty R.E.,
Superintending Engineer, 4th Circle.

To

The Chief Engineer,
P. W. Department.

Sir

Enclosures

1 Estimate
Rs. 4500

1 Plan

1 Specification

1 Duplicate
abstr. Estimate.

I have the honor to submit for
sanction of Government, and provision of
funds, a plan and Estimate amounting
to Rs. 4,500 for Extending the Coach House
at Government House Ootacamund, to-
gether with a specification and dupli-
cate Abstract of the estimate.

2. This Estimate has been prepared
and the work commenced, at the request
of H. E. the Governor, and the Military
Secretary to H. E. the Governor has in-
formed the Executive Engineer that
the charge may be met from the savings
of

of No. 6015 on item No. 3 of the Comple-
tion Estimate of Government House
which is "Constructing New Govern-
ment House."

2439
3

I have the honor to be,

Sir,

Your most obedt servant.

L. Beatty - Col. R.E.,

Supg. Engineer & the circle.

Public Works Department.

Current No. 6731
Letter No. 354
Dated the 24th August 1897
From the S. E. IV Circle

NOTE OF REMARKS.

1. The accompanying plan and estimate provide for extending Coach House at Government House Botacarnund. The amount of estimate is Rupees 4,500.
2. This estimate has been prepared and the work commenced at the desire of H. B. the Governor.
3. The existing coach house will be extended by an additional room 40 x 25 internal dimensions, the end wall of the present coach house will be prolonged in front 11 feet to a thickness of 1.1/2", the remaining 3 walls will be 1.6" thick; the front and

6.6.9.87 2.9.9.87

From, (4)
Col. J. Reatty - R. E.
Supg: Engt. 4 Circle

Dated 24th } August 1897.
Recd 29 }

No. 354
201

Encl. 4.

Extending Coach House
at Government House
Botacarnund.

Submits for sanction
and provision of funds
an estimate of Rs. 4,500
for —

6.6.2402W. 6.9.87
6.6.2457W. 3.9.83
" 1915W. 9.7.83

and rear walls will have 3 pillar projection $2'0" \times 0'6"$ on the outer face; these will be carried up to the full height of the walls. The whole of the left end wall, pillars and corners of the extended room will be built of brick in mortar (as shown in etched lines on the plan) and the intermediate gaps built in brick in clay.

4. The depth of the foundation is $1\frac{1}{2}$ ft. resting on concrete $1\frac{1}{2}$ ft. thick. As this depth is insufficient it will be better to increase it to $2\frac{1}{2}$ ft. on a layer of concrete $1\frac{1}{2}$ ft. thick but as the work seems to have been already commenced, it will be impossible to alter the depth hereafter.

The nature of soil is not stated, and the height of the wall above basement is 14 feet.

5. The flooring is to be of brick jelly concrete & plastered with cement.

6. The roofing is to be of corrugated

corrugated iron + mission tiles on the rear slope, and the front slope is to be covered with glass on teak sashes resting on iron trusses as shown on section. There will be a ridge ventilator running the whole length of the roof, this will also be covered with corrugated iron and mission tiles.

7. On the left end of the extended room there will be a gallery with a flight of wooden steps supported by 3 cast iron columns set in a bed of concrete foundation $2\frac{1}{2} \times 2\frac{1}{2} \times 2$. the roof of this gallery will be the prolongation of the main roof supported on teak posts, rafters, burlins and wall plates, propped up by cantilevers; there will be

be only one entrance
to the building in front
by a door 8' x 9'.

8. The rates are fair except
few items provided in the
estimate as mentioned
below which cannot be
checked.

Rs. 112 per 100 sq. ft. of roofing
with iron or tin, corrugated
iron trusses, ironing & complete
with ridge ventilator.

Rs. 8 1/2 per 1 sq. ft. of teak battened
door with frames & lock

Rs. 1 1/2 is allowed in the Dist.
Schedule of 1886-87 for ^{the same} without
frames.

Rs. 30 for each Cantilever
for sustaining gallery
roof.

Rs. 150 provided for teak
wooden staircase with
hand rails & complete.

Rs. 30 for painting woodwork
& Rs. 25 for excavation
foundation & filling basements.

9. Contingencies & Petty supervision
are separately charged at 2% percent.

10. The estimate has been counterchecked
by the Military Secretary.

Sto

3.9.87.

corrugated

No. 2439 W

PUBLIC WORKS DEPARTMENT.

PROCEEDINGS OF THE MADRAS GOVERNMENT.

UNDER date the 9th Sept 1887

Read the following

From the Suptg. Engineer IV Circle. H. Co. No. 354 Co. W. A/24 August 1887

The plan and estimate amounting
to Rs. 4,500, for extending the coach house
at Government House, Astanacumund, are
sanctioned against the saving on item
No. 3 of the completion estimate for Coach
House referred to in G. O. No. 1915 W dated
9th July 1883.

2. The Suptg. Engineer's attention is
drawn to G. O. No. 2602 W dated 6th September
1887, with reference to which he will
propose a transfer of funds required for
the work.

3. This sanction has been regis-
tered as Provincial No. 87 W of 1887-88,
and classified as Civil Buildings,
Original Works.

The S. E. IV Circle with 4 copies
.. Examiner of P. W. A. with the
duplicate abstract estimate
.. Military Secy to H. Co. the Engineer

The below has been
sent to the Secy to
H. Co. the Engineer
for the same to be made

W. W.

6.9.87

Dec
7/9/87

11/8/87

2439
7

50.12
24.11.97

0.6.9.87.2.4.5.8

corrugated

6731.

Govt. of Madras

PUBLIC WORKS

Dated

Recd.

Encl.

9/9/87 No. 2439 W

Government House Ooracumund

Re Coach house. Plan
and estimate of Rs 4500
for extending the — at
— sanctioned with
remarks.

50

4

9/9/87