

2008 or 27.7.57

1008 or 27.7.57
Govt. of 1881 Madras.

No. 2829 Wd Oct 21, 1887

Communicated to the
Suptg. Engr. I Circle for
preparation of the
required estimates.

Wm
20.10.57

Dec
20/10/57

To

The M. Dept

18 + 9
Proceedings, dated 17-10-1887
No. 2225

Subject.

No. 2829 Wd Oct 21, 1887

- Issuing orders for
the preparation of
plans & estimates
for the Court House
at Samukha in
Podanur Dt.

B
21/10

L.S.
S. & T. Circle ✓ 21/10

21/10
20/10

With order.

21/10

Accompaniment to G.O., No. 2008 W., dated 27th July 1887.

SUB-JUDGE OR DISTRICT MUNSIF'S COURT-HOUSE.

ALTERNATIVE DESIGN WITH TERRACED ROOFING.

DESCRIPTIVE SPECIFICATION.

Foundations.—A depth of 5 feet is provided in the quantities, but this should be settled locally in accordance with the nature of the soil.

Walling.—The walls should be built in English bond, $2\frac{1}{2}$ bricks, 2 bricks and $1\frac{1}{2}$ bricks thick. It may be necessary to mould special bricks for the verandah piers shown 15 inches square.

Stonework.—Stone slabs should be placed at the bearings of all beams and over the terrace to receive water falling from the spouts. The steps may also be of stone, if procurable without great expense.

Woodwork.—The beams and joists may be of well seasoned Burma or Indian teak or any other durable country wood proof against white-ants.

Doors and windows.—The doors and windows to be of well seasoned Burma or Indian teak-wood. All doors opening into verandahs will be of $\frac{1}{2}$ panel and $\frac{2}{3}$ venetians. Inner doors to be panelled throughout. The windows will have outer venetian shutters and glazed shutters opening inside with 1 inch square iron bars fixed diagonally. The ventilators will be of fixed glazed sashes in two parts set apart not less than 6 inches, for permanent ventilation, with galvanized iron wire netting with $\frac{1}{2}$ inch holes stretched across to prevent bats from entering.

Roofing.—The roofing will consist of "pukka terracing," care being taken that proper slopes are made for drainage towards the weep-holes, which will have shoots made of red-wood or teak-wood covered with sheet lead as shown in detail.

Flooring.—The floor may be laid with square bricks or stone slabs, if the latter are easily procurable. Where the soil is damp, the space below the flooring should be filled with river sand. Asphalte flooring is provided for the record and property room.

Interior and exterior finishing.—The interior walls will be fine plastered with shell lime and polished or plastered and washed. Where good bricks are obtainable, the exterior should be pointed. In damp soils the plinth and interior walls, about 3 feet above floor level, should also be plastered with cement.

The different kinds of work to be done will be executed in conformity with the standard specification of the Public Works Department.

(Signed) J. W. BRASSINGTON,
Offg. Consulting Architect to Government.

ESTIMATE FORM.—Detail Measurements.

Detail of Work.	Number.	MEASUREMENTS IN FEET.			Area or Contents.	Total Quantity of each description of Work.
		Length.	Breadth.	Depth.		
<i>Excavation for Foundations.</i>						
Court walls, four sides	...	103 6	4 10½	5 0	2,523	
Record and property room, outer walls	...	62 9	}	4 6	5 0	6,317
Do. do. partitions	...	19 0				
Front, rear and end walls of gumastahs', head clerk's and vakils' rooms, &c.	2	99 6				
Partitions of do. do.	3	12 0	4 1½	5 0	743	
Verandah in front	...	154 9	}	4 3	5 0	5,180
Do. in rear	2	44 6				
Steps	5	9 9	3 0	1 6	219	
Total, Cubic feet	...	...	...	...	...	14,982

Estimate Form.—Detail Measurements—cont.

Detail of Work.	Number.	MEASUREMENTS IN FEET.			Area or Contents.	Total Quantity of each description of Work.
		Length.	Breadth.	Depth.		
<i>Concrete in Foundations.</i>						
Court walls, four sides	...	103 6	4 10½	1 6	757	
Record and property room, outer walls	...	62 9	}	4 6	1 6	1,895
Do. do. partitions	...	19 0				
Front, rear and end walls of gumastahs', head clerk's, and vakils' rooms, &c.	2	99 6				
Partitions of do.	3	12 0	4 1½	1 6	223	
Verandah in front	...	154 9	}	4 3	1 6	1,554
Do. in rear	2	44 6				
Steps	5	9 9	3 0	1 6	219	
Total, Cubic feet	...	...	...	...	...	4,648
<i>Brickwork in Foundations.</i>						
<i>Footings.</i>						
Court walls, four sides	...	103 6	2 10½	1 6	446	
Record and property room, outer walls	...	64 9	}	2 6	1 6	1,083
Do. do. partitions	...	21 0				
Front, rear and end walls of gumastahs', head clerk's, and vakils' rooms, &c.	2	101 6				
Partitions of do.	3	14 0	2 1½	1 6	134	
Verandah in front	...	156 9	}	2 3	1 6	843
Do. in rear	2	46 6				
<i>Above Footings to Ground Level.</i>						
Court walls, four sides	...	103 6	1 10½	2 0	388	
Record and property room, outer walls	...	65 9	}	1 6	2 0	878
Do. do. partitions	...	22 0				
Front, rear and end walls of gumastahs', head clerk's, and vakils' rooms, &c.	2	102 6				
Partitions	3	15 0	1 1½	2 0	101	
Verandah in front	...	157 9	}	1 3	2 0	632
Do. in rear	2	47 6				
Extra thickness for plinth	...	345 0	0 3	2 0	173	
Total, Cubic feet	...	...	...	...	...	4,678
<i>Brickwork in Basement.</i>						
Court walls, four sides	...	103 6	1 10½	2 0	388	
Dais walls	...	22 0	1 6	2 0	66	
Do. steps	2	4 0	2 0	2 0	32	
Record and property room, outer walls	...	65 9	}	1 6	2 0	878
Do. do. partitions	...	22 0				
Front, rear and end walls of gumastahs', head clerk's, and vakils' rooms, &c.	2	102 6				
Partitions	3	15 0	1 1½	2 0	101	
Verandah in front	...	157 9	}	1 3	2 0	632
Do. in rear	2	47 6				
Extra thickness for plinth	...	345 0	0 3	2 0	173	
Steps	5	9 9	3 0	0 6	73	
Do.	5	7 9	2 0	0 6	39	
Do.	5	5 9	1 0	0 6	14	
Total, Cubic feet	...	...	...	...	...	2,396

Estimate Form.—Detail Measurements—cont.

Detail of Work.	Number.	MEASUREMENTS IN FEET.			Area or Contents.	Total Quantity of each description of Work.		
		Length.	Breadth.	Depth.				
<i>Brickwork in Superstructure.</i>								
Court walls, four sides	...	103 6	1 10½	20 9	3,881	15,949		
Dais ...	...	22 6	1 3	1 6	42			
Steps ...	2	4 0	2 0	0 6	8			
Do. ...	2	4 0	1 0	0 6	4			
Record and property room, outer walls	...	65 9	1 6	15 0	6,587			
Do. do. partition	1	22 0						
Front, rear and end walls of gumastahs', head clerk's, and vakils' rooms, &c.	2	102 6						
Partitions ...	3	15 0	1 1½	15 0	759			
Verandah walls in front	...	157 9	1 3	10 6	3,317			
Do. rear	2	47 6						
Parapet over court	...	106 0	1 3	1 6	199			
Do. extra height at corners	4	9 9	1 3	1 0	49			
Do. over property and record room	...	66 3	1 3	1 6	124			
Do. extra height at corners	2	5 6	1 3	1 0	14			
Binding wall over partition in do.	1	22 3	1 6	1 0	33			
Parapet over gumastahs', head clerk's and vakils' rooms, &c.	2	103 0	1 3	1 6	386			
Do. extra height at corners	4	9 3	1 3	1 0	46			
Binding walls over partitions	3	15 6	1 1½	1 0	52			
Parapet over verandah in front	...	159 5	0 10	1 3	266			
Do. in back verandah	2	47 11						
Do. extra height at corners	4	3 2						
Do. do. do.	2	3 8	0 10	1 0	17			
Coping to parapet	...	903 0						
Do.	...	641 0	0 3	0 3	40			
Band in verandah piers, &c.	...	247 0	0 3	0 6	31			
							15,949	
<i>Deductions—</i>								
Doorways in court	7	4 0	1 10½	8 0	420		4,082	
Do. in gumastahs', &c., rooms	14	4 0	1 6	8 0	672			
Do. in do. partitions	3	4 0	1 1½	8 0	108			
Windows	4	4 0	1 6	6 0	144			
Ventilators in court room	8	4 0	1 10½	1 9	105			
Do. in gumastahs', &c., rooms	14	3 0	1 6	1 9	126			
Ventilators in record and property room	2	3 0	1 6	1 9				
Verandah arches	27	5 9	1 3	8 0	1,753			
Do.	4	5 0	1 3	8 0				
Archwork as per details	...	...	...	...	754			
								4,082
Total, Cubic feet								11,867
<i>Filling in Basement.</i>								
Court	...	30 0	18 0	1 6	810			5,698
Dais	1	6 6	6 9	1 0	44			
Gumastahs' room	...	25 0	15 0	1 6	1,825			
Head clerk's do.	...	16 1½						
Judge's retiring-room	...	10 0						
Vakils' room	...	15 0						
Nazarat do.	...	15 0	8 7½	1 6	569			
Record and property room	2	23 0						
Verandah in front	...	140 3						
Do. in rear	2	38 9	7 6	1 6	2,450			
Total, Cubic feet							5,698	

Estimate Form.—Detail Measurements—cont.

Detail of Work.	Number.	MEASUREMENTS IN FEET.			Area or Contents.	Total Quantity of each description of Work.
		Length.	Breadth.	Depth.		
<i>Archwork.</i>						
Over court doorways ...	7	5 3	1 10 $\frac{1}{2}$	1 1 $\frac{1}{2}$	77	
Over doorways in gumastahs', &c., rooms ...	14	5 3	1 6	1 1 $\frac{1}{2}$	124	
Do. in partitions ...	3	5 3	1 1 $\frac{1}{2}$	1 1 $\frac{1}{2}$	20	
Over windows ...	4	5 3	1 6	1 1 $\frac{1}{2}$	35	
Do. ventilators in court ...	8	5 3	1 10 $\frac{1}{2}$	1 1 $\frac{1}{2}$	89	
Do. do. ...	16	4 0	1 6	1 1 $\frac{1}{2}$	108	
Do. verandah openings ...	27	7 0	1 3	1 1 $\frac{1}{2}$	301	
Do. do. ...	4	6 3	1 3	1 1 $\frac{1}{2}$		
Total, Cubic feet ...	...	...	...	...	...	754
<i>Stone-work, Dressed.</i>						
Slabs under beams for court ...	4	2 0	1 10 $\frac{1}{2}$	0 6	8	
Do. gumastahs', &c., rooms ...	16	1 6	1 6	0 4	12	
Do. for steps ...	5	29 3	1 0	0 6	73	
Slabs on terrace below shoots ...	32	2 0	2 0	0 3	32	
Total, Cubic feet ...	...	...	...	...	...	125
<i>Teak-wood wrought and put up.</i>						
Court—						
Beams ...	2	21 0	0 10	1 4	47	
Joists, 18" centre to centre ...	13	32 0	0 3	0 6 $\frac{1}{2}$	56	
Record and property room—						
Joists, 18" centre to centre ...	32	10 1 $\frac{1}{2}$	0 3	0 6	41	
Gumastahs' rooms—						
Beams ...	3	17 6	0 7 $\frac{1}{2}$	1 1	36	
Joists ...	11	27 0	0 3	0 5	31	
Head clerk's room—						
Beams ...	1	17 6	0 8	1 1	13	
Joists ...	11	17 9	0 3	0 5	20	
Judge's retiring-room—						
Joists ...	11	11 6	0 3	0 6 $\frac{1}{2}$	17	
Vakils' room—						
Beams ...	2	17 6	0 7 $\frac{1}{2}$	1 1	24	
Joists ...	11	16 6	0 3	0 5	19	
Nazarat establishment—						
Beams ...	2	17 6	0 7 $\frac{1}{2}$	1 1	24	
Joists ...	11	16 6	0 3	0 5	19	
Verandahs—						
Beams at angles ...	4	12 0	0 5	0 7 $\frac{1}{2}$	13	
Joists ...	126	9 0	0 3	0 5	140	
Do. at angles ...	8	8 3				
Do. do. ...	8	6 9				
Do. do. ...	8	4 9				
Do. do. ...	8	3 9				
Do. do. ...	8	2 6				
Total, Cubic feet ...	...	...	...	...	...	500
<i>Venetian and Panel Doors with Frames.</i>						
Doors opening into verandah ...	19	4 0	...	8 0	608	S. ft.
<i>Panelled Doors with Frames.</i>						
Inner doors ...	5	4 0	...	8 0	160	S. ft.
Venetian windows with frames and iron bars including glazed inner shutters ...	4	4 0	...	6 0	96	S. ft.

Estimate Form.—Detail Measurements—cont.

Detail of Work.	Number.	MEASUREMENTS IN FEET.			Area or Contents.	Total Quantity of each description of Work.
		Length.	Breadth.	Depth.		
<i>Ventilators with fixed glazed sashes and wire netting across.</i>						
For court rooms	8	4 0	...	2 1	67	100
„ other „	16	3 0	...	2 1		
Total, Square feet ...	...	...	...	...	...	167
<i>Terraced Roofing.</i>						
Court	...	31 0	...	19 0	1,026	
Record and property room ...	...	23 0	...	19 0		
Gumastahs', judge's, &c., rooms ...	2	43 0	...	16 0	1,376	
Verandah, front	...	142 3	...	8 0	1,138	
Do. back	2	39 9	...	8 0	636	
Square feet ...	...	...	...	...	...	4,176
Total, Squares ...	...	...	...	...	...	41.76
<i>Flooring basement with 9" square bricks over concrete 6 inches thick.</i>						
Court	1	18 0	...	30 0	540	
Gumastahs', head clerk's rooms judge's retiring room, &c. ...	...	81 1 $\frac{1}{2}$	...	15 0	1,217	
Verandahs, front	...	140 3	}	7 6	1,633	
Do. rear	2	38 9				
Square feet ...	...	...	...	...	...	3,390
Total, Squares ...	...	...	...	...	...	33.90
<i>Paving door pieces with 9" square bricks.</i>						
Court doorways	7	4 0	...	1 10 $\frac{1}{2}$	53	
Doorways	12	4 0	...	1 6	72	
Do.	3	4 0	...	1 1 $\frac{1}{2}$	14	
Verandah arches	27	5 9	}	1 6	263	
Do.	4	5 0				
Square feet ...	...	...	...	...	...	402
Total, Squares ...	...	...	...	...	...	4.02
<i>Flooring with asphalt $\frac{3}{4}$" thick over a bed of concrete 6" thick.</i>						
Record and property room ...	2	22 0	...	8 7 $\frac{1}{2}$	380	
Door pieces	2	4 0	...	1 6	12	
Square feet ...	...	...	...	...	...	392
Total, Squares ...	...	...	...	...	...	3.92
<i>Plastering interior.</i>						
Court	...	96 0	...	19 0	1,824	
Dais sides	2	8 0	...	1 0	16	
Record and property room ...	2	61 3	...	14 0	1,715	
Gumastahs' room	...	80 0	...	14 0	1,120	
Head clerk's room	...	62 3	...	14 0	872	
Judge's retiring-room ...	...	50 0	...	14 0	700	

Estimate Form.—Detail Measurements—cont.

Detail of Work.	Number.	MEASUREMENTS IN FEET.			Area or Contents.	Total Quantity of each description of Work.
		Length.	Breadth.	Depth.		
<i>Plastering interior—cont.</i>						
Vakils' and nazarat room ...	2	60 0	...	14 0	1,680	
Door, jambs and soffits ...	7	20 0	...	1 10 1	263	
Do. do. ...	14	20 0	...	1 6	420	
Do. do. ...	3	20 0	...	1 1 1	68	
Window do. ...	4	20 0	...	1 6	120	
Ventilator do. ...	8	11 6	...	0 11 1	86	
Do. do. ...	16	9 6	...	0 9	114	
Binding walls ...	3	15 6	...	3 1 1	145	
Do. ...	1	22 3	...	3 6	78	
						9,321
<i>Deductions—</i>						
Doorways ...	29	4 0	...	8 0	928	
Windows ...	4	4 0	...	6 0	96	
Ventilator ...	8	4 0	...	1 6	48	
Do. ...	16	3 0	...	1 6	72	
						1,144
Square feet ...	...	...	...	...	...	8,077
Total, Squares ...	...	...	...	...	...	80-77
<i>Pointing exterior.</i>						
Basement all round ...	...	310 9	...	2 0	622	
Front verandah interior ...	...	305 6	...	9 6	4,660	
Back do. ...	2	92 6	...			
Property room rear and ends ...	...	41 9	...	15 0	626	
Do. clearstorey ...	2	8 9	...	4 6	79	
Court do. ...	...	62 9	...	9 6	596	
Do. do. ...	...	48 3	...	5 0	241	
Gumastahs' and nazarat ends ...	2	25 6	...	15 0	765	
Do. do. clearstorey ...	4	40 0	...	4 6	720	
Verandah exterior ...	...	160 3	...	10 6	2,706	
Back verandah exterior ...	2	48 9	...			
Parapet walls over court ...	...	108 6	...	4 3	461	
Do. additional height ...	4	9 9	...	2 0	78	
Do. over property and record room ...	...	60 0	...	4 3	255	
Do. additional height ...	2	5 6	...	2 0	22	
Do. over gumastahs', &c., rooms ...	2	104 3	...	4 3	886	
Do. additional height ...	4	9 3	...	2 0	74	
Do. over front verandah ...	...	100 3	...	3 4	334	
Do. additional height ...	...	20 0	...	2 0	40	
Ventilator jambs ...	8	11 6	...	0 11 1	86	
Do. ...	16	9 6	...	0 9	114	
						13,365
<i>Deductions—</i>						
Doorways ...	19	4 0	...	8 0	608	
Windows ...	4	4 0	...	6 0	96	
Ventilators ...	8	4 0	...	1 6	48	
Do. ...	16	3 0	...	1 6	72	
						824
Square feet ...	...	...	...	...	...	12,541
Total, Squares ...	...	...	...	...	...	125-41
Wooden hand railing for dais ...	...	...	...	...	25	Lineal feet.

Estimate Form.—Detail Measurements—cont.

Detail of Work.	Number.	MEASUREMENTS IN FEET.			Area or Contents.	Total Quantity of each description of Work.
		Length.	Breadth.	Depth.		
<i>Painting doors and windows, 3 coats of Carson's oak paint.</i>						
Venetian and panel doors	3	...	...	608	1,824	
Panelled doors	2	...	...	160	320	
Venetian windows with iron bars ...	4	...	...	96	384	
Ventilators	2	...	...	167	334	
Square feet	...	...	...	...	...	2,862
Total, Squares	...	...	...	...	...	28-62
<i>Painting with 3 coats of zinc white paint.</i>						
Glazed shutters for windows	2	...	...	96 0	192	
Court—						
Beams	2	21 0	...	3 6	147	
Joists	13	32 0	...	0 10	347	
Record and property room—						
Joists	32	10 1 1/2	...	1 3	405	
Gumastahs' room—						
Beams	3	17 6	...	2 9 1/2	147	
Joists	11	27 0	...	1 1	322	
Head clerk's room—						
Beams	1	17 6	...	2 10	50	
Joists	11	17 9	...	1 1	212	
Judge's retiring-room—						
Joists	11	11 6	...	1 4	169	
Vakils' room—						
Beams	2	17 6	...	2 9 1/2	98	
Joists	11	16 6	...	1 1	197	
Nazarat establishment—						
Beams	2	17 6	...	2 9 1/2	98	
Joists	11	16 6	...	1 1	197	
Verandah—						
Beams	4	12 0	...	1 6	72	
Joists	126	9 0	...	1 1	} 1,454	
Do. at angles	...	203 0	...	1 1		
Square feet	...	...	...	...	...	4,107
Total, Squares	...	...	...	...	...	41-07
Punkah, 10 feet long	...	1 in number.			...	...

ESTIMATE FORM.—Abstract.

Quantity.	Description of Work.	Rate.	Per	Amount.	Total.
		RS.		RS.	RS.
14,982 C. ft.	Excavation for foundations ...		1,000 C. ft.		
4,648 "	Concrete in do. ...		100 "		
4,678 "	Brickwork in do. ...		100 "		
2,396 "	Do. in basement ...		100 "		
11,867 "	Do. in superstructure ...		100 "		
5,698 "	Filling in basement ...		1,000 "		
754 "	Archwork ...		160 "		
125 "	Stonework, dressed ...		C. ft.		
500 "	Teak-wood wrought and put up ...		"		

Estimate Form—Abstract—cont.

Quantity.	Description of Work.	Rate.	Per	Amount.	Total.
		RS.		RS.	RS.
608 Sq. ft.	Venetian and panel doors with frames ...		Sq. ft.		
160 "	Panelled doors with frames ...		"		
96 "	Venetian windows with frames, iron bars and inner glazed shutters ...		"		
167 "	Ventilators with fixed glazed sashes and wire netting across ...		"		
41.76 Sqrs.	Terraced roofing ...		Sqr.		
33.90 "	Flooring basement with 9-inch square bricks over concrete 6-inches thick ...		"		
4.02 "	Paving door pieces with 9-inch square bricks.		"		
3.92 "	Flooring with asphalt $\frac{3}{4}$ inch thick over a bed of concrete 6-inches thick ...		"		
80.77 "	Plastering interior ...		"		
125.41 "	Pointing exterior ...		"		
25 L. ft.	Railing for dais ...		L. ft.		
28.62 Sqrs.	Painting doors and windows with 3 coats of Carson's oak paint ...		Sqr.		
41.07 "	Painting glazed shutters and roof timbers with 3 coats of zinc white paint ...		"		
1 in No.	Punkah, 10 feet long ...		Each.		
	Petty supervision ...		"		
	Contingencies ...		"		

MADRAS,
19th July 1887.

(Signed) J. W. BRASSINGTON,
Offg. Consulting Architect to Government.

27th JULY 1887, No. 2008 W., PUBLIC WORKS.

GOVERNMENT OF MADRAS.

PUBLIC WORKS DEPARTMENT.

Buildings and Roads.
Civil Works.

READ—the following papers :—

From J. W. BRASSINGTON, Esq., Officiating Consulting Architect to the Government of Madras, to the Chief Engineer, Public Works Department, dated Chepak, 25th May 1887, No. 248.

With reference to paragraph 2 of G.O., No. 1098 W., dated the 21st April 1887, I have the honor to submit, for approval, a design for a sub-judge or district munsif's court-house with a terraced roof.

No. 164 D.

Forwarded for the approval of Government in the Judicial Department.

(Signed) J. O. HASTED, Colonel, R.E.,
27th May 1887. Secy. to Govt., P.W.D.

No. 1259, Judicial.

Approved, and retransferred to the Public Works Department.

(By Order.)

(Signed) A. G. CARDEW,
13th June 1887. Acting Under Secretary.

From J. W. BRASSINGTON, Esq., Consulting Architect to Government, to the Chief Engineer, Public Works Department, dated Chepak, 19th July 1887, No. 592.

With reference to G.O., No. 1259, dated the 13th June 1887, forwarded with your endorsement, No. 232 D., dated the 15th June 1887, I have the honor to submit the revised standard plan of court-house for a sub-judge or district munsif, with a terraced roof, with descriptive specification and schedule of quantities.

ORDER—dated 27th July 1887, No. 2008 W., Public Works.

The revised type design, with schedule of quantities and descriptive specification, for a sub-judge's or district munsif's court-house, with terraced roof, will be circulated to officers of the Public Works Department, for information and guidance, in continuation of G.O., No. 1098 W., dated 21st April 1887, and in supersession of the design circulated with G.O., No. 2854 W., dated 15th November 1884.

(True Extract.)

(Signed) J. O. HASTED, Colonel, R.E.,
Secretary to Govt., P.W.D.

To Superintending Engineers.
To the Consulting Architect to Government.
" Judicial Department.

Encl. E. Fernandez.
Spare Copies

BUILDINGS AND ROADS.
CIVIL WORKS.

Govt. of 1887 Madras.
PUBLIC WORKS.

Dated July, 27th.

Recd.

Encl.

G.O., 27th July 1887, No. 2008 W.

JULY.

Sub-Judge's or District Munsif's
Court-house

A revised type design for a —, with
terraced roof, circulated to officers of the
Public Works Department.

[24]



Judicial Department.

PROCEEDINGS OF THE MADRAS GOVERNMENT.

Read the following paper

From the Registrar of the High Court, Op-
pellate Side, dated 18th August and 22nd Sep-
tember 1887 Nos. 2114 and 2409.

Order thereon 17 October 1887 No 2325
The Government agree with the
opinion expressed by the Honorable the Judges
of the High Court that the District Munsif's
Court at Tanuku ought not to be closed,
though it does not appear that the work
of the Court is heavy. Orders will issue in
the Public Works Department for the preparation
of the necessary plans and estimates to provide
the District Munsif with a Court House on
the standard plan.

/ True Extract /

H. H. K. K.

A. Chief Secretary

To The Public Works Dept.
Honble the Chief Justice of the High Court

x 25.8