GOVERNMENT OF MADRAS.

PUBLIC WORKS DEPARTMENT.

Buildings and Roads.
Civil Works.

READ—the following paper :—

No. 554 T.N.

REPORT by the Superintending Engineer, VI Circle, on the estimate for constructing a sub-registrar's office at Rádhápuram, in Nángunéri taluk, Tinnevelly district, Rs. 2,330.

The estimate was called for in G.O., No. 1926 W., dated 10th July 1883, but it has been delayed owing to difficulty in the selection of a proper site. The estimate is prepared in accordance with the standard design sheet No. 21 (terraced roof) approved in G.O., No. 120 W., dated 14th January 1882.

2. The site selected is private land, and the owner agrees to part with it for a sum of Rs. 100, as will be seen from the agreement attached. The site has the approval of both the Collector and the registrar. The surface soil is reported to be loam and gravel, which is met with at $4\frac{1}{2}$ feet below it. It is therefore considered that the depth of the foundation allowed in the estimate, viz., 1 foot concrete and $3\frac{1}{2}$ feet masonry, is sufficient.

3. No deviation is made from the standard plan except the substitution of cement flooring for square bricks and imitation venetian for panel venetian door between the registrar's and record rooms. In accordance with the G.O., No. 509 W., dated 15th February 1883, weather-boards are provided for windows of the office-room.

4. Considering the distances from which materials are to be brought, the rates given are fair. The estimate is forwarded to the Inspector-General of Registration for submission to Government for their sanction in the Judicial Department (*vide* paragraph 1168 A of the Public Works Code).

5. The building will be completed within nine months from the date of sanction and allotment of funds.

RAMNAD,
2nd February 1886.

(Signed) H. R. MEAD, Colonel, R.E.,
Superintending Engineer, VI Circle.

G. No. 231.

Submitted for the sanction of the Government.

(Signed) G. HAMNETT,
Inspector-General of Registration.

6th February 1886.

To the Chief Secretary to Government.

No. 293 C., Judicial.

Approved, and transferred to the Public Works Department.

(By Order.)

(Signed) A. G. CARDEW,
Acting Assistant Secretary.

13th February 1886.

Order—dated 20th February 1886, No. 415 W., Public Works.

The estimate, amounting to Rs. 2,330, for constructing a sub-registrar's office at Rádhápuram, in the Tinnevelly district, is sanctioned for execution when funds are available.

2. This sanction has been registered as Provincial, No. 212 W. of 1885-86, and classified as Civil Buildings, Original Works.

(True Extract.)

(Signed) J. SHAW-STEWART, Colonel, R.E.,
Secretary to Govt., P.W.D.

To the Superintending Engineer, VI Circle, with * four enclosures (* one plan).
" Examiner, Public Works Accounts, with the estimate for note and return to Superintending Engineer, VI Circle.
" Judicial Department.

Exd. E. Fernandez.
Spare Copies

BUILDINGS AND ROADS.
CIVIL WORKS.

Govt. of {1886} Madras

PUBLIC WORKS.

Dated February, 20th.

Encl.

Recd.

G.O., 20th Feb. 1886, No. 415 W.

FEBRUARY.

Sub-Registrar's Office at Radhapuram, Tinnevelly District

Estimate for a —, sanctioned.

No 492, T. IV

Submitted to the Chief Engineer P. W. D. with a request that a grant of Rs 100 may be sanctioned as soon as possible to pay the amount of compensation with a view to obtain possession of the site for the work referred to.

Aldsmith Major R.E.
Supg Engineer 6th
8/2/87.

Reg. No. 957 Sh of 87

D. P. W.

SUPERINTENDING ENGINEER'S OFFICE 7 FEB 87 MADRAS

From

The Executive Engineer
Tinnevelly Division.

To

The Supg Engineer
6th Circle

Station Palamcottah

No 2760

Dated 4th
Despatched 5th
Received

February 1887

ENCLOSURES

Reference.

Sir,

I have the honor to inform you that an Estimate amounting to Rs. 2330 for Construction a sub Registrar's office at Radapuram in Sangumeri Taluq has been sanctioned in G.O. No. 415 W / 20-2-86 and a sum of Rs 100 is provided in the Estimate

Over

for compensation for the land to be
taken up for the same building.

2 I learn now from the Head
Assistant Collector of this District that
the owner of the land demands payment
of the compensation settled and states that
he has been offered a higher price for the
land and therefore the above said officer
wants to know whether there is any chance
of the compensation being paid to the owner
soon and if not, to give up the site & to
select another one when the work is ready
to be taken in hand.

3 I find that there is no provi-
-sion ~~is~~ made in the preliminiary budget
for the work for the year 1887-88.

4 I have therefore the honor to
request you will be so good as to let me
know whether I may give up the land back
to the owner if there is no chance of al-
-lotting funds at least for the compen-
-sation for (Rs 100).

I have &c

A. M. Hunter.
Executive Engrs

Sikkim

P.W.C. F 1097

From.

The Supt. Engr
6 Circle

To,

The Chief Engr
P.W.D

No 492, T.D.

Dated 8: February 87

R.C. 10-2-87

PUBLIC WORKS DEPARTMENT.

W-247-W

PROCEEDINGS OF THE MADRAS GOVERNMENT.

UNDER date the 12 Feby: 87

READ the following

From the Supty. Engineer VI circle. M. O. No: 492 T. D. 8th February 1887.

Request that a grant of Rs. 100 may be sanctioned to pay the amount of compensation of the site for the Sub-Registrar's office at Radapuram. Nanguneri Taluq.

A sum of Rs. 100 is appropriated from the Provincial reserve with the Govt. to meet the cost of the land taken up for the construction of a Sub-Registrar's office at Radhapuram sanctioned in G. O. No: 415 W dated 20th February 1886.

WWS
12.2.87

To
The Supty. Engr. VI circle
" Examiner of P.W. Accts
" Judicial Department.

D 14/2/87

DL
14/2/87

Cy

Mr 11/2

415 W 90.2.06

B. № 447 W af 12-2-89.

B. № 448 W af 12-2-89