(1) பக்கங்களின் எண்ணிக்கை 38

(2) புதுக்கித் திருப்பிய நாள் 20.6.88

(3) ஆதாரங்குறிப்பவர் சருக்கொப்பம்

தமிழ்நாடு ஆவணக் காப்பகம்.

தமிழ்நாடு அரசு

பொதுப்பணித் துறை

அரசாணை எண். 1536. W. அச்சகம்
மு. கோப்புத் தாள் எண். அலுவகை

நாள் : 25-5-1888. 198 .

மடிக்கவோ கண்டபடி கையாளவோ கூடாது

ஆவண. கா-1—18,000—15-6-87.

GOVERNMENT OF MADRAS.

PUBLIC WORKS DEPARTMENT.

Buildings and Roads.
Civil Works.

READ—the following Proceedings of the Board of Revenue (Land Revenue), dated 6th April 1888, Mis. No. 2201 :—

HON'BLE W. S. WHITESIDE.

Read—the following letter from G. T. WALCH, Esq., Superintending Engineer, I Circle, to the Collector of the Godávari District, dated Suradá, 27th February 1888, No. 2657 G.D. :—

I have the honor to submit the accompanying re-revised estimate, amounting in the aggregate to Rs. 23,770, for constructing a taluk cutcherry at Narsápur, and to request that you will be so good as to transmit the same for sanction of Government. The revised estimate for this work for Rs. 22,900 was sanctioned in G.O. No. 3563 of 20th December 1875. The re-revision of the estimate is due to the following reasons :—

(*a*) Alterations sanctioned (in G.O., dated 3rd June 1887, No. 1495 W,) by Government in the standard plan, according to which the revised estimate was prepared.

(*b*) Provision for jail latrine in the revised estimate which is omitted in the re-revised estimate in accordance with G.O. No. 2440 W. of 20th September 1882.

(*c*) Provision of land compensation in the revised estimate which is omitted in the re-revised estimate, as the site selected by you is Government land.

(*d*) Provision of public latrine in the revised estimate ; this is omitted in the re-revised estimate, as the division officer says that a latrine of any kind at Narsápur would be most objectionable, as the site is surrounded with buildings, and the compound is but small ; he also says that public latrines seem to be open to the objection urged against jail latrines in G.O. No. 2440 W. of 20th September 1882, and recommends that they be omitted. I agree with his opinion.

2. The work has already been put in hand, as Government have allotted Rs. 10,000 for expenditure on the work during the current official year.

3. Enclosures forwarded with this letter are detailed below :—

1 General abstract estimate, Rs. 23,770.
1 Detailed and abstract estimate, with comparative statement for cutcherry, Rs. 21,840.
1 Do. do. for ryots' shed.
1 Do. do. for cook-house.
1 Do. do. for gates and compound.
1 Specification.
1 Report.
1 General comparative statement.
1 Site plan.

No. 116.

Submitted to the Commissioners of Land Revenue for sanction.

COCANADA, 15th March 1888. (Signed) W. A. HAPPELL, Collector.

Resolution—dated 6th April 1888, Mis. No. 2201.

The revised estimate and plan for the construction of a taluk cutcherry, at a cost of Rs. 23,770, are submitted for the sanction of Government.

(True Extract.)

(Signed) R. S. BENSON, Acting Secretary.

No. 2482, Revenue.

Approved and transferred to the Public Works Department.

(By Order.)

OOTACAMUND, 26th April 1888. (Signed) H. A. STUART, Under-Secy. to Govt.

ORDER—dated 25th May 1888, No. 1536 W., Public Works.

The revised estimate, amounting to Rs. 23,770, for constructing a taluk office at Narsápur in the Godávari District, is sanctioned in supersession of the estimate of Rs. 22,900 sanctioned in G.O. No. 3563, dated 20th December 1875.

2. A sum of Rs. 10,000 has been provided for the work in the current year's budget.

3. This sanction has been registered as Provincial No. 25 W. of 1888-89, and classified as Civil Buildings, Original Works.

(True Extract.)

Captain, R.E.,
Under-Secy. to Govt., P.W.D.

To the Superintending Engineer, I Circle, with sixteen enclosures.
" Examiner, Public Works Accounts, with the general abstract estimate.
" Revenue Department.

Exd. F. R. Bantleman.
Spare Copies

BUILDINGS AND ROADS.
CIVIL WORKS.

Govt. of {1888} Madras.

PUBLIC WORKS.

Dated May, 25th.

Recd.

Encl.

G.O., 25th May 1888, No. 1536 W.

MAY.

Taluk office at Narsapur

Revised estimate for constructing a — in the Godávari District, sanctioned.

Proceedings of the Madras Government, Judicial Department,
21st June 1869.

Read the following papers :—

No. 149. From the Acting Superintending Engineer, 1st Division, to the Secretary to Government, Public Works Department, Fort Saint George; dated Dowlaishweram, 2nd June 1869, No. 922.

With reference to G.O., No. 654, dated 1st March 1869, and in continuation of my letter, No. 739, dated 20th ultimo, I na

Two abstract estimates.

tion of Government, two [illegible], amounti
Tahsildars' [illegible] the subsidiary
st
ac[illegible]ance with [illegible] pla[illegible],

	Rs.
Bheemaveram	22,560
Tanuku	21,240
Total	43,800

ard 1, circulated with G. O., Nos. 3552
ard 2791, dated 18th November 1867
ard 1st September 1868, respectively.

2. A sum of Rupees 10,000 for each of the Tahsildar's Cutcherries, for which estimates are now forwarded, has been provided in the statement of works estimated to cost Rupees 2500 each, which accompanied my predecessor's letter of the 7th April last, No. 60.

—

Referred to the Judicial Department, with reference to the order Department, No. 265, of the 18th February 1869.

FORT SAINT GEORGE,
11th June 1869.

(Signed) C. A. ORR, Colonel, R. E.,
Secy. to Govt., P. W. D.

—

No. 150. From the Acting Superintending Engineer, 1st Division, to the Secretary to Government, Public Works Department, Fort Saint George; dated Dowlaishweram, 3rd June 1869, No. 925.

With reference to G. O., No. 3986, dated 21st December 1868, and in continuation of my letter, No. 402, dated 30th April 1869, I have the honour to forward, for the sanction of Government, an estimate, amounting to Rupees 22,440, for constructing a Tahsildar's Cutcherry, with the subsidiary jail and usual outbuildings, at Narsapur, prepared in accordance with standard plans, Nos. 3 and 1, circulated with G. O., Nos. 3552 and 2791, dated 18th November 1867 and 1st September 1868, respectively.

One abstract estimate.

2. My predecessor has applied* for a sum of Rupees 10,000 for expenditure on these buildings during the current official year, which if granted the work will be put in hand at once by beginning to collect materials and prepare the woodwork.

* Vide statement which accompanied letter, No. 60, dated 7th April 1869.

—

Referred to the Judicial Department, with reference to the orders in that Department, No. 1844, of the 8th December 1868.

FORT SAINT GEORGE,
11th June 1869.

(Signed) C. A. ORR, Colonel, R. E.,
Secy. to Govt., P. W. D.

Proceedings of the Madras Government, Judicial Department,
21st June 1869.

No. 151. ORDER THEREON, 21st June 1869, No. 1037.

With the foregoing letters the Superintending Engineer, 1st Division, submits estimates for the erection of three new Taluq Cutcherries, with subsidiary jails and out-buildings, at the following stations, in the Godavery district, viz. :—

	RS.
[illegible]aver[illegible]	22,560
[illegible]	21,240
[illegible]	22,440
[illegible]	[illegible]240

[illegible]ions the proposed outlay of Rupees 66,240 [illegible]nsferred to the Public Works Department hence instructions will be issued, when funds are granted for subsidiary jails, for e erection of the buildings above referred to.

(True Extract).

R. A. DALYELL,
Actg. Secy. to Govt.

To the Public Works Department, with three estimates.
" Revenue Department.
" Magistrate of the Godavery district.
" Accountant General.

Exd. J. Wright.

Govt. of 1869, Madras.

JUDICIAL.

To

THE PUBLIC WORKS DEPARTMENT.

&c. &c. &c.

Dated 2nd July 1869.

Read.

G.O., 21st June 1869, No. 1037.

—

JUNE.

Nos. 143—161.

Sanctioning estimates, amounting to Rs. 66,240, for Talook Cutcherries and Subsidiary Jails, with out-buildings at Bheemaveram, Tanuku, and Nursapur, in the Godavery district.

Proceedings of the Madras Government, Public Works Department, 2nd July 1869.

No. 45. Read the following Proceedings of the Madras Government in the Judicial Department :—

Sanctioning estimates, amounting to Rupees 66,240, for Talook Cutcherries and Subsidiary Jails, with out-buildings at Bheemaveram, Tanuku, and Nursapur, in the Godavery district. (Here enter 21st June 1869, No. 1,037.)

No. 46. ORDER THEREON, 2nd July 1869, No. 2,150.

CIVIL WORKS, No. 9.

COMMUNICATED to the Superintending Engineer of the 1st Division.

(True Extract.)

(Signed) CHARLES A. ORR, Colonel, R. E.,

Secretary to Government.

To the Superintending Engineer, 1st Division, with Estimates.

„ Controller of Public Works Accounts.

Exd. S. T. Augustin.

Govt. of [1869] Madras

PUBLIC WORKS

To

THE SUPERINTENDING ENGINEER,

1st Division.

&c., &c., &c.

Dated July, 2nd.

Recd.

Encl.

G. O. 2nd July 1869, No. 2,156.

JULY.

Nos. 45-46

Catcherries and Subsidiary Jails.—Proceedings Judicial Department, sanctioning estimates, amounting to Rupees 66,240, for the erection of Taluk Catcherries and Subsidiary Jails in the Godavery District, communicated to the Superintending Engineer of the 1st Division.

Proceedings of the Madras Government, Public Works Department,
20th December 1875.

Read the following letters:—

No. 329. From Major J. BEATTY, R.E., District Engineer, Godavery, to Major-General G. W. WALKER, R.E., Secretary to Government, Public Works Department, dated Camp at Peravelly, 24th March 1875, No. 4,022.

As directed in paragraph 2 of G.O., No. 162-A, of the 24th January 1874, I have the honor to submit herewith revised estimates for first-class Taluq Cutcherries at Tanuku, Bheemaveram, and Nursapur, according to the sanctioned standard plans.

3 Estimates of Cutcherries.
2 Well Estimates.
2 Specifications.
3 Site Plans.
1 Sheet of Sections.
1 General Abstract.

2. This revision has become necessary in consequence of alterations sanctioned in the standard plans of main and out buildings.

3. The general abstract which accompanies this letter will show the items provided in the estimates.

4. Of these three Cutcherries I recommend that the one at Nursapur should be built first, as that is at present the head-quarters of the Range Officer and can therefore be better supervised by him, while there is also a canal to the place by which the supply of building material can be conveniently made.

No. 329-A. From the same Officer, dated Dowlaishweram, 1st December 1875, No. 2,615.

With reference to your Under Secretary's Memorandum, No. 430, of 23rd August 1875, I have the honor to report on certain deviations from the standard plans as regards quantities, and deviations from the district schedule as regards rates.

1 Copy of No. 3 Range Officer's letter, No. 343, of 7th November 1875.
2 Statements received from the Under Secretary to Government.

2. The deviations in quantity are comparatively trifling, and the explanation is that the printed list of quantities appears not to have been received when the estimates were framed.

3. As regards rates, I have been unable to obtain any explanation because it is not known what is meant by the term "district schedule," given in your comparative statement. It does not appear to be the range schedule; but if so, the rates naturally vary for stone, lime, gravel, sand, &c., according to the distance of places in the delta from the source of supply; and no general rate for the whole range can be used as a check on particular works. I send copy of a letter from the Range Officer on the subject.

4. So far as I can judge, alteration of the estimates already submitted is unnecessary, but if you wish me to send in revised estimates please return the papers already submitted, and the document called "district schedule."

Proceedings of the Madras Government, Public Works Department,
20*th December* **1875.**

No. 330. ORDER THEREON, 20th December 1875, No. 3,563.

CIVIL WORKS, No. 18.

THE following revised estimates are sanctioned and will be inserted if practicable in the Budget of 1876-77 :—

					RS.
Constructing a first-class Taluq Cutcherry			at Nursapur	... ...	22,900
Do.	do.	do.	at Tanuku	... ...	21,420
Do.	do.	do.	at Bheemaveram	...	22,650

(True Extract.)

(Signed) G. W. WALKER, Major-General, R.E.,
Secretary to Government.

To the District Engineer, Godavery.
" Controller of Public Works Accounts.
" Political Dept.

Rud. S. T. Austin.
Spare Copies

Govt. of 1875 Madras.

PUBLIC WORKS.

To

THE DISTRICT ENGINEER,
GODAVERY,

&c., &c., &c.

Dated December 20th.

Issued

Recd. Encl.

G. O., 20th December 1875, No. 3,563.

DECEMBER.

Nos. 329-330

Taluq Cutcherries at Narsapur, Tanuku, and Bheemaveram, Godavery District.—Revised estimates amounting to Rs. 66,970 for constructing first-class ,, sanctioned.

3RD JUNE 1887, No. 1495 W., PUBLIC WORKS.

GOVERNMENT OF MADRAS.

PUBLIC WORKS DEPARTMENT.

Buildings and Roads.
Civil Works.

READ—the following papers:—

From J. W. BRASSINGTON, Esq., Officiating Consulting Architect to the Government of Madras, to the Chief Engineer, Public Works Department, dated Chepâk, 25th April 1887, No. 95.

In continuation of my letter, No. 1530, dated the 12th March last, I have the honor to submit a revised plan and schedule of quantities for tahsildars' cutcherries.

2. The plan and quantities for deputy tahsildars' cutcherries will follow.

No. 72 D.

Forwarded for the approval of Government in the Revenue Department.

2. The design has already been approved in Committee by the Honorable Members and Secretaries to Government.

6th May 1887. (Signed) J. O. HASTED, Col., R.E., Chief Engineer, P.W.D.

G.O., dated 23rd May 1887, No. 2981, Revenue.

Read—endorsement of Public Works Department, dated 6th May 1887, No. 72 D., forwarding, for approval, revised standard design for taluk offices.

Order—dated 23rd May 1887, No. 2981, Revenue.

Approved.

(True Extract.)

(Signed) J. F. PRICE,
Ag. Secy. to Govt.

ORDER—dated 3rd June 1887, No. 1495 W., Public Works.

The revised type design, with schedule of quantities and descriptive specification for a first-class taluk office, will be circulated to officers of the Public Works Department, for information and guidance, in supersession of all previous standard designs for similar buildings.

(True Extract.)

(Signed) J. O. HASTED, Colonel, R.E.,
Secretary to Govt., P.W.D.

To Superintending Engineers.
,, the Consulting Architect to Government.
,, the Revenue Department.

Exd. P. L. Pereira.
Spare Copies

BUILDINGS AND ROADS.
CIVIL WORKS.

Govt. of {1887} Madras.

PUBLIC WORKS.

Dated June, 3rd.

Recd. *Encl.*

G.O., 3rd June 1887, No. 1495 W.

JUNE.

Taluk Office

A revised type design for a first-class —, circulated to officers of the department.

Annexure to G.O., No. 1495 W., dated 3rd June 1887.

ESTIMATE FORM—Detail Measurements.

Detail of work.	No.	Measurements in Feet. Length.	Breadth.	Depth.	Area or contents.	Total quantity of each description of work.
EXCAVATION FOR FOUNDATIONS.						
Court, outer walls	..	92 0	4 0	4 6	1,656	
Property and private room, end walls	3	5 4½	3 7½	4 6	1,007	
Do. do. outer walls	..	45 7½	3 7½	4 6		
Cashier's, sheristadar's, clerk's room, longitudinal walls	2	70 0	4 0	4 6	5,079	
Do. do. partition	3	15 6	4 0	4 6		
Record room, outer walls	..	95 6	4 0	4 6		
Treasury and inspector's room, &c., outer walls	..	115 9	4 4½	4 6	3,268	
Do. do. inner walls	2	20 4½	4 4½	4 6		
Do. do.	1	9 6	4 4½	4 6		
Jail wards, outer walls	..	173 0	4 0	4 6	3,114	
Do. partitions	4	12 6	3 7½	4 6	816	
Verandah and covered way walls near jail	..	89 0	3 3	4 6	5,404	
Do. in front	..	130 0	3 3	4 6		
Do. in rear and sides of record room	..	150 6	3 3	4 6		
Extra thickness at verandah posts	32	1 1½	0 4½	4 6	64	
Do. do. at corners	5	0 4½	0 4½	4 6		
Do. do.	4	1 10½	0 4½	4 6	13	
Steps	2	12 6	3 0	1 6	214	
Do.	1	11 6	3 0	1 6		
Do.	2	5 6	3 0	1 6		
Total, Cubic feet	..	..	..	..	..	20,632
CONCRETE IN FOUNDATIONS.						
Court, outer walls	..	92 0	4 0	1 6	552	
Property and private room, end walls	3	5 4½	3 7½	1 6	336	
Do. do. outer walls	..	45 7½	3 7½	1 6		
Cashier's, sheristadar's and clerk's room, longitudinal walls	2	70 0	4 0	1 6	1,692	
Do. do. partitions	3	15 6	4 0	1 6		
Record room, outer walls	..	95 6	4 0	1 6		
Treasury and inspector's room, outer walls	..	115 9	4 4½	1 6	1,089	
Do. do. inner walls	2	20 4½	4 4½	1 6		
Do. do.	1	9 6	4 4½	1 6		
Jail wards, outer walls	..	173 0	4 0	1 6	1,038	
Do. partitions	4	12 6	3 7½	1 6	272	
Verandah and covered way walls near jail	..	89 0	3 3	1 6	1,800	
Do. in front	..	130 0	3 3	1 6		
Do. in rear and sides of record room	..	150 6	3 3	1 6		
Extra thickness at verandah posts	32	1 1½	0 4½	1 6	26	
Do. do. at corners	5	0 4½	0 4½	1 6		
Do. do.	4	1 10½	0 4½	1 6		
Steps	2	12 6	3 0	1 6	214	
Do.	1	11 6	3 0	1 6		
Do.	2	5 6	3 0	1 6		
Total, Cubic feet	..	..	..	..	..	7,019
BRICKWORK IN FOUNDATIONS.						
Footings.						
urt, outer walls	..	92 0	2 3	1 0	207	
ivate and property room end walls	3	7 1½	1 10½	1 0	122	
Do. do. outer walls	..	43 10½	1 10½	1 0		
shier's, sheristadar's and clerk's room, longitudinal walls	2	71 9	2 3	1 0	658	
Do. do. partitions	3	17 3	2 3	1 0		
cord room, outer walls	..	97 3	2 3	1 0		
easury and inspector's room, outer walls	..	115 9	2 7½	1 0	450	
Do. do. inner walls	2	22 1½	2 7½	1 0		
Do. do.	1	11 3	2 7½	1 0		
l wards, outer walls	..	173 0	2 3	1 0	389	
Do. partitions	4	14 3	1 10½	1 0	107	
randah and covered way near jail	..	92 6	1 6	1 0	565	
Do. in front	..	131 9	1 6	1 0		
Do. in rear and sides of record room	..	152 3	1 6	1 0		
tra thickness at verandah posts	32	1 1½	0 4½	1 0	17	
Do. do. at corners	5	0 4½	0 4½	1 0		
Do. do.	4	1 10½	0 4½	2 0	276	
ove footings to ground level, court, outer walls	..	92 0	1 1½	2 0	150	
ivate and property room, end walls	3	7 10½	1 1½	2 0		
Do. do. outer walls	..	43 1½	1 1½	2 0		

Estimate Form—Detail Measurements—*cont.*

Detail of work.	No.	Measurements in Feet. Length.	Breadth.	Depth.	Area or contents.	Total quantity of each description of work.
Brickwork in Foundations—*cont.*						
Footings—cont.						
Cashier's, sheristadar's and clerk's rooms, longitudinal walls	2	92 6	1 6	2 0	891	
Cashier's, sheristadar's and clerk's rooms, longitudinal partitions	3	18 6 98 0	1 6 1 6	2 0 2 0		
Record room, outer walls						
Treasury and Inspector's room.		116 9	1 10½	2 0	654	
Outer walls	2	22 10½	1 10½	2 0		
Do. inner walls	1	12 0	1 10½	2 0	519	
Do. do.		173 0	1 6	2 0	135	
Jail wards, outer walls	4	15 0	1 1½	2 0		
Do. partitions		94 0	0 9	2 0	569	
Verandah and covered ways near jail		132 6	0 9	2 0		
Do. in front	32	153 0	0 4½	2 0	34	
Do. in rear and sides of record room	5	1 1½	0 4½	2 0		
Extra thickness at verandah posts	4	0 4½	0 4½	2 0	100	
Do. at corners		1 10½	0 3	2 0		
Do. do.		108 6	0 3	2 0	100	
Extra thickness for plinth for jail wards		47 6	0 3	2 0		
Inspector's and arms' room		43 7½				5,843
Private and property room						
Total, Cubic feet					276	
Brickwork in basement.		92 0	1 6	2 0	150	
Court, outer walls	3	7 10½	1 1½	2 0		
Private and property room end walls		43 1½	1 1½			
Do. do. outer walls						
Cashier's, sheristadar's, &c., rooms, longifudinal walls	2	72 6	1 6	2 0	891	
Cashier's, sheristadar's, &c., rooms, longitudinal partitions	3	18 0 98 0	1 6 1 6	2 0		
Record room, outer walls						
Treasury and Inspector's room.		116 9	1 10½	2 0	654	
Outer walls	2	22 10½	1 10½	2 0		
Do. inner walls	1	12 0	1 10½	2 0	519	
Do. do.		173 0	1 6	2 0	135	
Jail, outer walls	4	15 0	1 1½	2 0		
Do. partitions		94 0	0 9	2 0	569	
Verandah and covered way rear jail		132 6	0 9	2 0		
Do. in front	32	153 0	0 4½	2 0	34	
Do. in rear and sides of record room	5	1 1½	0 4½	2 0		
Extra thickness at verandah posts	4	0 4½	0 4½	2 0	100	
Do. at corners		1 10½	0 4½	2 0		
Do. do.		199 7½	0 3	1 6	35	
Extra thickness for plinth		20 9	1 1½	0 6	55	
Dais walls		36 6	3 0	0 6	31	
Steps		20 6	2 0	0 6	12	
Do.		24 6	1 0	0 6	33	3,494
Do.	2	5 6	3 0	1 0		72
Do. near jail						3,422
Deduct—						
Stone in steps						
Total, Cubic feet					1,829	
Brickwork in superstructure.		92 0	1 6	13 3	35	
Court, outer walls		20 9	1 1½	1 6	292	
Do. dais walls	3	7 10½	1 1½	3 0		
Private and property room end walls	3	7 10½	1 1½	8 0	388	
Do. do. half gables		43 1½	1 1½			
Do. do. outer walls				13 3	3,955	
Cashier's, sheristadar's and clerk's room, longitudinal walls	2	72 6	1 6	13 3		
Cashier's, sheristadar's and clerk's room, longitudinal partitions	3	18 0	1 6	3 6	441	
Cashier's, sheristadar's and clerk's room, longitudinal gables	4	21 6 98 0	1 6 1 6	12 0 3 9	1,764 182	
Record room, outer walls	2	18 6				
Do. gables		116 9	1 10½	20 0	4,378	
Treasury and inspector's room, outer walls, including battlement	2	22 10½	1 10½	15 0	1,824	
Treasury and inspector's room, inner walls	1	12 0	1 6	12 0	3,114 810	
Do. do. do.		173 0	1 1½	12 0	162	
Jail wards, outer walls	4	15 0	1 6	3 6	243	19,179
Do. partitions	2	18 0	1 1½			
Do. gables at ends	4					
Do. do. for partitions						

Estimate Form—Detail Measurements—*cont.*

Detail of work.	No.	Measurements in Feet. Length.	Breadth.	Depth.	Area or contents.	Total quantity of each description of work.
Brickwork in Superstructure—*cont.*						
Deductions—						
Doors in treasury	8	4 0	1 10½	8 0	750	
Windows do.	6	4 0	1 10½	6 0		
Archway in treasury square portion	1	12 0	1 10½	4 0	90	
Do. semi-circular do.		56 6	Area.	1 10½	106	
Doors in court, &c.	17	4 0	1 6	8 0	861	
Do. do.	1	4 0	1 6	7 6		
Do. in private and property room	2	4 0	1 6	7 6	104	
Windows in do.	2	4 0	1 1½	4 0		
Doors in jail	5	4 0	1 6	7 6	225	
Ventilators in jail	7	4 0	1 6	2 0	84	
Record-room windows	18	1 9	1 6	5 6	260	
Archwork as per details					535	3,015
Total, Cubic feet						16,182
Archwork.						
Over treasury doors and windows	14	5 0	1 10½	1 1½	148	
Do. arch semi-circular	1	21 6	1 10½	1 6	60	
Over doors in court, &c.	18	5 0	1 6	1 1½	152	
Do. and windows in private and property room	4	5 0	1 1½	1 1½	25	
Over doors and end ventilators in jail	7	5 0	1 6	1 1½	150	
Over record-room windows	18	3 0	1 6	1 1½		
Total, Cubic feet						535
Cut stonework.						
Slabs under posts	48	1 0	1 0	0 6	24	
Steps		143 0	1 0	0 6	72	
Slabs under trusses	22	2 0	1 6	0 4	22	
Total, Cubic feet						118
Earth filling in basement.						
Court	1	25 0	18 0	1 6	675	
Dais	1	5 10½	6 9	1 0	40	
Private and property rooms		30 9	7 10½	1 6	363	
Clerk's, sheristadar's, &c., rooms		68 0	18 0	1 6	1,836	
Treasury and verandah	1	21 0	12 0	1 6	378	
Arms and inspector's room	2	22 10½	8 0	1 6	549	
Jail wards		64 0	15 0	1 6	2,340	
Record room	1	40 0	15 0	1 6		
Verandahs		170 0	8 3	1 6	2,104	
Do.		167 0	5 9	1 6	1,440	
Covered way	1	18 0	13 6	1 6	365	
Total, Cubic feet						10,090
Teakwood wrought and put up.						
Court, clerk, sheristadar's, &c., room—						
Five trusses to span 18 feet. Tie beams	5	21 0	0 4	0 7	20	
Principal rafters	10	11 9	0 4	0 6	20	
Struts	10	5 9	0 4	0 4	6	
Purlins allowing for halving		196 0	0 4	0 6	33	
Wall purlins do.		206 0	0 3	0 4	17	
Ridge do.		94 0	0 3	0 9	18	
Hip rafters for court	5	17 0	0 3½	0 6	17	
Do. for sheristadar's room	2	15 0	0 3½	0 4		
Common rafters, 18 inches centre to centre	102	12 6	0 3	0 4		
Jack rafters for court	48	9 0	0 3	0 4	154	
Do. for sheristadar's room	20	Average length. 7 0	0 3	0 4		
Record-room—						
Three trusses to span 15 feet. Tie beams	3	18 0	0 4	0 6	9	
Principal rafters	6	9 9	0 4	0 5	8	
Struts	6	4 9	0 4	0 4	3	
Purlins (allowing for halving)	2	49 0	0 4	0 5	14	
Wall purlins	2	44 0	0 3	0 3	6	
Ridge	1	53 0	0 3	0 3	9	
Common rafters, 18 inches centre to centre	58	10 9	0 3	0 3	42	
Do. do. at ends	4	12 6				
Treasury, inspector and arms' room—						
Joists, 18 inches centre to centre	16	14 0	0 3½	0 8	44	
Do. do.	32	9 6	0 3	0 6	38	

Estimate Form—Detail Measurements—*cont.*

Detail of work.	No.	Measurements in Feet. Length.	Breadth.	Depth.	Area or contents.	Total quantity of each description of work.
TEAKWOOD WROUGHT AND PUT UP—*cont.*						
Jail wards.						
Three trusses to span 15 feet. { Tie beams	3	18 0	0 4	0 6	9	
Principal rafters	6	9 9	0 4	0 5	8	
Struts	6	4 9	0 4	0 4	3	
Purlins allowing for halving	2	75 6	0 4	0 5	21	
Wall purlins do.	2	75 6	0 3	0 3	9	
Ridge	1	75 6	0 3	0 8	13	
Common rafters, 18 inches centre to centre	56	12 6	0 3	0 3	} 76	
Do. do. do.	48	10 9	0 3	0 3	}	
Covered way.						
One truss to span 15 feet. { Tie beam	1	16 6	0 4	0 6	3	
Principal rafters	2	9 9	0 4	0 5	3	
Struts	2	4 9	0 4	0 4	1	
Purlins	2	20 0	0 4	0 5	6	
Do. over posts	2	20 0	0 4	0 4	4	
Ridge	1	20 0	0 3	0 8	3	
Hip rafters	2	15 0	0 3	0 5	3	
Common rafters	18	12 6	0 3	0 3	} 17	
Jack rafters	8	6 6	0 3	0 3	}	
Verandah.						
Posts	48	0 6	0 6	7 4	88	
Breastsummers for 9 feet verandah		187 0	0 6	0 7½	58	
Do. for 6½ feet do.		222 0	0 6	0 6	56	
Hip rafters	4	12 6	0 3	0 6	}	
Do.	1	18 6	0 3	0 6	}	
Do.	1	15 6	0 3	0 6	} 18	
Do.	3	12 6	0 3	0 6	}	
Ridges	2	11 0	0 3	0 6	}	
Common rafters for 9 feet verandahs and private and property room 18″ centre to centre.	122	13 6	0 3	0 5	}	
Jack rafters for do. do.	24	5 6	0 3	0 5	}	
		Average length.				
Do.	4	7 6	0 3	0 5	} 199	
		Average length.				
Do.	12	8 6	0 3	0 5	}	
Common rafters for 6½′ verandah 18″ centre to centre	102	10 0	0 3	0 4	} 98	
Jack rafters	28	5 6	0 3	0 4	}	
Boarding at ends of Jail.						
Verandahs	2	8 0	0 1	3 0	4	
Barge boards for jail and record room gables	6	13 0	0 1	0 9	5	
Do.	6	3 0	0 1	1 0	2	
Do. collar piece	3	9 0	0 3	0 4	2	
Barge boards for finials	3	6 6	0 3	0 3	1	
Do. do.	3	1 0	0 8	0 8	1	
Do. do.	6	4 0	2 0	0 1¼	5	
Front Verandah gables.						
Barge boards	4	7 6	0 1	0 7½	2	
Collar pieces	2	7 0	0 2	0 4	1	
Finials	2	6 0	0 3	0 3	1	
Planks	2	2 6	0 1½	1 6	1	
Weather boards for Jail.						
Brackets	4	3 6	0 2	0 2½	}	
Struts	4	3 0	0 2	0 2½	} 1	
Breastsummers	2	6 0	0 2	0 2½	}	
Rafters	8	4 6	0 1½	0 2	1	
Planks including overlap	12	6 3	0 3¼	0 9	4	
Total, Cubic feet						1,185
VENETIAN AND PANEL DOORS WITH FRAMES COMPLETE.						
Outer doors of court, clerk's, sheristadar's, &c., rooms	11	4 0		8 0	352	
Private room	1	4 0		7 6	30	
Total, Square feet						382
PANELLED DOORS WITH FRAMES.						
Inner doors of court, clerk's, sheristadar's, &c., room	6	4 0		8 0	192	
Do. do. do.	1	4 0		7 6	30	
Total, Square feet						222

Estimate Form—Detail Measurements—*cont.*

Detail of work.	No.	Measurements in Feet. Length.	Breadth.	Depth.	Area or contents.	Total quantity of each description of work.
WROUGHT IRON GRATED DOORS WITH WOODEN FRAMES.						
For jail wards	5	4 0	..	7 6	150	
Treasury, &c.	8	4 0	..	8 0	256	
Total, Square feet						406
Strong battened shutters for treasury doors without frames	4	3 6	..	7 6	105	Sq. ft.
Strong battened door with frame for property room	1	4 0	..	7 6	30	Sq. ft.
VENETIAN WINDOWS WITH FRAMES AND IRON BARS.						
For private and property room	2	4 0	..	4 0	32	Sq. ft.
BATTENED WINDOWS WITH FRAMES AND IRON BARS.						
For arms and inspector's room	6	4 0	..	6 0	144	
For record room	18	1 9	..	5 6	173	
Total, Square feet						317
Teak frames with iron bars for jail ventilators	7	4 0	..	2 0	56	Sq. ft.
WROUGHT IRON WORK IN TRUSSES.						
1″ diar. king rods for 18 feet trusses	5	8 0	= 40 0	× 2·62	= 105	
1″ hex. nut and bolt head for do.	15	..	..	× 1·10	= 17	
3″ diar. ¼″ thick washers for do.	10	..	..	× 0·32	= 3	
1½″ × ⅜″ heel straps for do.	10	2 9	27 6	× 2·50	= 69	
1½″ × ½″ bearing plates for 18 feet trusses	10	0 6½	= 5 3¾	× 2·50	= 13	
⅝″ hex. nuts for do. do.	20	..	..	× ·267	= 5	
Caps of ⅜″ plate 6″ wide	5	2 0	= 10 0	× 7·51	= 75	
⅞″ diar. kingrod for 15 feet trusses	7	6 7½	= 46 4½	× 2·01	= 93	
⅞″ hex. nut and head for trusses	21	..	..	× 0·73	= 15	
3″ diar. ¼″ thick washers for trusses	14	..	..	× 0·32	= 4	
1½″ × ⅜″ heel straps for trusses	14	2 3	= 31 6	× 1·87	= 58	
1½ × ⅜ bearing plate for trusses	14	0 6¼	= 7 10½	× 1·87	= 15	
⅝″ hex. nut for trusses	28	..	..	× ·267	= 7	
Caps of ⅜″ plate 6″ wide	7	1 6	= 10 6	× 7·51	= 79	
Total, lb.						558
TERRACE ROOFING.						
For treasury, inspector's and arms' rooms		32 9	..	23 10½	782	Sq. ft.
Squares						7·82
TILED ROOFING.						
Court room		28 0	..	26 0	} 2,808	
Clerk's, sheristadar's, &c., rooms		80 0	..	26 0	}	
Record room		49 0	..	23 0	1,127	
Jail		74 6	..	24 6	1,825	
Covered way		15 3	..	25 0	381	
Verandah 9 feet wide		210 0	..	12 0	2,520	
Do. 6½ do.		182 0	..	9 0	1,638	
Square feet						10,299
Total, Squares						103
FLOORING WITH 8″ SQUARE BRICKS.						
Court	1	25 0	..	18 0	450	
Private room	1	7 10½	..	18 9	} 242	
Property room	1	7 10½	..	12 0	}	
Clerk's, sheristadar's, &c., room		68 0	..	18 0	1,244	
Treasury and verandah		22 10½	..	12 0	} 641	
Inspector's and arms' room	2	22 10½	..	8 0	}	
Covered way	1	18 0	..	15 0	270	
Verandah 9 feet wide		175 0	..	9 0	1,575	
Do. 6½ do.		167 0	..	6 6	1,086	
Door pieces	18	4 0	..	1 6	108	
Do.	8	4 0	..	1 10½	60	
Do.	2	4 0	..	1 1½	9	
Square feet						5,685
Total, Squares						56·85

Estimate Form—Detail Measurements—*cont.*

Detail of work.	No.	Measurements in Feet. Length.	Breadth.	Depth.	Area or contents.	Total quantity of each description of work.
Flooring record room and jail with asphalte ¾" thick over a bed of concrete.						
Record room	1	40 0	..	15 0	1,560	
Jail	1	64 0	..	15 0		
Door pieces	5	4 0	..	1 6	30	
Square feet	..	..	..	..	..	1,590
Total, Squares	..	..	..	..	..	15·90
Plastering interior (two coats).						
Court	..	86 0	..	13 3	1,140	
Private room	..	53 3	..	10 6	559	
Property room	..	19 10½	..	8 0	159	
Do.	2	7 10½	..	10 6	165	
Do.	1	4 1½	..	13 3	55	
Clerk's, sheristadar's, &c., room	..	280 0	..	13 3	3,710	
Gables	9	18 0	..	3 0	486	
Record room	..	110 0	..	12 0	1,320	
Gables	2	15 0	..	2 6	75	
Treasury	..	54 0	..	14 0		
Do. verandah	..	42 0	..	14 0	3,073	
Inspector's and arms' room	2	61 9	..	14 0		
Jail wards	..	278 0	..	12 0	3,336	
Do. gables	10	15 0	..	2 6	375	
Door jambs and soffits	17	20 0	..	1 6	510	
Do. do.	1	19 0	..	1 6	29	
Do. do.	8	20 0	..	1 10½	300	
Do. do.	2	19 0	..	1 1½	43	
Do. do.	5	19 0	..	1 6	143	
Arch do.	..	27 0	..	1 10½	51	
Window do.	6	20 0	..	1 10½	225	
Do. do.	2	16 0	..	1 1½	36	
Do. do.	18	14 6	..	1 6		
Ventilator jambs	2	12 0	..	1 6	488	
Do.	5	8 0	..	1 6		
						16,278
Deductions—						
Doorways	32	4 0	..	8 0	1,024	
Do.	9	4 0	..	7 6	270	
Archway, square portion	1	12 0	..	4 0	48	
Do. semi-circular portion	1	56 6	Area.	..	57	
Windows	2	4 0	..	4 0	32	
Do.	6	4 0	..	6 0	144	
Do.	18	1 9	..	5 6	174	
Ventilators	7	4 0	..	2 0	56	
						1,805
Square feet	..	..	..	..	..	14,473
Total, Squares	..	..	..	..	..	144·73
Pointing exterior.						
Court	..	50 9	..	13 3	3,028	
Clerk's, sheristadar's, &c., rooms	..	177 9	..	13 3		
Property and private room	..	62 3	..	7 6	467	
Do. half gables	2	9 0	..	3 0	54	
Record room	..	101 0	..	12 0	1,212	
Do. gable	1	18 0	..	3 0	54	
Treasury and inspector's, &c., rooms	..	124 3	..	21 6	2,671	
Do. inside parapet	..	102 3	..	5 0	513	
Jail wards	..	179 0	..	12 0	2,148	
Do. gables	2	18 0	..	3 0	108	
Basement all round	..	609 0	..	2 0	1,218	
						11,506
Deduct—						
Doorways	16	4 0	..	8 0	512	
Do.	7	4 0	..	7 6	210	
Archway, square portion	1	12 0	..	4 0	48	
Do. semi-circular portion	1	56 6	Area.	..	57	
Windows	2	4 0	..	4 0	32	
Do.	6	4 0	..	6 0	144	
Do.	18	1 9	..	5 6	174	
Ventilators	7	4 0	..	2 0	56	
End wall, cashier's room	1	21 0	..	16 0	336	
						1,56
					..	9,23
Square feet	..	..	..	..	..	99·3
Total, Squares	..	..	..	..	..	
					Per foot lb.	lb.
Lead sheeting for roof valleys	..	184 0	1 6	× 276	× 5	1,38
Mouldings over windows for inspector's and arms' room.	6	6 0	..	..	36	L. ft.

Estimate Form—Detail Measurements—*cont.*

Detail of work.	No.	Measurements in Feet. Length.	Breadth.	Depth.	Area or contents.	Total quantity of each description of work.
Coping for treasury	..	..	..	125	L. ft.	
Railing for dais	..	..	..	23	,,	
Finials over court	..	..	2 in number.			
Painting with three coats of Carson's paint.						
Venetian and panel doors	3	382 0	..	..	1,146	
Panelled doors	2	222 0	..	..	444	
Wrought iron grated doors	2	406 0	..	..	812	
Batten shutters	2	105 0	..	..	210	
Do. do.	2	30 0	..	..	60	
Do. windows	2	317 0	..	..	634	
Ventilators	2	56 0	..	..	112	
Roof timbers including weather boards, &c.	..	..	..	..	11,972	
Square feet	..	..	..	..	..	15,390
Total, Squares	..	..	..	..	..	154
Add extra labor in finishing bargeboards and finials	..	..	5 in number.			
Punkah 10 feet long	..	..	1 ,,		—	

Estimate Form—Abstract.

Quantity.	Description of work.	Rate.	Per	Amount.	Total.
		Rs.		Rs.	Rs.
20,632 C. feet	Excavation for foundation		1,000 C. feet.		
7,019 ,,	Concrete in foundation		100 C. feet.		
5,843 ,,	Brickwork in foundations		,,		
3,422 ,,	Do. in basement		,,		
16,182 ,,	Do. in superstructure		,,		
535 ,,	Archwork		C. feet.		
118 ,,	Cut stonework		1,000 C. feet.		
10,090 ,,	Filling in basement		C. feet.		
1,185 ,,	Teakwood wrought and put up		Square feet.		
382 Sq. feet.	Venetian and panel doors with frames		,,		
222 ,,	Panelled doors with frames		,,		
406 ,,	Wrought iron grated doors with teak frames		,,		
105 ,,	Strong battened shutters for treasury doors without frames		,,		
30 ,,	Strong battened door with frame for property room		,,		
32 ,,	Venetian windows with frames and iron bars		,,		
317 ,,	Battened do. do.		,,		
56 ,,	Teak frames with iron bars for jail ventilators		lb.		
558 lb.	Wrought iron work in trusses		Square.		
7·82 Squares.	Terrace roofing		,,		
103 ,,	Tiled roofing with flat and pan tiles including teak reepers		,,		
56·85 ,,	Flooring with 8-inch square pavement tiles		,,		
15·90 ,,	Flooring record room and jail with asphalte ¾ inch thick over a bed of concrete		,,		
144·73 ,,	Plastering interior (two coats)		,,		
99·37 ,,	Pointing exterior		lb.		
1,380 lb	Lead sheeting for roof valleys		L. feet.		
36 L. feet.	Mouldings over windows		,,		
125 ,,	Coping for treasury parapet		,,		
23 ,,	Hand railing for dais		Each.		
2 in No.	Finials over court		Square.		
154 Squares.	Painting with three coats of Carson's paint		Each.		
5 in No.	Add extra labor in finishing barge boards and finials		,,		
1 ,,	Punkah 10 feet long		..		
..	Petty supervision		..		
..	Contingencies		..		

Madras,
25th April 1887.

(Signed) J. W. BRASSINGTON,
Offg. Consulting Architect to Government.

Tahsildar's Cutcherry.

Descriptive Specification.

Foundations.—A depth of 4 feet 6 inches is provided in the quantities, but this should be settled locally in accordance with the nature of the soil.

Walling.—The walls should be carried up in English bond, walls of treasury 2½ bricks thick, court, offices, record room and outer walls of jail 2 bricks thick, jail partitions and verandah rooms near court 1½ bricks. Verandah retaining walls 1 brick thick, except under posts which will be half a brick thicker.

Stonework.—Stone slabs 12″ × 12″ × 6″ with mortice holes 2 inches square and 2 inches deep cut into them into which the verandah posts will be tennoned.

Slabs will also be placed at the bearings of trusses. The steps may also be of stone, if procurable without great expense.

Woodwork.—The doors, windows, weather boards, verandah posts and trusses should be of well-seasoned teakwood, the rafters and other minor roof timbers may be of approved country wood.

Roofing.—The roof of the treasury, arms, and inspector's room will be of pucka terrace. The rest of the building will be covered with flat and pan tiles; if the quality of these are good the usual unsightly "chunam bands" might be dispensed with; all valleys should be protected with sheet lead.

Flooring.—The floor may be of square bricks or stone slabs if the latter are easily procurable. Jail wards and record room floors to be asphalted.

Interior and exterior finishing.—The interior walls will be fine plastered with shell lime or plastered and washed. Where good bricks are obtainable the exterior should be pointed.

Where the soil is damp the space below the flooring should be filled with river sand to a depth of 1 foot at least and the interior walls plastered with Portland cement ½ an inch thick to a height of 3 feet all over above floor level. The exterior plinth should also be plastered with cement.

Finials.—The finials may be of copper, iron or wood.

The different kinds of work to be done will be executed in conformity with the standard specification of the Public Works Department.

(Signed) J. W. BRASSINGTON,
Offg. Consulting Architect to Government.

Chepák,
25th April 1887.

Public Works Department.

Current No. 4153

Letter No. 2482

Dated 26th April 1888

From the Secy: to Govt: P.W. Dept:

Sanction given 11.5.88

Note of Remarks.

The revised Estimate under review amounting to Rs 23,770 for Constructing a Tahsildar's Cutcherry at Narsapur is submitted for sanction in supersession of the Estimate for Rs 22,900 sanctioned in G.O. No 3563 d/20th December 87.

The Excess viz Rs 870 is due to Excess quantities and Excess rates, as may be seen by checking the Excess rates noted with the rates given in the Schedule.

The revision of the Estimate is due to certain modifications

Sanctioned in G.O. No 1493 d/3rd June 1887 and
2- The entire omission of Latrines which are considered objectionable in a sanitary point of view as the site is surrounded with buildings.-
Land Compensation has been omitted as the present site belongs to Govt:-
The work has been commenced and an allotment of Rs 10,000 has been made on this account for Expenditure during the current official year.-
The estimate has been countersigned by the Collector and approved by Govt in the Revenue Deptt.-

[illegible]
11/5/88.

No. 2657 G.D.

118

From

G. F. Walch Esquire
Superintending Engineer
First Circle

To

The Collector
Godavari District

Camp Sucada 27th Feby 1888.

Enclosures 7

1. Gl abstract estimate Rs. 23,770.
1. Detailed & abstract estimate with comparative statement for Cutchery Rs. 21,840
1. Do do for Ryots' shed
1. Do do for Cook house
1 Do do for Gates and Compound
1. Specification
1- Report
1. Genl. comparative statement.
1. Site plan

Sir,

I have the honour to submit the accompanying revised estimate amounting in the aggregate to Rs. 23770 for constructing a Taluk Cutchery at Narasapur and to request that you will be so good as to transmit the same for sanction of Government. The revised estimate for this work for Rs. 22900 was sanctioned in

×

Rev: 2478/88.

in G. O. No. 3563 of 20th December 175. The re-provision of the estimate is due to the following reasons:-

(a) Alterations sanctioned by Government in the standard plan according to which the revised estimate was prepared.

(b) Provision for Jail Latrine in the revised estimate which is omitted in the re-revised estimate in accordance with G.O No. 2240 W of 20th September 182

(c) Provision of land compensation in the revised estimate which is omitted in the re-revised estimate as the site selected by you is Government land.

(d) Provision of public latrine in the revised estimate; this is omitted in the re-revised estimate as

as the Division Officer says that a latrine of any kind at Vara-sapur would be most objectionable as the site is surrounded with buildings and the compound is but small, he also says that Public Latrines seem to be open to the objection urged against Jail Latrines in G. O. No. 2240 W of 20th September 182 and recommends that they be omitted. I agree with his opinion.

2. The work has already been put in hand as Government land allotted Rs. 10,000 for expenditure on the work during the current official year.

3. Enclosures forwarded with this letter are detailed in

in the margin.

I have &c &c

(Signed) G. T. Walch (S)

Supg Engineer 1st Circle

BOARD'S GEN. REG. No. 916 OF 1888

No. 116

3P

Submitted to the Commissioners of Land Revenue for sanction

W. Wattpell
Collector

Godavari District
Collector's Office
Cocanada 15th March
1888

Comp'd J.C.

17/3/88

16

REVENUE BOARD OFFICE. MADRAS.

Proceedings of the Board of Revenue

(Land Revenue).

Dated 6th April 1888.

No. 2201 Miscellaneous.

Honorable W. S. Whiteside.

4P

READ Endorsement of the Collector of Godavari, dated 15th March 1888, No. 116 on letter from the Superintending Engineer, 1st Circle, dated 27th February 1888, No. 2657 G.D.

Resolution

The revised estimate and plan for the construction of a taluk Cutcherry at a cost of Rupees 23,770 are submitted for the sanction of Government.

(True Extract)

R. B. Benson
Acting Secretary.

To

The Secretary to Government R.D.
with letter and Encls: in orig. to be retd.

Copy to the Collector of Godavari

IRP

2440 W d/ 20.7.82
" 2150 d/ 2.7.69
" 3563 d/ 20.12.75
" 1495 W

SECRETARY TO GOVERNMENT. -2 MAY 88 P.W. DEPARTMENT, MADRAS. 87

PWC No. 415

(1888)

REVENUE DEPARTMENT.

No. 2478.

Order No. 2482. 5P

Approved and transferred to the Public Works Department.

(By Order)

H A [illegible]

Under Secretary to Govt.

Ootacamund
26th April 1888.

From

The Board of Revenue
(Land Revenue)

Dated 6th } April 1888.
Received 9th } 4.5.88
Enclosures 9 / 19 (+1 plan)

No. 2201 Misc.

X [illegible]
4759

To the Public Works Dept with 9 enclosures

SUBJECT.

Submitting for the sanction of Government the revised Estimate and plan for the construction of a taluk Cutcherry at Narsapur, Godavari District, at a cost of Rs. 23,770.

[illegible] 11/5/88

P. T. O.

[illegible] 2.5.88
17/5

No. 1536 W — Civil works

PUBLIC WORKS DEPARTMENT.

18

A

PROCEEDINGS OF THE MADRAS GOVERNMENT,

UNDER date the 25th May 1888

READ the following

Proceedings of the Board of Revenue. H. E. No: 2201 Misc. d/ 6th April 1888.
Endorsement by the Revenue Department. H. E. No: 2482 d/ 26th April 1888.

The revised estimate amounting to Rs. 23,770, for constructing a taluk office at Narsapur in the Godavari District, is sanctioned in supersession of the estimate of Rs. 22,900 sanctioned in G. O. No: 3563 dated 20th December 1875.

2. A sum of Rs 10,000 has been provided for the work in the current year's budget.

3. This sanction has been registered as Provincial No: 25 W of 1888-89 and classified as Civil Buildings, Original Works.

[signature]
17.5.88

To The Supdg. Engr. I Circle with 16 encls.
" Examiner of P. W. Accts with the general abstract estimate
" Revenue Department.

PPH 21 May

[initials] 19/5/88

[initials] 12/5

Govt. of {1888} Madras.

PUBLIC WORKS.

26/5/88

Dated

Recd. Encl.

G.O., 25th May 1888, No. 1536W

Taluq office at Narsapur

=

Revised estimate for constructing a — in the Godavari District, Sanctioned.

95
5

26/5