(1) பக்கங்களின் எண்ணிக்கை 26
(2) புதுக்கித் திருப்பிய நாள் 16. 6. 88
(3) ஆதாரங்குறிப்பவர் சுருக்கொப்பம்

தமிழ்நாடு ஆவணக் காப்பகம்.

தமிழ்நாடு அரசு

P. W. D துறை

அரசாணை எண். / மு. கோப்புத் தாள் எண். 1572 — W அச்சகம் / பலவகை

நாள் : 30 — 5 — 1888 ~~198~~.

மடிக்கவோ கண்டபடி கையாளவோ கூடாது

V. S. M.

ஆவண. கா-1—18,006—15-6-87.

1572/6

30th May 1888, No. 1572 W., Public Works.

GOVERNMENT OF MADRAS.

PUBLIC WORKS DEPARTMENT.

Buildings and Roads.
Civil Works.

Read—the following Proceedings of the Board of Revenue (Land Revenue), dated 26th March 1888, Mis. No. 2003 :—

W. Wilson, Esq., M.A.

Read—the following letter from Colonel J. BEATTY, R.E., Superintending Engineer, IV Circle, to the Collector of Coimbatore, dated Coimbatore, 3rd March 1888, No. 81 M. :—

Adverting to your letter No. 1025/Sub., of 15th September last, to the Executive Engineer, Coimbatore Division, I have the honor to forward, for transmission to Government, for sanction and provision of funds, a plan and estimate, amounting to Rs. 3,220, for constructing a sub-jail near the Deputy Tahsildar's cutcherry at Mettupálaiyam.

2. A report, site-plan and a duplicate abstract of the estimate are also submitted.

Mis. No. 339.

Submitted, with enclosures, to the Commissioners of Land Revenue, in view to the sanction of Government in the Public Works Department being obtained.

Coimbatore,
10th March 1888.

(Signed) K. SUBBARAYUDU,
for Acting Collector.

Resolution—dated 26th March 1888, Mis. No. 2003.

The plan and estimate for constructing a new sub-jail at Mettupálaiyam at a cost of Rs. 3,220, are submitted for the sanction of Government and for the provision of funds in the Public Works Department.

2. The necessity for the building is fully explained in the report of the Executive Engineer accompanying.

(True Extract.)

(Signed) R. S. BENSON,
Acting Secretary.

No. 2596, Revenue.

Transferred to the Judicial Department.

(By Order.)

Ootacamund,
2nd May 1888.

(Signed) H. A. STUART,
Under-Secy. to Government.

Approved and transferred to the Public Works Department.

(By Order.)

14th May 1888.

(Signed) A. G. CARDEW,
Ag. Under-Secy. to Govt.

Order—dated 30th May 1888, No. 1572 W., Public Works.

The estimate, amounting to Rs. 3,220, for constructing a sub-jail at Mettupálaiyam in the Coimbatore District, is sanctioned, and the amount is appropriated from the Provincial reserve with the Government.

2. This sanction has been registered as Provincial No. 28 W. of 1888-89, and classified as Civil Buildings, Original Works.

(True Extract.)

Captain, R.E.,
Under-Secy. to Govt., P.W.D.

To the Superintending Engineer, IV Circle, with five enclosures.
„ Examiner, Public Works Accounts, with the duplicate abstract estimate.
„ Judicial Department.

Exd. F. R. Bantleman.
Spare Copies

1572
2

BUILDINGS AND ROADS.
CIVIL WORKS.

Govt. of {1888} Madras.

PUBLIC WORKS.

Dated May, 30th.

Recd. *Encl.*

G.O., 30th May 1888, No. 1572 W.

MAY.

Sub-jail at Mettupalaiyam

Estimate for constructing a — in the Coimbatore District, sanctioned.

1547
3

Accompaniment to G.O., No. 1602 *W., dated* 15*th June* 1887.

DEPUTY TAHSILDAR'S CUTCHERRY.

Descriptive Specification.

Foundations.—A depth of 4 feet is provided in the quantities, but this should be settled locally in accordance with the nature of the soil.

Walling.—The walls should be built in English bond, outer walls 2 bricks thick, partitions 1½ bricks thick, verandah walls 1 brick thick, except under posts which will be half a brick thicker.

Stonework.—Stone slabs 12″ × 12″ × 6″ with mortice holes 2 inches square and 2 inches deep cut into them into which the verandah posts will be tenoned. Slabs will also be placed at the bearings of trusses. The steps may also be of stone, if procurable without great expense.

Woodwork.—The doors, windows, weather boards, verandah posts and trusses should be of well seasoned teakwood, the rafters and other minor roof timbers may be of approved country wood.

Roofing.—The roof will be covered with flat and pan tiles; if the quantity of these are good, the usual unsightly "chunam bands" might be dispensed with. All valleys should be protected with sheet lead.

Flooring.—The floor may be of square bricks or stone slabs, if the latter are easily procurable. Asphalte flooring is provided for jail wards.

Interior and exterior finishing.—The interior walls will be fine plastered with shell lime or plastered and washed. Where good bricks are obtainable the exterior should be pointed.

Note.—Where the soil is damp, the space below the flooring should be filled with river sand to a depth of 1 foot at least.

The interior walls to a height of 3 feet above floor level and the plinth all round should be plastered with Portland cement ½ an inch thick.

Finials.—The finials over the court may be of copper, iron or wood.

The different kinds of work to be done will be executed in conformity with the standard specification of the Public Works Department.

(Signed) J. W. BRASSINGTON,
Offg. Consulting Architect to Government.

Estimate Form.—Detail Measurements.

Detail of Work.	Number.	Measurements in Feet.						Area or Contents.	Total Quantity of each description of Work.
		Length.		Breadth.		Depth.			
Excavation for Foundation.									
Court and retiring room—									
Outer walls	...	92	3	4	6	4	0	1,661	
Partition	1	12	0	4	1½	4	0	198	
Clerks, record and police—									
Outer walls	2	49	3	4	6	4	0	1,773	
Partitions	2	12	0	4	1½	4	0	396	
Jail wards, outer walls	...	122	9	4	6	4	0	2,210	
Do. partitions	3	12	0	4	1½	4	0	594	
Verandah at front and end ...	...	122	9	3	6	4	0	2,408	
Do. at rear	...	49	3	3	6	4	0		
Extra thickness under posts ...	21	1	1½	0	4½	4	0	45	
Do. do. at corners	1	1	10½	0	4½	4	0		
Do. do. do.	3	0	4½	0	4½	4	0		
Do. next to walls	4	0	9½	0	4½	4	0		
Steps	2	16	6	3	0	1	6	194	
Do.	1	10	0	3	0	1	6		
Total, Cubic feet ...	...	...		...		...		...	9,479

Estimate Form.—Detail Measurements—*cont.*

Detail of Work.	Number.	Measurements in Feet.			Area or Contents.	Total Quantity of each description of Work.
		Length.	Breadth.	Depth.		
Concrete.						
Court and retiring room—						
Outer walls	...	92 3	4 6	1 6	623	
Partition	1	12 0	4 1½	1 6	74	
Clerks, record and police—						
Outer walls	2	49 3	4 6	1 6	665	
Partitions	2	12 0	4 1½	1 6	149	
Jail wards, outer walls	...	122 9	4 6	1 6	829	
Do. partitions	3	12 0	4 1½	1 6	223	
Verandah at front and end	...	122 9	3 6	1 6	903	
Do. at rear	...	49 3	3 6	1 6		
Extra thickness under posts	21	1 1½	0 4½	1 6	17	
Do. do.	1	1 10½	0 4½	1 6		
Do. do.	3	0 4½	0 4½	1 6		
Do. do.	4	0 9½	0 4½	1 6		
Steps	2	16 6	3 0	1 6	194	
Do.	1	10 0	3 0	1 6		
Total, Cubic feet	...	...	...	...	...	3,677
Brickwork in Foundations.						
Footings.						
Court and retiring room—						
Outer walls	...	92 3	2 3	1 6	311	
Partition	1	14 3	1 10½	1 6	40	
Clerks, record and police—						
Outer walls	2	51 6	2 3	1 6	348	
Partitions	2	14 3	1 10½	1 6	80	
Jail wards, outer walls	...	122 9	2 3	1 6	414	
Do. partitions	3	14 3	1 10½	1 6	120	
Verandah at front and end	...	125 0	1 6	1 6	397	
Do. at rear	...	51 6	1 6	1 6		
Extra thickness under posts	21	1 1½	0 4½	1 6	17	
Do. corners	1	1 10½	0 4½	1 6		
Do. do.	3	0 4½	0 4½	1 6		
Do. next to walls	4	0 9½	0 4½	1 6		
Above footings to ground level.						
Court and retiring room—						
Outer walls	...	92 3	1 6	1 0	138	
Partition	1	15 0	1 1½	1 0	17	
Clerks, record and police—						
Outer walls	2	52 3	1 6	1 0	157	
Partitions	2	15 0	1 1½	1 0	34	
Jail wards, outer walls	...	122 9	1 6	1 0	184	
Do. partitions	3	15 0	1 1½	1 0	51	
Verandah at front and end	...	125 9	0 9	1 0	134	
Do. at rear	...	52 3	0 9	1 0		
Extra thickness under posts	21	1 1½	0 4½	1 0	11	
Do. at corners	1	1 10½	0 4½	1 0		
Do. do.	3	0 4½	0 4½	1 0		
Do. next to walls	4	0 9½	0 4½	1 0		
Extra thickness for plinth	...	117 3	0 3	1 0	29	
Total, Cubic feet	...	...	...	...	...	2,482
Brickwork in Basement.						
Court and retiring room—						
Outer walls	...	92 3	1 6	2 0	277	
Partition	1	15 0	1 1½	2 0	34	

Estimate Form.—Detail Measurements—*cont.*

Detail of Work.	Number.	Measurements in Feet.			Area or Contents.	Total Quantity of each description of Work.
		Length.	Breadth.	Depth.		
Brickwork in Basement—cont.						
Clerks, record and police—						
Outer walls	2	52 3	1 6	2 0	314	
Partitions	2	15 0	1 1½	2 0	68	
Jail wards—						
Outer walls	...	122 9	1 6	2 0	368	
Partitions	3	15 0	1 1½	2 0	101	
Verandah at front and end	...	125 9	0 9	2 0	189	
Do. at rear	...	52 3	0 9	2 0	78	
Do. extra thickness under posts	21	1 1½	0 4½	2 0	22	
Do. do. at corners	1	1 10½	0 4½	2 0		
Do. do. do.	3	0 4½	0 4½	2 0		
Do. do. next to walls.	4	0 9½	0 4½	2 0		
Extra thickness for plinth	...	117 3	0 3	2 0	59	
Steps	2	16 6	3 0	0 6	50	
Do.	2	14 6	2 0	0 6	29	
Do.	2	12 6	1 0	0 6	13	
Do.	1	10 0	3 0	0 6	15	
Do.	1	8 0	2 0	0 6	8	
Do.	1	6 0	1 0	0 6	3	1,628
Deduct—						
Cut stones in steps and under posts	...	...	...	...	...	79
Total, Cubic feet	...	...	...	...	...	1,549
Brickwork in Superstructure.						
Court front and end walls	...	60 3	1 6	12 9	1,152	
Do. rear wall	1	15 0	1 1½	12 9	215	
Do. dais	1	19 9	1 1½	1 6	33	
Retiring room rear wall	1	18 0	1 6	8 0	216	
Do. sides	2	7 0	1 6	10 4½	218	
Clerks, record and police—						
Outer walls	2	52 3	1 6	12 9	1,999	
Partitions	2	15 0	1 1½	12 9	430	
Gables	1	18 0	1 6	3 0	81	
Do.	2	18 0	1 1½	3 0	122	
Jail wards—						
Outer walls	...	122 9	1 6	12 9	2,348	
Partitions	3	15 0	1 1½	12 9	645	
Gables	3	18 0	1 6	3 0	243	
Do.	3	18 0	1 1½	3 0	182	7,884
Deductions—						
Doorways	9	4 0	1 6	8 0	432	
Do.	1	4 0	1 1½	8 0	70	
Do.	1	4 0	1 1½	7 6		
Do.	4	4 0	1 6	6 6	156	
Windows	3	4 0	1 6	5 0	114	
Do.	1	4 0	1 6	4 0		
Ventilators	6	4 0	1 6	2 0	72	
Openings in police room	2	7 6	1 6	6 6	146	
Archwork as per details	...	...	...	...	210	1,200
Total, Cublic feet	...	...	...	...	...	6,684

Estimate Form.—Detail Measurements—*cont.*

Detail of Work.	Number.	Measurements in Feet.			Area or Contents.	Total Quantity of each description of Work.
		Length.	Breadth.	Depth.		
Archwork.						
Over doors and windows	16	5 0	1 6	1 1½	135	
Do. do.	2	5 0	1 1½	1 1½	13	
Ventilators	2	5 0	1 6	1 1½	17	
Openings in police room	2	10 0	1 6	1 6	45	
Total, Cubic feet ...	...	...	...	...	...	210
Cutstone Work.						
Slabs under posts	29	1 0	1 0	0 6	79	
Steps	...	129 0	1 0	0 6		
Slabs under trusses	10	2 0	1 6	0 4	10	
Total, Cubic feet ...	...	...	...	...	...	89
Earth filling in Basement.						
Court and retiring room	...	27 0	15 0	1 6	2,633	
Clerks, record and police	...	50 0	15 0	1 6		
Jail wards	...	40 0	15 0	1 6		
Verandahs in front and end ...	...	110 9	6 9	1 6	1,650	
Do. in rear	...	52 3	6 9	1 6		
Dais	...	5 9	5 10½	1 0	34	
Total, Cubic feet ...	...	...	...	...	...	4,317
Teakwood wrought and put up.						
5 trusses to span 15 feet — Tie beams	5	18 0	0 4	0 6	15	
Principal rafters ...	10	9 9	0 4	0 5	14	
Struts	10	4 9	0 4	0 4	5	
Purlins (allowing for halving) ...	2	22 0	0 4	0 6	46	
Do. do.	2	63 6	0 4	0 6		
Do. do.	2	52 0	0 4	0 6		
Wall purlins do.	2	22 0	0 3	0 4	24	
Do.	2	17 0	0 3	0 4		
Do.	2	55 0	0 3	0 4		
Do.	2	52 0	0 3	0 4		
Ridge	1	5 6	0 3	0 8	21	
Do.	1	71 0	0 3	0 8		
Do.						
Wall plate for outer wall of retiring room	1	52 0	0 3	0 8		
Hip rafters	1	17 0	0 3	0 2	1	
Common rafters, 18" centre to centre for court	7	15 0	0 3	0 5	11	
Clerks, records, and police	10	10 9	0 3	0 4	157	
Jail wards	72	10 9	0 3	0 4		
Do.	20	10 9	0 3	0 4		
	44	12 6	0 3	0 4		
Jack rafters	40	average 6 0	0 3	0 4		
Rafters for retiring room	11	11 6	0 3	0 5	13	
Verandah—						
Posts	29	0 5	0 5	7 6	38	
Breastsummers allowing for halving	...	186 0	0 5	0 5	32	
Hip rafters	7	16 0	0 3	0 5	14	
Do.	2	10 0	0 3	0 5		
Ridge for verandah gables ...	2	6 0	0 3	0 6	2	

Estimate Form.—Detail Measurements—*cont.*

Detail of Work.	Number.	Measurements in Feet.			Area or Contents.	Total Quantity of each description of Work.
		Length.	Breadth.	Depth.		
Teakwood wrought and put up—cont.						
Verandah—*cont.*						
Common rafters	76	11 6	0 3	0 5	138	
Jack rafters } average length.	40	9 6	0 3	0 5		
Do. } average length.	8	5 6	0 3	0 5		
Do. } average length.	6	8 6	0 3	0 5		
Do. } average length.	12	5 0	0 3	0 5		
Barge boards for jail gables ...	4	13 0	0 1	0 9	3	
Do.	4	3 0	0 1	1 0	1	
Do. collar pieces ...	2	9 0	0 3	0 4	2	
Do. finials	2	6 6	0 3	0 3	1	
Do. do.	2	1 0	0 8	0 8	1	
Do. do.	2	4 0	2 0	0 1¼	2	
Verandah gables—						
Barge boards	4	7 0	0 1	1 0	2	
Collar pieces	2	7 0	0 2	0 4	1	
Finials	2	6 0	0 3	0 3	1	
Planks	2	2 6	0 1¼	1 6	1	
Weather boards for jail—						
Brackets	4	3 6	0 2	0 2½	1	
Struts	4	3 0	0 2	0 2⅓		
Breastsummers	2	6 0	0 2	0 2⅓		
Rafters	8	4 6	0 1½	0 2	1	
Planks including overlap ...	12	6 3	0 ¾	0 9	4	
Boarding at ends of jail—						
Verandahs	2	8 0	0 1	3 0	4	
Battens	2	7 6	0 3	0 4	1	
Total, Cublic feet ...	...	...	...	...	...	557
Venetian and Panel Doors with Frames.						
Outer doors ... ... Square feet ...	8	4 0	...	8 0	256	
Panelled Doors with Frames.						
Inner doors	2	4 0	...	8 0	64	
Do.	1	4 0	...	7 6	30	
Total, Square feet ...	...	...	...	...	94	
Wrought-iron grated Doors with wooden Frames.						
For jail wards ... Square feet ...	4	4 0	...	6 6	104	
Venetian Windows with Frames.						
For police and retiring room ...	3	4 0	...	5 0	60	
For retiring room	1	4 0	...	4 0	16	
Total, Square feet ...	...	...	...	...	76	
Teak Frames with Iron Bars for Jail.						
Ventilators ... ... Square feet ...	6	4 0	...	2 0	48	
Wrought-iron Work in Trusses.						
⅞" Dia. king rods	5	6 7½	= 33	×2·01	66	
⅞" Hex. nuts and heads	15	...	...	×0·73	11	

Detail of Work.	Number.	Measurements in Feet.			Area or Contents.	Total Quantity of each description of Work.
		Length.	Breadth.	Depth.		
Wrought-iron Work in Trusses—cont.						
3" Dia. ⅛" Thick washers	10	...	...	× 0·32	3	
1½" × ⅜" Heel straps	10	2 3	= 23	1·87	43	
1½" × ⅜" Bearing plate	10	0 6¾	= 6	1·87	11	
⅝" Hexagon nuts for straps ...	20	...	...	·267	5	
Caps of ⅜" plate 6" wide	5	1 6	= 8	× 7·51	= 60	
Total, lb. ...	...	...	...	...	...	199
Tiled Roofing.						
Court and verandahs	...	40 6	...	43 0	1,742	
Clerks, record and police, including verandah	...	53 0	...	43 0	2,279	
Jail	...	50 0	...	25 0	1,250	
Do.	2	7 0	...	4 6	63	
Square feet ...	...	...	...	...	5,334	
Total, Squares ...	...	...	...	...	...	53·34
Flooring with 8" square Bricks.						
Court and retiring room	...	27 0	...	15 0	1,155	
Clerks, records and police	...	50 0	...	15 0		
Verandahs	...	164 6	...	7 6	1,234	
Archways in police room	2	7 6	...	1 6	23	
Door pieces	9	4 0	...	1 6	54	
Do.	2	4 0	...	1 1½	9	
Square feet ...	...	...	...	...	2,475	
Total, Squares ..	...	...	...	...	...	24·75
Flooring with Asphalte ¾" thick over a bed of Concrete.						
Jail wards	4	10 0	...	15 0	600	
Door pieces	4	4 0	...	1 6	24	
Square feet ...	...	...	...	...	624	
Total, Squares ...	...	...	...	...	...	6·24
Plastering Interior, two coats.						
Court	...	70 0	...	12 9	893	
Retiring room	...	44 0	...	10 4½	457	
Clerks, records and police	...	190 0	...	12 9	4,973	
Jail wards	4	50 0	...	12 9		
Gables	16	18 0	...	3 0	864	
Arch jambs	2	21 0	...	1 6	63	
Door jambs	9	20 0	...	1 6	270	
Do.	1	20 0	...	1 1½	44	
Do.	1	19 0	...	1 1½		
Do.	4	17 0	...	1 6	285	
Window jambs	3	18 0	...	1 6		
Do.	1	12 0	...	1 6		
Ventilator jambs	2	12 0	...	1 6		
Do.	4	8 0	...	1 6		
Deduct—						7,849
Archways	2	7 6	...	6 6	98	
Doorways	12	4 0	...	8 0	384	
Do.	2	4 0	...	7 6	60	
Do.	6	4 0	...	6 6	156	

Detail of Work.	Number.	Measurements in Feet.			Area or Contents.	Total Quantity of each description of Work.
		Length.	Breadth.	Depth.		
Plastering Interior, two coats—cont.						
Deduct—						
Windows	3	4 0	...	5 0	60	
Do.	1	4 0	...	4 0	16	
Ventilators	6	4 0	...	2 0	48	
						822
Square feet ...	...	...	...	...	...	7,027
Total, Squares ...	...	...	...	...	...	70·27
Pointing Exterior.						
Court	...	45 3	...	12 9	577	
Retiring room	...	18 0	...	7 6	135	
Do. end walls	2	8 6	...	10 4½	176	
Clerks, records and police	2	52 3	...	12 9	2,744	
Jail	...	110 9	...	12 9		
Jail gables	2	18 0	...	3 0	108	
Basement all round	..	293 3	...	2 0	587	
						4,327
Deductions—						
Archways	2	7 6	...	6 6	98	
Doorways	8	4 0	...	8 0	256	
Do.	2	4 0	...	6 6	52	
Windows	3	4 0	...	5 0	60	
Do.	1	4 0	...	4 0	16	
Ventilators	6	4 0	...	2 0	48	
						530
Square feet ...	...	...	...	...	...	3,797
Total, Squares ...	...	...	...	...	...	3,797
					Per foot lb.	
Lead sheeting for roof valleys ...	...	112 0	1 6	168	× 5	840 lb.
Railing for dais	...	...	...	...	22	Lineal ft.
Finials over court	...	...	2 in number.		...	...
Painting with three coats of Carson's Paint.						
Venetian and panel doors	3	256 0	= ...	...	768	
Panelled doors	2	94 0	= ...	...	188	
Wrought-iron grated doors ...	2	104 0	= ...	...	208	
Venetian windows with frames ...	4	76 0	= ...	...	304	
Jail ventilators	2	48 0	= ...	...	96	
Roof timbers including weather boards, posts, &c.	...	...	...	...	6,336	
Square feet ...	...	...	...	...	7,900	...
Total, Squares ...	...	...	...	...	...	79
Extra labor in finishing barge boards and finials.						
Jail gables	2	...	...	...	...	...
Verandah gables	2	...	...	...	...	...
	4	in number.		...	...	...
Punkah 8 feet long for court room.	1	in number.		...	...	...

Estimate Form.—Abstract.

Quantity.	Description of Work.	Rate.	Per	Amount.	Total.
9,479 C. ft.	Excavation for foundations (rate to include refilling of trenches)	RS.		RS.	RS.
3,677 „	Concrete in do. do. ...	...	1,000 C. ft.		
2,482 „	Brickwork in foundation	...	100 „		
1,549 „	Do. in basement	...	100 „		
6,684 „	Do. in superstructure	...	100 „		
210 „	Archwork	...	100 „		
89 „	Cutstone work	...	100 „		
4,317 „	Filling in basement	...	C. ft.		
557 „	Teakwood wrought and put up	...	1,000 C. ft.		
256 Sq. ft.	Venetian and panel doors with frames complete	...	C. ft.		
94 „	Panelled doors	...	Sq. ft.		
104 „	Wrought-iron grated doors with teak frames complete	...	„		
76 „	Venetian windows with frames complete ...	...	„		
48 „	Teak frames with iron bars for jail ventilator	...	„		
199 lb.	Wrought-iron in trusses	...	„		
53·34 Sqrs.	Tiled roofing with flat and pan tiles including teak reepers	...	lb.		
24·75 „	Flooring with 8-inch square bricks	...	Sqr.		
6·24 „	Do. with asphalte ¾ inch thick over a bed of concrete	...	„		
70·27 „	Plastering interior, 2 coats	...	„		
37·97 „	Pointing exterior	...	„		
840 lb.	Lead sheeting for roof valleys	...	„		
22 L. ft.	Railing for dais	...	lb.		
2 in No.	Finials over court	...	L. ft.		
79 Sqrs.	Painting with 3 coats of Carson's paint ...	...	Each.		
4 in No.	Add extra for labor in finishing barge boards and finials	...	Sqr.		
1 „	Punkah 8 feet long	...	Each.		
...	Petty supervision	...	...		
...	Contingencies	...	...		

Madras,
17th May 1887.

(Signed) J. W. BRASSINGTON,
Offg. Consulting Architect to Government.

1572

7

15th June 1887, No. 1602 W., Public Works.

GOVERNMENT OF MADRAS.

PUBLIC WORKS DEPARTMENT.

Buildings and Roads.
Civil Works.

Read—the following papers:—

From J. W. BRASSINGTON, Esq., Officiating Consulting Architect to the Government of Madras, to the Chief Engineer, Public Works Department, dated Chepâk, 17th May 1887, No. 224.

In continuation of my letter, No. 95, dated 25th April 1887, I have the honor to submit the revised standard plan with schedule of quantities for a deputy tahsildar's cutcherry.

No. 139 D, Public Works.

Forwarded, in continuation of No. 72 D., dated 6th May 1887, for the approval of Government in the Revenue Department.

(Signed) J. O. HASTED, Colonel, R.E.,
Secy. to Govt., P.W.D.

20th May 1887.

Proceedings of the Madras Government, Revenue Department, dated 1st June 1887, No. 3106.

Read—endorsement of the Public Works Department, dated 20th May 1887, No. 139 D., on letter from the Consulting Architect to the Government of Madras, dated 17th May 1887, No. 224, submitting revised standard design and schedule of quantities for deputy tahsildars' cutcherries.

Order—dated 1st June 1887, No. 3106, Revenue.

Approved.

(True Extract.)

(Signed) J. F. PRICE,
Ag. Secretary to Govt.

Order—dated 15th June 1887, No. 1602 W., Public Works.

The revised type design, with schedule of quantities and descriptive specification, for second-class taluk offices, will be circulated to officers of the Public Works Department, for information and guidance, in continuation of G.O., No. 1495 W., dated 3rd June 1887.

(True Extract.)

(Signed) J. O. HASTED, Colonel, R.E.,
Secretary to Govt., P.W.D.

To Superintending Engineers.
To the Consulting Architect to Government.
„ Revenue Department.

Exd. P. L. Pereira.

Spare Copies

BUILDINGS AND ROADS.
CIVIL WORKS.

Govt. of {1887} Madras.
PUBLIC WORKS.

Dated June, 15th.

Recd. Encl.

G.O., 15th June 1887, No. 1602 W

JUNE.

Second-class Taluk Offi

A revised type design for — c
to officers of the Public Works Dep

1512/8 110/8

No. 81/M

Supg Engineer's Office
IV Circle Coimbatore
3rd March 1888

From,
Colonel J. Beatty R. E.
Superintending Engineer.
IV circle.

To,
The Collector of Coimbatore.

Encl: 5
1. Plan
1. Site plan
1. Estimate
1. Duplicate abstract estimate
1. Report
5

Sir,
Adverting to your letter, No. 1025/Sub of 15th September last, to the Executive Engineer, Coimbatore Division, I have the honor to forward for transmission to Government for sanction and provision of funds, a Plan and Estimate amounting to Rs 3,220 for constructing a Sub-jail near the Deputy Tahsildar's cutcherry at Mettupalayam.

2. — A report, site plan and a duplicate abstract of the estimate are also submitted —

[illegible] 762 OF 1888

I have &c

Refce on No. 334/Mis

(Sd) J. Beatty. Colonel R.E.
Supg: Engineer IV circle

(True copy)

5 Rev. 22.92/88

Submitted, with enclosures, to the

Commissioners of Land Revenue in view to the sanction of Government in the Department of Public Works being obtained.

Coimbatore Collector's Office 10th March 1888 } K. Subbada Iyengar
for Ag. Collector.

1572
9

Proceedings of the Board of Revenue

(Land Revenue).

Dated 26th March 1888.

No. 2003, Miscellaneous.

W. Wilson Esq. M.A.

READ Endorsement of the Collector of Coimbatore, dated 10th March 1888, Reference on No: 339/Mis:

Resolution.

The plan and estimate for constructing a new Subjail at Mettupalayam at a cost of Rs. 3220, are submitted for the Sanction of Government and for the provision of funds in the Public Works Department.

2. The necessity for the building is fully explained in the report of the Executive Engineer accompanying.

(True Extract)

Ag. Secretary.

To
The Secy: to Govt R. D with letter & enclosures in original
Copy to the Collector of Coimbatore

No 2238 – 25 – 7 – 87
L 1500 – 12 – 7 – 87

CURRENT NO. 2113

1602 W/15 – 6. 87

3 P

Endorsement No. 2596.

Transferred to the Judicial Department.

(By order)

H. H. Stuart.

Under Secretary to Govt.

Ootacamund 7 May

SECRETARY TO GOVERNMENT, 15 MAY 88, P. W. DEPARTMENT, MADRAS.

ck 9/5 May/88

Approved and transferred to the P.W.D.

(by order)

A. G. Cardew.

Ag. Under Secretary

No. 79 15/5 22/5 30.5.88

Judl ~~CURRENT NO.~~ ~~2215~~

(1888.)

REVENUE DEPARTMENT.

No. 2292.

From

The Board of Rev:

(Land Rev:)

Dated 26th } March/88
Received 29th } R 18.5.88
Enclosures 8 (8) eight

CHIEF SECRETARY 5 MAY 88 GOVERNMENT OF MADRAS

No. 2003.

SUBJECT.

Submitting with remarks for the sanction of Govt. and for provision of the Funds in the P.W. Dept. the plan and estimate for constructing a new sub jail at Mettupalaiyam, Coimbatore District.

Over

Endorsement

---

157 W

Public Works Department.

B/4

Current No. 4685

Letter No. Nil

Dated 14th May 1888

From the Secy. to Govt. Rev. Deptt.

Ootacamund

19.5.88

NOTE OF REMARKS.

The estimate under review amounting to Rs 3220 provides for constructing a sub jail at Mettupalayam.

It is explained that the existing sub jail is a long low tiled building attached to the Dy Tahsildar's Cutcherry, was originally an open shed and was converted into a sub jail in 1869. The building, although in good order, is stated to be low and insecure for prisoners, it is therefore proposed to construct a sub jail in accordance with type design circulated with G.O. No 1602 W 15th

The following rate is in excess of that given in the Schedule for the Coimbatore division.

Asphalte Flooring – $\frac{3}{4}$" over 4" of concrete, the rate quoted in the Estimate for this item is Rs 25 against Rs 20 in the Schedule; if the latter rate is adopted a saving of Rs 47 will be effected in the Estimate.

The Estimate has been countersigned by the Collector and approved by Govt in the Revenue Deptt:–

19/5/88.

B & R

Civil Works

No. 1572

PUBLIC WORKS DEPARTMENT.

1572/12

PROCEEDINGS OF THE MADRAS GOVERNMENT.

UNDER date the 30th May 88

5P

READ the following

Proceedings of the Board of Revenue. H. E. No: 2003 Mis: d/26th March 1888.
Endorsement by the Revenue Department. H. E. No: 2596 d/2nd May 1888.
Endorsement by the judicial Department. d/14th March 1888.

The estimate amounting to Rs. 3,220, for constructing a sub-jail at Mettupalaiyam in the Coimbatore District, is sanctioned, and the amount is appropriated from the Provincial reserve with the Govt.

2. This sanction has been registered as Provincial No: 28 W of 1888-89, and classified as Civil Buildings, Original Works.

22.5.88

23/5/88

To
The Suptg. Engr. III Circle with 5 enclos.
" Examiner of P. W. Accts with the duplicate abstract estimate
" Judicial Department.

1/6/88

W/26/5

R. 80
0/22/5
1579.v
Kam. 24.v

1572/13

Govt. of {1888} Madras.

PUBLIC WORKS.

3/15

Dated

Recd. Recd.

G.O. 30th May, 1888, No. 1572 W.

[illegible] Mettupalayam

Extra cost of permanently [illegible]

a [illegible] in the Coimbatore

District, sanctioned.

80/5

D. 2615

823 31/5

13