(1) பக்கங்களின் எண்ணிக்கை 74

(2) புதுக்கித் திருப்பிய நாள் 5 July '88

(3) ஆதாரங்குறிப்பவர் சுருக்கொப்பம்

தமிழ்நாடு ஆவணக் காப்பகம்.

தமிழ்நாடு அரசு

பொதுப் பணித் துறை

அரசாணை எண்.
மு. கோப்புத் தாள் எண். 2236 W

அச்சகம்
~~பல்வகை~~

நாள் : 21. 7. 1988

~~198~~

...கவோ கண்டபடி கையாளவோ கூடாது

...வண. கா-1—18,006—15-6-87.

2236
1

GOVERNMENT OF MADRAS.

PUBLIC WORKS DEPARTMENT.

Buildings and Roads.
Civil Works.

Read—the following paper :—

Proceedings of the Board of Revenue (Land Revenue), dated 5th June 1888, Mis. No. 3410.

The Hon'ble W. S. Whiteside.

Read—the following letter from Colonel H. SMALLEY, R.E., Superintending Engineer, III Circle, to the Collector of Cuddapah, dated Váyalpád, 23rd April 1888, No. 128 :—

I have the honor to forward, for your countersignature and transmission to Government, an estimate, amounting to Rs. 22,184, for constructing a first-class taluk office at Badvél, with out-houses, in accordance with the standard plan approved in G.O. No. 1495 W., dated 3rd June 1887.

2. The estimate was called for in G.O. No. 1526 W., dated 16th June 1886, on G.O. No. 3414, dated 10th June 1886, in the Revenue Department.

Endorsement on the above, dated 7th May 1888, No. 3215.

Submitted to the Secretary to the Commissioners of Land Revenue, with a request that early sanction of the Government may be obtained, so that the work may be put in hand this year.

(Signed) G. KOTHANDA RAMAIYA,
for Acting Collector.

Resolution—dated 5th June 1888, Mis. No. 3410.

The estimate for constructing a first-class taluk office at Badvél, at a cost of Rs. 22,184, is submitted for the sanction of Government and the provision of funds in the budget of the Public Works Department.

2. Reference to the matter was made in para. 2 of G.O. No. 4414, dated 26th July 1886.

(A true Copy and Extract.)

(Signed) H. A. SIM.
Acting Secretary.

Mis. No. 3698, Revenue.

Transferred to the Public Works Department with the remark that, with reference to G.O. No. 1681 W., dated 7th June 1888, the provision of a ryots' shed is unnecessary.

(By Order.)

(Signed) H. A. STUART,
Under-Secretary.

Ootacamund,
25th June 1888.

Order—dated 21st July 1888, No. 2236 W., Public Works.

The estimate, amounting to Rs. 22,184, for constructing a first-class taluk office, with out-houses, at Badvél, in the Cuddapah District, has been reduced by Rs. 854, the cost of a ryots' shed, which is considered unnecessary, and sanction is accorded to the reduced amount, Rs. 21,330.

2. The Superintending Engineer will report what sum can be spent on the work during the current official year.

3. This sanction has been registered as Provincial No. 55 W. of 1888-89, and classified as Civil Buildings, Original Works.

(True Extract.)

Captain, R.E.,
Under-Secy. to Govt., P.W.D.

To the Superintending Engineer, III Circle, with six enclosures.
" Examiner, Public Works Accounts, with the duplicate general abstract estimate.
" Revenue Department.

Exd. F. R. Bantleman.
Spare Copies

BUILDINGS AND ROADS.
CIVIL WORKS.

Govt. of {1888} Madras.

PUBLIC WORKS.

Dated July, 21*st.*

Recd. *Encl.*

G.O., 21st July 1888, No. 2236 W.

JULY.

Taluk office

The reduced estimate for constructing a first-class —, with out-houses, at Badvél, in the Cuddapah District, sanctioned.

2236/3

30TH JUNE 1886, No. 1650 W., PUBLIC WORKS.

GOVERNMENT OF MADRAS.

PUBLIC WORKS DEPARTMENT.

General.
Account.

READ—the following paper:—

G.O., dated 25th June 1886, No. 573, Financial.

Read—the following paper:—

From the Public Works Department, dated 15th June 1886, No. 250 D.

Order—dated 25th June 1886, No. 573, Financial.

The Government resolve to make the following additional grants to the Public Works Department for expenditure during the current official year:—

Civil Buildings.

	Rs.
I. Sub-magistrate's office, with out-houses, at Arkónam, North Arcot district	8,000
II. Combined Bench Magistrates' court and 3rd-class police station at Kótagiri, Nílgiri district	8,000
III. Combined court-house for the district munsifs of Kumbakónam and Valangaman, Tanjore district	10,000
IV. Improving the District court-house at Kokarakulam (Tinnevelly)	10,000
V. Collector's office, Cuddapah	40,000
VI. New buildings for the Breeks Memorial School, Ootacamund ...	10,000
Reserve	50,000
Total, Civil Buildings ...	1,36,000

Irrigation and Navigation.

Buckingham canal	54,500
Madras water supply	10,000
Total, Irrigation and Navigation ...	64,500
Grand Total ...	2,00,500

(True Extract.)

(Signed) E. F. WEBSTER,
Chief Secretary.

ORDER—dated 30th June 1886, No. 1650 W., Public Works.

Communicated to the Chief Engineer for Irrigation and to the Superintending Engineers concerned.

2. Immediate arrangements should be made to utilise the allotments now sanctioned. The grants for "Collector's office, Cuddapah," and "New buildings for the Breeks Memorial School, Ootacamund," will not be available for expenditure until plans and estimates for those works have been sanctioned; but meanwhile the preparation of

materials may be proceeded with. The question of increasing the grant for the Breeks school buildings may be submitted for consideration later in the year, if necessary.

3. The submission of plans and estimates for additions to the Madras College* of Engineering, and for taluk offices† at Pullampet and Bádvel, Cuddapah district, should be expedited. On receipt of the estimates, the question of allotting funds for the works will be considered.

* Called for in G.O., No. 1539 W., dated 17th June 1886.

† Called for in G.O., No. 1526 W., dated 16th June 1886.

(True Extract.)

(Signed) J. SHAW-STEWART, Colonel, R.E.,
Secretary to Govt., P.W.D.

To the Chief Engineer for Irrigation.
" Superintending Engineer, III Circle.
" " " IV "
" " " V "
" " " VI "
" Consulting Architect to Government.
" Examiner, Public Works Accounts.
"

Exd. E. Fernandez.
Spare Copies

GENERAL.
ACCOUNT.

Govt. of {1886} Madras.

PUBLIC WORKS.

Dated June, 30*th*.

Read. *Enol.*

G.O., 30th June 1886, No. 1650 W.

JUNE.

Provincial Funds

Proceedings, Financial Department, making additional assignments from — to the extent of Rs. 2,00,500, communicated to the Chief Engineer for Irrigation and to the Superintending Engineers concerned, with remarks.

2236/5

PROCEEDINGS OF THE BOARD OF REVENUE.

Read—the following letter from G. STOKES, Esq., Acting Collector of Cuddapah, to the Secretary to the Board of Revenue, dated Yerraguntla, 28th November 1886, No. 977 :—

With reference to G.O., No. 6023,* dated 11th October 1886, I have the honor to report as follows.

2. With regard to paragraph 1 of the Government order, I have the honor to report that of the three buildings newly built at Pullampet, one seemed a fairly built building in tolerable order, one a terraced building is dangerous and is just about to fall, and the third, the new sub-jail, is quite useless. The roof has been constructed by the Revenue Department with the most inferior wood, and already it is sagged and will all have to be at once taken down. I have directed that a balance due to the contractor is not to be paid until the building is properly constructed. The Executive Engineer who saw it has condemned the building.

3. With regard to paragraph 2, I would report that there is an admirable site in possession of the Forest Department as a Tangedu tope on the left-hand side of the road to Nandalúr, about 2 furlongs from the centre of the town of Rajampet.

4. I can find nothing in the papers to alter the view I have before expressed. I find I have noticed shortly in my former letter all the points touched on in the former correspondence except the water question. All the advantages claimed for Pullampet have, as pointed out by the Board, disappeared. In fact now Rajampet is much the more central.

5. In regard to the question of the water-supply, I have lately visited Rajampet especially to look into the whole matter. I took with me the Assistant Surgeon, and I herewith submit his report. The water-supply of Rajampet is quite as good and is in some ways better than that of Pullampet. But I think the fact that 3,500 people continue to live at Rajampet more healthily than half the number do at Pullampet, is a sufficient answer on this point. The difference in the appearance of the people, as pointed out by the Assistant Surgeon, is very marked. There is life and movement in Rajampet, but Pullampet is a very sleepy hollow.

* The petition received with Board's Proceedings, Mis. No. 7968, dated 25th October 1886 (communicating the Government order), is herewith returned.

Enclosure No. 1.—Petition.

Enclosure No. 2.

Inspection report of the town of Rajampet, dated the 17th November 1886.

The village consists of about 650 houses, and a population of about 4,000. The village, although surrounded by hills on all sides, is on a higher level compared with the parts immediately surrounding it; and the streets and the yards of the houses look quite dry and tidy in spite of the heavy rains they had lately. The soil is mostly of a hard kunker nature. There is not much wet cultivation close to the town, except some on the south-east side, on both sides of channel Chuckrala Madugu. This wet cultivation, I do not think, will affect the health of the village, its distance from and direction to the village being not unfavorable. General appearance of the people is healthy, lively and cheerful.

2. Water-supply seems good and sufficient. There are a good many wells all over the village (about 25 to 30), containing clear water of good taste and free from all bad odours; there is also a channel, called Chuckrala Madugu, running from south to north on the eastern border of the village; this channel is formed from the escape water of the Poly tank, which is said to contain a good quantity of water throughout the year. The channel is also said to contain water throughout the year; but some of the wells in the village are said to dry up for a month or so during the hot weather. But if these wells are deepened a little more, or deeper ones are sunk newly, I think they will supply water throughout the year. In case of supply failing in these wells, there is the channel Chuckrala Madugu, which also contain good water. The only objection that may be raised against this water is that on both sides of the channel there is wet cultivation. Although this is certainly objectionable, it is not a sufficient ground to condemn the water. We rarely find an Indian town that has not such defects in its water-supply. As this channel is formed from the escape water of Poly tank, the bulk of its supply could be increased, when necessary, on a small cost.

3. I saw also the site selected for building a new cutcherry. It is on a high ground quite open and situated about 2 furlongs from the village on the Cuddapah road. This is the only and the best site available. There is a large well of good water in the site selected.

4. In comparing Pullampet with Rajampet, I have to make the following remarks regarding the former place:—That it is situated on, comparatively, a low ground, surrounded by wet cultivation, and good many large topes, which prevent a free current of fresh air, and keep the place damp and moist. I have not examined any of the wells, but have seen the river running on the eastern border of the village; the water seemed to me to be good, but greatly polluted by people washing their dirty clothes and easing themselves on the banks of the river. I heard that a great portion of the people get their supply of water from the wells. The general appearance of the people at Pullampet is sickly and dull.

5. I have also to make a few suggestions towards the improvement of sanitation of Rajampet: there is a collection of dirty, stagnant water on the (1) southern side of the village on Rayachóti road, and another on the western side. These are very objectionable. To make the matter worse again they are also used as manure pits. These ditches ought to be filled up. (2) All the wells require a raised parapet wall of brick and mortar with a slope of about 4 feet all round, and a drain to carry off the washings and other dirt which at present find its way into the well again. The large wells are all covered with shrubs on their sides and banks, and some Soonkasala trees overhanging. All these have to be removed and also improved, the steps leading into them which are at present very narrow and unsafe. (3) There are now only two latrines—one on the south and another on north end of the village. This is sufficient for such a large populated village. Two more may be erected—one on the east, another on the west end of the village. The old latrines are well built and kept very clean.

6. There are no cess-pits nor any dust-bins at present. Two dust-bins for each large street and one for each small street may be erected of stone slabs, which will be cheaper and also answer the purpose well. The house-owners may be ordered to have cess-pits dug for for each house.

CUDDAPAH,
20th November 1886.

(Signed) C. P. GANAPATI, L.M.S.,
Assistant Surgeon.

READ—the following letter from G. STOKES, Esq., Acting Collector of Cuddapah, to the Secretary to the Board of Revenue, dated Yerruguntla, 25th November 1886, No. 976:—

With reference to the correspondence which has taken place in regard to the change of the head-quarters of the Pullampet taluk to Rajampet, I have the honor to state that I understand it is under contemplation to erect new offices for the deputy tahsildar of Chitvél at that place.

2. Before this matter is settled, I would like to raise the question whether, if the taluk cutcherry is placed at Rajampet, the deputy tahsildar should not be placed at Kódúr.

3. Chitvél was formerly a place of some importance as being the seat of a raja, but it has of late years decreased in size and has little or no trade. It is also cut off frequently by a very impracticable river. If the taluk cutcherry be at Rajampet, the limits of the deputy tahsildar's jurisdiction will come needlessly close to the tahsildar's head-quarters—in fact even at Pullampet they do so. The only thing which seems to me to call for the location of a magistrate about there is the fact of the proximity of an important pass into Nellore, but there is also an important pass near Kódúr.

REVENUE DEPARTMENT.

1886.

Board of Revenue,

MADRAS.

Printed December 14th.

Proceedings, 6th Dec. 1886, *No.* 2649.

Submitting to Government letters from the Collector of Cuddapah regarding the transfer of the head-quarters of the tahsildar of Pullampet and the deputy tahsildar of Chitvél from Pullampet and Chitvél to Rajampet and Kódúr, respectively.

2236/7

GOVERNMENT OF MADRAS.

REVENUE DEPARTMENT.

READ—again G.O., dated 11th October 1886, Mis. No. 6023, Revenue.

ABSTRACT.—Asking for further information regarding the proposed transfer of Taluk Head-quarters from Pullampett to Rájampet.

READ—the following Proceedings of the Board of Revenue, dated 6th December 1886, No. 2649 :—

Read—the following letter from G. STOKES, Esq., Acting Collector of Cuddapah, to the Secretary to the Board of Revenue, dated Yerraguntla, 28th November 1886, No. 977 :—

With reference to G.O., No. 6023,* dated 11th October 1886, I have the honor to report as follows.

* The petition received with Board's Proceedings, Mis. No. 7968, dated 25th October 1886 (communicating the Government order), is herewith returned.

2. With regard to paragraph 1 of the Government order, I have the honor to report that of the three buildings newly built at Pullampet, one seemed a fairly built building in tolerable order, one a terraced building is dangerous and is just about to fall, and the third, the new sub-jail, is quite useless. The roof has been constructed by the Revenue Department with the most inferior wood, and already it is sagged and will all have to be at once taken down. I have directed that a balance due to the contractor is not to be paid until the building is properly constructed. The Executive Engineer who saw it has condemned the building.

3. With regard to paragraph 2, I would report that there is an admirable site in possession of the Forest Department as a Tangedu tope on the left-hand side of the road to Nandalúr, about 2 furlongs from the centre of the town of Rájampet.

4. I can find nothing in the papers to alter the view I have before expressed. I find I have noticed shortly in my former letter all the points touched on in the former correspondence except the water question. All the advantages claimed for Pullampet have, as pointed out by the Board, disappeared. In fact now Rájampet is much the more central.

5. In regard to the question of the water-supply, I have lately visited Rájampet especially to look into the whole matter. I took with me the Assistant Surgeon, and I herewith submit his report. The water-supply of Rájampet is quite as good and is in some ways better than that of Pullampet. But I think the fact that 3,500 people continue to live at Rájampet more healthily than half the number do at Pullampet, is a sufficient answer on this point. The difference in the appearance of the people, as pointed out by the Assistant Surgeon, is very marked. There is life and movement in Rájampet, but Pullampet is a very sleepy hollow.

ENCLOSURE No. 1.—Petition.

ENCLOSURE No. 2.

INSPECTION Report of the Town of Rájampet, dated the 17th November 1886.

The village consists of about 650 houses, and a population of about 4,000. The village, although surrounded by hills on all sides, is on a higher level compared with the parts immediately surrounding it; and the streets and the yards of the houses look quite dry and tidy in spite of the heavy rains they had lately. The soil is mostly of a hard kunkor nature. There is not much wet cultivation close to the town, except some on the south-east side, on both sides of channel Chuckrala Madugu. This wet cultivation, I do not think, will affect the health of the village, its distance from and direction to the village being not unfavorable. General appearance of the people is healthy, lively and cheerful.

2. Water-supply seems good and sufficient. There are a good many wells all over the village (about 25 to 30), containing clear water of good taste and free from all bad odours; there is also a channel, called Chuckrala Madugu, running from south to north on the eastern border of the village; this channel is formed from the escape water of the Poly tank, which is

said to contain a good quantity of water throughout the year. The channel is also said to contain water throughout the year; but some of the wells in the village are said to dry up for a month or so during the hot weather. But if these wells are deepened a little more, or deeper ones are sunk newly, I think they will supply water throughout the year. In case of supply failing in these wells, there is the channel Chuckrala Madugu, which also contain good water. The only objection that may be raised against this water is that on both sides of the channel there is wet cultivation. Although this is certainly objectionable, it is not a sufficient ground to condemn the water. We rarely find an Indian town that has not such defects in its water-supply. As this channel is formed from the escape water of Poly tank, the bulk of its supply could be increased, when necessary, on a small cost.

3. I saw also the site selected for building a new cutcherry. It is on a high ground quite open and situated about 2 furlongs from the village on the Cuddapah road. This is the only and the best site available. There is a large well of good water in the site selected.

4. In comparing Pullampet with Rájampet, I have to make the following remarks regarding the former place:—That it is situated on, comparatively, a low ground, surrounded by wet cultivation, and good many large topes, which prevent a free current of fresh air, and keep the place damp and moist. I have not examined any of the wells, but have seen the river running on the eastern board of the village; the water seemed to me to be good, but greatly polluted by people washing their dirty clothes and easing themselves on the banks of the river. I heard that a great portion of the people get their supply of water from the wells. The general appearance of the people at Pullampet is sickly and dull.

5. I have also to make a few suggestions towards the improvement of sanitation of Rájampet: there is a collection of dirty, stagnant water on the (1) southern side of the village on Ráyachóti road, and another on the western side. These are very objectionable. To make the matter worse again they are also used as manure pits. These ditches ought to be filled up. (2) All the wells require a raised parapet wall of brick and mortar with a slope of about 4 feet all round, and a drain to carry off the washings and other dirt which at present find its way into the well again. The large wells are all covered with shrubs on their sides and banks, and some Soon-kasals trees overhanging. All these have to be removed and also improved, the steps leading into them which are at present very narrow and unsafe. (3) There are now only two latrines—one on the south and another on north end of the village. This is not sufficient for such a large populated village. Two more may be erected—one on the east, another on the west end of the village. The old latrines are well built and kept very clean.

6. There are no cess-pits nor any dust-bins at present. Two dust-bins for each large street and one for each small street may be erected of stone slabs, which will be cheaper and also answer the purpose well. The house-owners may be ordered to have cess-pits dug for for each house.

(Signed) C. P. GANAPATI, L.M.S.,
Assistant Surgeon.

CUDDAPAH,
20th November 1886.

Read—also the following letter from G. STOKES, Esq., Acting Collector of Cuddapah, to the Secretary to the Board of Revenue, dated Yerraguntla, 25th November 1886, No. 976:—

With reference to the correspondence which has taken place in regard to the change of the head-quarters of the Pullampet taluk to Rájampet, I have the honor to state that I understand it is under contemplation to erect new offices for the deputy tahsildar of Chitvél at that place.

2. Before this matter is settled, I would like to raise the question whether, if the taluk cutcherry is placed at Rájampet, the deputy tahsildar should not be placed at Kódúr.

3. Chitvél was formerly a place of some importance as being the seat of a raja, but it has of late years decreased in size and has little or no trade. It is also cut off frequently by a very impracticable river. If the taluk cutcherry be at Rájampet, the limits of the deputy tahsildar's jurisdiction will come needlessly close to the tahsildar's head-quarters—in fact even at Pullampet they do so. The only thing which seems to me to call for the location of a magistrate about there is the fact of the proximity of an important pass into Nellore, but there is also an important pass near Kódúr.

4. Kódúr, on the other hand, is a rising place of considerable trade. It is second, in fact, to Rájampet in the taluk. It is on the railway, and a mainthrough line of road. If the southern portion of the taluk were assigned to the deputy tahsildar there would be two compact divisions in the taluk, and the greatest distance of a court from any part of the taluk would be much reduced. I do not think Kódúr is particularly unhealthy or more unhealthy than Chitvél.

5. I have addressed the Board separately on this subject as it is distinct or rather contingent on that of locating the tahsildar at Rájampet, but perhaps the Board may think it well to dispose of both together. I would ask for early orders in any case.

Resolution—dated 6th December 1886, No. 2649.

The two letters read above from the Collector of Cuddapah will be submitted to Government in reference to G.O., dated 11th October 1886, No. 6023.

2. In the former, the Collector reports that the water is better at Rájampet than it is at Pullampet, that there is a good site available at Rájampet, and that of the three buildings existing at Pullampet, two are useless and unsafe. He makes no suggestion about the third, which seems to be in fairly good order, but the Board presume that it is the old public bungalow, described in paragraph 3 of Mr. LeFanu's letter, dated 25th March 1886, No. 240, embodied in Board's Proceedings, dated 17th May 1886, No. 1102, and G.O., No. 3414, dated 10th June 1886, and that, when vacated by the tahsildars, it will be possible to use it, as proposed by Mr. LeFanu in paragraph 7 of the same letter, as a taluk school.

3. In the second, the Collector proposes, as the corollary to the tahsildar's move to Rájampet, the move of the deputy tahsildar from Chitvél to Kódúr and he makes the proposal "on the understanding that it is under contemplation" to build new offices at Chitvél. The Board, however, are not aware of the existence of any such intention, and, before criticising the Collector's proposal, therefore they beg to be informed by Government if his supposition is correct.

(True Copies and Extract.)

(Signed) H. A. SIM,
Acting Sub-Secretary.

To the Secretary to Government, Revenue Department,
with petition.

Copy to the Collector of Cuddapah.

ORDER—dated 5th March 1887, No. 238, Revenue.

Miscellaneous.

Government accept the Collector's recommendation which is strongly supported by the Board; but before passing final orders, inquiry will be made in the Judicial Department as to whether any objection exists on police grounds to the taluk head-quarters being fixed at Rájampet.

2. Meanwhile, orders will issue in the Public Works Department for the preparation of a plan and estimate for the construction of a taluk cutcherry at the site specified in paragraph 3 of the Collector's letter, dated 28th November last. It will also be considered in the Public Works Department whether provision cannot be made in the budget for 1887-88 for the commencement of the work.

(True Extract.)

(Signed) J. F. PRICE,
Ag. Secretary to Government.

To the Board of Revenue, with petition returned.
" the Judicial Department.
" the Public Works Department.

Exd. W. H. French.

80 Copies.

Govt. of [1887] Madras.

REVENUE.

Issued

Recd. *Encl.*

G.O., 5th March 1887, No. 238.

MARCH.

Transfer of Taluk Head-quarters.

Accepting the Collector's recommendation for the — from Pullampet to Rájampet in the Cuddapah district, and asking for the opinion of the Judicial Department whether any objection exists on police grounds; requesting the Public Works Department to issue orders for the preparation of a plan and estimate for the construction of a cutcherry at the site in question.

2236/9

3RD JUNE 1887, No. 1495 W., PUBLIC WORKS.

GOVERNMENT OF MADRAS.

PUBLIC WORKS DEPARTMENT.

Buildings and Roads.
Civil Works.

READ—the following papers:—

From J. W. BRASSINGTON, Esq., Officiating Consulting Architect to the Government of Madras, to the Chief Engineer, Public Works Department, dated Chepâk, 25th April 1887, No. 95.

In continuation of my letter, No. 1530, dated the 12th March last, I have the honor to submit a revised plan and schedule of quantities for tahsildars' cutcherries.

2. The plan and quantities for deputy tahsildars' cutcherries will follow.

No. 72 D.

Forwarded for the approval of Government in the Revenue Department.

2. The design has already been approved in Committee by the Honorable Members and Secretaries to Government.

6th May 1887. (Signed) J. O. HASTED, Col., R.E.,
Chief Engineer, P.W.D.

G.O., dated 23rd May 1887, No. 2981, Revenue.

Read—endorsement of Public Works Department, dated 6th May 1887, No. 72 D., forwarding, for approval, revised standard design for taluk offices.

Order—dated 23rd May 1887, No. 2981, Revenue.

Approved.

(True Extract.)

(Signed) J. F. PRICE,
Ag. Secy. to Govt.

ORDER—dated 3rd June 1887, No. 1495 W., Public Works.

The revised type design, with schedule of quantities and descriptive specification for a first-class taluk office, will be circulated to officers of the Public Works Department, for information and guidance, in supersession of all previous standard designs for similar buildings.

(True Extract.)

(Signed) J. O. HASTED, Colonel, R.E.,
Secretary to Govt., P.W.D.

To Superintending Engineers.
" the Consulting Architect to Government.
" the Revenue Department.

Exd. P. L. Pereira.
Spare Copies

BUILDINGS AND ROADS.
CIVIL WORKS.

Govt. of {1887} Madra

PUBLIC WORKS.

Dated June, 3rd.

Encl.

Read.

G.O., 3rd June 1887, No. 1495 W

JUNE.

Taluk Office

A revised type design for a first-class
circulated to officers of the department.

2236/10

Annexure to G.O., No. 1495 W., dated 3rd June 1887.

ESTIMATE FORM—Detail Measurements.

Detail of work.	No.	Measurements in Feet. Length.	Breadth.	Depth.	Area or contents.	Total quantity of each description of work.
EXCAVATION FOR FOUNDATIONS.						
Court, outer walls	..	92 0	4 0	4 6	1,656	
Property and private room, end walls	3	5 4½	3 7½	4 6	1,007	
Do. do. outer walls	..	45 7½	3 7½	4 6		
Cashier's, sheristadar's, clerk's room, longitudinal walls	2	70 0	4 0	4 6	5,076	
Do. do. partition	3	15 6	4 0	4 6		
Record room, outer walls	..	95 6	4 0	4 6		
Treasury and inspector's room, &c., outer walls	..	115 9	4 4½	4 6	3,268	
Do. do. inner walls	2	20 4½	4 4½	4 6		
Do. do.	1	9 6	4 4½	4 6		
Jail wards, outer walls	..	173 0	4 0	4 6	3,114	
Do. partitions	4	12 6	3 7½	4 6	615	
Verandah and covered way walls near jail	..	89 0	3 3	4 6	5,404	
Do. in front	..	130 0	3 3	4 6		
Do. in rear and sides of record room	..	150 6	3 3	4 6		
Extra thickness at verandah posts	32	1 1½	0 4½	4 6	64	
Do. do. at corners	5	0 4½	0 4½	4 6		
Do. do.	4	1 10½	0 4½	4 6	13	
Steps	2	12 6	3 0	1 6	214	
Do.	1	11 6	3 0	1 6		
Do.	2	5 6	3 0	1 6		
Total, Cubic feet	..	..	..	..	..	29,632
CONCRETE IN FOUNDATIONS.						
Court, outer walls	..	92 0	4 0	1 6	552	
Property and private room, end walls	3	5 4½	3 7½	1 6	336	
Do. do. outer walls	..	45 7½	3 7½	1 6		
Cashier's, sheristadar's and clerk's room, longitudinal walls	2	70 0	4 0	1 6	1,692	
Do. do. partitions	3	15 6	4 0	1 6		
Record room, outer walls	..	95 6	4 0	1 6		
Treasury and inspector's room, outer walls	..	115 9	4 4½	1 6	1,989	
Do. do. inner walls	2	20 4½	4 4½	1 6		
Do. do.	1	9 6	4 4½	1 6		
Jail wards, outer walls	..	173 0	4 0	1 6	1,038	
Do. partitions	4	12 6	3 7½	1 6	272	
Verandah and covered way walls near jail	..	89 0	3 3	1 6	1,800	
Do. in front	..	130 0	3 3	1 6		
Do. in rear and sides of record room	..	150 6	3 3	1 6		
Extra thickness at verandah posts	32	1 1½	0 4½	1 6	26	
Do. do. at corners	5	0 4½	0 4½	1 6		
Do. do.	4	1 10½	0 4½	1 6		
Steps	2	12 6	3 0	1 6	214	
Do.	1	11 6	3 0	1 6		
Do.	2	5 6	3 0	1 6		
Total, Cubic feet	..	..	..	..	..	7,019
BRICKWORK IN FOUNDATIONS.						
Footings.						
Court, outer walls	..	92 0	2 3	1 0	207	
Private and property room end walls	3	7 1½	1 10½	1 0	122	
Do. do. outer walls	..	43 10½	1 10½	1 0		
Cashier's, sheristadar's and clerk's room, longitudinal walls	2	71 9	2 3	1 0	658	
Do. do. partitions	3	17 3	2 3	1 0		
Record room, outer walls	..	97 3	2 3	1 0		
Treasury and inspector's room, outer walls	..	115 9	2 7½	1 0	450	
Do. do. inner walls	2	22 1½	2 7½	1 0		
Do. do.	1	11 3	2 7½	1 0		
Jail wards, outer walls	..	173 0	2 3	1 0	389	
Do. partitions	4	14 3	1 10½	1 0	107	
Verandah and covered way near jail	..	92 6	1 6	1 0	565	
Do. in front	..	131 9	1 6	1 0		
Do. in rear and sides of record room	..	152 3	1 6	1 0		
Extra thickness at verandah posts	32	1 1½	0 4½	1 0	17	
Do. do. at corners	5	0 4½	0 4½	1 0		
Do. do.	4	1 10½	0 4½	1 0		
Above footings to ground level, court, outer walls	..	92 0	1 6	2 0	276	
Private and property room, end walls	3	7 10½	1 1½	2 0	160	
Do. do. outer walls	..	43 1½	1 1½	2 0		

Estimate Form—Detail Measurements—*cont.*

Detail of work.	No.	Measurements in Feet. Length.	Breadth.	Depth.	Area or contents.	Total quantity of each description of work.
BRICKWORK IN FOUNDATIONS—*cont.*						
Footings—cont.						
Cashier's, sheristadar's and clerk's rooms, longitudinal walls	2	72 6	1 6	2 0	891	
Cashier's, sheristadar's and clerk's rooms, longitudinal partitions	3	18 0	1 6	2 0		
Record room, outer walls		98 0	1 6	2 0		
Treasury and Inspector's room.						
Outer walls		116 9	1 10½	2 0	654	
Do. inner walls	2	22 10½	1 10½	2 0		
Do. do.	1	12 0	1 10½	2 0		
Jail wards, outer walls		173 0	1 6	2 0	519	
Do. partitions	4	15 0	1 1½	2 0	135	
Verandah and covered ways near jail		94 0	0 9	2 0		
Do. in front		132 6	0 9	2 0	569	
Do. in rear and sides of record room		153 0	0 9	2 0		
Extra thickness at verandah posts	32	1 1½	0 4½	2 0		
Do. at corners	5	0 4½	0 4½	2 0	34	
Do. do.	4	1 10½	0 4½	2 0		
Extra thickness for plinth for jail wards		108 6	0 3	2 0		
Inspector's and arms' room		47 6	0 3	2 0	100	
Private and property room		43 7½	0 3	2 0		
Total, Cubic feet						5,843
BRICKWORK IN BASEMENT.						
Court, outer walls		92 0	1 6	2 0	276	
Private and property room end walls	3	7 10½	1 1½	2 0	150	
Do. do. outer walls		43 1½	1 1½	2 0		
Cashier's, sheristadar's, &c., rooms, longitudinal walls	2	72 6	1 6	2 0		
Cashier's, sheristadar's, &c., rooms, longitudinal partitions	3	18 0	1 6	2 0	891	
Record room, outer walls		98 0	1 6	2 0		
Treasury and Inspector's room.						
Outer walls		116 9	1 10½	2 0	654	
Do. inner walls	2	22 10½	1 10½	2 0		
Do. do.	1	12 0	1 10½	2 0		
Jail, outer walls		173 0	1 6	2 0	519	
Do. partitions	4	15 0	1 1½	2 0	135	
Verandah and covered way rear jail		94 0	0 9	2 0		
Do. in front		132 6	0 9	2 0	569	
Do. in rear and sides of record room		153 0	0 9	2 0		
Extra thickness at verandah posts	32	1 1½	0 4½	2 0		
Do. at corners	5	0 4½	0 4½	2 0	34	
Do. do.	4	1 10½	0 4½	2 0		
Extra thickness for plinth		199 7½	0 3	2 0	100	
Dais walls		20 9	1 1½	1 6	35	
Steps		36 6	3 0	0 6	65	
Do.		30 6	2 0	0 6	31	
Do.		24 6	1 0	0 6	12	
Do. near jail	2	5 6	3 0	1 0	33	
						3,494
Deduct—						
Stone in steps						72
Total, Cubic feet						3,422
BRICKWORK IN SUPERSTRUCTURE.						
Court, outer walls		92 0	1 6	13 3	1,829	
Do. dais walls		20 9	1 1½	1 6	35	
Private and property room end walls	3	7 10½	1 1½	8 0	292	
Do. do. half gables	3	7 10½	1 1½	3 0		
Do. do. outer walls		43 1½	1 1½	8 0	388	
Cashier's, sheristadar's and clerk's room, longitudinal walls	2	72 6	1 6	13 3	3,956	
Cashier's, sheristadar's and clerk's room, longitudinal partitions	3	18 0	1 6	13 3		
Cashier's, sheristadar's and clerk's room, longitudinal gables	4	21 0	1 6	3 6	441	
Record room, outer walls		98 0	1 6	12 0	1,764	
Do. gables	2	18 0	1 6	3 0	162	
Treasury and inspector's room, outer walls, including battlement		116 9	1 10½	20 0	4,378	
Treasury and inspector's room, inner walls	2	22 10½	1 10½	15 0	1,624	
Do. do. do.	1	12 0	1 10½	15 0		
Jail wards, outer walls		173 0	1 6	12 0	3,114	
Do. partitions	4	15 0	1 1½	12 0	810	
Do. gables at ends	2	18 0	1 6	3 0	162	
Do. do. for partitions	4	18 0	1 1½	3 0	243	
						19,179

2236/11

Estimate Form—Detail Measurements—*cont.*

Detail of work.	No.	Measurements in Feet. Length.	Breadth.	Depth.	Area or contents.	Total quantity of each description of work.
BRICKWORK IN SUPERSTRUCTURE—*cont.*						
Deductions—						
Doors in treasury	8	4 0	1 10½	8 0	750	
Windows do.	6	4 0	1 10½	6 0		
Archway in treasury square portion	1	12 0	1 10½	4 0	99	
Do. semi-circular do.		56 6	Area.	1 10½	106	
Doors in court, &c.	17	4 0	1 6	8 0	861	
Do. do.	1	4 0	1 6	7 6		
Do. in private and property room	2	4 0	1 1½	7 6	104	
Windows in do.	2	4 0	1 1½	4 0		
Doors in jail	5	4 0	1 6	7 6	225	
Ventilators in jail	7	4 0	1 6	2 0	84	
Record-room windows	18	1 9	1 6	5 6	260	
Archwork as per details					535	
						3,015
Total, Cubic feet						15,182
ARCHWORK.						
Over treasury doors and windows	14	5 0	1 10½	1 1½	148	
Do. arch semi-circular	1	21 6	1 10½	1 6	60	
Over doors in court, &c.	18	5 0	1 6	1 1½	152	
Do. and windows in private and property room	4	5 0	1 1½	1 1½	25	
Over doors and end ventilators in jail	7	5 0	1 6	1 1½	150	
Over record-room windows	18	3 0	1 6	1 1½		
Total, Cubic feet						535
CUT STONEWORK.						
Slabs under posts	48	1 0	1 0	0 6	24	
Steps		143 0	1 6	0 6	72	
Slabs under trusses	22	2 0	1 6	0 4	22	
Total, Cubic feet						118
EARTH FILLING IN BASEMENT.						
Court	1	25 0	18 6	1 6	675	
Dais	1	5 10½	6 9	1 0	40	
Private and property rooms		30 9	7 10½	1 6	363	
Clerk's, sheristadar's, &c., rooms		68 0	18 0	1 6	1,836	
Treasury and verandah	1	21 0	12 0	1 6	378	
Arms and inspector's room	2	22 10½	8 0	1 6	549	
Jail wards		64 0	15 0	1 6	2,340	
Record room	1	40 0	15 0	1 6		
Verandahs		170 0	8 3	1 6	2,104	
Do.		167 0	6 9	1 6	1,440	
Covered way	1	18 0	13 6	1 6	365	
Total, Cubic feet						10,090
TEAKWOOD WROUGHT AND PUT UP.						
Court, clerk, sheristadar's, &c., room—						
Five trusses to span 18 feet. Tie beams	5	21 0	0 4	0 7	20	
Principal rafters	10	11 9	0 4	0 6	20	
Struts	10	5 2	0 4	0 4	6	
Purlins allowing for halving		196 0	0 4	0 6	33	
Wall purlins do.		206 0	0 3	0 4	17	
Ridge do.		94 0	0 3	0 3	18	
Hip rafters for court	5	17 0	0 3½	0 6	17	
Do. for sheristadar's room	2	15 0	0 2½	0 6		
Common rafters, 18 inches centre to centre	102	12 6	0 3	0 4		
Jack rafters for court	48	9 0	0 3	0 4	154	
		Average length.				
Do. for sheristadar's room	20	7 0	0 2	0 4		
		Average length.				
Record-room—						
Three trusses to span 15 feet. Tie beams	3	18 0	0 4	0 6	9	
Principal rafters	6	9 9	0 4	0 5	8	
Struts	6	4 9	0 4	0 4	3	
Purlins (allowing for halving)	2	49 0	0 4	0 5	14	
Wall purlins	2	44 0	0 3	0 3	6	
Ridge	1	53 0	0 3	0 3	9	
Common rafters, 13 inches centre to centre	58	10 9	0 3	0 3	42	
Do. do. at ends	4	12 6	0 3	0 3		
Treasury, inspector and arms' room—						
Joists, 18 inches centre to centre	16	14 0	0 3½	0 3	44	
Do. do.	32	9 6	0 3	0 3	38	

Estimate Form—Detail Measurements—*cont.*

Detail of work.	No.	Measurements in Feet. Length.	Breadth.	Depth.	Area or contents.	Total quantity of each description of work.
TEAKWOOD WROUGHT AND PUT UP—*cont.*						
Jail wards.						
Three trusses to span 15 feet. { Tie beams	3	18 0	0 4	0 6	9	
Principal rafters	6	9 9	0 4	0 5	8	
Struts	6	4 9	0 4	0 4	3	
Purlins allowing for halving	2	75 6	0 4	0 5	21	
Wall purlins do.	2	75 6	0 3	0 3	9	
Ridge	1	75 6	0 3	0 8	13	
Common rafters, 18 inches centre to centre	56	12 6	0 3	0 3	} 76	
Do. do. do.	48	10 9	0 3	0 3		
Covered way.						
One truss to span 15 feet. { Tie beam	1	16 6	0 4	0 6	3	
Principal rafters	2	9 9	0 4	0 5	3	
Struts	2	4 9	0 4	0 4	1	
Purlins	2	20 0	0 4	0 5	6	
Do. over posts	2	20 0	0 4	0 4	4	
Ridge	1	20 0	0 3	0 8	3	
Hip rafters	2	15 0	0 3	0 5	3	
Common rafters	18	12 6	0 3	0 3	} 17	
Jack rafters	8	6 6	0 3	0 3		
Verandah.						
Posts	48	0 6	0 6	7 4	88	
Breastsummers for 9 feet verandah	..	187 0	0 6	0 7½	58	
Do. for 6½ feet do.	..	222 0	0 6	0 6	56	
Hip rafters	4	12 6	0 3	0 6		
Do.	1	18 6	0 3	0 6		
Do.	1	15 6	0 3	0 6	18	
Do.	3	12 6	0 3	0 6		
Ridges	2	11 0	0 3	0 6		
Common rafters for 9 feet verandahs and private and property room 18″ centre to centre.	122	13 6	0 3	0 5		
Jack rafters for do. do.	24	5 6 Average length.	0 3	0 5		
Do.	4	7 6 Average length.	0 3	0 5	} 199	
Do.	12	8 6	0 3	0 5		
Common rafters for 6½′ verandah 18″ centre to centre	102	10 0	0 3	0 4	} 98	
Jack rafters	28	5 6	0 3	0 4		
Boarding at ends of Jail.						
Verandahs	2	8 0	0 1	3 0	4	
Barge boards for jail and record room gables	6	13 0	0 1	0 9	5	
Do.	6	3 0	0 1	1 0	2	
Do. collar piece	3	9 0	0 3	0 4	2	
Barge boards for finials	3	6 6	0 3	0 3	1	
Do. do.	3	1 0	0 8	0 8	1	
Do. do.	6	4 0	2 0	0 1¼	5	
Front Verandah gables.						
Barge boards	4	7 6	0 1	0 7½	2	
Collar pieces	2	7 0	0 2	0 4	1	
Finials	2	6 0	0 3	0 3	1	
Planks	2	2 6	0 1¼	1 6	1	
Weather boards for Jail.						
Brackets	4	3 6	0 2	0 2½		
Struts	4	3 0	0 2	0 2½	} 1	
Breastsummers	2	6 0	0 2	0 2½		
Rafters	8	4 6	0 1½	0 2	1	
Planks including overlap	12	6 3	0 3¾	0 9	4	
Total, Cubic feet	..	..	..	..	..	1,185
VENETIAN AND PANEL DOORS WITH FRAMES COMPLETE.						
Outer doors of court, clerk's, sheristadar's, &c., rooms	11	4 0	..	8 0	352	
Private room	1	4 0	..	7 6	30	
Total, Square feet	..	..	..	..	..	382
PANELLED DOORS WITH FRAMES.						
Inner doors of court, clerk's, sheristadar's, &c., room	6	4 0	..	8 0	192	
Do. do. do.	1	4 0	..	7 6	30	
Total, Square feet	..	..	..	..	..	222

2286/12

Estimate Form—Detail Measurements—*cont.*

Detail of work.	No.	Measurements in Feet. Length.	Breadth.	Depth.	Area or contents.	Total quantity of each description of work.
WROUGHT IRON GRATED DOORS WITH WOODEN FRAMES.						
For jail wards	5	4 0	..	7 6	150	
Treasury, &c.	8	4 0	..	8 0	256	
Total, Square feet	..	..	..	..	..	406
Strong battened shutters for treasury doors without frames	4	3 6	..	7 6	105	Sq. ft.
Strong battened door with frame for property room	1	4 0	..	7 6	30	Sq. ft.
VENETIAN WINDOWS WITH FRAMES AND IRON BARS.						
For private and property room	2	4 0	..	4 0	32	Sq. ft.
BATTENED WINDOWS WITH FRAMES AND IRON BARS.						
For arms and inspector's room	6	4 0	..	6 0	144	
For record room	18	1 9	..	5 6	173	
Total, Square feet	..	..	..	..	..	317
Teak frames with iron bars for jail ventilators	7	4 0	..	2 0	56	Sq. ft.
WROUGHT IRON WORK IN TRUSSES.						
1″ diar. king rods for 18 feet trusses	5	8 0	= 40 0	× 2·62	= 105	
1″ hex. nut and bolt head for do.	15	..	..	× 1·10	= 17	
3″ diar. ¼″ thick washers for do.	10	..	..	× 0·32	= 3	
1½″ × ½″ heel straps for do.	10	2 9	27 6	× 2·50	= 69	
1½″ × ½″ bearing plates for 18 feet trusses	10	0 6¾	= 5 3¾	× 2·50	= 13	
⅞″ hex. nuts for do. do.	20	..	..	× ·267	= 5	
Caps of ⅜″ plate 6″ wide	5	2 0	= 10 0	× 7·51	= 75	
7″ diar. kingrod for 15 feet trusses	7	6 7½	= 46 4½	× 2·01	= 93	
⅞″ hex. nut and head for trusses	21	..	..	× 0·73	= 15	
3″ diar. ¼″ thick washers for trusses	14	..	..	× 0·32	= 4	
1½″ × ⅜″ heel straps for trusses	14	2 3	= 31 6	× 1·87	= 58	
1½″ × ⅜″ bearing plate for trusses	14	0 6¾	= 7 10½	× 1·87	= 15	
⅞″ hex. nut for trusses	28	..	..	× ·267	= 7	
Caps of ⅜″ plate 6″ wide	7	1 6	= 10 6	× 7·51	= 79	
Total, lb.	..	..	..	..	..	558
TERRACE ROOFING.						
For treasury, inspector's and arms' rooms	..	32 9	..	23 10½	782	Sq. ft.
Squares	..	..	..	..	..	7·82
TILED ROOFING.						
Court room	..	28 0	..	26 0	} 2,808	
Clerk's, sheristadar's, &c., rooms	..	80 0	..	26 0		
Record room	..	49 0	..	23 0	1,127	
Jail	..	74 6	..	24 6	1,825	
Covered way	..	15 3	..	25 0	381	
Verandah 9 feet wide	..	210 0	..	12 0	2,520	
Do. 6½ do.	..	182 0	..	9 0	1,638	
Square feet	..	..	..	..	..	10,299
Total, Squares	..	..	..	..	..	103
FLOORING WITH 8″ SQUARE BRICKS.						
Court	1	25 0	..	18 0	450	
Private room	1	7 10½	..	18 9	} 242	
Property room	1	7 10½	..	12 0		
Clerk's, sheristadar's, &c., room	..	68 0	..	18 0	1,244	
Treasury and verandah	..	22 10½	..	12 0	} 641	
Inspector's and arms' room	2	22 10½	..	8 0		
Covered way	1	18 0	..	15 0	270	
Verandah 9 feet wide	..	175 0	..	9 0	1,575	
Do. 6½ do.	..	167 0	..	6 6	1,086	
Door pieces	18	4 0	..	1 6	108	
Do.	8	4 0	..	1 10½	60	
Do.	2	4 0	..	1 1½	9	
Square feet	..	..	..	..	..	5,685
Total, Squares	..	..	..	..	..	56·85

Estimate Form—Detail Measurements—*cont.*

Detail of work.	No.	Measurements in Feet. Length.	Breadth.	Depth.	Area or contents.	Total quantity of each description of work.
Flooring record room and jail with asphalte ½" thick over a bed of concrete.						
Record room	1	40 0	..	15 0	1,560	
Jail	1	64 0	..	15 0		
Door pieces	5	4 0	..	1 6	30	
Square feet	..	..	..	..	..	1,590
Total, Squares	..	..	..	..	..	15·90
Plastering interior (two coats).						
Court	..	86 0	..	13 3	1,140	
Private room	..	53 3	..	10 6	559	
Property room	..	19 10½	..	8 0	159	
Do.	2	7 10½	..	10 6	165	
Do.	1	4 1½	..	13 3	55	
Clerk's, sheristadar's, &c., room	..	280 0	..	13 3	3,710	
Gables	9	18 0	..	3 0	486	
Record room	..	110 0	..	12 0	1,320	
Gables	2	15 0	..	2 6	75	
Treasury	..	54 0	..	14 0	3,073	
Do. verandah	..	42 0	..	14 0		
Inspector's and arms' room	2	61 9	..	14 0	3,336	
Jail wards	..	278 0	..	12 0	375	
Do. gables	10	15 6	..	2 6	510	
Door jambs and soffits	17	20 0	..	1 6	29	
Do. do.	1	19 0	..	1 6	300	
Do. do.	8	20 0	..	1 10½	43	
Do. do.	2	19 0	..	1 1½	143	
Do. do.	5	19 0	..	1 6	51	
Arch do.	..	27 0	..	1 10½	225	
Window do.	6	20 0	..	10½	36	
Do. do.	2	16 0	..	1 1½		
Do. do.	18	14 6	..	1 6	488	
Ventilator jambs	2	12 0	..	1 6		
Do.	5	8 0	..	1 6		16,278
Deductions—					1,024	
Doorways	32	4 0	..	8 0	270	
Do.	9	4 0	..	7 6	48	
Archway, square portion	1	12 0	..	4 0	57	
Do. semi-circular portion	1	56 6	Area.	..	32	
Windows	2	4 0	..	4 0	144	
Do.	6	4 0	..	6 0	174	
Do.	18	1 9	..	5 6	56	1,805
Ventilators	7	4 0	..	2 0		14,473
Square feet	..	..	..	..	..	144·73
Total, Squares	..	..	..	..	..	
Pointing exterior.						
Court	..	50 9	..	13 3	3,028	
Clerk's, sheristadar's, &c., rooms	..	177 9	..	13 3	467	
Property and private room	..	62 3	..	7 6	54	
Do. half gables	2	9 0	..	3 0	1,212	
Record room	..	101 0	..	12 0	54	
Do. gable	1	18 0	..	3 0	2,671	
Treasury and inspector's, &c., rooms	..	124 3	..	21 6	546	
Do. inside parapet	..	109 3	..	5 0	2,148	
Jail wards	..	179 0	..	12 0	108	
Do. gables	2	18 0	..	3 0	1,218	11,506
Basement all round	..	609 0	..	2 0		
Deduct—					512	
Doorways	16	4 0	..	8 0	210	
Do.	7	4 0	..	7 6	48	
Archway, square portion	1	12 0	..	4 0	57	
Do. semi-circular portion	1	56 6	Area.	..	32	
Windows	2	4 0	..	4 0	144	
Do.	6	4 0	..	6 0	174	
Do.	18	1 9	..	5 6	56	
Ventilators	7	4 0	..	2 0	336	1,562
End wall, cashier's room	1	21 0	..	16 0		9,937
Square feet	..	..	..	..	..	99·37
Total, Squares	..	..	..	..	..	
					Per foot lb.	lb.
Lead sheeting for roof valleys	..	184 0	1 6	× 276	× 5	1,380
Mouldings over windows for inspector's and arms' room.	6	6 0	..	..	36	L. ft.

2286/13

Estimate Form—Detail Measurements—*cont.*

Detail of work.	No.	Measurements in Feet. Length.	Breadth.	Depth.	Area or contents.	Total quantity of each description of work.
Coping for treasury	..	..	..	125	L. ft.	
Railing for dais	..	..	..	23	,,	
Finials over court	..	..	2 in number.			
Painting with three coats of Carson's paint.						
Venetian and panel doors	3	382 0	..	..	1,146	
Panelled doors	2	222 0	..	..	444	
Wrought iron grated doors	2	406 0	..	..	812	
Batten shutters	2	105 0	..	..	210	
Do. do.	2	30 0	..	..	60	
Do. windows	2	317 0	..	..	634	
Ventilators	2	56 0	..	..	112	
Roof timbers including weather boards, &c.	..	..	..	..	11,972	
Square feet	..	..	..	..	..	15,390
Total, Squares	..	..	..	..	..	154
Add extra labor in finishing bargeboards and finials.	..	..	5 in number.			
Punkah 10 feet long	..	..	1 ,,			

Estimate Form—Abstract.

Quantity.	Description of work.	Rate.	Per	Amount.	Total.
		Rs.		Rs.	Rs.
20,632 C. feet	Excavation for foundation	..	1,000 C. feet.		
7,019 ,,	Concrete in foundation	..	100 C. feet.		
5,843 ,,	Brickwork in foundations	..	,,		
3,422 ,,	Do. in basement	..	,,		
16,182 ,,	Do. in superstructure	..	,,		
535 ,,	Archwork	..	C. feet.		
118 ,,	Cut stonework	..	1,000 C. feet.		
10,090 ,,	Filling in basement	..	C. feet.		
1,185 ,,	Teakwood wrought and put up	..	Square feet.		
382 Sq. feet.	Venetian and panel doors with frames	..	,,		
222 ,,	Panelled doors with frames	..	,,		
406 ,,	Wrought iron grated doors with teak frames	..	,,		
105 ,,	Strong battened shutters for treasury doors without frames	..	,,		
30 ,,	Strong battened door with frame for property room	..	,,		
32 ,,	Venetian windows with frames and iron bars	..	,,		
317 ,,	Battened do. do.	..	,,		
56 ,,	Teak frames with iron bars for jail ventilators	..	,,		
558 lb.	Wrought iron work in trusses	..	lb.		
7·82 Squares.	Terrace roofing	..	Square.		
103 ,,	Tiled roofing with flat and pan tiles including teak reepers	..	,,		
56·85 ,,	Flooring with 8-inch square pavement tiles	..	,,		
15·90 ,,	Flooring record room and jail with asphalte ½ inch thick over a bed of concrete	..	,,		
144·73 ,,	Plastering interior (two coats)	..	,,		
99·37 ,,	Pointing exterior	..	,,		
1,380 lb.	Lead sheeting for roof valleys	..	lb.		
36 L. feet.	Mouldings over windows	..	L. feet.		
125 ,,	Coping for treasury parapet	..	,,		
23 ,,	Hand railing for dais	..	,,		
2 in No.	Finials over court	..	Each.		
154 Squares.	Painting with three coats of Carson's paint	..	Square.		
5 in No.	Add extra labor in finishing barge boards and finials	..	Each.		
1 ,,	Punkah 10 feet long	..	,,		
..	Petty supervision	..	..	..	
..	Contingencies	..	..	..	

MADRAS,
25th April 1887.

(Signed) J. W. BRASSINGTON,
Offg. Consulting Architect to Government.

TAHSILDAR'S CUTCHERRY.

Descriptive Specification.

Foundations.—A depth of 4 feet 6 inches is provided in the quantities, but this should be settled locally in accordance with the nature of the soil.

Walling.—The walls should be carried up in English bond, walls of treasury 2½ bricks thick, court, offices, record room and outer walls of jail 2 bricks thick, jail partitions and verandah rooms near court 1½ bricks. Verandah retaining walls 1 brick thick, except under posts which will be half a brick thicker.

Stonework.—Stone slabs 12″ × 12″ × 6″ with mortice holes 2 inches square and 2 inches deep cut into them into which the verandah posts will be tennoned.

Slabs will also be placed at the bearings of trusses. The steps may also be of stone, if procurable without great expense.

Woodwork.—The doors, windows, weather boards, verandah posts and trusses should be of well-seasoned teakwood, the rafters and other minor roof timbers may be of approved country wood.

Roofing.—The roof of the treasury, arms, and inspector's room will be of pucka terrace. The rest of the building will be covered with flat and pan tiles; if the quality of these are good the usual unsightly "chunam bands" might be dispensed with; all valleys should be protected with sheet lead.

Flooring.—The floor may be of square bricks or stone slabs if the latter are easily procurable. Jail wards and record room floors to be asphalted.

Interior and exterior finishing.—The interior walls will be fine plastered with shell lime or plastered and washed. Where good bricks are obtainable the exterior should be pointed.

Where the soil is damp the space below the flooring should be filled with river sand to a depth of 1 foot at least and the interior walls plastered with Portland cement ½ an inch thick to a height of 3 feet all over above floor level. The exterior plinth should also be plastered with cement.

Finials.—The finials may be of copper, iron or wood.

The different kinds of work to be done will be executed in conformity with the standard specification of the Public Works Department.

(Signed) J. W. BRASSINGTON,
Offg. Consulting Architect to Government.

CHEPÂK,
25th April 1887.

2236/14

1ST SEPTEMBER 1887, No. 2349 W., PUBLIC WORKS.

GOVERNMENT OF MADRAS.

PUBLIC WORKS DEPARTMENT.

General.
Account.

READ—the following letter from C. J. PETERS, Esq., Superintending Engineer, III Circle, to the Chief Engineer, Public Works Department, dated Bellary, 15th August 1887, No. 839:—

With reference to G.O., No. 1835 W., dated 8th July 1887, I have the honor to report that a sum of Rs. 10,000 may, as a temporary measure, be transferred from the grant for the Collector's Cutcherry at Cuddapah—item No. 3 final budget of 1887-88—to the Tahsildar's office at Rájampet, provided that the above amount may again be granted to the Collector's Cutcherry at Cuddapah when funds have become available.

ORDER—dated 1st September 1887, No. 2349 W., Public Works.

The following transfer of funds is sanctioned:—

From.	RS.	*To*	RS.
(1) Collector's office at Cuddapah ...	10,000	(2) Tahsildar's office at Rájampet ...	10,000

2. Any additional allotment that may hereafter be found necessary for item 1 will, if feasible, be provided if applied for later in the year.

(True Extract.)

(Signed) J. O. HASTED, Colonel, R.E.,
Secretary to Govt., P.W.D.

To the Superintending Engineer, III Circle.
" Examiner, Public Works Accounts.
" Revenue Department.

Exd. W. H. French.
Spare Copies.

GENERAL.
ACCOUNT.

Govt. of {1887} Madras.

PUBLIC WORKS.

Dated September, 1*st*.

Recd. *Encl*

G. O ., 1st Sept. 1887, No. 2349 W.

SEPTEMBER.

Transfer of Funds

Certain — from the Collector's office at Cuddapah to the Tahsildar's office at Rájampet, sanctioned.

2286/15

7TH MAY 1888, No. 1336 W., PUBLIC WORKS.

GOVERNMENT OF MADRAS.

PUBLIC WORKS DEPARTMENT.

Buildings and Roads.
Civil Works.

READ—the following papers:—

G.O., dated 7th April 1888, Mis. No. 2084, Revenue.

Read—the following Proceedings of the Board of Revenue (Land Revenue), dated 19th March 1888, Mis. No. 1822:—

Read—the following letter from Col. H. SMALLEY, R.E., Superintending Engineer, III Circle, to the Collector of Cuddapah, dated Bellary, — February 1888:—

With reference to G.O. No. 457, dated 11th May 1887, in the Revenue Department, I have the honor to forward, for transmission to Government for sanction, an estimate of Rs. 24,838 for constructing a first-class taluk office with out-houses at Rájampet, in accordance with the standard design approved in G.O. No. 1495 W., dated 3rd June 1887.

No. 1152.

Submitted to Government through the Secretary to the Commissioner of Land Revenue, with the enclosures, in original.

(Signed) G. KOTHUNDA RAMAYYA,
for Ag. Collector.

15th February 1888.

Resolution—dated 19th March 1888, Mis. No. 1822.

The estimates received with the foregoing letter for the construction of a taluk cutcherry at Rájampet, at a cost of Rs. 24,838, are submitted to Government with reference to G.O., dated 11th May 1887, No. 457.

2. The Collector is requested to state why the plan called for in para. 2 of the Government Order has not been submitted.

(True Extract.)

(Signed) R. S. BENSON,
Acting Secretary.

To the Secretary to Government, Revenue Department,
with letter and enclosures, in original.

Order—dated 7th April 1888, Mis. No. 2084, Revenue.

The estimate is approved and transferred to the Public Works Department.

(True Extract.)

(Signed) J. F. PRICE,
Secretary to Government.

Note by the Chief Engineer, Public Works Department.

The foundations should be of stone throughout.

The rates for brick-work, plastering, honey-comb work and tarring are in excess of the schedule rates for the division, and should be reconsidered.

The provision for scaffolding and a store-shed should be met from the lump sum allowed for contingencies, which have been calculated at 5 per cent. on the estimate.

No information is given regarding land compensation.

With these remarks, the plan and estimate are submitted for the sanction of Government.

ORDER—dated 7th May 1888, No. 1336 W., Public Works.

The estimate, amounting to Rs. 24,838, for constructing a first-class taluk office at Rájampet, in the Cuddapah district, is sanctioned.

2. A sum of Rs. 10,000 has been provided for the work in the current year's budget.

3. Attention is drawn to the Note by the Chief Engineer, Public Works Department, above recorded.

4. The sanction accorded in para. 1 of these Proceedings has been registered as Provincial No. 17 W. of 1888-89, and classified as Civil Buildings, Original Works.

(True Extract.)

(Signed) J. O. HASTED, Colonel, R.E.,
Secretary to Govt., P.W.D.

To the Superintending Engineer, III Circle, with four enclosures.
" Examiner, Public Works Accounts, with the duplicate general abstract estimate.
" Revenue Department.

Exd. F. R. Bantleman.
Spare Copies.

BUILDINGS AND ROADS.
CIVIL WORKS.

Govt. of {1888} Madras.

PUBLIC WORKS.

Dated May, 7th.

Read. *Encl.*

G.O., 7th May 1888, No. 1336 W.

MAY.

Taluk Office at Rajampet

Estimate for constructing a first-class — in the Cuddapah district, sanctioned.

2236
17

GOVERNMENT OF MADRAS.

PUBLIC WORKS DEPARTMENT.

Buildings and Roads.
Civil Works.

READ—the following paper:—

Proceedings of the Board of Revenue (Land Revenue), dated 25th April 1888, Mis. No. 2646.

HON'BLE W. S. WHITESIDE.

Read—the following letter from Colonel H. SMALLEY, R.E., Superintending Engineer, III Circle, to the Collector of Bellary, dated Bellary, 9th April 1888, No. 60:—

I have the honor to forward, for your countersignature and transmission to Government for sanction, an estimate, amounting to Rs. 24,862, for constructing a first-class taluk office at Kúdligi on the standard plan approved in G.O. No. 1495 W., dated 3rd June 1887.

2. An estimate, amounting to Rs. 31,520, was approved for this work in G.O. No. 401, dated 31st May 1886, in the Revenue Department, but the estimate was returned in the Public Works Department for revision in accordance with the standard design above referred to.

Submitted to Government for sanction through the Board of Revenue (Land Revenue).

17th April 1888. (Signed) H. ST. A. GOODRICH,
Collector.

Resolution—dated 25th April 1888, Mis. No. 2646.

The site-plan and the revised estimate for constructing a first-class taluk cutcherry at Kúdligi, at a cost of Rs. 24,862, are submitted for the sanction of Government and the provision of funds in the budget of the Public Works Department.

(True Extract.)

(Signed) H. A. SIM,
Ag. Secretary.

No. 2866, Revenue.

Approved and transferred to the Public Works Department.

OOTACAMUND,
15th May 1888. (Signed) J. F. PRICE,
Secretary to Government.

ORDER—dated 7th June 1888, No. 1681 W., Public Works.

The estimate for constructing a first-class taluk office at Kúdligi, in the Bellary district, reduced to Rs. 23,871 by omission of the cost (Rs. 991) of a ryot's shed, is sanctioned.

2. It is not intended that ryot's sheds should be built in connection with taluk cutcherries on the revised standard plan.

3. The Superintending Engineer will report what sum can be spent on the work during the current official year.

4. This sanction has been registered as Provincial No. 34 W. of 1888-89, and classified as Civil Buildings, Original Works.

(True Extract.)

(Signed) J. O. HASTED, Colonel, R.E.,
Secretary to Govt., P.W.D.

To the Superintending Engineer, III Circle, with six enclosures.
" Examiner, Public Works Accounts, with duplicate abstract estimate.
" Revenue Department.

Exd. F. R. Bantleman.
Spare Copies

BUILDINGS AND ROADS.
CIVIL WORKS.

Govt. of {1888} Madras.

PUBLIC WORKS.

Dated June, 7th.

Recd. *Encl.*

G.O., 7th June 1888, No. 1681 W.

JUNE.

Taluk office at Kudligi

Estimate for constructing a first-class —, in the Bellary district, sanctioned with remarks.

(28)

1922
2236/19

Tow

For orders whether the preparation of the estimate called for shall stand over until the proposed new standard plan has been published.

C.
10.3.87

The new standard design must be awaited.

[illegible]
10/3/87.

[illegible]
10/3/87

2236/20

2236/20

Revenue Department.

PROCEEDINGS OF THE MADRAS GOVERNMENT.

READ again G.O. dated 11th October 1886, No 6023 Misc:

* Copy attached

Read also Proceedings of the Board of Revenue, dated 6th December 1886, No 2649.

Order thereon, 5th March 1887, No 238.

Government accept the Collector's recommendation which is strongly supported by the Board; but before passing final orders, enquiry will be made in the Judicial Department as to whether any objection exists on Police grounds to the taluk head quarters being fixed at Rajampet.

2. Meanwhile, orders will issue in the Public Works Department for the preparation of a plan and estimate for the construction of a taluk Cutcherry

Dated 9.3.88.

PWC № 1922

Cutcherry at the site specified in para 3 of the Collector's letter, dated 28th November last. It will also be considered in the Public Works Department whether provision cannot be made in the budget for 1887-88 for the commencement of the work.

(True Extract)
Redacted
Ag. Secretary to Govt

To
The Board of Revenue
Judicial Deptt
Public Works Deptt X

2234/21

PUBLIC WORKS DEPARTMENT.

PROCEEDINGS OF THE MADRAS GOVERNMENT.

UNDER date the

READ the following

Proceedings, Revenue Department No. № 238 d/ 5th March 87.

Communicated to
the Supty: Engr: III Circle
in continuation of G.O. No.
2740. W d/ 18th October 1886.

2. A revised standard design for taluk offices is now under preparation, and on its publication, the Supty: Engineer will submit an estimate for a taluk office at Rajampet on the site selected.

3. The question of providing funds for the work

work will be considered
on receipt of the estimate.

McN
23.3.87

Jd
20/3/87

2740 … 18.10.86.
1960 … 7.8.86
1526 … 16.6.86
1207 … 22.8.85
338 … 13.2.85.

No 906 W of …

B …
7 – 24/3/87

S.E. III Circle
~~Ex … works~~
Rev. Dept.

Cn Jd … 28/3 …

2286/22

Superintending Engineer's Office,
3RD CIRCLE
Bellary 2d March 1888.

No. 2479

FROM Col: H.C. Smalley R.E.
~~THE~~ SUPERINTENDING ENGINEER,
IIIRD CIRCLE.

TO
THE Chief Engineer
P.W. Department
Madras

SIR,

I have the honor to request that the following reappropriation of funds under Provincial Civil Buildings Original Works may be sanctioned

Enclosures.

From	amount not required	To	amount required
Tahsildar's Office at Rajampett G.O. no. 2349 Wd/1st September 1887.	7,300	Collector's Office at Cuddapah	7,300

Of the grant of Rs 10,000, more than Rs 2700 cannot be spent on the work as cholera is still so bad at Rajampett that no labor can be kept there.

I have the honor, to be
Sir
Your most Obedient Servant
H Smalley Col R.E.
Superintg Engineer 3d Circle

N
… 3.88.

PWC No. 2165

4.68 W – 8 – 2 – 88
14 W – 14 – 1 – 88
15-22 W – 7 – 6 – 87
15-30 W – 8 – 6 – 87
90 W – 24 – 6 – 87
27.60 W – 15 – 10 – 86
19.68 W – 7 – 8 – 86
15-60 W – 6 – 6 – 86
1207 W – 22 – 5 – 85
338 W – 13 – 2 – 88
1835 W – 8 – 7 – 87
2349 W – 1 – 9 – 87
2704 W – 13 – 10 – 87
345-7 W – 17 – 02 – 88
3166 W – 22 – 11 – 87

From The Superintending Engineer, IIIrd Circle.

To The Chief Engineer P.W.D. Madras

Dated 2d March 1888.
Received 6-3-88

Enclosures.

No. 779 W. a/8th March/88
4.68 W a/8-2-88

No. 2479.
Provincial Civil Buildings
Original works.
Requesting sanction for certain reappropriation of funds under

B

PUBLIC WORKS DEPARTMENT.

2236/13

No. 779 W

PROCEEDINGS OF THE MADRAS GOVERNMENT.

UNDER date the 8th March 88

READ the following

From the Supty. Engineer III Circle No. 2479 dt 2nd March 1888.

The following transfer of funds is sanctioned:-

Provincial
Civil Buildings.
Original Works.

Rs.

Tahsildar's office at Rajampet Rs. 7,300 Collector's office at Cuddapah Rs. 7,300

WOM
6.3.88
6/3/88

To
The Supty. Engr. III Circle
" Examiner of P. W. Accts
" Revenue Department.

Dated 9.3.88.

2231/24

PROCEEDINGS OF THE MADRAS GOVERNMENT.

READ the following ~~letter~~

Proceedings of the Board of Revenue dy. 9th July 86. No. 5087, on letter from the Asst. Collector of Cuddapah dy. 25th June 86. No. 541.

In continuation of my letter No. 490 dy. 12th Instant, I have the honor to state that the Executive Engineer Cuddapah reports that an estimate for Rs. 1144 for repairing the Record Room of the Budvel taluq Cutchery, was already sanctioned by Govt. in their order No. 338 R dated 13th February 1885, but that no funds have been as yet provided.

He also reports that an estimate for the construction of a new taluk Cutchery at Voyalpad - the present one there, he says, is the worst in the District - has long been sanctioned and that grants for two consecutive years have been withdrawn on account of financial pressure.

I have the honor therefore strongly to press on the Board the necessity of having funds placed at

2036/25

rat the disposal of the Public Works Department for the above works as soon as possible. The state of the public offices in this district as a disgrace to the administration. It is not in one or two places only that proper public offices are wanted, the difficulty is to find any where in the district a public office possessing the requirements of such a building. As regards the stability of the taluk Cutcheries of Bardoli and Pullampet, Mr. Johnston promised to submit a special report, which will be forwarded on receipt.

Resolution.

Para 1 will be ordered to lie over pending receipt of a reply to Board's reference dated 22nd June 1886 on Secret Register Nr. 3011.

Paras 2 and 3 will be submitted for the information of Government; funds will nevertheless be provided when available.

Order thereon, 26th July 1886, Nr. 4414.

The question of providing funds for

for the taluk Cutchery at Vayalpad for which an estimate has been already sanctioned (G.O. dated 22nd May 1885 Nr. 1207 M) will receive early consideration in the Public Works Department.

2. As regards the record room of the taluk Cutchery at Bardoli, the Board will be referred to G.O.s dated 10th and 25 June 1886 Nos. Nr. 3811 and 3762, from which they will see that the construction of a new Cutchery at that place has been decided upon, and that it has been ordered that this work shall take precedence of other buildings elsewhere. This renders the repair of the present record room unnecessary. The Board will in communication with the Collector settle as to any temporary arrangement that may be necessary for the accommodation of the records in the meantime.

True Extract
W. Stokes
Secy to Govt.

To The Board of Revenue
" Mr. Prentice

2236/26

11th May 1887, No. 457, Revenue.

GOVERNMENT OF MADRAS.

REVENUE DEPARTMENT.

Read—again G.O., dated 5th March 1887, No. 238, Revenue.

Abstract.—Accepting the Collector's recommendation for the transfer of taluk head-quarters from Pullampet to Rájampet in the Cuddapah district, and asking for the opinion of the Judicial Department whether any objection exists on police grounds; requesting the Public Works Department to issue orders for the preparation of a plan and estimate for the construction of a cutcherry at the site in question.

Read—the following G.O., dated 9th April 1887, No. 765, Judicial :—

Read—G.O., dated 5th March 1887, No. 238, Revenue.

Read—also the following letter from the Inspector-General of Police, dated 24th March 1887, No. 1388 :—

Adverting to endorsement of the Under Secretary to Government, Judicial Department, dated 12th March 1887, on G.O., No. 238, of the 5th idem, Revenue Department, I have the honor to say that from a police point of view there is no objection to the proposed transfer of taluk head-quarters from Pullampet to Rájampet.

Order—dated 9th April 1887, No. 765, Judicial.

Communicated to the Revenue Department, with reference to their Proceedings, dated 5th March 1887, No. 238.

(True Extract.)

(Signed) W. S. MEYER,
for Under Secretary.

To the Revenue Department.

Order—dated 11th May 1887, No. 457, Revenue.

Miscellaneous.

His Excellency the Governor in Council is pleased to sanction the transfer of the head-quarters of the Pullampet taluk to Rájampet.

2. With reference to G.O., No. 906-W., dated 24th March 1887, the Public Works Department will, now that the revised standard design for taluk offices has been settled, be requested to issue orders for the early preparation of the plan and estimate for the taluk cutcherry at Rájampet, in order that, if possible, the work may be commenced during the current year.

3. The consideration of the question of moving the head-quarters of the Deputy Tahsildar from Chitvél to Kódúr, which the Collector has raised in his letter No. 976, dated 25th November 1886, recorded in the G.O. read at the head of these Proceedings, may lie over until the new taluk cutcherry has been built and is occupied. Government are not aware of any proposal to build new offices at Chitvél.

(True Extract.)

Ag. Secretary to Government.

To the Commissioners of Land Revenue.
" the Public Works Department.
" the Judicial Department.

Exd. W. H. French.

75 Copies.

B. No 906 W. of 24.3.87
" 2740 W. " 18.10.86
" 1968 W. " 7.8.86
" 1526 W. " 16.6.86
G.O. 1207 W. " 22.5.85
" 338 W. 13.2.85
B

No. 1530 W. of 8th June 87

Communicated to the Supdg. Engr. III circle in continuation of G.O. No 906 W dated 24th March 1887 in view to the early submission of the required plan and estimate.

2. The S.E. will report what amount can be expended on the work during the current official year.

1.6.87

2/6/87

S.E. III C. 9/6/87

8.6.87

8/6

P.W.C. No. 4130

Govt. of {1887} Madras.

REVENUE.

(9)

24.6

Issued

Recd. 1.6.87

Encl.

G.O., 11th May 1887, No. 457.

No. 1530 W. of 8th June 87

5

MAY.

Taluk Head-quarters.

Sanctioning the transfer of the — from Pullampet to Rájampet, Cuddapah district, and requesting the Public Works Department to issue orders for the preparation of the plan and estimate of the cutcherry.

2 copies to ...

DW

No. 548

Superintending Engineer's Office,
3RD CIRCLE
Camp Anantapur ~~Bellary~~ 25 June 1887.
Despd 29

2236/27

FROM,
C. J. Peters Esquire
~~THE~~ SUPERINTENDING ENGINEER,
IIIRD CIRCLE.

TO,
THE Chief Engineer
P. W. Department
Madras

Enclosures.

SIR,

With reference to para 2 of G.O. No. 1530 W d/ 8th June 1887, I have the honor to report that the Executive Engineer states that he can arrange to spend Rs 10,000, on the Tahsildar's Office at Rajampett, provided that he is allowed to collect materials at once, and that the land chosen (for the building) by the Collector is transferred at an early date.

2. The plan and estimate for the building will be submitted on the receipt of the revised standard plan for Taluq Offices.

I have the honor to be
Sir
Your most Obedient Servant

C. J. Peters
Superintending Engineer
3d Circle

B. Wo 1530W 8.6.87 G.6 - 1207W - 22.5.85
" 906W - 24.3.87 " 338W. 13.2.85
" 2740W - 18.10.86
Revenue G. 238. 5.3.87
B. Wo 1968W. 7.8.86
" 1376W. 16.6.86

B/ No. 1835 W d/ 8th July /87

As no funds are available at present, the Supdg Engineer will, if feasible, propose transfer of funds from the grants for other works in the Circle. In the meanwhile he is authorised to collect the required material and pay for them in anticipation of funds being provided hereafter.

2. The necessary orders transferring the site in question will issue in the Revenue dept.

3. The revised standard plan for taluq offices will issue shortly.

1.7.87

4/7/87

SE III Circle
Ex PW Accts
Revenue dept

5/7

G. 1.7.87. R. 2.7.87.
G. 1.6.87. R. 6.6.87.

P.W.C. No. 4957

(2)

From,
The Superintending Engineer,
IIIrd Circle.

To,
The Chief Engineer P.W.D. Madras

GOVERNMENT OF MADRAS
5 JUL 87
REVENUE DEPARTMENT

Dated 25 / Received 29 } June 1887.

Enclosures.

No. 1835 W d/ 8th July /87

No. 548

Thasildar's office at Rajampett

Reporting that the Exec Engineer states that he can arrange to spend Rs 1000 on the work if he is allowed to collect materials at once and the site transferred at an early date.

With orders.

Revenue Dept.
Pros: of the Madras Govt
Read the folg:—

Board of Revenue, 17th May 1886, No. 1102.

2038 / 28

PROCEEDINGS OF THE BOARD OF REVENUE.

Read—the following letter from W. J. H. LE FANU, Esq., Collector of Cuddapah, to the Secretary to the Board of Revenue, dated 25th March 1886, No. 240:—

I have the honor to draw the attention of the Board to the need for a new taluk cutcherry at Pullampet.

2. The history of the housing of the taluk office at that station is as follows. Up to 1868-69 the office was held in a hut in the bazaar. A cutcherry of stone and chunam was built and finished in 1869, and the office moved there. In October 1874 part of the ceiling fell down, and the tahsildar and clerks rushed out of the building. They had scarcely got out when the whole building collapsed like a house of cards. On the authority, as I am informed, of the Head Assistant Collector the office was then located in the public bungalow, where it now is.

3. That building is wholly unsuited for the purpose. It contains the usual two small rooms, with dressing-rooms and bath-rooms adjoining. Part of one room is railed off for the treasury, and the rest just accommodates the cash gumastah and shroff. The other room contains the records. A bath-room and dressing-room form the subsidiary jail and treasury guard-room, the other dressing-room and bath-room accommodating some of the gumastahs; but, the space being insufficient, the rest of them have had to overflow into the verandah, which they share with the stamp-vendor. The Board will observe that the tahsildar and sheristadar are not provided for, and that the jail accommodation is not in accordance with the recommendations of the Jail Committee of 1866.

4. An attempt has been made to remedy this. Another building was erected, with terraced roof, at an estimate of Rs. 539, as I am told, to accommodate the tahsildar and the correspondence clerks. This was built in 1882-83. The estimate, as I conclude from the sum spent on the Sub-Registrar's office, should have come to a good Rs. 2,500, and it was preposterous to expect to get good value for the money. I am further told that a late tahsildar spent Rs. 120 on it out of his own pocket. The result, however, is that this building, within three years of its construction, is in ruins. In fact it is so dangerous and rotten, roof and walls together, that it is not safe to enter it for inspection.

5. Encouraged by the success of the latter building, an estimate for Rs. 800 was sanctioned to build a record-room and another sum of Rs. 1,000 to build a sub-jail of three cells, which, even if otherwise satisfactory, would not meet the requirements of the Sub-Jail Committee. These buildings were reared in 1884-85, and are supposed to be completed. On the former Rs. 643-12-8 were spent, and on the latter Rs. 567. Charge has not been taken of them; but the tahsildar, perforce, is using a room in the former building, the roof of which is shaky. As to the other, the roof is shaky and breaking; the reapers are too light; the tiles and chunam are too heavy, as also the bressumers; the walls over the doors and windows are deeply cracked, and, in my opinion, the building should be taken down rather than patched up.

6. Instead of any further tinkering, I think that it would be much better to build a new standard cutcherry. An adjacent and most suitable site of about three acres could be had for about Rs. 35 per acre. There is a lot of valuable stone handy in the ruins of the cutcherry of 1869, and other heaps piled close by. Within a quarter of a mile, in the river bed, is an inexhaustible quarry of easily won and worked limestone of the finest quality for building purposes.

7. There need be no thought of waste in the abandonment of the public bungalow, for it can be utilized as a taluk school for the villages of Pullampet, Reddipalle, Anantarazupet, &c. I was surprised to find that there was no taluk school at Pullampet, and still more surprised to find that there had been one and that it had

been abandoned. In fact the pretty, and prettily-situated, little edifice, now used as a dispensary, was built for a taluk school. The resuscitation of this defunct institution will be a matter for further care.

8. I regret to have to trouble the Board with these proposals for further expenditure; but something must be done, and I think that it would be cheaper in the long run to give Pullampet a standard cutcherry in stone and chunam than to try any further amateur experiments in brick and mud.

READ—the following letter from W. J. H. LE FANU, Esq., Collector of Cuddapah, to the Secretary to the Board of Revenue, dated 18th March 1886, No. 248:—

In my letter, No. 246, dated 18th instant, I reported the destruction of the taluk cutcherry at Pulivendla by fire. I have the honor to request that early consideration may be given to the urgent need for a new cutcherry at Badvél.

2. The present building is, I am told, part of some Nawab's house. It is quite unfit to be a taluk cutcherry. The whole office is crowded into one room, if it may be called so. It is rather an immense verandah facing the north; in front of it and immediately west it is a space roofed in with heavy thatch, and beyond that is a long rotten shed dignified by the name of record-room; to the east of this is what is called the subsidiary jail.

3. To the record-room I use the word "rotten" advisedly; for there is little of it that would not come down if a judicious push were administered. One large piece of the wall *has* come down, and access to the records from outside is prevented only by a tatty. I despair of repairing this wall temporarily, for the local mud—the wall is a mud wall—is made of slaty dust and has no binding properties. The roof it is needless to observe leaks *passim*. To this however we are well accustomed. The jail—if two rooms, one like a small cook-house and the other like a smaller stable, with wooden gratings in front can be called a jail—does not fulfil any of the requirements of the Committee on Subsidiary Jails which was sitting twenty years ago. There is, I must add, another stable adjoining, erected, I believe, during the famine. Even, however, with three stalls available, it is evident that males and females, under trial and convicted, cannot be accommodated; solitary confinement is impossible; there is no latrine, and no cook-room, and no hospital., I thought that the cutcherry at Dharmapuri was the most unsuitable building I had ever seen, but that at Badvél surpasses it.

4. I do not propose to order the thatch in front of the cutcherry to be removed, even with the experience of Pulivendla before me; for the cutcherry would be unbearable without it. I find a Chisholm-muster cutcherry at Sidhout, old enough to have cracks in the walls and its wood-work seedy. I allude especially to the record-room venetians. I cannot understand, when progress reached Sidhout, that it should have stopped short of Badvél. I am going on to Pullampet to-morrow and hope not to find things there as at Badvél. May I ask the Board to try and see if provision cannot be made for Badvél in the current year. I am sorry to have to make so many requests, but the district suffers from over-modesty on this score in former years.

READ—the following letter from C. H. MOUNSEY, Esq., Acting Sub-Collector in charge, Cuddapah, to the Secretary to the Board of Revenue, dated 1st May 1886, No. 367:—

With reference to my letter, No. 240, dated 25th March 1886, I have the honor to inform you that the site particularized below was selected by Mr. LeFanu as suitable for the construction of the new taluk cutcherry at Pullampet.

Government.	Number.	Extent.	Assessment.	Names of owners.
		ACRES.	RS. A. P.	
Dry	276	0·22	0 3 8	D. Vencoba Row and Kristnamma, trustee of Angennyaswamy temple.
Do.	277	1·27	1 4 8	Papayyagari Chinnabbi.

2236/25

The owner of land No. 276, Duvur Vencoba Row, pensioned Tahsildar, has consented to give the land without any compensation, and for acres 1·27 of field No. 277 money payment at the rate of Rs. 26-10-8 has been fixed by a punchayet, to which the owners have agreed. I request that permission of the Board may be obtained for acquiring the land which, if not needed immediately, will be required sooner or later and is the best site at Pullampet.

RESOLUTION—dated 17th May 1886, No. 1102.

Submitted for the orders of Government.

2. The necessity for building new taluk offices both at Pullampet and Badvél appears to be great, and the Board therefore request that orders may be issued in the Public Works Department for the preparation of plans and estimates at an early date, and, if the financial pressure will allow of it, for the provision of funds in the current year's budget.

3. The opinion of the Public Works Department, the Board think, should also be taken as to the stability of the buildings now in occupation.

(True Copies and Extract.)

(Signed) H. A. SIM,
Acting Sub-Secretary.

To the Secretary to Government, Revenue Department.
„ Collector of Cuddapah.
Copy to W. J. H. LeFanu, Esq.,
care of Messrs. Binny & Co., Madras.

order thereon, 10th June 1886, No. 3414

Transferred to the Public Works dept. for early orders. The Govt. in this Dept. are of opinion that the construction of taluk cutcheries at Pullampet and Badvel is most urgent and should take precedence of other buildings elsewhere.

(True Extract)

Exd. J. Moses.

(Sd) Frederick Price
Ag. Secy. to Govt

To
The P. W. D

REVENUE DEPARTMENT.

1886.

Board of Revenue,

MADRAS.

Printed May 26th.

Proceedings, 17th *May* 1886, *No.* 1102.

Submitting, for the orders of Government, with remarks, letters from the Collector of Cuddapah reporting the necessity for the construction of new taluk cutcheries at Pullampet and Badvél.

No. 1526 W. 4/16 June 86

Communicated to the Supdg. Engr. III Circle, for very early submission of the requisite estimates.

2. The question of provision of funds for the two buildings, will be considered on receipt of the estimates.

3. This call should be treated as urgent.

(sd) J. S.

S. E. III Circle
Rev. Dept.

With order

No 128

Superintending Engineer's Office
3rd Circle
Camp Vellpet 23rd April 1886

From

Col. H. Sealy R.E.
Superintending Engineer
3rd Circle

To

The Collector
Cuddapah.

Sir,

I have the honor to forward for your Countersignature & transmission to Government an Estimate amounting to Rs. 22184 for constructing a first class Taluk office at Badvel with out houses in accordance with the Standards plans approved in G.O. No 1495 W dated 8th June 1887.

2. The Estimate was called for in G.O. No 1526 W dated 16th June 1886 on G.O. No 3414 dated 15th June 1886 in the Revenue Department.

I have &c

(Signed) H. Sealy Col. R.E.
Supdg. Engr. 3rd Circle

(True Copy)

3833/86.

No 3215 / 7-5-88 Enclo: 7

[illegible]'S GEN. REG. No 1576 OF 188 LAND REVENUE.

Submitted to the Secretary to the Commissioner of Land Revenue with a request that early sanction of the Government may be obtained so that the work may be put in hand this year.

[illegible] for acting Collector

[illegible] / 6912/88

39 / 5.5

[illegible] 5.5

2236 / 31

REVENUE BOARD OFFICE MADRAS

Proceedings of the Board of Revenue

(Land Revenue).

Dated 5 June 1888.

No. 3410 Miscellaneous.

Honble W S Whiteside

READ endorsement of late Collector of Cuddapah dated 7 May 1887, No 3215, on letter from the Deputy Engr 2nd circle dated 23rd April 1888, No 128.

Resolution.

3P

The estimate for constructing a first class. [illegible] submitted for at a cost of Rs 2,194 [illegible] Government and the the sanction [illegible] in the budget of provision of funds [illegible] Department the Public Works Department.

2 Reference to the mat[illegible] was made in para: 2 of Govt order 26 [illegible] No [illegible]

(True extract)

[illegible]
Ag Secretary

U.O. 1968 R / 7.7.88

To The Secretary to Government P.W.D. with letter of enclos: in orig. to be retd.
Copy to Collr of Cuddapah.

Ms. No 15268 } 11.1.86 S.6.23692 } 1.9.87
" 18358 " 8.7.87
" 15308 " 3.6.87 B.Ms 7798 8.3.88
" 9068 " 24.3.87 " 2162 13.5.87
" 2740 " 18.11.86 S.6.13368 27.5.88
G.O. 14958 " 3.6.87 " 1681 7.6.88
B.Ms 19688 " 7.8.86
G.O. 16528 " 30.6.86

P.W. 646

(1888.)

REVENUE DEPARTMENT.

No. 3833

Ms. No 3698 4P

Transferred to the Public Works Department with the remark that with reference to G.O. dated 7th June 1888 No 1681 W, the provision of a ryots' shed is unnecessary.

(By Order)

H. Albert

Under Secy. to Govt.

Copy 25.6.88

To
The P.W. Deptt. ✓ with [illegible]
" Commr. of Land Reve.

From Pres. Board of Reve. (Land Revenue)

Enclos. 8

(1 plan)

Dated 5th } June
Received 8th } 88
Enclosures 8

Ms. No. 3410

SUBJECT.

Submitting for the sanction of Govt. an estimate amounting to Rs 22,184 (21,330) for constructing a first class Taluk office with out houses at Badvel Cuddapah Dt.

CR

[illegible] 11/7/88 | 28/88

With an [illegible]

27/33

Public Works Department.

B/

Current No. 6413

Letter No. 3698

Dated 25th June 1888

From the Secy. to Govt Rev. Deptt.

Sanction for Rs 21,330

NOTE OF REMARKS. MCB 13.7.88

The estimate under review amounting to Rs 22,184 provides for the construction of a First Class Taluk Office with subsidiary buildings at Badvel in the Cuddapah dist.

The estimate provides for a Ryots Shed at a cost of Rs 854 but as G.O. No 1681 W of 7th June 1888 disallowed a Ryots Shed it has been struck out of the estimate and the amount reduced from Rs 22,184 to Rs 21,330.

The Taluk Office is to be built in accordance with the typical

circulated with G.O. No 1495 W
d/3rd June 187 and the
Subsidiary buildings
are to be constructed
in accordance with the
type plan circulated
with G.O. No 1014 d/21st
April 1874, with the
exception of the Ryots
Shed which has been
struck out in deference
to the order of Govt.
quoted above.

The following rates
are in excess of the
rates given in the
Schedule of the Cuddapah
Division —

Table moulded bricks
in mortar per 100 cft Rs 18-1-
against Rs 16-3-9 in the
Schedule.

Teak wood wrought
and put up Rs 4-8-9 against
Rs 4-8-0 - per cft.

+ ~~[illegible] Roofing Rs [illegible] per 100 sq ft against Rs [illegible]~~

~~Tiled Roofing with flat and pan tiles per Rs 18-13- per 100 sq ft against Rs 15-2-9~~

~~Flooring with cobble 3/4" thick and 1" [illegible] Rs 9-12-0 against Rs [illegible] per 100 sq ft~~

[illegible]

× These remarks are struck out as the rates agree with the rates given in the Schedule received after these remarks were written vide C No 6803.

[illegible]
13/7/88

+ These rates are corrected according to the rates subsequently submitted for the Cuddapah Dn vide C No 6803 —

[illegible]
12/7/88

including 2 coats of
white washing Rs 4-1-6
per 100 sq ft against
Rs ~~3-15-~~ 4-"-" . ×

Painting 2 coats of
Carrons paint Rs 4-8-
per 100 sq ft against 3-4-

Woodoiling 2 coats Rs 2-
per 100 sq ft against Rs 1-8-

A saving of Rs ~~734~~ 545
would be effected
if the rates given in
the Schedule are adopted
and the Est still further
reduced viz from
Rs 21,330 to Rs ~~21,574~~ 20,785

The following lump
sum provisions are
made in the Est.

Gravelling Rs 100
Stone Shed — " 50

Rs 105 is provided
for land compensation
for 3 acres of land
which is at the
rate of Rs 35 per acre

Contingencies and
Petty Supervision are
charged for at 5 & 2½
per cent respectively

The estimate has
been countersigned

by the Collector and is approved by Govt and the Revenue Deptt. with the remark that the provision for the Tapp. Shed is unnecessary.

[illegible]
12/7/86.

C. No. 6413

22/35

P. W. Secretariat.

Note by Budget Section.

Work Cons. a first class taluk office with outhouses at Badvel

Remarks and References

Fund	Provincial		
Service Head	Civil Building		
Departmental Head	Original Works		
Amount of Estimate	... ...	Rs.	21,330
Expenditure in previous year	...	"	"
Allotment in current year ...	...	"	"
Balance required to complete	...	"	"
Total Rs.	...		2,330

Note of available funds.

In G. O. No: 3414 (Revenue) d/10th June 1886 the work was considered most urgent and was ordered that it should take precedence of other buildings elsewhere. Further the question of providing funds for the work was promised to be considered on receipt of the estimate.

× 1526 Wa/16-6-86
1650 Wa/30-6-86.

The balance of the reserve at present is Rs 2,386. As it is very small, the work may be included in the list for additional funds proposed to be obtained from the Financial Department

14th July 1888

[illegible]
Budget Clerk.

[illegible]
14.7.88

B.P.W. & Works

PUBLIC WORKS DEPARTMENT.

2236/36

PROCEEDINGS OF THE MADRAS GOVERNMENT.

UNDER date the

READ the following

Proceedings of the Board of Revenue. N.E. No: 3410 Dtd: 5th June 1888.
Endorsement by the Revenue Deptt. N.E. No: 3698 d/25th June 1888.

The estimate amounting to Rs. 22,184, for constructing a first class taluk office with out houses at Badvel in the Cuddapah District, has been reduced by Rs. 854, being the cost of the ryot's shed which is considered unnecessary, and sanction is accorded to the reduced amount, Rs. 21,330.

2. The Suptg. Engineer will report what sums can be spent on the work during the current official year.

3. This sanction has been registered as Provincial No: 55 W of 1888-89 and classified as Civil Buildings. Original Works.

D 18

To The Suptg. Engr. III Circle with 6 enclos
a Examiner of A.W. Accts with the duplicate general abstract estimate
a Revenue Department.

14.7.88

Jore 18/7/88

15.20 W 26-6-86
1650 W 30-6-88
1968 W 7-8-86
1495 W 3-6-87
1835 W 8-7-87
1530 W 8-6-87
1345 W 1-5-87
779 W 8-388
1330 W 7-1-88
1681 W 7-6-88

16-7-88

Govt. of | 1888 | Madras.

PUBLIC WORKS.

417

Dated

Recd.　　Encl.

G.O. 21st July 1888, No. 2236 W.

Taluq Office

The reduced estimate for constructing a first class — with out-houses at Badvel in the Cuddapah District sanctioned.

95/6