

Q/16-8-88

B
No 2533 W of 17 August 1888

Communicated to the
Supt of Engineer to Arch
with reference to G.O.
2123 W of 13 July 1888
2123 W of 13 July 1888

See
14/8/88

P/11/88

LS of Arch ✓ 21/8
S.E. of Arch 21/8

123 30:8
m: 14/8

P 23/8

21/8

GOVERNMENT OF MADRAS.

PUBLIC WORKS DEPARTMENT.

Buildings and Roads.
Military Works.

READ—the following papers:—

From Colonel J. BEATTY, R.E., Superintending Engineer, IV Circle, to the Chief Engineer, Public Works Department, dated Coimbatore, 6th June 1888, No. 220 E.W.

In forwarding, for your information, copy of a letter from the Superintendent of the Remount Depot, Matigiri, No. 1392, of 9th March 1888, I have the honor to submit plans and an estimate, amounting to Rs. 525, for extending the existing weir of the Jegoor tank, being a part of the depot works.

2. At the request of the Depot Superintendent, the tank was examined and the Executive Engineer, Coimbatore division, forwarded, for sanction, two estimates, one of Rs. 670 for necessary repairs and raising the tank-bund, which I have sanctioned under "Repairs, Military," and the other is the one now forwarded to you for sanction under Original Works and Allotment of funds, as it is for improving the existing weir of the tank, and the amount exceeds the limit of my sanction.

No. 59 E.W.

Note by the Chief Engineer for Irrigation.

With reference to No. 2201 C., of 11th June 1888, regarding proposed extension of the weir of Jegoor tank, as there is no information given as regards hydraulic details, the Chief Engineer for Irrigation is unable to give an opinion as to its necessity, as, however, lengthening the weir will lower M.F.L., and must make the tank more safe, there can be no objection to the work.

It is considered that if a new retaining wall is built, it should be placed, say, 7 feet from the crest wall, and the rough stone apron so saved (3 feet in width) should be put down as a rear apron to the retaining wall, say, 1 foot below apron level.

In the estimate foundations for the new wing are allowed, but no superstructure. Probably all that is required is a rough stone wing like those made for cheap escapes; the Superintending or Executive Engineer should have corrected this.

CHEPÂK,
26th June 1888.

(Signed) C. A. SMITH,
for Chief Engineer for Irrigation.

To the Chief Engineer, Public Works Department.

Note by the Chief Engineer, Public Works Department.

The estimate, amounting to Rs. 525, for extending the existing weir of the Jegoor tank at the Remount Depot, Hosûr, is submitted for the sanction of Government with the following remarks.

The retaining wall should be placed 7 feet from the crest of the weir; and a subsidiary apron, 3 feet in width, should be put down in rear of the retaining wall, about 1 foot lower than the main apron.

No provision has been made in the estimate for the superstructure of the rear wing, but it is assumed that the cost of a rough stone wing like those made for cheap escapes can be met from the estimate.

16th July 1888.

(Signed) J. O. HASTED, Colonel, R.E.,
Chief Engineer, P.W.D.

ORDER—dated 13th July 1888, No. 2123 W., Public Works.

The estimate, amounting to Rs. 525, for extending the existing weir of the Jegoor tank at the Remount Dépôt, Hosúr, is sanctioned.

2. As the available balance of the grant for Military Minor Works has been placed at the disposal of the officers commanding divisions and districts, the Superintending Engineer will apply to the Officer Commanding the Southern District for funds required for this work.

3. Attention is drawn to the Note by the Chief Engineer, Public Works Department, above recorded.

4. The sanction accorded in para. 1 of these Proceedings has been registered as Imperial Ordinary No. 19 W. of 1888-89, and classified as Military Original Works.

(True Extract.)

(Signed) J. O. HASTED, Colonel, R.E.,
Secretary to Govt., P.W.D.

To the Superintending Engineer, IV Circle, with three enclosures.

„ Examiner, Public Works Accounts, with the estimate
for note and return to Superintending Engineer, IV Circle.

„ Military Department.

Exd. F. R. Bantleman.
Spare Copies

BUILDINGS AND ROADS.
MILITARY WORKS.

Gobt. of (1888) Madras.
PUBLIC WORKS.

Dated July, 13th.

Recd.

Encl.

G.O., 13th July 1888, No. 2123 W.


JULY.

Jegoor Tank.

Estimate for extending the existing weir
of the —, at the Remount Depôt, Hosur,
sanctioned, with remarks.

military Buildings.

No. 6525



Government of Madras.

MILITARY DEPARTMENT,
Ootacamund the 13 August 1888.

From the Quarter Master General to
the Secretary to the Government of Madras,
Military Department, N^o 2830 A, dated
6th August 1888.

Referring to para 2 of O.G. N^o 2123 W
of 13th July 1888, N. D. N^o 5192 of 30th idem, I am
desired to state that Hosur being in the
Bangalore Division, the General Officer Com-
manding that Division and not the
Southern District should be required to
provide the funds for extending the exist-
ing weir of the Jegoor Tank at that station.

2. The General Officer Commanding,
Bangalore Division, has accordingly been
instructed to decide in communication
with the Superintending Engineer whether
he can provide the funds for the work
with reference to other demands in his
command.

Order

Order: — Communicated to the
Public Works Department, with reference to
O.G. No 2123 W, dated 13th July 1888.

(True Extract.)

Alfred Herbert Brigadier General,
Secretary to Government.

To
The Public Works Department.