655 பொ.ப. 24-2-1888

① பக்கங்களின் எண்ணிக்கை = 30

② புதுக்கித் திரும்பிய நாள் = [illegible]-1988

③ ஆதாரக் குறிப்பவர் சுருக்கொப்பம் =

தமிழ் நாடு ஆவணக் காப்பகம்.

தமிழ் நாடு அரசு.

பொதுப்பணி துறை.

அரசாணை எண் 655 பொதுப்பணி. நாள் 24-2-1888.

கே.த

GOVERNMENT OF MADRAS.

PUBLIC WORKS DEPARTMENT.

Buildings and Roads.
Civil Works.

Read—the following papers :—

From Colonel H. M. VIBART, R.E., Superintending Engineer, V Circle, to the Inspector-General of Registration, dated Chepâk, 16th January 1888, No. 4330.

With reference to G.O., No. 1368 W., dated 18th May 1887, I have the honor to forward to you for disposal an estimate of Rs. 2,575 for constructing a Sub-Registrar's office at Arkónam, prepared on the latest type design approved in G.O., No. 1049 W., dated 5th May 1885, with the exception of foundations and roofing; the former is altered from brick in mortar to concrete block foundations to suit the nature of the soil, and the latter to Mangalore Mission tiles instead of common tiles to harmonise with the roof of the new Sub-Magistrate's Cutcherry, in the compound of which the Sub-Registrar's office is proposed to be built.

T. No. 71.

Submitted for the sanction of the Government.

2. The necessity for constructing a Sub-Registry office at Arkónam was brought to the notice of the Government in my letter, T. No. 859, dated the 29th April 1887. The estimate provides for all that is necessary.

Cuddapah,
2nd February 1888.

(Signed) G. HAMNETT,
Inspector-General of Registration.

No. 168 R., Judicial.

Approved and transferred to the Public Works Department.

(By Order.)

Fort St. George,
14th February 1888.

(Signed) A. G. CARDEW,
Under Secretary to Government.

Note by the Chief Engineer, Public Works Department.

The estimate, amounting to Rs. 2,575, for constructing a Sub-Registrar's office at Arkónam, is submitted for the sanction of Government, with the remark that the attention of the Superintending Engineer should be called to G.O., No. 163 W., dated 16th January 1888, which refers to certain defects in the standard design that can be easily remedied in actual construction.

Chepâk,
22nd February 1888.

(Signed) J. O. HASTED, Colonel, R.E.,
Chief Engineer, Public Works Department.

Order—dated 24th February 1888, No. 655 W., Public Works.

The estimate, amounting to Rs. 2,575, for constructing a Sub-Registrar's office at Arkónam, in the North Arcot district, is sanctioned for execution when funds are available.

2. Attention is drawn to the note by the Chief Engineer, Public Works Department, above recorded.

3. This sanction has been registered as Provincial, No. 175 W. of 1887-88, and classified as Civil Buildings, Original Works.

(True Extract.)

(Signed) H. R. MEAD, Colonel, R.E.,
Joint Secretary to Govt., P.W.D.

To the Superintending Engineer, V Circle, with four enclosures.
„ Examiner, Public Works Accounts, with the duplicate abstract estimate.
„ Judicial Department.

Exd. J. Henricus,
Spare Copies

BUILDINGS AND ROADS.
CIVIL WORKS.

Govt. of (1888) Madras.

PUBLIC WORKS.

Dated February, 24th.

Recd. *Encl.*

G.O., 24th Feb. 1888, No. 655 W.

FEBRUARY.

Sub-Registrar's Office at Arkonam

Estimate for constructing a — in the North Arcot district, sanctioned with remarks.

655/3

Estimate form—Detail measurements.

Detail of work.	Number.	Measurements in feet.			Area or contents.	Total quantity of each description of work.
		Length.	Breadth.	Depth.		
EXCAVATION FOR FOUNDATION.						
Wall all round the office	1	108 0	4 6	4 6	2,187	
Partition wall to do.	1	22 6	3 8	4 6	371	
Verandah all round	1	35 0	3 3	4 6	512	
Step	1	12 6	3 0	1 0	38	
Total, excavation ...	...	...	...	...	...	3,108
EARTH-FILLING IN BASEMENT.						
Rooms	2	24 9	11 7½	1 6	863	
Platform	1	11 7½	7 7½	1 0	89	
Verandah	1	25 0	5 4½	1 6	202	
Total, filling ...	...	...	...	...	...	1,154
CONCRETE.						
Wall all round	1	108 0	3 6	1 0	378	
Partition wall	1	23 6	2 8	1 0	63	
Verandah do.	1	35 6	2 3	1 0	80	
Step	1	12 6	3 3	1 0	41	
Total, Concrete ...	...	...	...	...	...	562
BRICKWORK IN FOUNDATIONS.						
Footing course.						
Wall all round	1	108 0	2 8	1 6	432	
Partition wall	1	24 4	1 10	1 6	67	
Verandah all round	1	36 10	1 3	1 3	58	
FOUNDATION AND BASEMENT OVER FOOTING.						
Wall all round	1	108 0	2 3	3 6	851	
Partition wall	1	24 9	1 6	3 6	130	
Verandah do.	1	37 3	0 9	3 6	98	
Steps	1	12 6	3 0	0 6	19	
	1	10 6	3 0	0 6	16	
	1	8 6	3 0	0 6	13	
Total, foundation and basement	...	...	...	...	...	1,684
BRICKWORK IN SUPERSTRUCTURE.						
Wall all round	1	108 0	1 6	12 6	2,025	
Partition wall including gable ...	1	25 6	1 6	17 3	660	
					2,685	
Deductions.						
Doors	2	4 0	1 6	8 0	96	
Windows	8	3 6	1 6	5 0	210	
Archwork as per details	...	...	...	...	102	
Granite stone under posts as per details	...	...	...	...	5	
					413	
Total, superstructure ...	...	...	...	...	...	2,272

Estimate form—Detail measurements—*cont.*

Detail of work.	Number.	Measurements in feet.			Area or contents.	Total quantity of each description of work.
		Length.	Breadth.	Depth.		
ARCHWORK.						
Over doors	2	5 0	1 6	1 6	23	
Over windows	8	4 4½	1 6	1 6	79	
Total, archwork ...	...	...	...	...	...	102
CUT-STONE WORK.						
Stone under posts	4	1 0	1 0	0 6	2	
Carble stone under flèche	2	3 0	0 6	0 9	2	
TEAKWOOD.						4
Main room.						
Hip rafters	4	25 0	0 4	0 8	22	
Jack rafters	22	10 6	0 3½	0 7	39	
	58	9 3	0 3½	0 7	91	
Brackets	22	1 0	0 7	0 7½	8	
Uprights, double	44	4 3	0 3½	0 1½	7	
Struts	22	3 0	0 4	0 3½	6	
Ridge piece for dome	2	5 0	0 3	0 6	1	
Rafters to do.	12	3 0	0 3	0 4	3	
Gable plank	2	5 0	0 1	1 6	1	
Barge board	2	12 0	0 2	0 9	3	
Collar piece	2	5 0	0 3	0 3	1	
Verandah posts	2	0 5	0 5	8 0	3	
	2	0 5	0 5	6 3	2	
Bressummer	1	32 0	0 5	0 7½	8	
Valley rafters	2	11 0	0 3½	0 5	3	
Ridge piece	1	8 3	0 3	0 6	1	
Rafters	12	9 3	0 3	0 4	9	
Jack rafters	16	4 6	0 3	0 4	6	
Finial	1	7 3	0 4	0 4	1	
Collar piece	2	3 0	0 3	0 3	1	
Gable plank	1	2 9	0 1	1 9		
Barge board	1	17 0	0 2	1 0	3	
WOODWORK FOR FLECHE.						
Bottom frames	4	4 0	0 6	0 7	5	
Uprights (allowing for wastage) ...	8	0 7	0 7	4 6	12	
Frames above do. ...	8	1 3	0 4	0 4	1	
Uprights (allowing for wastage) ...	8	0 5	0 5	3 6	5	
				average		
Brackets	16	0 4	0 3	0 4	2	
Bressummers	8	1 3	0 4	0 4		
Horizontal pieces	8	2 0	0 3	0 4	1	
Central boss	1	0 9	0 9	0 4	8	
Rafters (allowing for wastage) ...	8	5 5	0 9	0 3		
Solid block at termination	1	0 9	0 9	1 9	1	
Pieces between feet of rafters ...	8	1 6	0 4	0 3	1	
Planks at eaves	8	1 6	0 ½	0 6	3	
Boarding (including one tapping)...	8	7 9	0 ½	1 0		
Venetians	40	0 10	0 ½	0 6	2	
Do. returns	80	0 10	0 ½	0 3		
Do. do.	8	0 10	0 ½	3 3		
Planking to cover lower part of flèche	8	1 9	0 1	1 9	2	
						262
Teak railings	1	9 0	...	Running feet.		9
Do. doors	2	4 0	...	8 0	64	64
Do. windows	4	3 6	...	5 0	70	70
Do. glazed shutters to windows ...	2	2 11	...	4 7	27	27
Do. do. windows with frames to record-room	4	3 6	...	5 0	70	70

655
4

Estimate form—Detail measurements—*cont.*

Detail of work.	Number.	Measurements in feet.			Area or contents.	Total quantity of each description of work.
		Length.	Breadth.	Depth.		
ROOFING.						
Front and rear slopes	2	18 0	16 6	...	594	
Side slopes	2	9 9	18 6	...	361	
	2	8 0	16 6	...	264	
Ridge	4	3 0	3 0	...	36	
Verandah	2	10 0	9 0	...	180	
	2	7 6	4 6	...	68	
Total, roofing ...	...	...	...	...	...	1,503
PLASTERING.						
Records and clerks' rooms	2	75 0	...	13 0	1,950	1,950
Outer wall all round	1	114 0	...	13 0	1,482	
Basement do.	1	114 0	...	2 0	228	
					1,710	
Deduct.						
Doors	2	4 0	...	8 0	64	
Windows	8	3 6	...	5 0	140	
Total, plastering ...	...	...	...	...	204	1,506
FLOORING.						
Rooms	2	25 6	12 0	...	612	
Verandah	1	26 6	6 6	...	172	
Steps	1	12 6	3 0	...	38	
Spaces of window	8	3 6	0 9	...	21	
Do. of doors	2	4 0	1 0	...	8	
Total, flooring ...	...	...	...	...	...	851
PAINTING, CARSON'S.						
Doors	3×2	4 0	8 0	...	192	
Windows	3×8	3 6	5 0	...	420	
Glazed shutters	8	3 0	4 6	...	108	
Brackets	22	0 6	1 9	...	19	
Doublings	44	2 9	0 10	...	101	
Struts	22	2 3	1 3	...	62	
Gable planks	2	4 3	0 9	...	6	
Barge board	2	12 0	1 9	...	42	
Collar piece	2	4 6	1 0	..	9	
Posts	2	7 6	2 0	...	30	
	2	6 0	2 0	...	24	
Bressummer	1	30 0	1 10	...	55	
Finial	1	7 3	1 4	...	10	
Collar piece	1	2 3	2 0	...	5	
Gable plank	2	2 6	1 9	...	9	
Barge board	1	17 0	2 2	...	37	
Flèche	3×1	10 0	6 6	...	195	
	3×1	8 0	2 6	...	60	
						1,384
WOOD-OILING.						
Hip rafters	4	21 0	1 8	...	140	
Jack rafters	22	8 6	1 6	...	281	
	58	8 3	1 6	...	718	
Ridge piece	2	5 0	1 3	...	13	
Rafters to piece	12	3 0	1 0	...	36	

Estimate form—Detail measurements—*cont.*

Detail of work.	Number.	Measurements in feet. Length.	Breadth.	Depth.	Area or contents.	Total quantity of each description of work.
WOOD-OILING—*cont.*						
Valley rafters	2	10 0	1 $1\frac{1}{2}$	...	23	
Ridge piece	1	7 0	1 3	...	9	
Rafters	12	8 3	1 0	...	99	
Jack rafters	16	4 0	1 0	...	64	
Flèche bottom frames	4	3 6	1 9	...	25	
Uprights	8	4 0	3 0	...	96	
Total, wood-oiling ...	...	...	...	...	...	1,504
Sheet lead $\frac{1}{16}$" thick	...	14 0	...	2 3	32	
....	...	11 6	...	1 3	14	
....	...	1 3	...	0 9	1	
	...	...	...	Sq. ft.	47	
			× 3·7 lb. per sq. ft.			173 lb.

ESTIMATE Form—Abstract.

Quantity.	Description of work.	Rate.	Per	Amount.	Total.
		RS.	C. FT.	RS.	RS.
3,108 C. ft.	Excavation for foundation	...	1,000	...	
1,154 ,,	Earth-filling in basement	...	,,	...	
562 ,,	Concrete	...	100 c. ft.	...	
1,684 ,,	Brickwork in foundation and basement	...	C. feet. 100	...	
2,272 ,,	Brickwork in superstructure ...	...	,,	...	
102 ,,	Archwork	...	,,	...	
4 ,,	Cut-stone work	...	C. feet.	...	
262 ,,	Teakwood, wrought, and put up ...	...	,,	...	
9 R. ft.	Teak railings as per plan	...	R. foot.	...	
64 S. ft.	Pannelled venetian doors with frames and fittings complete	...	S. foot.	...	
70 ,,	Venetian windows with do. do. ...	...	,,	...	
27 ,,	Glazed shutters only for side windows of clerks and registrar's room including fittings	...	,,	...	
70 ,,	Glazed shutters with frames and iron bars to record-room	...	,,	...	
1,503 ,,	Tile roofing with flat and pan tiles including teak reepers	...	100 Sq. feet.	...	
1,950 ,,	Plastering the interior walls with two coats of chunam	...	,,	...	
1,506 ,,	Pointing exterior walls	...	,,	...	
851 ,,	Flooring with 8" square feet bricks in chunam including a levelling course of third sort wall bricks	...	,,	...	
1,384 ,,	Carson's oak paint, three coats to doors, windows and exposed woodwork ...	...	,,	...	
1,504 ,,	Wood-oilings, three coats to roof timber, &c.	...	,,	...	
	Wrought iron finial as per plan ...	...	...	...	
173 lb.	Sheet lead $\frac{1}{16}$" thick	...	lb.	...	
	Allow for finishing verandah and ridge gables, &c.	...		...	
	Petty supervision at $2\frac{1}{2}$ per cent. ...	...		...	
	Contingencies at $2\frac{1}{2}$ per cent. ...	...		...	
	Grand Total ...	...		...	...

MADRAS,
21st April 1885.

(Signed) J. L. L. MORANT, Lieut.-Col., R.E.,
Officiating Consulting Architect to Government.

655/4

5TH MAY 1885, No. 1049 W., PUBLIC WORKS.

GOVERNMENT OF MADRAS.

PUBLIC WORKS DEPARTMENT.

Buildings and Roads.
Civil Works.

READ—the following letter from Lieutenant-Colonel J. L. L. MORANT, R.E., Officiating Consulting Architect to Government, to the Chief Engineer, Public Works Department, dated Chepâk, 21st April 1885, No. 78 :—

With reference to G.O., No. 702 W., dated 20th March 1885, I have the honor to submit three plans and detailed quantities for a sub-registrar's office with tiled roof to be erected in compounds with cutcherries built on the standard design.

2. This design has been approved by the Inspector-General of Registration, who has signed a copy (herewith forwarded) in token of his approval.

3. At Madras rates of work this design will cost Rs. 3,130. The rooms have been slightly enlarged to fit into the treatment adopted. Projecting eaves are provided for the office rooms. And a flèche affords roof ventilation to the whole building.

ORDER—dated 5th May 1885, No. 1049 W., Public Works.

In continuation of G.O., No. 702 W.,* dated 20th March 1885, the Government direct that copies of the revised type design and schedule of quantities prepared by the Consulting Architect to Government be circulated to officers of the Public Works Department for use when it is proposed to build registration offices in the same compounds with cutcherries on the standard plan.

2. The type design and estimate circulated with G.O., No. 100 W., dated 14th January 1884, are cancelled.

* G.O., dated 27th February 1885, No. 543, Judicial.

(True Extract.)

(Signed) J. SHAW-STEWART, Colonel, R.E.,
Secretary to Govt., P.W.D.

To Superintending Engineers.
To the Consulting Architect to Government.
,, Judicial Department.

Exd. A. Grubert.
Spare Copies

BUILDINGS AND ROADS.
CIVIL WORKS.

Govt. of (1885) Madras.
PUBLIC WORKS.

Dated May, 5th.

Recd. *Encl.*

G.O., 5th May 1885, No. 1049 W.

MAY.

Sub-Registrar's Office

Revised type design and schedule of quantities prepared by the Consulting Architect for —, ordered to be circulated to officers of the department.

665/6

GOVERNMENT OF MADRAS.

PUBLIC WORKS DEPARTMENT.

Buildings and Roads.
Civil Works.

Read—the following letter from G. HAMNETT, Esq., Inspector-General of Registration, to the Chief Secretary to Government, dated Ootacamund, 29th April 1887, T. No. 859 :—

Under the sanction accorded by the Government in their order, Judicial, dated the 10th January 1885, No. 74, a new Sub-registry office was opened at Arkónam in the district of North Arcot, on the Madras Railway, on the 1st April 1885. From that date the results are as follow :—

—	Registration.	Receipts.	Expenditure.
		RS.	RS.
1st April 1885 to 31st March 1886 ..	1,396	1,691	1,179
1st April 1886 to 31st March 1887 ..	1,458	1,649	1,300
Total ..	2,854	3,340	2,479

2. The office supports itself, and the time has arrived for putting it into a proper building.

3. The building used at present as an office belongs to a native, and a monthly rent of Rs. 12 is paid for it. It is not altogether adapted for an office, but no better building is procurable, while the owner wishes that the office might be removed.

4. Under the circumstances, I have the honor to recommend that the sanction of the Government may be obtained for the preparation of plan and estimate for a Sub-registry office at Arkónam on the revised standard tiled design.

Endorsement on the above.

Approved and transferred to the Public Works Department.

(By Order.)

Ootacamund,
14th May 1887.

(Signed) A. G. CARDEW,
Under Secy., J.D.

Order—dated 18th May 1887, No. 1368 W., Public Works.

Communicated to the Superintending Engineer, V Circle, for submission of the requisite estimate.

(True Extract.)

(Signed) J. O. HASTED, Colonel, R.E.,
Secretary to Govt., P.W.D.

To the Superintending Engineer, V Circle.
" Judicial Department.

Exd. P. L. Pereira.

Spare Copies

BUILDINGS AND ROADS.
CIVIL WORKS.

Govt. of 1887 Madras.

PUBLIC WORKS.

Dated May, 18th.

Recd. *Encl.*

G.O., 18th May 1887, No. 1368 W.

MAY.

Sub-Registrar's Office

Estimate called for, for constructing a — at Arkónam in the North Arcot district.

655/7

16TH JANUARY 1888, No. 163 W., PUBLIC WORKS.

GOVERNMENT OF MADRAS.

PUBLIC WORKS DEPARTMENT.

Buildings and Roads.
Civil Works.

READ—the following papers :—

From A. S. RUSSELL, Esq., Executive Engineer, Tinnevelly Division, to the Superintending Engineer, VI Circle, dated Palamcottah, 8th December 1887, No. 2763.

In continuation of my letter No. 1994, dated 25th September 1887, I have the honor to report that I receive continual complaints from the Registration Department regarding the inconvenience the Registrars are exposed to in this district owing to the absence of glass windows at the sides of the Registrar's room and clerks' room (*vide* standard design for a Registrar's office).

2. For about half the year in this district there is a strong wind, and during the north-east monsoon heavy rain. If the venetian windows at the sides of the room are closed there is not sufficient light to see, and there is thus no alternative but to keep the venetians open and be exposed to the inconvenience of wind and rain driving into the room.

3. I have therefore had to call for estimates for the addition of glass windows to several of the Registrar's office in this district, and would suggest that the standard design be improved by the addition of glass windows to the sides of the building not protected by verandahs.

No. 667 T.N.

True copy forwarded to the Inspector-General of Registration for his opinion and for such suggestions as he may consider it desirable to make to Government about the provision of additional glazed shutters to the side windows of the Registrar and Sub-Registrar's rooms where there is no verandah.

2. The undersigned considers that the additional shutters are desirable.

(Signed) J. PENNYCUICK, Lieut.-Col., R.E.,
Superintending Engineer, VI Circle.
14th December 1887.

G. No. 5147.

Submitted to the Government, with the recommendation that glazed shutters be sanctioned, as suggested by the Superintending Engineer, for all offices.

2. Experience has shown that such glazed shutters should also be provided for all record-rooms in addition to the wooden shutters, that substantial doors should be provided in lieu of half venetian and half pannelled doors for record-rooms, and that the walls near windows should be sloped *outwards*, and *not inwards* as is done, as the rain-water gets in through the crevices and finds its way into the record-rooms and offices.

MADRAS,
23rd December 1887.

(Signed) G. HAMNETT,
Inspector-General of Registration.

No. 19 R., Judicial.

Approved and transferred to the Public Works Department.

(By Order.)

Fort St. George,
12th January 1888.

(Signed) A. G. CARDEW,
Under Secretary.

Order—dated 16th January 1888, No. 163 W., Public Works.

Communicated to Superintending Engineers, who will, in future, carry out the recommendations of the Inspector-General of Registration in framing estimates for Registration offices.

(True Extract.)

(Signed) H. R. MEAD, Colonel, R.E.,
Joint Secretary to Govt., P.W.D.

To Superintending Engineers.
To the Consulting Architect to Government.
,, Judicial Department.

Exd. J. Moses.
Spare Copies

655/8

BUILDINGS AND ROADS.
CIVIL WORKS.

Govt. of (1888) Madras.

PUBLIC WORKS.

Dated January, 16th.

Recd. *Encl.*

G.O., 16th Jan. 1888, No. 163 W.

JANUARY.

Registration Offices

Communicating, with instructions, to Superintending Engineers correspondence relative to certain improvements to be made in future in —.

P 1

SUPERINTENDING ENGINEER'S OFFICE,
V Circle, Madras,
Chepâk, 16 January 1887.

No. 2330.

655/9

From
Colonel A. M. Vibart R.E.
SUPERINTENDING ENGINEER, V CIRCLE,

To
THE Inspector General
of Registration
Madras

Enclosures.
1 Site plan.
1 Detail Estimate
1 Abstract Estimate in Duplicate
1 Report

SIR,

With reference to G.O. No. 1368 W dated 18 May 1887, I have the honor to forward to you for disposal an Estimate of Rs 2575 for Constructing a Sub-Registrar's Office at Arkonam prepared on the latest type design approved in G.O. No. 1049 W dated 5th May 1885, with the exception of foundations and roofing; the former is altered from brick in mortar to Concrete block foundations to suit the nature of the soil and the latter to Mangalore Mission tiles instead of Common tiles to harmonise with the

roof

p. 2

roof of the New Sub-Magistrate's Cutcherry in the Compound of which the Sub-Registrar's Office is proposed to be built.

I have the honor to be
Sir,
Your most obedt. servt.

Col. R.E.
Superintending Engineer.
5th Circle

T. N. 71 — 2d February 1888.
Cuddapah.

Submitted for the sanction of the Government.

2. The necessity for constructing a Sub-registry Office at [illegible] was brought to the notice of the Government in my letter T. N. 859 dated the 29 April 1887. The Estimate provides for all that is necessary.

W. Hamnett
Inspr. Genl. of Regn.

To
The Chief Secretary to the Government.

653/10

1359. 22 5-85 [illegible]
[illegible] 1941 [illegible]

P.W.C. No. 1536

CURRENT NO. 46/137

No. 1049 W d/5. 5. 85
" 1368 W d/18. 5. 87
" 163 W d/16. 1. 88

[illegible]

P. 13

Order 14 Feby/88 PPH
No. 168 R 11 Feb

Approved and
transferred to the P.W. Dept.
(By order)

A. G. Cardew.

Under Secy

Judicial (1888) Department

"Registration"

From.

The Inspector General
of Registration
Madras.

To

The Chief Secretary
to the Government
Fort St. George.

Dated 2nd } February 1888.
Received. (4) }
R. 17. 2. 88

I. No. 71

Enclosures. ~~Four~~ 6
(+1 plan)

No.

Subject.

Submitting an estimate from the Superintending Engineer V Circle for the Sub Registrar's Office at Arkonam.

over

C. 9/2
R. 13/2

655/12 P. 4

Note by the Chief Engineer P.W.D.

The estimate amounting to Rs. 2,575 for constructing a sub-registrar's office at Arkonam is submitted for the sanction of Govt. with the remark that the attention of the Supdg. Engr. should be called to G. O. No. 163 W dated 16th January 1888, which refers to certain defects in the standard design that can be easily remedied in actual construction

22. 2. 88

E. W.

22/2/88

655/13

Public Works Department.

Current No. 1536
Letter No. 168R
Dated the 11th February 1888
From the Secy. to Govt. Judicial Depth.

NOTE OF REMARKS.

The estimate under
review, amounting
75
to Rs 2535, provides
for constructing a
Sub Registrar's Office
at Arcoonum in
the North Arcot
district.

The plan of the
building is in
accordance with
the type design
approved in G.O.
No. 1049 W d/5th
May 1885.

The nature of the
soil is stated to be
gravel and earth
for the first yard

11/2/2

in depth and moorum and light rock for the second yard. The foundations are to be of concrete carried down to a depth of 3'-6" with a width of 3' for the main walls.

Mangalore pattern tiles are to be used for the roof in order ~~front~~ it may be in keeping with the roof of the Cutchery building.

The rates are fair. Contingencies and petty supervision are apparently charged for at 5 & 2½ per cent respectively.

The estimate has been countersigned by the Inspector General of Registration and approved by Govt. in the Judicial Dept. 21/2/88

N.B. Perhaps it would be well to mention that the window sills should be sloped so as to fall outwards and that a strong batten door should be substituted for the half venetian & half panelled door provided for the record room in the type design. 21/2/88.

Sanction 655

Note by CW.

The attention of the S.E. should be called to G.O. No. 163 W. d/ 16.1.88, which refers to certain defects in the standard design that can be easily remedied in actual construction.

21. 2. 88.

O.S

PUBLIC WORKS DEPARTMENT.

655/1A

No. 655 W.

PROCEEDINGS OF THE MADRAS GOVERNMENT,

UNDER date the 24th Feby/88

READ the following

From the Inspector General of Registration. H. E. No: 71 d/ 2nd February 1888

Endorsement by the Judicial Department. H. E. No: 168 R d/ 14th February 1888

Note by the Chief Engineer P. W. Department d/ 22-2-88.

The estimate amounting to Rs. 2,575, for constructing a sub-registrar's office at Arkonam in the North Arcot District, is sanctioned for execution when funds are available.

2. Attention is drawn to the note by the Chief Engineer, P. W. Department, above recorded.

3. This sanction has been registered as Provincial No: 175 W of 1887-88, and classified as Civil Buildings, Original Works.

22. 2. 88

22/2/88

To The Suptg. Engr. V Circle with 4 enclos.
" Examiner of P. W. Accts with the duplicate abstract estimate
" Judicial Department.

6/3

22/2

Govt. of {188*8*} Madras.

PUBLIC WORKS.

25/2

Dated

Recd. Encl.

G.O. 24/2/188 No. 655W

Sub Registrar's office at Arkonam

Estimate for constructing a — in the North Arcot District sanctioned with remarks &c.

75/4

8/28/2

820f 27/2