(1) பக்கங்களின் எண்ணிக்கை 42

(2) புதுக்கித் திருப்பிய நாள் May 1988

(3) ஆதாரங்குறிப்பவர் சுருக்கொப்பம்

தமிழ்நாடு ஆவணக் காப்பகம்.

தமிழ்நாடு அரசு

பொதுப்பணித் துறை

அரசாணை எண். / மு. கோப்புத் தாள் எண். — 770—ல — அச்சகம் / பலவகை

நாள் : 7-3-1988

மடிக்கவோ கண்டபடி கையாளவோ கூடாது

ஆவண, கா-1—18,006—15-6-87.

1/770

7TH MARCH 1888, No. 770 W., PUBLIC WORKS.

GOVERNMENT OF MADRAS.

PUBLIC WORKS DEPARTMENT.

Buildings and Roads.
Civil Works.

READ—the following papers:—

Proceedings of the Board of Revenue (Land Revenue), dated 16th December 1887, Mis. No. 5247.

H. S. THOMAS, ESQ., F.L.S., F.Z.S.

READ—the following letter from H. SEWELL, Esq., Collector of South Arcot, to the Secretary to the Commissioners of Land Revenue, dated Vriddháchalam, 19th November 1887, No. 202/87:—

With reference to G.O., dated 21st February 1884, No. 483 W., Public Works, communicated in Board's Proceedings, dated 10th March 1884, No. 839, I have the honor to forward for transmission to Government an estimate for Rs. 21,270 for the construction of a first-class Taluk Cutcherry at Tirukoilúr, and to request that funds may be provided for the work at an early date.

Read—also the following letter from H. SEWELL, Esq., Collector of South Arcot, to the Secretary to the Commissioners of Land Revenue, dated Cuddalore, 1st December 1887, No. 171:—

With reference to paragraph 2 of G.O., No. 483 W., of the 21st February 1884, recorded in Board's Proceedings, No. 839, of the 10th March 1884, I have the honor to submit herewith for transmission to Government an estimate (with plan, &c.), amounting to Rs. 23,945, for constructing a first-class Taluk Cutcherry with out-houses at Tindivanam, received from the Superintending Engineer with his letter, No. 3096 A., of the 1st ultimo.

2. The Executive Engineer suggests the substitution of Portland cement concrete flooring $2\frac{1}{2}$ inches thick laid on a bed of $3\frac{1}{2}$ inches thick ordinary concrete for the square tile and asphalte floors on a bed of 6 inches ordinary concrete as provided for in the sanctioned arrangement.

3. The modification is said to be proposed as the tile flooring will soon wear away and get out of order and as the asphalte will not harden sufficiently to bear heavy weight, in consequence of which the record-racks will sink in the asphalte floor.

4. The substitution of the proposed flooring is said to cost about Rs. 1,330, or about Rs. 80 in excess of the cost of the square tile and asphalte flooring provided for in the estimate.

5. The Superintending Engineer considers the proposed alterations judicious, and I concur with him.

Resolution—dated 16th December 1887, Mis. No. 5247.

The plans and estimates, amounting to Rs. 21,270 and Rs. 23,945, for the construction of first-class Taluk Cutcherries at Tirukoilúr and Tindivanam respectively, are herewith forwarded for the sanction of Government and for the provision of funds in the Public Works Department.

2. It is presumed that in providing jail latrines the Superintending Engineer has attended to the instructions conveyed in paragraph 2 of G.O., dated 20th September 1882, No. 2440 W.

(A true Copy and Extract.)

(Signed) R. S. BENSON,
Acting Secretary.

No. 999, Revenue.

The estimates are approved and transferred to the Public Works Department.

Fort St. George,
11th February 1888.

(Signed) J. F. PRICE,
Secretary to Government.

Note by the Chief Engineer, Public Works Department.

Submitted for the sanction of Government.

2. In the estimate for the Tirukoilúr Taluk office provision has been made for two latrines— a jail latrine in accordance with the standard design issued with G.O., No. 1014, dated 20th April 1874, and a public latrine in accordance with the design circulated with G.O., No. 731, dated 22nd March 1876. In the estimate for the Tindivanam Taluk office three public latrines have been provided, based on the design issued with G.O., No. 731, dated 22nd March 1876.

3. The estimates have been reduced, as shown in the margin, by the omission of the jail latrine in accordance with G.O., No. 2440 W., dated 20th September 1882, and by providing for each taluk office one public latrine, to be built in accordance with the design issued with G.O., No. 1014, dated 20th April 1874.

	RS.		RS.
Tirukoilúr Taluk office, from	21,270	to	20,680
Tindivanam Taluk office, from	23,945	to	22,640

(Signed) H. R. MEAD, Col., R.E.,
Chief Engineer, P.W.D.

Order—dated 7th March 1888, No. 770 W., Public Works.

The undermentioned estimates for Taluk offices in the South Arcot district are sanctioned for execution when funds are available :—

Provincial.
Civil Buildings.
Original Works.

	RS.	
Taluk office, Tirukoilór	20,680,	No. 182 W. of 1887-88.
Taluk office, Tindivanam	22,640,	No. 183 W. of 1887-88.

(True Extract.)

Captain, R.E.,
Under Secy. to Govt., P.W.D.

To the Superintending Engineer, V Circle, with nine enclosures.
" Examiner, Public Works Accounts, with two general abstract estimates.
" Revenue Department.

Exd. J. Moses.

Spare Copies

BUILDINGS AND ROADS
CIVIL WORKS.

Govt. of 1888 Madras.

PUBLIC WORKS.

Dated March, 7th.

Recd. *Encl.*

G.O., 7th March 1888, No. 770 W.

MARCH.

Taluk Offices

Estimates for the construction of — at Tirukoilúr and Tindivanam in the South Arcot district, sanctioned.

3/770

GOVERNMENT OF MADRAS.

PUBLIC WORKS DEPARTMENT.

Buildings and Roads.
Civil and Military Works.

Order—dated 21st February 1884, No. 483 W., Public Works.

In modification of the practice at present followed with regard to the submission of plans and estimates for buildings required by other departments, the Government direct that the following procedure be invariably adopted in future.

2. Plans and estimates for buildings required by the Revenue Department should be submitted by the Executive Engineer to the Superintending Engineer, who, after scrutiny, will forward them to the Collector of the district for approval and counter-signature. If the Collector be satisfied as to the suitableness of the proposed accommodation, &c., he will transmit the papers through the Board of Revenue to Government in the Revenue Department, by whom, if approved, they will be transferred to the Public Works Department for disposal, after final scrutiny by the Chief Engineer.

3. In the case of plans and estimates for court-houses, the documents will be forwarded by the Superintending Engineer to the District Judge for transmission, through the High Court, to Government in the Judicial Department, and the same principle will be followed with regard to estimates for Registration, Police, Jail, and other Civil Departments. The Superintending Engineer will forward the documents to the Head of the Department concerned, who will submit them to Government in the Department of the Secretariat from which he receives his orders.

4. The course at present adopted with regard to estimates for Military buildings is laid down in G.O. No. 1381 W., dated 14th June 1880, but here also a modification of practice appears desirable. In future such plans and estimates will be forwarded by Superintending Engineers for approval to the General Officer Commanding the District or Division. The General Officer will transmit the papers to the Quartermaster-General, who,* after obtaining the approval of His Excellency the Commander-in-Chief, will submit them direct to Government in the Military Department. After approval in the Military Department they will be transferred to the Public Works Department for disposal, after final scrutiny by the Chief Engineer.

5. It must be understood that these orders apply only to works which are beyond the power of sanction of local authorities, and are not intended to alter the procedure laid down in G.O., No. 3211 W., dated 6th December 1882, with regard to the submission of Local Fund projects.

---

* Note.—In the case of Ordnance, Commissariat or other departmental buildings, the approval of the head of the department should be obtained before the plans and estimates are submitted to His Excellency the Commander-in-Chief.

6. The Secretary, Code Committee, will take the necessary steps for embodying these rules in the Public Works Code, in modification of paragraphs 1168 and 1335.

(True Extract.)

(Signed) J. SHAW-STEWART, Colonel, R.E.,
Secretary to Govt., P.W.D.

To Superintending Engineers.
To the Consulting Architect to Government.
" Examiner, Public Works Accounts.
" Public, &c., Departments.
" Revenue Department.
" Military "

Exd. A. Grubert.
Sdare Copies

4/770

BUILDINGS AND ROADS.
CIVIL AND MILITARY WORKS.

Govt. of (1884) Madras.

PUBLIC WORKS.

Dated February, 21st.

Recd. *Encl.*

G.O., 21st Feb. 1884, No. 483 W.

FEBRUARY.

Buildings required by other Departments

Modification of the practice for the submission of plans and estimates for —.

5/770

Annexure to G.O., No. 1495 W., dated 3rd June 1887.

ESTIMATE FORM—Detail Measurements.

Detail of work.	No.	MEASUREMENTS IN FEET.			Area or contents.	Total quantity of each description of work.
		Length.	Breadth.	Depth.		
EXCAVATION FOR FOUNDATIONS.						
Court, outer walls	..	92 0	4 0	4 6	1,656	
Property and private room, end walls	3	5 4½	3 7½	4 6	1,007	
Do. do. outer walls	..	45 7½	3 7½	4 6		
Cashier's, sheristadar's, clerk's room, longitudinal walls	2	70 0	4 0	4 6	5,076	
Do. do. partition	3	15 6	4 0	4 6		
Record room, outer walls	..	95 6	4 0	4 6		
Treasury and inspector's room, &c., outer walls	..	115 9	4 4½	4 6	3,268	
Do. do. inner walls	2	20 4½	4 4½	4 6		
Do. do.	1	9 6	4 4½	4 6		
Jail wards, outer walls	..	173 0	4 0	4 6	3,114	
Do. partitions	4	12 6	3 7½	4 6	816	
Verandah and covered way walls near jail	..	89 0	3 3	4 6	5,404	
Do. in front	..	130 0	3 3	4 6		
Do. in rear and sides of record room	..	150 6	3 3	4 6		
Extra thickness at verandah posts	32	1 1½	0 4½	4 6	64	
Do. do. at corners	5	0 4½	0 4½	4 6		
Do. do.	4	1 10½	0 4½	4 6	13	
Steps	2	12 6	3 0	1 6	214	
Do.	1	11 6	3 0	1 6		
Do.	2	5 6	3 0	1 6		
Total, Cubic feet ..	..	..	..	..	..	20,632
CONCRETE IN FOUNDATIONS.						
Court, outer walls	..	92 0	4 0	1 6	552	
Property and private room, end walls	3	5 4½	3 7½	1 6	336	
Do. do. outer walls	..	45 7½	3 7½	1 6		
Cashier's, sheristadar's and clerk's room, longitudinal walls	2	70 0	4 0	1 6	1,692	
Do. do. partitions	3	15 6	4 0	1 6		
Record room, outer walls	..	95 6	4 0	1 6		
Treasury and inspector's room, outer walls	..	115 9	4 4½	1 6	1,089	
Do. do. inner walls	2	20 4½	4 4½	1 6		
Do. do.	1	9 6	4 4½	1 6		
Jail wards, outer walls	..	173 0	4 0	1 6	1,038	
Do. partitions	4	12 6	3 7½	1 6	272	
Verandah and covered way walls near jail	..	89 0	3 3	1 6	1,800	
Do. in front	..	130 0	3 3	1 6		
Do. in rear and sides of record room	..	150 6	3 3	1 6		
Extra thickness at verandah posts	32	1 1½	0 4½	1 6	26	
Do. do. at corners	5	0 4½	0 4½	1 6		
Do. do.	4	1 10½	0 4½	1 6		
Steps	2	12 6	3 0	1 6	214	
Do.	1	11 6	3 0	1 6		
Do.	2	5 6	3 0	1 6		
Total, Cubic feet ..	..	..	..	..	..	7,019
BRICKWORK IN FOUNDATIONS.						
Footings.						
Court, outer walls	..	92 0	2 3	1 0	207	
Private and property room end walls	3	7 1½	1 10½	1 0	122	
Do. do. outer walls	..	43 10½	1 10½	1 0		
Cashier's, sheristadar's and clerk's room, longitudinal walls	2	71 9	2 3	1 0	658	
Do. do. partitions	3	17 3	2 3	1 0		
Record room, outer walls	..	97 3	2 3	1 0		
Treasury and inspector's room, outer walls	..	115 9	2 7½	1 0	450	
Do. do. inner walls	2	22 1½	2 7½	1 0		
Do. do.	1	11 3	2 7½	1 0		
Jail wards, outer walls	..	173 0	2 3	1 0	389	
Do. partitions	4	14 3	1 10½	1 0	107	
Verandah and covered way near jail	..	92 6	1 6	1 0	565	
Do. in front	..	131 9	1 6	1 0		
Do. in rear and sides of record room	..	152 3	1 6	1 0		
Extra thickness at verandah posts	32	1 1½	0 4½	1 0	17	
Do. do. at corners	5	0 4½	0 4½	1 0		
Do. do.	4	1 10½	0 4½	1 0		
Above footings to ground level, court, outer walls.	..	92 0	1 6	2 0	276	
Private and property room, end walls	3	7 10½	1 1½	2 0	150	
Do. do. outer walls	..	43 1½	1 1½	2 0		

Estimate Form—Detail Measurements—*cont.*

Detail of work.	No.	MEASUREMENTS IN FEET.			Area or contents.	Total quantity of each description of work.
		Length.	Breadth.	Depth.		
BRICKWORK IN FOUNDATIONS—*cont.*						
Footings—cont.						
Cashier's, sheristadar's and clerk's rooms, longitudinal walls	2	72 6	1 6	2 0	891	
Cashier's, sheristadar's and clerk's rooms, longitudinal partitions	3	18 0	1 6	2 0		
Record room, outer walls	..	98 0	1 6	2 0		
Treasury and Inspector's room.						
Outer walls	..	116 9	1 10½	2 0	654	
Do. inner walls	2	22 10½	1 10½	2 0		
Do. do.	1	12 0	1 10½	2 0		
Jail wards, outer walls	..	173 0	1 6	2 0	519	
Do. partitions	4	15 0	1 1½	2 0	135	
Verandah and covered ways near jail	..	94 0	0 9	2 0	569	
Do. in front	..	132 6	0 9	2 0		
Do. in rear and sides of record room	..	153 0	0 9	2 0		
Extra thickness at verandah posts	32	1 1½	0 4½	2 0	34	
Do. at corners	5	0 4½	0 4½	2 0		
Do. do.	4	1 10½	0 4½	2 0		
Extra thickness for plinth for jail wards	..	108 6	0 3	2 0	100	
Inspector's and arms' room	..	47 6	0 3	2 0		
Private and property room	..	43 7½	0 3	2 0		
Total, Cubic feet	..	..	..	..	..	5,843
BRICKWORK IN BASEMENT.						
Court, outer walls	..	92 0	1 6	2 0	275	
Private and property room end walls	3	7 10½	1 1½	2 0	150	
Do. do. outer walls	..	43 1½	1 1½	2 0		
Cashier's, sheristadar's, &c., rooms, longitudinal walls	2	72 6	1 6	2 0	891	
Cashier's, sheristadar's, &c., rooms, longitudinal partitions	3	18 0	1 6	2 0		
Record room, outer walls	..	98 0	1 6	2 0		
Treasury and Inspector's room.						
Outer walls	..	116 9	1 10½	2 0	654	
Do. inner walls	2	22 10½	1 10½	2 0		
Do. do.	1	12 0	1 10½	2 0		
Jail, outer walls	..	173 0	1 6	2 0	519	
Do. partitions	4	15 0	1 1½	2 0	135	
Verandah and covered way rear jail	..	94 0	0 9	2 0	569	
Do. in front	..	132 6	0 9	2 0		
Do. in rear and sides of record room	..	153 0	0 9	2 0		
Extra thickness at verandah posts	32	1 1½	0 4½	2 0	34	
Do. at corners	5	0 4½	0 4½	2 0		
Do. do.	4	1 10½	0 4½	2 0		
Extra thickness for plinth	..	199 7½	0 3	2 0	100	
Dais walls	..	20 9	1 1½	1 6	35	
Steps	..	36 6	3 0	0 6	55	
Do.	..	30 6	2 0	0 6	31	
Do.	..	24 6	1 0	0 6	12	
Do. near jail	2	5 6	3 0	1 0	33	3,494
Deduct—						
Stone in steps	..	..	..	..	..	72
Total, Cubic feet	..	..	..	..	..	3,422
BRICKWORK IN SUPERSTRUCTURE.						
Court, outer walls	..	92 0	1 6	13 3	1,829	
Do. dais walls	..	20 9	1 1½	1 6	35	
Private and property room end walls	3	7 10½	1 1½	8 0	292	
Do. do. half gables	3	7 10½	1 1½	3 0		
Do. do. outer walls	..	43 1½	1 1½	8 0	388	
Cashier's, sheristadar's and clerk's room, longitudinal walls	2	72 6	1 6	13 3	3,955	
Cashier's, sheristadar's and clerk's room, longitudinal partitions	3	18 0	1 6	13 3		
Cashier's, sheristadar's and clerk's room, longitudinal gables	4	21 0	1 6	3 6	441	
Record room, outer walls	..	98 0	1 6	12 0	1,764	
Do. gables	2	18 0	1 6	3 0	162	
Treasury and inspector's room, outer walls, including battlement	..	116 9	1 10½	20 0	4,378	
Treasury and inspector's room, inner walls	2	22 10½	1 10½	15 0	1,624	
Do. do. do.	1	12 0	1 10½	15 0		
Jail wards, outer walls	..	173 0	1 6	12 0	3,114	
Do. partitions	4	15 0	1 1½	12 0	810	
Do. gables at ends	2	18 0	1 6	3 0	162	
Do. do. for partitions	4	18 0	1 1½	3 0	243	19,179

6/770

Estimate Form—Detail Measurements—*cont.*

Detail of work.	No.	MEASUREMENTS IN FEET.			Area or contents.	Total quantity of each description of work.
		Length.	Breadth.	Depth.		
BRICKWORK IN SUPERSTRUCTURE—*cont.*						
Deductions—						
Doors in treasury	8	4 0	1 10½	8 0	750	
Windows do.	6	4 0	1 10½	6 0		
Archway in treasury square portion	1	12 0	1 10½	4 0	90	
Do. semi-circular do.	..	56 6	Area.	1 10½	106	
Doors in court, &c.	17	4 0	1 6	8 0	861	
Do. do.	1	4 0	1 6	7 6		
Do. in private and property room	2	4 0	1 1½	7 6	104	
Windows in do.	2	4 0	1 1½	4 0		
Doors in jail	5	4 0	1 6	7 6	225	
Ventilators in jail	7	4 0	1 6	2 0	84	
Record-room windows	18	1 9	1 6	5 6	260	
Archwork as per details	..	..	..	..	535	3,015
Total, Cubic feet	..	..	..	..	..	16,182
ARCHWORK.						
Over treasury doors and windows	14	5 0	1 10½	1 1½	148	
Do. arch semi-circular	1	21 6	1 10½	1 6	60	
Over doors in court, &c.	18	5 0	1 6	1 1½	152	
Do. and windows in private and property room	4	5 0	1 1½	1 1½	25	
Over doors and end ventilators in jail	7	5 0	1 6	1 1½	150	
Over record-room windows	18	3 0	1 6	1 1½		
Total, Cubic feet	..	..	..	..	..	535
CUT STONEWORK.						
Slabs under posts	48	1 0	1 0	0 6	24	
Steps	..	143 0	1 0	0 6	72	
Slabs under trusses	22	2 0	1 6	0 4	22	
Total, Cubic feet	..	..	..	..	..	118
EARTH FILLING IN BASEMENT.						
Court	1	25 0	18 0	1 6	675	
Dais	1	5 10½	6 9	1 0	40	
Private and property rooms	..	30 9	7 10½	1 6	363	
Clerk's, sheristadar's, &c., rooms	..	68 0	18 0	1 6	1,836	
Treasury and verandah	1	21 0	12 0	1 6	378	
Arms and inspector's room	2	22 10½	8 0	1 6	549	
Jail wards	..	64 0	15 0	1 6	2,340	
Record room	1	40 0	15 0	1 6		
Verandahs	..	170 0	8 3	1 6	2,104	
Do.	..	167 0	5 9	1 6	1,440	
Covered way	1	18 0	13 6	1 6	365	
Total, Cubic feet	..	..	..	..	..	10,090
TEAKWOOD WROUGHT AND PUT UP.						
Court, clerk, sheristadar's, &c., room—						
Five trusses to span 18 feet. Tie beams	5	21 0	0 4	0 7	20	
Five trusses to span 18 feet. Principal rafters	10	11 9	0 4	0 6	20	
Five trusses to span 18 feet. Struts	10	6 9	0 4	0 4	6	
Purlins allowing for halving	..	196 0	0 4	0 6	33	
Wall purlins do.	..	206 0	0 3	0 4	17	
Ridge do.	..	94 0	0 3	0 9	18	
Hip rafters for court	5	17 0	0 3½	0 6	17	
Do. for sheristadar's room	2	15 0	0 3½	0 6		
Common rafters, 18 inches centre to centre	102	12 6	0 3	0 4	154	
Jack rafters for court	48	9 0 Average length.	0 3	0 4		
Do. for sheristadar's room	20	7 0 Average length.	0 3	0 4		
Record-room—						
Three trusses to span 15 feet. Tie beams	3	18 0	0 4	0 6	9	
Three trusses to span 15 feet. Principal rafters	6	9 9	0 4	0 5	8	
Three trusses to span 15 feet. Struts	6	4 9	0 4	0 4	3	
Purlins (allowing for halving)	2	49 0	0 4	0 5	14	
Wall purlins	2	44 0	0 3	0 3	6	
Ridge	1	53 0	0 3	0 8	9	
Common rafters, 18 inches centre to centre	58	10 9	0 3	0 3	42	
Do. do. at ends	4	12 6	0 3	0 3		
Treasury, inspector and arms' room—						
Joists, 18 inches centre to centre	16	14 0	0 3½	0 8	44	
Do. do.	32	9 6	0 3	0 6	38	

Estimate Form—Detail Measurements—*cont.*

Detail of work.	No.	Measurements in Feet.			Area or contents.	Total quantity of each description of work.
		Length.	Breadth.	Depth.		
TEAKWOOD WROUGHT AND PUT UP—*cont.*						
Jail wards.						
Three trusses to span 15 feet. Tie beams	3	18 0	0 4	0 6	9	
Principal rafters	6	9 9	0 4	0 5	8	
Struts	6	4 9	0 4	0 4	3	
Purlins allowing for halving	2	75 6	0 4	0 5	21	
Wall purlins do.	2	75 6	0 3	0 3	9	
Ridge	1	75 6	0 3	0 8	13	
Common rafters, 18 inches centre to centre ..	56	12 6	0 3	0 3	76	
Do. do. do. ..	48	10 9	0 3	0 3		
Covered way.						
One truss to span 15 feet. Tie beam	1	16 6	0 4	0 6	3	
Principal rafters	2	9 9	0 4	0 5	3	
Struts	2	4 9	0 4	0 4	1	
Purlins	2	20 0	0 4	0 5	6	
Do. over posts	2	20 0	0 4	0 4	4	
Ridge	1	20 0	0 3	0 8	3	
Hip rafters	2	15 0	0 3	0 5	3	
Common rafters	18	12 6	0 3	0 3	17	
Jack rafters	8	6 6	0 3	0 3		
Verandah.						
Posts	48	0 6	0 6	7 4	88	
Breastsummers for 9 feet verandah	..	187 0	0 6	0 7½	58	
Do. for 6½ feet do.	..	222 0	0 6	0 6	56	
Hip rafters	4	12 6	0 3	0 6	18	
Do.	1	18 6	0 3	0 6		
Do.	1	15 6	0 3	0 6		
Do.	3	12 6	0 3	0 6		
Ridges	2	11 0	0 3	0 6		
Common rafters for 9 feet verandahs and private and property room 18" centre to centre.	122	13 6	0 3	0 5	199	
Jack rafters for do. do. ..	24	5 6	0 3	0 5		
Do.	4	Average length. 7 6	0 3	0 5		
Do.	12	Average length. 8 6	0 3	0 5		
Common rafters for 6½' verandah 18" centre to centre	102	10 0	0 3	0 4	98	
Jack rafters	28	5 6	0 3	0 4		
Boarding at ends of Jail.						
Verandahs	2	8 0	0 1	3 0	4	
Barge boards for jail and record room gables ..	6	13 0	0 1	0 9	6	
Do.	6	3 0	0 1	1 0	2	
Do. collar piece	3	9 0	0 3	0 4	2	
Barge boards for finials	3	6 6	0 3	0 3	1	
Do. do.	3	1 0	0 8	0 8	1	
Do. do.	6	4 0	2 0	0 1¼	5	
Front Verandah gables.						
Barge boards	4	7 6	0 1	0 7½	2	
Collar pieces	2	7 0	0 2	0 4	1	
Finials	2	6 0	0 3	0 3	1	
Planks	2	2 6	0 1½	1 6	1	
Weather boards for Jail.						
Brackets	4	3 6	0 2	0 2½	1	
Struts	4	3 0	0 2	0 2½		
Breastsummers	2	6 0	0 2	0 2½	1	
Rafters	8	4 6	0 1½	0 2	4	
Planks including overlap	12	6 3	0 3¼	0 9		
Total, Cubic feet ..	..	..	..	..	..	1,185
VENETIAN AND PANEL DOORS WITH FRAMES COMPLETE.						
Outer doors of court, clerk's, sheristadar's, &c., rooms	11	4 0	..	8 0	352	
Private room	1	4 0	..	7 6	30	
Total, Square feet ..	..	..	..	..	..	382
PANELLED DOORS WITH FRAMES.						
Inner doors of court, clerk's, sheristadar's, &c., room	6	4 0	..	8 0	192	
Do. do. do. ..	1	4 0	..	7 6	30	
Total, Square feet ..	..	..	..	..	..	222

2/70

Estimate Form—Detail Measurements—*cont.*

Detail of work.	No.	Measurements in Feet.			Area or contents.	Total quantity of each description of work.
		Length.	Breadth.	Depth.		
WROUGHT IRON GRATED DOORS WITH WOODEN FRAMES.						
For jail wards	5	4 0	..	7 6	150	
Treasury, &c.	8	4 0	..	8 0	256	
Total, Square feet ..	..	..	..	..	..	406
Strong battened shutters for treasury doors without frames	4	3 6	..	7 6	105	Sq. ft.
Strong battened door with frame for property room ..	1	4 0	..	7 6	30	Sq. ft.
VENETIAN WINDOWS WITH FRAMES AND IRON BARS.						
For private and property room	2	4 0	..	4 0	32	Sq. ft.
BATTENED WINDOWS WITH FRAMES AND IRON BARS.						
For arms and inspector's room	6	4 0	..	6 0	144	
For record room	18	1 9	..	5 6	173	
Total, Square feet ..	..	..	..	..	..	317
Teak frames with iron bars for jail ventilators ..	7	4 0	..	2 0	56	Sq. ft.
WROUGHT IRON WORK IN TRUSSES.						
1" diar. king rods for 18 feet trusses	5	8 0	= 40 0	× 2·62	= 105	
1" hex. nut and bolt head for do.	15	..	..	× 1·10	= 17	
3" diar. ⅛" thick washers for do.	10	..	..	× 0·32	= 3	
1½" × ½" heel straps for do.	10	2 9	27 6	× 2·50	= 69	
1½" × ½" bearing plates for 18 feet trusses ..	10	0 6¾	= 5 3¾	× 2·50	= 13	
⅝" hex. nuts for do. do.	20	..	..	× ·267	= 5	
Caps of ⅜" plate 6" wide	5	2 0	= 10 0	× 7·51	= 75	
⅞" diar. kingrod for 15 feet trusses	7	6 7½	= 46 4½	× 2·01	= 93	
⅞" hex. nut and head for trusses	21	..	..	× 0·73	= 15	
3" diar. ⅛" thick washers for trusses	14	..	..	× 0·32	= 4	
1½" × ⅜" heel straps for trusses	14	2 3	= 31 6	× 1·87	= 58	
1½ × ⅜ bearing plate for trusses	14	0 6¾	= 7 10½	× 1·87	= 15	
⅝" hex. nut for trusses	28	..	..	× ·267	= 7	
Caps of ⅜" plate 6" wide	7	1 6	= 10 6	× 7·51	= 79	
Total, lb. ..	..	..	..	..	..	558
TERRACE ROOFING.						
For treasury, inspector's and arms' rooms ..	..	32 9	..	23 10½	782	Sq. ft.
Squares ..	..	..	..	..	..	7·82
TILED ROOFING.						
Court room	..	28 0	..	26 0	2,808	
Clerk's, sheristadar's, &c., rooms	..	80 0	..	26 0		
Record room	..	49 0	..	23 0	1,127	
Jail	..	74 6	..	24 6	1,825	
Covered way	..	15 3	..	25 0	381	
Verandah 9 feet wide	..	210 0	..	12 0	2,520	
Do. 6½ do.	..	182 0	..	9 0	1,638	
Square feet ..	..	..	..	..	..	10,299
Total, Squares ..	..	..	..	..	..	103
FLOORING WITH 8" SQUARE BRICKS.						
Court	1	25 0	..	18 0	450	
Private room	1	7 10½	..	18 9	242	
Property room	1	7 10½	..	12 0		
Clerk's, sheristadar's, &c., room	..	68 0	..	18 0	1,244	
Treasury and verandah	..	22 10½	..	12 0	641	
Inspector's and arms' room, ...	2	22 10½	..	8 0		
Covered way	1	18 0	..	15 0	270	
Verandah 9 feet wide	..	175 0	..	9 0	1,575	
Do. 6½ do.	..	167 0	..	6 6	1,086	
Door pieces	18	4 0	..	1 6	108	
Do.	8	4 0	..	1 10½	60	
Do.	2	4 0	..	1 1½	9	
Square feet ..	..	..	..	..	..	5,685
Total, Squares ..	..	..	..	..	..	56·85

Estimate Form—Detail Measurements—*cont.*

Detail of work.	No.	Measurements in Feet. Length.	Breadth.	Depth.	Area or contents.	Total quantity of each description of work.
Flooring record room and jail with asphalte ¾" thick over a bed of concrete.						
Record room	1	40 0	..	15 0	1,560	
Jail	1	64 0	..	15 0		
Door pieces	5	4 0	..	1 6	30	
Square feet ..	..	..	..	..	..	1,590
Total, Squares ..	..	..	..	..	..	15·90
Plastering interior (two coats).						
Court	..	86 0	..	13 3	1,140	
Private room	..	53 3	..	10 6	559	
Property room	..	19 10½	..	8 0	159	
Do.	2	7 10½	..	10 6	165	
Do.	1	4 1½	..	13 3	55	
Clerk's, sheristadar's, &c., room	..	280 0	..	13 3	3,710	
Gables	9	18 0	..	3 0	486	
Record room	..	110 0	..	12 0	1,320	
Gables	2	15 0	..	2 6	75	
Treasury	..	54 0	..	14 0	3,073	
Do. verandah	..	42 0	..	14 0		
Inspector's and arms' room	2	61 9	..	14 0		
Jail wards	..	278 0	..	12 0	3,336	
Do. gables	10	15 0	..	2 6	375	
Door jambs and soffits	17	20 0	..	1 6	510	
Do. do.	1	19 0	..	1 6	29	
Do. do.	8	20 0	..	1 10½	300	
Do. do.	2	19 0	..	1 1½	43	
Do. do.	5	19 0	..	1 6	143	
Arch do.	..	27 0	..	1 10½	51	
Window do.	5	20 0	..	1 10½	225	
Do. do.	2	16 0	..	1 1½	36	
Do. do.	13	14 6	..	1 6	488	
Ventilator jambs	2	12 0	..	1 6		
Do.	5	8 0	..	1 6		16,278
Deductions—						
Doorways	22	4 0	..	8 0	1,024	
Do.	9	4 0	..	7 6	270	
Archway, square portion	1	12 0	..	4 0	48	
Do. semi-circular portion	1	56 6	Area.	..	57	
Windows	2	4 0	..	4 0	33	
Do.	6	4 0	..	6 0	144	
Do.	18	1 9	..	5 6	174	
Ventilators	7	4 0	..	2 0	56	1,805
						14,473
Square feet ..	..	..	..	..	..	144·73
Total, Squares ..	..	..	..	..	..	
Pointing exterior.						
Court	..	50 9	..	13 3	3,028	
Clerk's, sheristadar's, &c., rooms	..	177 9	..	13 3		
Property and private room	..	62 3	..	7 6	467	
Do. half gables	2	9 0	..	3 0	54	
Record room	..	101 0	..	12 0	1,212	
Do. gable	1	18 0	..	3 0	54	
Treasury and inspector's, &c., rooms	..	124 3	..	21 6	2,671	
Do. inside parapet	..	109 3	..	5 0	546	
Jail wards	..	179 0	..	12 0	2,148	
Do. gables	2	18 0	..	3 0	108	
Basement all round	..	609 0	..	2 0	1,218	11,506
Deduct—						
Doorways	16	4 0	..	8 0	512	
Do.	7	4 0	..	7 6	210	
Archway, square portion	1	12 0	..	4 0	48	
Do. semi-circular portion	1	56 6	Area.	..	57	
Windows	2	4 0	..	4 0	32	
Do.	6	4 0	..	6 0	144	
Do.	18	1 9	..	5 6	174	
Ventilators	7	4 0	..	2 0	56	
End wall, cashier's room	1	21 0	..	16 0	336	1,569
						9,937
Square feet ..	..	..	..	..	..	99·37
Total, Squares ..	..	..	..	..	Per foot lb. × 5	lb. 1,380
Lead sheeting for roof valleys	..	184 6	1 6	× 276		
Mouldings over windows for inspector's and arms' room.	6	6 0	..	..	36	L. ft.

Estimate Form—Detail Measurements—*cont.*

Detail of work.	No.	Measurements in Feet. Length.	Breadth.	Depth.	Area or contents.	Total quantity of each description of work.
Coping for treasury	..	..	..	125	L. ft.	
Railing for dais	..	..	..	23	,,	
Finials over court	..	..	2 in number.			
Painting with three coats of Carson's paint.						
Venetian and panel doors	3	382 0	..	..	1,146	
Panelled doors	2	222 0	..	..	444	
Wrought iron grated doors	2	406 0	..	..	812	
Batten shutters	2	105 0	..	..	210	
Do. do.	2	30 0	..	..	60	
Do. windows	2	317 0	..	..	634	
Ventilators	2	56 0	..	..	112	
Roof timbers including weather boards, &c. ..	..	..	..	..	11,972	
Square feet ..	..	..	..	..	..	15,390
Total, Squares ..	..	..	..	..	..	154
Add extra labor in finishing barge boards and finials.	..	..	5 in number.			
Punkah 10 feet long	..	..	1 ,,			

Estimate Form—Abstract.

Quantity.	Description of work.	Rate.	Per	Amount.	Total.
		RS.		RS.	RS.
20,632 C. feet ..	Excavation for foundation	..	1,000 C. feet.		
7,019 ,, ..	Concrete in foundation	..	100 C. feet.		
5,843 ,, ..	Brickwork in foundations	..	,,		
3,422 ,, ..	Do. in basement	..	,,		
16,182 ,, ..	Do. in superstructure	..	,,		
535 ,, ..	Archwork	..	,,		
118 ,, ..	Cut stonework	..	C. feet.		
10,090 ,, ..	Filling in basement	..	1,000 C. feet.		
1,185 ,, ..	Teakwood wrought and put up	..	C. feet.		
382 Sq. feet.	Venetian and panel doors with frames	..	Square feet.		
222 ,, ..	Panelled doors with frames	..	,,		
406 ,, ..	Wrought iron grated doors with teak frames ..	..	,,		
105 ,, ..	Strong battened shutters for treasury doors without frames	..	,,		
30 ,, ..	Strong battened door with frame for property room ..	..	,,		
32 ,, ..	Venetian windows with frames and iron bars	..	,,		
317 ,, ..	Battened do. do. ..	..	,,		
56 ,, ..	Teak frames with iron bars for jail ventilators ..	..	,,		
558 lb. ..	Wrought iron work in trusses	..	,,		
7·82 Squares.	Terrace roofing	..	lb.		
103 ,, ..	Tiled roofing with flat and pan tiles including teak reepers	..	Square.		
56·85 ,, ..	Flooring with 8-inch square pavement tiles	..	,,		
15·90 ,, ..	Flooring record room and jail with asphalte ¾ inch thick over a bed of concrete	..	,,		
144·73 ,, ..	Plastering interior (two coats)	..	,,		
99·37 ,, ..	Pointing exterior	..	,,		
1,380 lb ..	Lead sheeting for roof valleys	..	,,		
36 L. feet.	Mouldings over windows	..	lb.		
125 ,, ..	Coping for treasury parapet	..	L. feet.		
23 ,, ..	Hand railing for dais	..	,,		
2 in No.	Finials over court	..	,,		
154 Squares.	Painting with three coats of Carson's paint	..	Each.		
5 in No. ..	Add extra labor in finishing barge boards and finials ..	..	Square.		
1 ,, ..	Punkah 10 feet long	..	Each.		
..	Petty supervision	..	,,		
..	Contingencies	..	..		

Madras,
25th April 1887.

(Signed) J. W. BRASSINGTON,
Offg. Consulting Architect to Government.

TAHSILDAR'S CUTCHERRY.

Descriptive Specification.

Foundations.—A depth of 4 feet 6 inches is provided in the quantities, but this should be settled locally in accordance with the nature of the soil.

Walling.—The walls should be carried up in English bond, walls of treasury 2½ bricks thick, court, offices, record room and outer walls of jail 2 bricks thick, jail partitions and verandah rooms near court 1½ bricks. Verandah retaining walls 1 brick thick, except under posts which will be half a brick thicker.

Stonework.—Stone slabs 12″ × 12″ × 6″ with mortice holes 2 inches square and 2 inches deep cut into them into which the verandah posts will be tennoned.

Slabs will also be placed at the bearings of trusses. The steps may also be of stone, if procurable without great expense.

Woodwork.—The doors, windows, weather boards, verandah posts and trusses should be of well-seasoned teakwood, the rafters and other minor roof timbers may be of approved country wood.

Roofing.—The roof of the treasury, arms, and inspector's room will be of pucka terrace. The rest of the building will be covered with flat and pan tiles; if the quality of these are good the usual unsightly "chunam bands" might be dispensed with; all valleys should be protected with sheet lead.

Flooring.—The floor may be of square bricks or stone slabs if the latter are easily procurable. Jail wards and record room floors to be asphalted.

Interior and exterior finishing.—The interior walls will be fine plastered with shell lime or plastered and washed. Where good bricks are obtainable the exterior should be pointed.

Where the soil is damp the space below the flooring should be filled with river sand to a depth of 1 foot at least and the interior walls plastered with Portland cement ½ an inch thick to a height of 3 feet all over above floor level. The exterior plinth should also be plastered with cement.

Finials.—The finials may be of copper, iron or wood.

The different kinds of work to be done will be executed in conformity with the standard specification of the Public Works Department.

(Signed) J. W. BRASSINGTON,
Offg. Consulting Architect to Government.

CHEPÂK,
25th April 1887.

9/770

3RD JUNE 1887, No. 1495 W., PUBLIC WORKS.

GOVERNMENT OF MADRAS.

PUBLIC WORKS DEPARTMENT.

Buildings and Roads.
Civil Works.

READ—the following papers:—

From J. W. BRASSINGTON, Esq., Officiating Consulting Architect to the Government of Madras, to the Chief Engineer, Public Works Department, dated Chepâk, 25th April 1887, No. 95.

In continuation of my letter, No. 1530, dated the 12th March last, I have the honor to submit a revised plan and schedule of quantities for tahsildars' cutcherries.

2. The plan and quantities for deputy tahsildars' cutcherries will follow.

No. 72 D.

Forwarded for the approval of Government in the Revenue Department.

2. The design has already been approved in Committee by the Honorable Members and Secretaries to Government.

6th May 1887. (Signed) J. O. HASTED, Col., R.E.,
Chief Engineer, P.W.D.

G.O., dated 23rd May 1887, No. 2981, Revenue.

Read—endorsement of Public Works Department, dated 6th May 1887, No. 72 D., forwarding, for approval, revised standard design for taluk offices.

Order—dated 23rd May 1887, No. 2981, Revenue.

Approved.

(True Extract.)

(Signed) J. F. PRICE,
Ag. Secy. to Govt.

ORDER—dated 3rd June 1887, No. 1495 W., Public Works.

The revised type design, with schedule of quantities and descriptive specification for a first-class taluk office, will be circulated to officers of the Public Works Department, for information and guidance, in supersession of all previous standard designs for similar buildings.

(True Extract.)

(Signed) J. O. HASTED, Colonel, R.E.,
Secretary to Govt., P.W.D.

To Superintending Engineers.
" the Consulting Architect to Government.
" the Revenue Department.

Exd. P. L. Pereira.
Spare Copies

BUILDINGS AND ROADS.
CIVIL WORKS.

Govt. of {1887} Madras.

PUBLIC WORKS.

Dated June, 3rd.

Recd. *Encl.*

G.O., 3rd June 1887, No. 1495 W.

JUNE.

Taluk Office

A revised type design for a first-class —, circulated to officers of the department.

---

770 W C No 1564

Reg. No.

10/770 [illegible] 5.iii.88

The estimates have been revised as directed. The amount of the Estimate for the Taluk Cutcherry at Tirukoilur is reduced from Rs 21,270 to Rs 20,680 or a saving of Rs 590 has been effected; that of Tindivanam has been reduced from Rs 23,945 to Rs 22,640 showing a saving of Rs 1305 making an aggregate saving of Rs 1895.

~~The~~ estimates have been altered in pencil ~~which~~ will be inked if approved.

24.2.88.

Take in the alterations; and Sanction the Est.

[illegible]

Public Works Department

Public Works Department

Current No. 1569

Letter No. 999

Dated the 11th February 1888

From the Secy. to Govt. Rev. Deptt.

NOTE OF REMARKS.

The estimates under review amounting to Rs 21,270 & Rs 23,944 provide for constructing First Class Taluk Cutcherries at Tirukoilur and Tindivanam in the South Arcot District.

From the report it would appear the main building has been planned in accordance with the design circulated with G.O. No 1495W d/ 3rd June 1887 for both cutcherries

The Privy shed and Cookroom in both instances accord with the Standard design circulated with G.O. No 1014 d/20th ~~March~~ April 1874 –

Two Latrines are provided for the Tirukoilur Cutcherry, the jail Latrine is in accordance with Standard design ci. with G.O. No 1014 d/20/3/74 and the public Latrine is taken from the design issued with G.O. No 731 d/22nd March 1876

In the case of the Tindivanam Cutcherry 3 public latrines only are provided & all of them are to be like the one issued with G.O. No 731 d/22nd March 187

It is not understood why the type plan for public latrines issued with G.O. No 731 d/22nd March /76 should have been selected as it has apparently no connection with Cutcherry buildings, moreover latrines for sub jails are considered unnecessary vide Pro: of the Board of Revenue Mis: No 6818 d/2nd Septr /82 embodied in G.O. No 2440 W. d/20th Septr 1882.

It may be well to return the Estimates to S.E. with a request that the jail latrine be omitted vide G.O. No 2440 W d/20/9/82 and that only one Public Latrine should be provided for in the estimate for each Cutcherry designed in accordance with the type plan circulated with G.O. No 1014 d/20/3/74.

Some of the rates are slightly in excess of the rates given in the District Schedule but the Supg: Engr has submitted special rate sheets for these estimates the necessity for which is open to question as the work to be done is only of an ordinary kind.

Land Compensation amounting to Rs 2000 for Tindivanam & Rs 50 for Tirukoilur

is provided in the estimates also Rs 200 for forming a road, Rs 275 for sinking a well of 6' diameter, Rs 60 for a shed for destitutes, and Rs 200 for forming a Karakapilly hedge with ditch –

The latter item seems high; the particulars of the roads & wells should have been furnished, in fact details of measurements for the entire estimate should have been submitted in each case which has not been done, but required by the P.W. Code vide paras 918 & 949....

The estimates are countersigned

by the Collector and approved by Govt. in the Revenue Deptt.:-

24/2/88

The Estimates should be revised in this Office, allowing one Latrine for each Cutcherry of the design furnished with GO 1014 of 20th April 1874

An approximate cost for these Latrines only is required & I think the amount is 600 Rs. each

24-2-88

SOUTH ARCOT.

Ref on Engr R NO. 202/87

1/270

COLLECTOR'S OFFICE,
Camp: Vriddhachalam
19th November 1887.

BOARD'S GEN. REG. No 2651 OF 1887
LAND REVENUE.

FROM

Henry Sewell Esquire
COLLECTOR OF SOUTH ARCOT.

P. 1

TO

THE SECRETARY TO THE
COMMISSIONER OF
Land Revenue
MADRAS.

SIR,

With reference to G. O dated 21st February 1884, No 483 W, Public works Communicated in Board's Proceedings dated 10th March 1884 No 839, I have the honor to forward for transmission to Government an estimate for Rs 21,270 for the construction of a first class Taluq Cutcherry at Tirukoilur and to request that funds may be provided for the work at an early date.

I have the honor to be
Sir,
Your most obedient servant

Deputy Collector
for Collector

L.K.

E.S.
LW. 1569/88

b
Rev: 10238/88

SOUTH ARCOT.

NO. 171 15/770

COLLECTOR'S OFFICE,
Cuddalore
1st December 1887.

BOARD'S GEN. REG. No. 2775 OF 1887
LAND REVENUE

FROM
Henry Sewell Esquire,
COLLECTOR OF SOUTH ARCOT.

TO
THE SECRETARY TO THE
COMMISSIONER OF
Land Revenue
MADRAS.

SIR,

1 With reference to para 2 of G. O No 483 W. of the 21st February 1884 recorded in Board's Proceedings No 839 of the 10th March 1884 I have the honor to submit herewith for transmission to Government an estimate[x] amounting to Rs 23945 for constructing a first Class Taluq katcheri with out houses at Tindivanam received from the Superintending Engineer with his letter No 3096A of the 1st Ultimo.

[x] with plan &c.

2. The Executive Engineer suggests the substitution of Portland Cement

Cement Concrete flooring 2½" thick laid on a bed of 3½" thick ordinary Concrete for the Square tile and asphalte floors on a bed of 6" ordinary Concrete as provided for in the Sanctioned arrangement.

3. The modification is said to be proposed as the tile flooring will soon wear away and get out of order and as the asphalte will not harden sufficiently to bear ~~away~~ heavy weight in consequence of which the record racks will sink in the asphalte floor.

4. The Substitution of the proposed flooring is said to cost about Rs 1330 or about 80 Rs in excess of the Cost of the Square tile and asphalte flooring provided for in the Estimate.

5. The Superintending Engineer considers the proposed alterations

judicious and I concur with him.

16/770

I have the honor to be
Sir
Your most obedient Servant

Collector

Cllo.
2.1.57

E. 2
Rd 1569/

5
Rev. CO 238/87

17/770

3P

Proceedings of the Board of Revenue

(Land Revenue).

Dated 16th December 1887.

No. 5247. Miscellaneous.

H. S. Thomas Esquire F.L.S., F.Z.S.

READ letters from the Collector of South Arcot dated 19th November and 1st December 1887, Reference on Engr. R No. $\frac{202}{87}$ and No. 171 respectively.

Resolution.

The plans and estimates amounting to Rs 21,270 and Rs 23,945 for the construction of first class Taluk Cutcherries at Tirukoilur and Tindivanam respectively are herewith forwarded for the sanction of Government and for the provision of funds in the P.W.D.

2. It is presumed that in providing jail latrines the Superintending Engineer has attended to the instructions conveyed in para 2 of G.O. dated 20th September 1882 No. 2440 W.

(True Extract.)

+ Put up with 583 W. of Apl/88 in Works.

R W Benson
Ag Secretary.

To The Secretary to Government R.D,
with letters and enclosures in original blue returned.

Copy to the Collector of South Arcot.

BP

18/770

4 P

Endorsement No. 999

The estimates are approved and transferred to the Public Works department.

Secretary to Govt.

Fort St. George }
8th February 1888 }

No. 483 W d/21-2-84
- 3034 W d/10-12-84
- 3035 W d/10-12-84
- 734 W d/24-3-85
- 644 W d/5-3-87
- 1493 W d/3-6-87
- 3376 W d/8-12-87
- 40 W d/4-1-88
- 2440 W d/20-9-82

To The Public Wks. Depts. with 4 encs. to be retd.
- Commissioner of L. Rev.

PWC No. 1569

(1888.)

REVENUE DEPARTMENT.

No. 6238

From The Board of Revenue
(Land Revenue.)

Dated 16th December } 1887
Received 17th December }
18.2.88
Enclosures 14 (+2 plans)

No. 5247 mis.

SUBJECT.

Submitting with remarks for the sanction of Govt. & for provision of funds in the P.W.D. the plans and estimates amounting to Rs. 21270
22,640
& Rs. 23945 for the construction of first class Taluk Cutcheries at Tirukoilur & Tindivanam S. Arcot Dt.

Endorsement.

19/770

5 P

Note by the Chief Engineer P. W. D.

Endt. by the Rev. Dept. No. 999 d/ 11th Feby 1888, on R. Bd's Pro. No. 5247 d/16-12-87

Submitted for the sanction of Govt.

2. In the estimate for the Tirukoilur Taluk office, provision has been made for two latrines, - a jail latrine in accordance with the standard design issued with G. O. No: 1014 d/ 20 April 1874, and a public latrine in accordance with the design circulated with G. O. No: 731 dated 22nd March 1876. In the estimate for the Tindivanam Taluk office three public latrines have been provided, based on the designs issued with G. O. No: 731 d/22nd March 1876.

3. The estimates have been reduced as shown in the margin* by the omission of the jail latrine in accordance with G. O. No: 2440 W d/20 September 1882, and by providing for each taluk office one public latrine to be built in accordance with the design issued with G. O. No: 1014 d/20th April 1874.

3. 3. 88

E. W.

* Tirukoilur taluk office,
~~Estimate reduced~~ from Rs 21,270 to Rs 20,680
Tindivanam taluk office,
~~Estimate reduced~~ from Rs. 23,945 to Rs. 22,640

No. 70 W

PUBLIC WORKS DEPARTMENT.

PROCEEDINGS OF THE MADRAS GOVERNMENT.

UNDER date the 7th March /88

READ the following

From the Collector of S. Arcot Nos 202/87 & 171 dt 19th Novr & 1st Decr 1887
Proceedings of the Board of Rev. " No 5247 Mis dt 16 Decr 1887
Endorsement by the Rev. Deptt " No. 999 dt 11 Feby 1888
Note by the Chief Engr. P.W.D. " No. dt

The undermentioned estimates for taluq offices in the South Arcot District are sanctioned for execution when funds are available.

Provincial

Civil Buildings

Original works

Taluq Office, Tirukoilur
Rs. 20,680 No. 182 W of 1887-88

Taluq Office, Tindivanam
Rs. 22,640 No. 183 W of 1887-88

D 19/3

To

The Supg. Engr. I Circle
with 9 Enclos.
" Exr. P.W.D. with 2 general abstract estimates
" Rev. Deptt.

3.3.88

3/3/88

HW 5. III. 88 R. 7-3-88

Govt. of {1888} Madras.

PUBLIC WORKS.

Dated Recd 9/3/88

Encl. Encl.

G.O., 7th Mch 1888 No. 770 W.

Taluq offices

Estimates for ~~[illegible]~~ the construction of — at Tirukoilur & Tiruvanna in the South Arcot Dt.

Sanctioned.

1/5