(1) பக்கங்களின் எண்ணிக்கை 60

(2) புதுக்கித் திருப்பிய நாள் [illegible] 1988

(3) ஆதாரங்குறிப்பவர் சுருக்கொப்பம்

தமிழ்நாடு ஆவணக் காப்பகம்.

தமிழ்நாடு அரசு

பொதுப்பணித் துறை

அரசாணை எண். — 786 W — அச்சகம்

மு. கோப்புத் தாள் எண். — பலவகை

நாள் : 9-3-1988.

மடிக்கவோ கண்டபடி கையாளவோ கூடாது

ஆவண. கா-1—18,006—15-6-87.

1/786

9TH MARCH 1888, No. 786 W., PUBLIC WORKS.

GOVERNMENT OF MADRAS.

PUBLIC WORKS DEPARTMENT.

Buildings and Roads.
Civil Works.

READ—the following papers :—

From H. R. GRIMES, Esq., Inspector-General of Jails, to the Chief Secretary to Government, dated Madras, 3rd January 1888, No. 3.

I have the honor to forward, for sanction and provision of funds, three plans and three estimates, amounting to Rs. 10,060, for constructing twelve cells in two blocks for lunatics in the District Jail at Calicut at a cost of ... ... Rs. 4,900

Adding four solitary cells to existing cells	„ 2,630
Adding four cells to existing condemned cells	„ 2,530
Total ...	„ 10,060

2. The necessity for additional cells for lunatics in this jail has already been fully discussed and admitted.

3. The necessity for the other two additions has been brought to my notice by the official visitors. There are at present only two cells for condemned prisoners and two for solitary confinement when this punishment is awarded judicially; they are situated in separate compartments on each side of the inner entrance to the jail, and, as there are frequently, or I may say generally, four condemned prisoners at a time in this jail, the whole of the cells are used as condemned cells. Sentences of solitary confinement cannot therefore be given effect to, except by transferring prisoners with such sentences to other jails, viz., to Cannanore or Coimbatore, which involves expenditure; it is therefore necessary to increase the number of cells for both classes of prisoners by four additional cells.

No. 34 R., Judicial.

Approved and transferred to the Public Works Department.

(By Order.)

FORT ST. GEORGE,
16th January 1888.

(Signed) A. G. CARDEW,
Acting Under Secretary.

From J. W. MARTIN, Esq., Officiating Superintending Engineer, IV Circle, to the Chief Engineer, Public Works Department, dated Coimbatore, 24th February 1888, No. 68 E.W.

I have the honor to return, duly corrected, the plans and estimates for constructing twelve cells in two blocks for lunatics, and for adding four cells to each of the existing solitary and condemned cells in the District Jail at Calicut, received with your memorandum, No. 418 C., dated 1st instant.

2. The estimates have been reduced from Rs. 10,060 to Rs. 9,280 by omitting the wooden ceilings to the roof and by decreasing the depth of concrete in flooring from 6 to 4 inches. The Jail Superintendent assents to the omission of the ceilings.

3. The site plan of the jail and the report, together with the letter of the Inspector-General of Jails forwarded with your memorandum, are also herewith returned. Three abstracts of the estimates were forwarded to the Inspector-General of Jails for transmission to Government with other documents, but were not received with your memorandum under reply.

Order—dated 9th March 1888, No. 786 W., Public Works.

The revised estimate, amounting to Rs. 9,280, for constructing twelve cells in two blocks for lunatics and for adding four cells to each of the existing solitary and condemned cells in the District Jail at Calicut, is sanctioned in supersession of the estimate of Rs. 5,820 sanctioned in G.O., No. 1710 W., dated 27th June 1887.

2. A sum of Rs. 4,820 has been provided for the work in the Provincial budget for 1888-89.

3. This sanction has been registered as Provincial, No. 185 W. of 1887-88, and classified as Civil Buildings, Original Works.

4. The Inspector-General of Jails will be requested in the Judicial Department to transmit to this department the three abstract estimates referred to by the Superintending Engineer in paragraph 3 of his letter.

(True Extract.)

Captain, R.E.,
Under Secy. to Govt., P.W.D.

To the Superintending Engineer, IV Circle, with eleven enclosures.
" Examiner, Public Works Accounts.
" Judicial Department.

Exd. J. Moses.
Spare Copies.

BUILDINGS AND ROADS.
CIVIL WORKS.

Govt. of {1888} Madras.

PUBLIC WORKS.

Dated March 9th.

Recd. *Encl.*

G.O., 9th March 1888, No. 786 W.

MARCH.

District Jail at Calicut

Revised estimate for constructing 12 cells in two blocks for lunatics and adding 4 cells to each of the existing solitary and condemned cells in the —, sanctioned with remarks.

Bd/767

27th June 1887, No. 1710 W., Public Works.

GOVERNMENT OF MADRAS.

PUBLIC WORKS DEPARTMENT.

Buildings and Roads.
Civil Works.

Read—the following letter from H. R. GRIMES, Esq., Inspector-General of Jails, to the Chief Secretary to Government, dated Ootacamund, 16th May 1887, No. 170 :—

I have the honor to transmit the revised plans and estimates, amounting to Rs. 5,820, for constructing twelve new cells for lunatics at the district jail at Calicut.

2. These estimates have been framed with reference to the orders noted in the margin, and, should the Government be pleased to sanction the estimate, I beg that the outlay may be included in the Provincial service budget estimate of the Public Works Department.

G.O., No. 1932, dated 22nd July 1886, J.D.
G.O., No. 2030 W., dated 13th August 1886, bearing Judicial No. 2211, dated 19th August 1886.
G.O., No. 2588, dated 28th September 1886.

Approved, and transferred to the Public Works Department.

(By Order.)

Ootacamund,
1st June 1887.

(Signed) A. G. CARDEW,
Under Secretary, Judicial Dept.

Note by the Chief Engineer, Public Works Department.

The revised estimate, amounting to Rs. 5,820, for constructing twelve new cells for lunatics at the district jail, Calicut, is submitted, for the sanction of Government, with the following remarks :—

1. The compound wall need not be founded at a greater depth than 2 feet 6 inches, of which 6 inches may be concrete.

2. The nature of the soil should invariably be stated when foundations have to be considered.

23rd June 1887.

(Signed) J. O. HASTED, Colonel, R.E.,
Chief Engineer, P.W.D.

Order—dated 27th June 1887, No. 1710 W., Public Works.

The revised estimate, amounting to Rs. 5,820,* for constructing twelve new cells for lunatics at the district jail, Calicut, is sanctioned in lieu of the estimate of Rs 3,200 for four such cells sanctioned in G.O., No. 926 W., dated 18th April 1885.

2. Attention is drawn to the note by the Chief Engineer, Public Works Department, above recorded.

* Includes Rs. 345, being the value of convict labor.

3. A sum of Rs. 1,800 was provided for the work in the current year's Provincial budget, and a further appropriation of Rs. 1,400 was made in the orders on the statements of demands on the reserve with the Government under Provincial.

4. The sanction accorded in paragraph 1 of these proceedings has been registered as Provincial, No. 42 W. of 1887-88, and classified as Civil Buildings, Original Works.

(True Extract.)

Captain, R.E.,
Under Secy. to Govt., P.W.D.

To the Superintending Engineer, IV Circle, with seven enclosures.
" Examiner, Public Works Accounts, with the duplicate abstract estimate.
" Judicial Department.

Exd. E. Fernandez.
Spare Copies

4/780

BUILDINGS AND ROADS.
CIVIL WORKS.

Govt. of {1887} Madras.

PUBLIC WORKS.

Dated June, 27th.

Recd. *Encl.*

G.O., 27th June 1887, No. 1710 W.

JUNE.

District Jail, Calicut

The revised estimate of Rs. 5,820, for constructing twelve new cells for lunatics at the —, sanctioned with remarks.

5/786

28th September 1886, No. 2588, Judicial.

GOVERNMENT OF MADRAS.

JUDICIAL DEPARTMENT.

Read,—the following paper :—

From H. R. GRIMES, Esq., Inspector-General of Jails, to the Chief Secretary to Government, dated Madras, 8th September 1886, No. 250.

With reference to paragraph 1 of G.O., dated 22nd July 1886, No. 1932, Judicial, I have the honor to state the Superintendent of the District Jail at Calicut reports that, in consultation with the Executive Engineer, Malabar, he finds the only available site for the proposed cells is that on which the two temporary insane sheds now stand; but that the best site would be just outside the hospital compound wall northward—*vide* jail plan already forwarded.

2. This plan was forwarded to Government with my letter, dated 1st June 1886, No. 155.

Order—dated 28th September 1886, No. 2588, Judicial.

Communicated to the Public Works Department, in continuation of G.O., 22nd July 1886, No. 1932.

2. The question of site will be determined by the Superintendent of the District Jail, Calicut, in consultation with the Executive Engineer, but no permanent structures should be interfered with.

(True Extract.)

Chief Secretary.

To the Public Works Department.
„ Inspector-General of Jails.

Exd. A. Raitt..

2442 w 22.9.86. 2147 w 26.8.86.
2030 w 13.8.86
926 w 18.4.85
1594 w 23.6.86
33 w 6.1.86
2876 w 18.11.84

P.W.C. No. 7752

No. 2032 W d/ Octr 8. 1886

B.

Commd. to the S.E. IV Circle in ~~continuation~~ of G.O. No. 2030 W d/ 13th August 1886

Govt. of {1886} Madras.

JUDICIAL.

13.S.C

Issued

Recd. 6-10-86 Encl.

G.O., 28th Sept. 1886, No. 2588.

No. 2632 W d/ Octr 8. 1886

Lee
5/10/86

Jole
5/10/86

SEPTEMBER.

Calicut Jail.

Communicating, with remarks, to the Public Works Department, a letter from the Inspector-General, regarding the best site for the cells for lunatics in connection with the —.

To S.E. IV Circle
– for C. Deptr
Despd. 9-10.86

2 Copies to [illegible]
W. Marden

6/786

Public Works Department.

Current No. 4234
Letter No. 2123
Dated the 1st June 1887
From the Secy. to Govt. Judicial Deptt:

NOTE OF REMARKS.

The revised plans and Estimates under review provide for constructing 12 new cells for lunatics at the District Jail at Calicut at a cost of Rs 5820.

2 The plans and Ests. have been revised in accordance with the Chief Engineers note of 13th July /86 embodied in G.O. 1932 d/23rd July 1886 but the first remark regarding the nature of the soil is not explained

3 The cells are to be built in a line the dimensions of each cell are 12' × 7'

G. 21.6.87.

There will be 12 such cells with a verandah in front 4 feet wide. The foundations consisting of laterite in mortar are to be 3 feet deep 2 or 2½ feet wide for sides & main walls, laid on a bed of concrete 2 feet thick, the basement will be 1½ feet high and 2 feet wide. The height of the main walls is to be 11¾ feet up to roof and 1½ ft wide, and the cross walls 1 foot wide carried up to the roof, the materials to be used are laterite in mortar to ~~the~~ be pointed outside and plastered inside 2 coats.

The roofing will consist of couples with collar pieces reepers &c with a ceiling of ¾ inch cedar

planks. The flooring of the rooms and verandah is to be of Asphalte ¾" laid on 4" of concrete.

The timber to be used is Irool or Karamaradu to be coated with wood oil 2 coats, the doors and ~~windows~~ ventilators will be painted 2 coats of common paint. Scantlings are correct.

The foundations of the proposed compound wall, which is only 5 feet in height, appears to be carried down to an unnecessary depth, 2 feet of laterite in mortar laid on 1 foot of concrete should be ample instead of 3 feet of the former & 2 feet of the latter which makes the foundations 5 deep as the wall is high.

A lump sum of Rs 240 is charged in the estimate for 12 weather boards which amount cannot be checked in this Office as the data is not given –

The work is to be carried out in accordance with the Standard Specification vide para 12 of the report.

Convict labor to the amount of Rs 345 is to be employed on the works vide foot note to abstract Estimate.

The plan and Estimate have not been counter-signed but approved by the Judicial Dept:

The site has been selected in consultation with the Superintendent

7a

of the Jail at Calicut. The site being Govt: land no compensation will have to be made.

Contingencies and Superintendence are charged in the Estimate at 3 & 2 per cent respectively

14/6/87

The plan & Est may be sanctioned.

Note by the Chief Engineer.

The compound wall need not be founded at a greater depth than 2'6" of which 6" may be concrete. The nature of the soil should invariably be stated, when foundations have to be considered.

14.6.87

B

1710 W

No. 170 & 8/86 Office of Inspr. Genl. of Jails

Ootacamund 16th May 1887

CURRENT NO. 2/23

From,

Henry. R. Grimes Esqre.

Inspector Genl of Jails

To

The Honble H. E. Stokes

Ag. Chief Secretary to Government

Ootacamund

G. O. No. 1932 d/ 22nd July 1886 J. D. ×

G. O. No. 2030 W. d/ 13th August 1886 bearing Judl. No. [illegible] d/ 17th August 1886 ×

G. O. No. 2358 d/ 28th September 1886 ×

Sir,

I have the honor to transmit the revised plans and Estimates amounting to Rupees 5820 for constructing 12 New Cells for lunatics, at the district jail at Calicut

These estimates have been framed with reference to the Orders noted in the margin, and should the Government be pleased to sanction the Estimate, I beg that the outlay may be included in the Provincial Service Budget Estimate of the Public Works Department.

I have the honor to be

Sir

Your most Obedient Servant

Henry R. Grimes

Inspector General of Jails

7/786

E.1/PN4234/67

10/786

p. 2081 – 21 – 9 – 86.
pu 2211 – 19 – 8 – 86
Br 2030 W – 13 – 8 – 86.
p. 1932 – 22 – 7 – 86
p. 1505 – 16 – 6 – 86.
m 842 – 17 – 3 – 87
J.O. 2632 W 8.10.86 G.O. 2876 W
G.O. 926 W 18.6.85 918.11.86
" 1544 W 23.6.86 " 3347 6.1.86
G.O. 2267 W 26.8.86
G.O. 3347 6.1.86
" 2876 W 18.11.86
" 1544 W 23.6.86

Ootacamund
1st June /87

p3

Approved and transferred to the Public Works Dept.

(By order)

D. G. Carden.
Under Secy.

G.O. 2030 W d/ 13.8.86

To the C. E. D.
copy to I.G. of Jail Dept.

C 26/5
R 27/5 Resubmitted 21.6.87

CURRENT NO. ~~2123~~

P.W.C. No. 4234

~~JUDICIAL.~~

Jail (1887,) Department.

FROM Henry R. Grimes Esqre
~~The~~ INSPECTOR-GENERAL
OF JAILS,
Ootacamund

TO The Honble H. E. Stokes
~~The~~ CHIEF SECRETARY
TO GOVERNMENT.
Ootacamund

Dated 16th } May 1887.
Received ~~"~~ }

R 4.6.87

No. 140

ENCLOSURES ~~4~~ 9
4 (+3 plans)

SUBJECT.

Transmitting revised plans and Estimates amounting to Rupees 5820 for Constructing 12 New Cells for Lunatics at the Dist Jail at Calicut for Sanction

---

11/786

Note by the Chief Engineer P. W. D.

—

The revised estimate amounting to Rs. 5,820, for constructing 12 new cells for lunatics at the District Jail, Calicut, is submitted for the sanction of Govt with the following remarks:-

1. The compound wall need not be founded at a greater depth than 2 ft 6 in of which 6 in. may be concrete.

2. The nature of the soil should invariably be stated when foundations have to be considered.

Ootc. 23/6/87
E. W.

21.6.87

12/786

B + Roads
Civil works

PUBLIC WORKS DEPARTMENT.

No. 1710 W

A/

PROCEEDINGS OF THE MADRAS GOVERNMENT.

UNDER date the 27th June/87.

READ the following

From the Inspector General of Jails. H. E. No: No: 170 d/ 16th May 1887
Endorsement by the Judicial Department. H. E. No: — d/ 1st June 1887
Note by the Chief Engineer P. W. D. d/ 23rd June/87

5

The revised estimate amounting to Rs. 5,820* for constructing 12 new cells for lunatics at the District Jail, Calicut, is sanctioned in lieu of the estimate of Rs. 3,200 for 4 such cells sanctioned in G. O. No: 926 W d/ 18th April 1885

* Includes Rs 345 being the value of convict labor

2. Attention is drawn to the note by the Chief Engineer P. W. Department above recorded.

3. A sum of Rs 1,800 was provided for the work in the current year's Provincial budget, and a further appropriation of Rs 1,400 was made in the orders on the statements of demands on the reserve with the Govt. under Provincial.

4. The sanction accorded in para 1 of these Proceedings has been

21.6.87 [illegible]

DW/W

registered as Provincial No: 42 W of
1887-88, and classified as Civil
Buildings, Original Works.

WCB
21.6.87

Jou
23/6/87

7 / 13
cm
27/6/87
W 27/6

D 6/7

To The Supty. Engr. IV Circle with 7 encls.
" Examiner of P. W. Accts with the duplicate abstract estimate
" Judicial Department.

W 21/6

Co. 21. 6-87

27-6-87

13/786

4234.

Govt. of {1887} Madras.

PUBLIC WORKS.

Dated

Recd.

G.O. 27th June 1887, No. 1710 W

District Jail, Calicut

The revised estimate of Rs 5,820, for constructing 12 new cells for lunatics at the — sanctioned with remarks

10/5

---

[25]

Judicial Department.

14

CHIEF SECRETARIAT, MADRAS.

PROCEEDINGS OF THE MADRAS GOVERNMENT.

READ the following paper

From the Inspector General of Jails, No: 291. D/ 12 August 87

Government sanctioned on 1 June 188 revised plans and estimates amounting to Rs 582 for constructing 12 new cells for lunatics at the District Jail at Calicut, and the site it was intended to erect them on, is shown on the accompanying tracing marked in yellow. This site however has been used as the Jail burial Groun and has been recently used for this purpose. The District Judge on visiting the Jail recently remarked in the Official visitors' book that the proposed site is most objectionable, and that the only one available is that on which the temporary lunatic shed now stands. The Executive Engineer, in a letter to the Superintendent of the Jail, states that to build the new cells on that site would involve demolishing the existing hospital, kitchen, and latrine, and rebuilding them elsewhere, and in order to do this a new estimate and plan and sanction of Government will be required, as he is precluded by the

Rules, from altering any existing structure or building any new one without express sanction.

2. I quite agree with the District Judge that it is most objectionable to build the cells on the site of the burial ground, and I should have liked the cells built in two blocks of 6 each; as marked on the tracing in blue pencil, however as the District Judge considers the only available site is that of the temporary shed, I have no objection to the new cells being built on that site, the existing kitchen and latrine being demolished, and smaller ones being built on the sites marked in blue, or behind the hospital itself, and I request that Government will sanction the Executive Engineer putting the new cells on the site of the temporary shed now occupied by lunatics. There ought to be a considerable saving on the estimate by this arrangement, as the walls and gateway to the former site (the burial ground) will not now be required, and the two new buildings which will have to be erected in lieu of those demolished, should not cost as much as the walls and gateway would have done.

3. I request that early orders may be passed on this subject.

4. I forward the correspondence I have received from the Superintendent, which I request may be returned with the order.

Order 26 August 1887 No: 1940.

The Government consider that the site indicated by the Inspector General is preferable to that proposed by the District Judge. The 12 cells should, accordingly, be built in two blocks of six each, as marked in blue pencil on the tracing, and orders will be issued in the Public Works Department for the preparation of fresh plans and estimates in accordance with this decision. The temporary shed can, under this arrangement, be left standing until the new cells are ready.

2. The Government do not understand the Superintendent's explanation of the mistake which has occurred in this matter. In December 1886 it appears that the Inspector General and Superintendent selected a site within the Jail walls and yet the Executive Engineer has been allowed by the Superintendent to frame plan and estimate on the understanding that the site selected was outside the Jail, while that site has during the same period, been used as a burial ground. Dr Cook appears to have exercised very insufficient care in a

Matter

Matter which he describes as very urgent.

(True Extract)

H Etches

Ag Chief Secretary

To

The Public Works Department
The Inspector General of Jails

Xd S.D.

G. O. 1710 W. 27. 6. 87
" 2632 W. 8. 10. 86
B. No 2442 W. 22. 9. 86
" 2030 W. 13. 8. 86
G. O. 926 W. 18. 4. 85
" 1594 W. 23. 6. 86
B. No 2147 W. 26. 8. 86
G. O. 33 W. 6. 1. 86
B/No 2432 W. d/8th Sept 1887

Communicated to the Supdg. Engineer IV circle who will submit fresh plans and estimates in lieu of those sanctioned in G. O. No 1710 W dated 27th June 1887.

3. 9. 87

5/9/87

8-9-87

9/9

S. E. IV circle
Exr. P. W. Accts.

9/9

Q. 3. 9. 87. P. 7. 9. 87

---

[6]

Govt. of {188 } Madras.

(5)

To The P W dept

12-9-87

Proceedings, dated 26/8 1887.
No. 1940

Subject.

B. No 2432 W d/8th Sept 1887

Passing orders on letter from I G of Jails regarding new cells to be built at Calicut for lunatics

---

1887.

P. W. DEPARTMENT.

Current No. 7383.

From The Supdg. Engineer IV circle.

Enclos.—

No. 378/Gw.
Dated 14. 9. 87.
Received 19-9-87.

Subject.

Lunatic Asylum Calicut

Requesting to be furnished with the tracing showing the proposed site for the erection of the 12 cells for the ——.

Disposal.

No. 600 D. Dated 23 Septr 1887.

Transferred to the Judicial Department with reference to G. O. No 1940, dated 26th augt 1887.

2. The tracing alluded to in para 1 of the above order has not been received in this office.

(Sd) J. O. Hasted Col R.E.

[illegible]

G.O. 1710 W. 27.6.87
" 2632 W. 8.10.86

B. A: 2432 W of 8.9.87 S: 33 W of 6.1.88.
1710 W of 27.6.87
" 2632 W of 8.10.86.
" 2442 W of 22.9.86.
" 2030 W of 13.8.86
" 926 W of 18.4.85
" 1594 W of 23.6.86.
" 2127 W of 26.8.86

17/786

G. 3.9.87. R. 7.9.87

Judicial Department

18/786

PROCEEDINGS OF THE MADRAS GOVERNMENT.

READ the following ~~paper~~

Endorsement in the Public Works Department dated 23rd September 1887 No. 600 D on letter from the Superintending Engineer, IVth Circle, dated 14th September 1887 No. 378, requesting return of the tracing showing the proposed site for the erection of the 12 cells for Lunatics at Calicut.

[illegible]

Order 30th September 1887 No. 766 R.

The Inspector General of Jails will be requested to forward the tracing to the Superintending Engineer, IVth Circle.

(True Extract)

W. C. Baddeley

Under Secretary P.W.D.
for Actg Chief Secretary

To

The Inspector General of Jails.
" Public Works Department. /

x 2/4 J.D.

19/786

PWC No 7842

No. 2701 W a/13th Octr/87

[6]

Govt. of {188 } Madras.

(4)

To

the P W Dept

Communicated to the Supdg Engr 4th Circle

WCW 11.10.87

8/10/87

Proceedings, dated 20/9/ 1887.
No. 766 R

Subject.

No. 2701 W a/13th October/87

Requesting I G of Jails to forward the tracing showing the proposed site for the erection of cells for Lunatics at Calicut, to the Supdg Engr IV Circle

No. 2432 W a/8.9.87
" 1710 W a/27.6.87
" 2632 W a/8.10.86
" 2442 W a/22.9.86
" 2030 W a/13.8.86
" 926 W a/18.4.85
" 1594 W a/23.6.86
" 2147 W a/26.8.86
" 33 W a/6.1.86
" 600 D a/23.9.87

13/10

C.S.
S.E. 4th Circle

Despd
13/10/87

6.10.87

With order

6.10.87

20/786

Public Works Department.

Current No. 490
Letter No. 34 R
Dated the 16th January 1888
From the Secy: to Govt: Judicial Depts:

NOTE OF REMARKS.

The estimate under review amounting to Rs 10,060 provides for the following additions to the District Jail at Calicut.

(a) Constructing 12 cells, in two blocks for Lunatics — Rs 4,900
(b) — do — 4 Solitary cells — " 2630
(c) — do — 4 Condemned Cells — " 2530

Total Rs 10,060

The necessity for the proposed additions is explained by the Inspector General of Jails in his letter

The rates, as far as can be checked, are fair, but the provision of wooden ceilings to the roofs increases the rate from Rs 14, as given in the Schedule, to Rs 28 —

The provision of 6" of concrete for the asphalte flooring seems too much. 4" should be sufficient which would reduce the rate from Rs 20 to Rs 15 or 18 —

The plans and Estimates although forwarded by the Inspector General of Jails are not countersigned by that Office but they are approved by Govt: in the Judicial Depts:—

26/1/88

T

Take out the wooden ceilings – reduce the concrete to 4" and sanction for the reduced amount.

27.1.88.

6-10-87

1888.

P. W. DEPARTMENT.

Current No. 490 21/786

Judicial Depts.

& R.

ENCLOS.— 1
4 pla

Dated 16. Jany 1888.

Received

SUBJECT.

Transfg: after approval lette from the Inspector-General of Jails submitg: for sanctio & provision of funds, pla & Estimates amounting to Rs10,060 for constructin 12 cells in the district jail Calicut.

DISPOSAL.

No. 418C Dated 1st Feby 188

Referred to the S.E. IV Circle, with remark that by the omission of the wooden ceilings and by reducing the depth of concrete in flooring from 6" to 4" a saving of Rs. 780 would be effected.

If these alterations ca be effected without in convenience, and with

The rates, as far as
can be checked, are

---

the consent of the Jail Supdt.
the estimate should be
corrected accordingly.
Early return requested.

(By order)
(Sd) W. L. C. Baddeley R.E.
Under Secy to Govt. P.W.D.

Despd 1-2.88
with 12 Encs.

J

No. 2701 to a/ 13.10.87. Files.

23
786

C No. 490

Secy W.

22
786.

By dispensing with
the ceilings and reducing
the depth of concrete
in the flooring from
6" to 4" a saving
of Rs 780 has been
effected in the Est.
which has been altered
in pencil accordingly.
As regards the ceilings
before finally striking
them out of the
Estimate perhaps
it would be well
to make a reference
to S.E. as to the necessity
for them. There may
have been provided
under instructions
for the additional
security of the prisoners
as the roofs are only
tiled.

30/1/88

Refd to S.E. pointing out
the saving which might be made
30.1.88

The rates, as far as
can be checked, are

No. 3

23/286

Madras 3d January 1888.

From

H. R. Grimes Esquire,
Inspector General of Jails.

To.

The Hon'ble H. E. Stokes,
Chief Secretary to Government
Fort Saint George.

18

Sir.

8 Enclosures.

3 Plans
3 Estimates
1 Site Plan
1 Report
8

I have the honor to forward for sanction and provision of funds 3 Plans and 3 Estimates amounting to Rs 10,060 for constructing 12 cells in two blocks for lunatics in the District Jail at Calicut at a cost of

	Rs 4,900
Adding 4 solitary cells to existing cells.	" 2,630
Adding 4 cells to existing condemned cells	" 2,530
Total	10,060

2. The necessity for additional cells for lunatics in this Jail has already been fully discussed

and

and admitted.

3. The necessity for the other two additions has been brought to my notice by the official visitors. There are at present, only two cells for condemned prisoners, and two for Solitary confinement when this punishment is awarded judicially, they are situated in separate compartments on each side of the inner entrance to the jail and as there are frequently or I may say generally 4 condemned prisoners at a time in this jail, the whole of the cells are used as condemned cells, sentences of solitary confinement cannot therefore be given effect to except by transferring prisoners with such sentences to other jails, viz to Cannanore or Coimbatore which involves expenditure, it is therefore necessary to increase the number of cells for both classes

classes of prisoners by 4 additional cells.

I have the honor to be,
Sir.
Your most obedient Servant.
Henry R. Grimes.
Inspector General of Jails

SUPG: ENGINEER'S OFFICE
NO.
3 FEB. 88
P. W. D.
FOURTH CIRCLE

EXECUTIVE ENGINEER'S OFFICE
No. 3/164
11 FEB. 88
P. W. D.
WEST COAST DIVISION

SUPG: ENGINEER'S OFFICE
NO.
23 FEB. 88
P. W. D.
FOURTH CIRCLE

E.E.

1936

Encls no 2/68/88 from the Supg Engr. IV Circle

25/786

No. 418 C d/1st Feby 1888

Referred to the Supg: Engineer IV Circle, with remark that by the omission of the wooden ceilings & by reducing the depth of concrete in flooring from 6" to 4", a saving of Rs 780 would be effected.

If these alterations can be effected without inconvenience, & with the consent of the Jail Supdt:, the estimate should be corrected accordingly.

Early return requested.

(By order)

W C Baddeley Captain
Under Secy to Govt. Mdrs

J. G. 1940 d 26/8/87 Jud
— 1522 d 14/7/87 Jud
— 592 d 7/3/87 Jud
766 - 30.9.87 Rs

G.O. 16 Jany/88 No. 34. R
Approved and transferred to the P.W.D.

H.l (by order)
A. G. Cardew,
Ag Under Secy

No. 60/WC.

Forwarded to the Executive Engineer West Coast Division to report, after consulting the Jail Supdt., if the alterations suggested by the Chief Engineer may be made —

J. W. Martin
Offg Supdg Engineer
7/2/88

Endo: 4
To be returned
Received
only 7 —

C.W.C. No. ~~49~~ 21
1931/88

Judicial

JUDICIAL.

Jail (188~~,~~8) Department.

No. 114 11 FEB. 88 P.W.D. WEST COAST DIVISION

FROM A. G. Cromer
~~The~~ INSPECTOR-GENERAL
OF JAILS,

To The Hon'ble H. E. Stokes
~~The~~ CHIEF SECRETARY
TO GOVERNMENT.
Fort St. George

SUPG: ENGINEER'S OFFICE No. 106 W 3- FEB. 88 P.W.D. FOURTH CIRCLE

SUPG: ENGINEER'S OFFICE 23 FEB. 88 P.W.D. FOURTH CIRCLE

Dated 3rd } January 1888.
Received 5th }

No. 3

ENCLOSURE. 8

CHIEF SECRETARY 6 JAN 88

SUBJECT.

Forwards for sanction and provision of funds, Plans and Estimates amounting to Rs. 10,060 for constructing 12 cells in the District Jail Calicut.

Enc. No. 1/68/88 from the Supg Engr 4 Circle

No. 68/WD ~~V/88~~

Supg. Engineer's Office IV Circle,
Coimbatore, 24 February 1888.

From

J. W. Martin, Esq.,
Offg. Superintending Engineer,
IV Circle.

4P

To

The Chief Engineer,
P. W. Department.

Enclosures 10.
3 Plans
1 Site plan
3 Estimates
1 Report
1 Letter of the Inspr. Genl. of Jails No. 3 of 3rd Jany/88. to the address of Chief Secy. to Govt.
1 Memo: of Chief Engr. No. 418C of 1st Feby/88.
10

Sir,

I have the honor to return duly corrected the Plans and estimates for constructing 12 Cells in two blocks for Lunatics, and for adding 4 Cells to each of the existing Solitary and Condemned Cells in the District Jail at Calicut, received with your Memo: No. 418C dated 1st Instant.

2. The estimates have been reduced from Rs 10,060 to Rs 9,280 by omitting the wooden Ceilings to the roof and by decreasing the depth of Concrete in flooring from 6 to 4 inches. The Jail Superintendent assents to the omission of the ceilings.

3. The Site plan of the jails, and the

the Report together with the letter of the Inspector General of Jails forwarded with your Memorandum are also herewith returned. Three Abstracts of the estimates were forwarded to the Inspector General of Jails for transmission to Government with other documents, but were not received with your Memorandum under reply.

I have the honor to be,
Sir,
Your most obedt. Servt.,

J W Martin
Offg. Supg. Engineer
IV Circle

---

786 W

28/786

Public Works Department.

Current No. 1936
Letter No. 68 W
Dated ~~the~~ 24th February 1888
From the Supg. Engr. IV Circle

Sanction recd
29.2.88

NOTE OF REMARKS.

B/

The accompanying Estimate for constructing 12 cells in two blocks for lunatics, and for adding 4 cells to each of the Existing solitary and condemned cells in the District Jail at Calicut ~~Cuddapah~~ was returned to E.E. IV for revision with reference to the instructions conveyed in this Office unofficial No 418C d/ 1st February 1888 The estimate has accordingly been revised and the amount reduced from Rs 10,060 to Rs 9,280 by omitting the wooden ceilings to the roof and decreasing the depth of concrete in flooring from 6" to 4 inches and is resubmitted for the sanction of Govt:-

24/2/86

P.W.C. No: 1936

From
The Offg. Supdg. Engineer
Fourth Circle, D.P.W.

No: 33 W d/ 6.1.86
" 1594 W d/ 23.6.86
" 33 W d/ 6.1.86
" 926 W d/ 18.4.85
" 2030 W d/ 13.8.86
" 2147 W d/ 26.8.86
" 2442 W d/ 22.9.86
" 2632 W d/ 8.10.86
" 1710 W d/ 27.6.87
" 2432 W d/ 8.9.87
" 600 D d/ 23.9.87
" 2780 W d/ 13.10.87
" 418 C d/ 1.2.88

Dated 24th February 1888

R 28.2.88

No: 68/E.W.

Enclo: ~~10.~~ 13 (+4 plan)

District Jail at Calicut:-

Returning duly corrected the plans and estimates for constructing 12 cells in two blocks for Lunatics, and for adding four cells to each of the existing solitary condemned cells in the —.

A/ [illegible]

29/786

B & [illegible] Works

No: 783 W

PUBLIC WORKS DEPARTMENT.

[illegible]

PROCEEDINGS OF THE MADRAS GOVERNMENT.

UNDER date the 9th March/88

READ the following

From the Inspector General of Jails. H. E. No: 3 d/ 3rd January 1888.
Endorsement by the Judicial Department. H. E. No: 34 R d/ 16th January 1888.
From the Supdg. Engr. IV Circle. H. E. No: 68 E. W. d/ 24th February 1888.

The revised estimate amounting to Rs. 9,280, for constructing 12 cells in two blocks for lunatics, and for adding 4 cells to each of the existing solitary and condemned cells in the District Jail at Calicut, is sanctioned in supersession of the estimate of Rs. 5,820 sanctioned in G. O. No: 1710 W d/ 27th June 1887.

2. A sum of Rs. 4,820 has been provided for the work in the Provincial budget for 1888-89.

3. This sanction has been registered as Provincial No: 185 W of 1887-88 and classified as Civil Buildings, Original Works.

4. The Inspector General of Jails will be requested in the Judicial Department to transmit to this Department the three abstract estimates referred to by the Supdg. Engineer in para 3 of his letter.

P.P.H. 8 mar

D 15/3

To The Supdg. Engr. IV Circle with 11 enclos.
" Examiner of P.W. Acts
" Judicial Department
~~To The Chief Engr. for [illegible] initials~~

9 Mar

1.3.88

The Hon'ble D. P. Nicholson C.S.

7
1 II
19/3

CS 2.III.88
8 7 3 88

L 8.III.88

Govt. of (1888) Madras.

PUBLIC WORKS.

Dated Fired 9/3/88

Recd.

Encl.

G.O. 9 March 1888 No. 786 W.

District Jail at Calicut

Revised estimate for constructing 12 cells in two blocks for lunatics, and adding 4 cells to each of the existing solitary & condemned cells in the — sanctioned. With remarks.

10/6

GDl. 9/3