2

(1) பக்கங்களின் எண்ணிக்கை 30

(2) புதுக்கித் திருப்பிய நாள் ஜூன்.-88

(3) ஆதாரங்குறிப்பவர் சுருக்கொப்பம்

தமிழ்நாடு ஆவணக் காப்பகம்.

தமிழ்நாடு அரசு

P.W.D. பொதுப்பணி துறை

அரசாணை எண்.
மு. கோப்புத் தாள் எண். 816-W.
அச்சகம்
பலவகை

நாள் : 12-3-1888. 198

மடிக்கவோ கண்டபடி கையாளவோ கூடாது

ஆவண, கா-1—18,006—15-8-87.

12th March 1888, No. 816 W., Public Works.

GOVERNMENT OF MADRAS.

PUBLIC WORKS DEPARTMENT.

Buildings and Roads.
Civil Works.

Read—the following letter from J. W. MARTIN, Esq., Officiating Superintending Engineer, IV Circle, to the Chief Engineer, Public Works Department, dated Coimbatore, 22nd February 1888, No. 63 E.W. :—

Adverting to G.O., dated 17th November 1887, No. 3106 W., I have the honor to submit for Government sanction and provision of funds a plan and estimate, amounting to Rs. 1,010, for improvements and additions to the Sub-Registrar's office at Quilandi in the Malabar district, together with a report and specification.

2. The plan and estimate have been approved and countersigned by the Inspector-General of Registration.

3. The five papers received with the above Government order are herewith returned.

Order—dated 12th March 1888, No. 816 W., Public Works.

The estimate, amounting to Rs. 1,010, for repairs and improvements to the Sub-Registrar's office at Quilandi in the Malabar district, is sanctioned.

2. The Superintending Engineer will arrange to commence the work early in April next in anticipation of funds being provided in the orders on the statements of demands for incomplete and minor works.

3. This sanction has been registered as Provincial, No. 187 W. of 1887-88, and classified as Civil Buildings, Original Works.

(True Extract.)

Captain, R.E.,
Under Secy. to Govt., P.W.D.

To the Superintending Engineer, IV Circle, with four enclosures.
,, Examiner, Public Works Accounts, with the estimate for note and return to Superintending Engineer, IV Circle.
,, Judicial Department.

Exd. J. Moses.
Spare Copies

BUILDINGS AND ROADS.
CIVIL WORKS.

Govt. of {1888} Madras.

PUBLIC WORKS.

Dated March, 12th.

Recd.   Encl.

G.O., 12th March 1888, No. 816 W.

MARCH.

Sub-Registrar's Office at Quilandi

Estimate for repairs and improvements to the — in the Malabar district, sanctioned.

Registration Department.
G. No. 4618.

CURRENT NO. 739

From
Geo. Hamnett, Esquire,
Inspector General of Registration,
Madras.

To
The Honorable H. E. Stokes,
Ag. Chief Secretary to the Govt.,
Fort St. George.

Madras, the 5th November 1887.

Sir,

I have the honor to submit the correspondence* marginally noted regarding the dilapidated condition of the roof of the Sub-Registrar's office at Quilandy in the Tellicherry district, and the necessity for repairing it thoroughly, and to request that the Government will be pleased to direct the preparation of an estimate for the execution of the necessary repairs, as the Executive Engineer, West Coast Division, is of opinion that the cost would be about a 1000 Rupees. It may be more when the details are worked out.

* From the Registrar of Tellicherry to the Inspector General, No. 1592. dt. 22' Septr. 87, with one enclosure.
To the Executive Engineer, West Coast Division, G. No. 3929, dt. 24' Septr. 1887.
From — do — do — No. 1071 dt. 3' Novr., 1887, with one enclosure.

I have the honor to be,
Sir
Your Most Obedient Servant,

G. Hamnett
Inspr. Genl. of Regn.

Executive Engineer.

D/ 12 November/87

Transfd to the P W dept as now known being issued for the preparation of an estimate of the cost of the necessary repairs to the Sub Regr. Office

/By order

Under Secy.

Communicated to the Supdg. Engr. IV Circle for submission of the requisite estimate

15.11.87

15/11/87

B 17/11

S.E. IV. Circle with 5 enclosures to be returned
S.S. IV.
Judicial Dept.

PWCN: 9196

Judicial (1887) Department.

"Registration."

From
The Inspector General
of Registration,
Madras.

To
The Actg. Chief Secretary
to the Government,
Fort St. George.

Dated 5th November 1887
Received 14 NOV 87

876 W

E. 5

G. No. 4618.
Enclos (5)
No.

Submitting certain correspondence and requesting that the Government may be pleased to direct the preparation of an estimate for repairing the Sub-registry office at Quilandy in Tellicherry district.

P. W. D.

Regns. 886 14-12-87

Executive Engineer's Office,
WEST COAST DIVISION,
CALICUT, 3rd November 1887

No. 1071

FROM
J. J. Wilson Esqre
EXECUTIVE ENGINEER,
WEST COAST DIVISION.

TO
The Inspector General,
of Registration,
Madras.

ENCLOSURES. /
(to be kindly retd)

SIR,

I have the honor to forward herewith Sub Conductor Hollingsworth's report on the State of the Sub Registrar's Office at Quilandy. It would appear that the building could be put in good order for about Rs 1000.

I have the honor to be,
Sir,
Your most obedient Servant,

J J Wilson
Executive Engineer.

A21

63929

SUPG: ENGINEER'S OFFICE
No. 1031/W
21 NOV. 87
P.W.D.
FOURTH CIRCLE

Endo. to
Registration (1887) Department
Office accommodation

FROM

EXECUTIVE ENGINEER'S OFFICE
No. 6/1201
24 NOV. 87
P.W.D.
WEST COAST DIVISION

EXECUTIVE ENGINEER,

WEST COAST DIVISION.

To

9/125

SUPG: ENGINEER'S OFFICE
5/116 W
20 FEB. 88
P.W.D.
FOURTH CIRCLE

Dated 3rd }
Despatched }
Received 5. } November 1887

R. No. 9345

ENCLOSURES. 1

No. 1071

Enclo. no 9/63/88 from [illegible]

SUBJECT.

Forwarding report on the state of the Quilandy Sub. Regis' Office -

---

From
The [illegible] the Sub-Divisional Officer
Cannanore

To
The Executive Engineer
West Coast Divn.
Calicut.

1 NOV 87

Dated Cannanore 29th October 1887

Sir,

With reference to your endorsement No. 1878 dated 3rd instant on the letter of the Inspector General of Registration and its enclosures herewith returned, I have the honor to report that, with the exception of the roof, the Sub-Registrar's Office at Quilandi is in good order, Some of the rafters of the roof are rotten from age and others are being eaten with white ants ~~also~~ the reepers are rotten and falling in pieces from the Same Causes, the building could be improved by putting on a roof of Mangalore tiles, new reepers & new rafters a ceiling of white Cedar planks, renewing the present floor with asphalte over Concrete and adding glazed shutters to the present batten windows; the Cost of these improvements would be about Rs 970.

I have

The building consi[illegible]
Office room 30'.3"x15' and a [illegible] Stamp
10' [illegible] is larger than the Stand[illegible]
for a Sub-Registrar's O[illegible] [illegible]ding
record room 17x15' wo[illegible]e, an [illegible]rah
open portion would [illegible] requi[illegible]o, and an
as a new office [illegible] Rs 2 [illegible], and
at about Rs [illegible] design would
[illegible] it would be
[illegible]ce to improve, and add to the present
building than to build a new one on the
Stan[illegible] design.

I have the honor to be
Sir,
Your Most Obdt. Servant

C. Hollingsworth Sub-Conductor
Sub-Divisional Officer

Enclo. 3

E. 2

8/125

Enclo: No 8/63 from the Sup Eng 4th Circle

EXECUTIVE ENGINEER'S OFFICE
No. 2306
2 NOV 87
P.W.D.
WEST COAST DIVISION

SUPG: ENGINEER'S OFFICE
No. 1031/47
21 NOV.87
P.W.D.
FOURTH CIRCLE

EXECUTIVE ENGINEER'S OFFICE
No. 3/1201
2 [illegible] 87
WEST COAST DIVISION

SUPG: ENGINEER'S OFFICE
No. 4/116 We
20 FEB.88
P.W.D.
FOURTH CIRCLE

Repairs [illegible] 14 [illegible] 87

Registration Department.
G-No. 3929.

From

Geo. Hamnett, Esquire,
Inspr.-Genl.- of Registration,
Madras.

To

The Executive Engineer,
West Coast Division,
Calicut.

Madras, the 24th September 1887.

Sir,

* No-1592 d/ 22' September 1887.

I have the honor to enclose copy of a letter* from the Registrar of Tellicherry and of its enclosure regarding the condition of the Sub-Registrar's office at Quilandi, and to request that you will do me the favour to direct a subordinate of your department to inspect, and state whether it would be worth while repairing the building at a large cost, or constructing a new office on the standard plan.

I have &c.
(Signed) Geo. Hamnett
Inspr.-Genl. of Regn.

(True Copy)

Geo. Hamnett
Inspr. Genl. of Regn.

SUPG. ENGINEER'S OFFICE
No. 10317W
21 NOV. 87.
P. W. D.
FOURTH CIRCLE

Enclo. 2

EXECUTIVE ENGINEER'S OFFICE
No. 2/1201/82
24 NOV 87
P. W. D.
WEST COAST DIVISION

7/125 S

SUPG. ENGINEER'S OFFICE
No. 3/116 W
20 FEB. 88
P. W. D.
FOURTH CIRCLE

9496
1828/87/88

Enclo. No. 5/63/88 from
[illegible] circle

---

806 Inwo
14-12-87

No. 1592.

District Registrar's Office,
Tellicherry, 22d September 1887.

From
T. C. Ryru Kurup,
Registrar of Assurances,
Tellicherry.

To
The Inspector General
of Registration, Madras.

Sir,

* No. 163 d/21 September 1887.

I have the honor to submit for your kind perusal and return a report* from the Sub-Registrar of Quilandy on the state of his office building. The alterations and repairs proposed promise to involve a large expenditure, and I think it desirable that the work should be undertaken by the Department of Public Works. A considerable sum of money has been spent by way of partial repairs, but the building is reported to be unfit for a public office unless it is thoroughly repaired and put in order.

I have &c.
(Signed) T. C. Ryru Kurup.
Registrar.

(True Copy)

W. Hammett
Inspr. Genl. of Regn.

SUPG: ENGINEER'S OFFICE
No. 1031 W
21 NOV. 87
P. W. D.
FOURTH CIRCLE

Enclo. 5.

5/1201
24 87
P. W. D.
WEST COAST DIVISION

10/1258.

SUPG: ENGINEER'S OFFICE
No. 1/116 WC
20 FEB. 88
P. W. D.
FOURTH CIRCLE

1828/88

No. 163.

Quilandi S.R.O.
21st September 1887

1 cle
22/9/87

From
The Sub Registrar of
Quilandy;

To
The Registrar of
Tellicherry;

Register sub/ 14/12/87

Sir,

With reference to the instruction of the Inspector General embodied in the Acting Registrar's Notes of inspection dated 7th & 8th February 1887, regarding the repairs of this office, I have the honor to state that the entire roof requires a thorough renewal, not one rafter of which is free from the ravages of white ants while but fragments of several reapers remain. A wooden ceiling is needed not for the record-room alone, but for the office-room too, as lumps of wet clay formed by white ants, and several insects with a moisture about them are continually dropping on the registers & soiling them, not to mention of the furniture & floor. The nuisance has become ~~more~~ now worse now owing to the rains. White ants also creep up through the several cracks in the floor, the very bad plastering of which has always kept the office furniture dusty. The floor therefore badly needs asphalting.

2. The Record Room is just large enough to hold the six almirahs at present placed in it & will have to be extended at the back of it when in the course of the current year or so another almirah which is indispensably necessary, is received.

3. The office stands west to east divided into two rooms with neither a verandah all round for the protection of the office against bad weather, nor a little porch in front for the use of the parties

The

The record room is the eastern one with a small window in the east wall through which hardly a ray of sun shine passed as the shutter is fixed to the top of the window frame. There are two windows in the northern & southern walls which from their position, cannot admit much sun. The court-yard is about four yards wide all round & is lower than the adjoining paramba by about two feet, so that when a shower of rain comes down the water becomes stagnant, especially about the record room towards which the court-yard slopes down. This will keep the building damp. The office door is in the north side and is so exposed that it has to be shut when it rains. It ought to be removed to the western side and a gate opened immediately in front of it, for want of which latter, and on account of the proximity of the Office to the Submagistrate's Cutcherry, many respectable women, both Hindu & Mohomedan, who culd ill afford to pay the attendance fee have, I am informed, been forced to give up optional registration as they could not enter thro' the one common gate before the said Cutcherry which the boors and ruffians in the Criminal Cases usually block up.

4. Some months ago I desired the Local Fund Supervisor at Calicut to do me the favour of inspecting this office while on his circuit & estimating the repairs, to enable me to give you full details at the very onset, but as that gentleman has not yet obliged me, I have deemed it prudent to defer no longer in addressing you on a subject which ought to be taken on hand without much delay. I beg you will be good enough to desire the

9

the Department of Public works to inspect this office and do what you may think necessary.

5. There are certain urgent repairs to be effected, such as replacing several pieces of reeper which have been so destroyed that they have dropped off leaving the tiles to hang in danger over the heads of those in the office, shifting tiles here & there & stopping leakage, & plastering the ridge of the roof where cracked, fixing a few hinges to the windows & whitewashing the whole building. I believe these repairs can be carried out with a sum of Rupees (15) fifteen. On your authorizing me to do it, I shall get any local contractor or any one else you may be pleased to refer me to, to prepare a formal estimate & submit it for your approval. This office was last repaired in February 1886.

I have the honor to be,
Sir
Your most obedient Servant
V. C. J. Conceicao
Sub Registrar

[illegible]
1886

SUPG. ENGINEER'S OFFICE
No. 103 1/W
21 NOV. 87
P. W. D.
FOURTH CIRCLE

Encls. 1

6/125 S.

Registration (1887) Department

From
The Sub Registrar of Quilandy
to
The Registrar of Tellicherry

Dated 21st } September 1887
Received 22
No. 163.
Enclosure
Report on the state of the Office buildings
Sub R 4098

Recd 22 38/87

SUPG. ENGINEER'S OFFICE
No. 2/111 E.W.
20 FEB. 88
P. W. D.
FOURTH CIRCLE

PW G.O. 964
1828/88
Sub memo No. 63/88 E.W. from the Supdg Engineer 4th Circle

SUPG. ENGINEER'S OFFICE 4TH CIRCLE,
Coimbatore 22nd February 1888

No. 63/E.W.

10

From,
J. W. Martin Esq.
Offg Superintending Engineer,
Fourth Circle.

To,
The Chief Engineer
P. W. Department.

Enclos: 9
1 Plan
1 Estimate
1 Report
1 Specification
5 Letters of correspondence

Sir,

Adverting to G.O. dated 17th November 1887 No. 3106 W. I have the honor to submit for Government sanction and provision of funds, a plan and estimate amounting to Rs. 1010 for improvements and additions to the Sub Registrar's Office at Quilandy in the Malabar District, together with a report and Specification.

2. The plan and estimate have been approved and countersigned by the Inspector General of Registration.

The five papers received with the

the above G.O. are herewith returned.

I have the honor to be,

Sir,

Your most obedt Servt,

E W Martin

Offg. Supg. Engineer

IV Circle.

No. 3106 W d/ 17-11-87

PWC No 1828

From
The Offg. Supg. Engineer,
Fourth Circle

Dated 22nd February 1888
Ry 24-2-88

No. 63
E.W.
Enc: 9 10
(+1 Plan)

Sub Registrar's Office at Quilandy, Malabar District.

Submitting for sanction of Government and provision of funds a plan and estimate of Rs. 1010 for improvements and additions to the —.

Ch. Secy 5-3-88

Hdr. R. 12-3-88

5-3-88
12

Public Works Department.

Current No. 1828
Letter No. 63 E.W.
Dated the 22nd February 1888
From the Supg. Engr. IV Circle
[illegible]
3.3.88

NOTE OF REMARKS.

B/

The Estimate under review amounting to Rs 1010 provides for the repairs and improvements to the Sub Registrar Office at Quilandy in the Malabar Dt.-

It is explained that the roof of the building is in a bad state and that a new roof is an absolute necessity, it is therefore proposed to dismantle and reconstruct the roof, to provide

No.

a porch and to effect a few other slight improvements.

The provision for a pailing seems unnecessary as the inconvenience complained of will not exist when the new roof is put on. If omitted there will be a saving in the estimate of Rs 42 and the amount will be reduced from Rs 1010 to Rs 968.

It would cost Rs 2920 to construct the Sub Registrar's Office at Tanurachere in the Malabar district so that it appears better to repair the existing building than to construct a new one on the lines of the type design.

It [illegible] that ceiling [illegible] necessary in the building

13

The rates are fair, the estimate is countersigned by the Inspector General of Registration.

2/3/88

c

Hbr.

Enclosures 1–9 of
a letter No. 63/EW of 22/2/88
from the Sup. of Engineer

- 1 Plan
- 1 Estimate
- 1 Report
- 1 Specification
- 5 letters of correspondence

B & R
Civil works
3

PUBLIC WORKS DEPARTMENT.

No. 816 W

A. 16

PROCEEDINGS OF THE MADRAS GOVERNMENT.

UNDER date the 12th March /88

READ the following

From the Supdg. Engineer IV Circle. B. E. No: 63 E. W. d/22nd February 1888.

The estimate amounting to Rs.1,010, for repairs and improvements to the Sub-Registrar's office at Quilandi in the Malabar District, is sanctioned.

2. The Supdg. Engr. will arrange to commence the work early in April next, in anticipation of funds being provided in the orders on the statements of demands for incomplete and minor works.

3. This sanction has been registered as Provincial No: 187 W of 1887-88, and classified as Civil Buildings, Original Works.

10 mar

Desp 7/3

5.3.88

5/3/88

To The Supdg. Engr. IV Circle with 4 encls.
" Examiner of P. W. Accts with the estimate for note & return to S. E. IV.
" Judicial Department.

(To ~~The Chief Engr for favor of counter initials~~)

7 mar

7/3

Govt. of 1888 Madras

PUBLIC WORKS.

13/3

Dated

Recd.

Encls.

G.O. 12th Mch 8 No. 816 W.

Sub Registrar's office at Quilandi

Estimate for repairs and improvements to the — in the Malabar District Sanctioned.

90/4