

(1) பக்கங்களின் எண்ணிக்கை 46

(2) புதுக்கித் திருப்பிய நாள் 7/89

(3) ஆதாரங்குறிப்பவர் சுருக்கொப்பம் lvs

தமிழ்நாடு ஆவணக் காப்பகம்.

தமிழ்நாடு அரசு

(39)

PWD

துறை

அரசாணை எண்.
மு. கோப்புத் தாள் எண்.

1859

அச்சகம்
பலவகை

நாள் : 12. 7. 1889

19

மடிக்கவோ கண்டபடி கையாளவோ கூடாது

23 sheets

ஆவண. கா-1-18,006-15-6-87.

GOVERNMENT OF MADRAS.
PUBLIC WORKS DEPARTMENT.

Buildings and Roads.
Civil Works.

READ—the following paper:—

No. 93 R.N.

Report by the Superintending Engineer on the estimate, amounting to Rs. 3,220, for constructing a Sub-Registrar's office at Paramakudi.

[Reference—G.O., dated 23rd November 1888, No. 3703 W.]

The estimate was called for in Government Order quoted above, and it is prepared in accordance with the revised standard design for the Sub-Registrar's office with tiled roof, circulated with G.O., No. 2230 W., dated 21st July 1888, with the exception of a slight deviation in the following sub-heads of works which are found unavoidably necessary:—

- (a) Substitution of plastering for pointing exterior walls, as bricks to be used in the structure are made unavoidably of salt-earth.
- (b) Substitution of flooring with concrete 4" thick and plastered with Portland cement for flooring of 8" square bricks, as good sound bricks are not obtainable.
- (c) Substitution of wood-oiling to teakwood work unexposed to weather in place of painting.

2. In his letter No. 3236, dated 24th October 1888, embodied in the above Government Order, the Inspector-General of Registration suggested to have the building in the same compound in which the District Munsif's Court is being built; but, on a reference being made, the District Judge remarked that the construction of the building within the District Munsif's Court compound is objectionable as it is very small.

3. The new site now proposed in communication with the Sub-Registrar is contiguous to the compound above alluded to and so it is a very suitable one. The site being private property, a compensation of Rs. 294 is allowed in the estimate as reported by the Head Assistant Collector.

4. The rates are fair and the estimate is submitted for the sanction of Government through the Inspector-General of Registration under para. 989 of the Public Works Code.

KODAIKANAL,
7th June 1889.

(Signed) A. C. SMITH, Lieut.-Col., R.E.,
Superintending Engineer, VI Circle.

T. No. 2894.

Submitted for the sanction of the Government.

2. G.O., dated the 14th November 1888, No. 2354, Judicial, approved of the construction of the office.

OOTACAMUND,
14th June 1889.

(Signed) G. HAMNETT,
Inspector-General of Registration.

2

12TH JULY 1889, No. 1859 W., PUBLIC WORKS.

Approved and transferred to the Public Works Department.

22nd June 1889.

(Signed) A. G. CARDEW,
Under-Secretary.

ORDER—dated 12th July 1889, No. 1859 W., Public Works.

The estimate, amounting to Rs. 3,220, for constructing a Sub-Registrar's office at Paramakudi, in the Madura district, is sanctioned for execution when funds are available.

2. This sanction has been registered as Provincial No. 34 W. of 1889-90 and classified as Civil Buildings, Original Works.

(True Extract.)

Captain, R.E.,
Under-Secy. to Govt., P.W.D.

To the Superintending Engineer, VI Circle,
with three enclosures.
" Examiner, Public Works Accounts,
with duplicate abstract estimate.
" Judicial Department.

Exd. J. Henricus.
Spare Copies

1859

2

BUILDINGS AND ROADS.
CIVIL WORKS.

Govt. of {1889} Madras.

PUBLIC WORKS.

Dated July, 12th.

Recd.

Encl.

G.O., 12th July 1889, No. 1859 W.

JULY.

Sub-Registrar's Office at
Paramakudi, Madura District
Estimate for a —, sanctioned.

1859
11TH JANUARY 1888, No. 101 W., PUBLIC WORKS.

GOVERNMENT OF MADRAS.

PUBLIC WORKS DEPARTMENT.

Buildings and Roads.
Civil Works.

READ—the following letter from W. MORGAN, Esq., Acting Registrar of the High Court of Judicature at Madras, Appellate Side, to the Chief Secretary to Government, dated Madras, 24th November 1887, No. 2877 :—

I am directed to forward, for the sanction of Government, the accompanying plan, estimates and report for constructing District Munsif's Court-house at Paramakudi, in the district of Madura, at a cost of Rs. 13,400.

2. From the said report it will be seen that the necessity of a Court-house at Paramakudi has been felt and brought to the notice of Government so long back as 1873.

No. 950, Judicial.

Approved and transferred to the Public Works Department.

(By Order.)

FORT ST. GEORGE,
14th December 1887.

(Signed) A. G. CARDEW,
Under Secretary to Govt.

ORDER—dated 11th January 1888, No. 101 W., Public Works.

The estimate, amounting to Rs. 13,400, for constructing a District Munsif's Court-house at Paramakudi, in the Madura district, is sanctioned.

2. A sum of Rs. 1,400 has been provided in G.O., No. $\frac{3471}{A}$ W., dated 19th December 1887, for expenditure on the work during the current official year, and the balance of the estimate, Rs. 12,000, has been allotted in the Provincial budget for 1888-89.

3. This sanction has been registered as Provincial, No. 143 W. of 1887-88, and classified as Civil Buildings, Original Works. Register No. 23 W. of 1876-77 is cancelled.

(True Extract.)

(Signed) W. L. C. BADDELEY, Captain, R.E.,
Under Secretary to Govt., P.W.D.

To the Superintending Engineer, VI Circle, with four enclosures.

" Examiner, Public Works Accounts, with the duplicate general abstract estimate.

" Judicial Department.

Exd. J. Moses.
Spare Copies

3

BUILDINGS AND ROADS.
CIVIL WORKS.

Gobt. of (1888) Madras.
PUBLIC WORKS.

Dated January, 11th.

Recd.

Encl.

G.O., 11th Jan. 1888, No. 101 W.

JANUARY.

District Munsif's Court-house at
Paramakudi, Madura District

Estimate for —, sanctioned.

1859

ANNEXURE.

Revised standard design for a Sub-Registrar's office with terraced roofing.

Descriptive Specification.

Foundations.—A depth of 4 feet is provided in the estimate, but this should be settled locally in accordance with the nature of the soil.

Walling.—The walls should be carried up in English bond two bricks thick, verandah wall one brick thick.

Stone-work.—The stone-slabs under verandah posts should measure $10\frac{1}{2}$ " $\times$ $10\frac{1}{2}$ " $\times$ 6" with mortice holes 2" square and 2" deep, into which the posts will be tenoned. The steps may also be of stone-slabs, if easily procurable.

Wood-work.—The verandah posts, bressummers and joists should be of Burma or Indian teakwood, well seasoned.

Doors.—Provide a venetian and panel door for the entrance and a strong battened door for the record room (according to the detail shown in the plan for tiled roofing), both doors to be provided with a good Europe rim lock.

Windows.—Venetian windows to be provided for the office and windows with glazed inner shutters, battened outer shutters and iron bars, $\frac{3}{4}$ inch square, set diagonally, for the record room. The sills of all windows should slope outwards with a small opening under the frame to allow water to flow out. All doors and windows to be provided with strong iron bolts and hinges and hooks for fastening when opened, and the venetians to have wooden buttons for securing when closed.

Sun-shades.—Sun-shades to be provided for each of the end windows of the office.

Roofing.—The roofing of the office and record room will be of "pucka terracing," care being taken that proper slopes are made for drainage towards the weep-holes, which will have shoots made with redwood or teakwood projecting at least 2 feet from the face of the wall. The verandah roof will be of Bengal terrace or of Mangalore tiles, where they are easily obtainable.

Flooring.—The floor may be of square bricks or stone-slabs, if the latter are easily procurable. The record room should be floored with asphalt, $\frac{3}{4}$ inch thick.

Interior and exterior finishing.—The interior of the building should be plastered and rubbed smooth or plastered and whitewashed. Where good bricks or stone is available, the exterior should be pointed, otherwise plastered.

If the soil is damp, river sand to a depth of 1 foot at least should be laid below the flooring, and the interior walls to a depth of about 3 feet all round plastered with Portland cement half an inch thick. The exterior plinth should also be plastered with cement.

Painting.—The roof timbers, sun-shades, doors and windows to be painted with three coats of Carson's oak paint.

Ventilation.—Holes to be left between the joists measuring 4" $\times$ 6" sloping outwards and closed with wire-netting of $\frac{3}{4}$ inch mesh to prevent birds and bats entering.

(Signed) J. W. BRASSINGTON,
Consulting Architect to Government.

Detail measurements.

Detail of work.	Number.	MEASUREMENTS IN FEET.			Area of contents.	Total quantity of each description of work.
		Length.	Breadth.	Depth.		
Excavation for foundations—		FT. IN.	FT. IN.	FT. IN.		
Outer walls	...	108 0	3 6	4 0	1,855	
Cross wall	1	24 6	3 6	4 0		
Verandah wall	...	35 6	2 4 $\frac{1}{2}$	4 0		
Steps	...	12 0	3 6	1 0	42	
					C. feet.	2,234

Detail measurements—cont.

Detail of work.	Number.	MEASUREMENTS IN FEET.			Area or contents.	Total quantity of each description of work.
		Length.	Breadth.	Depth.		
Earth filling in basement—		FT. IN.	FT. IN.	FT. IN.		
Record room ...	1	25 6	12 0	1 6	747	
Clerks' do. ...	1	16 0	12 0	1 6	285	
Registrar's room ...	1	9 6	12 0	2 6	211	
Verandah ...	1	24 6	5 9	1 6		
					C. feet.	1,243
Concrete—						
Outer walls ...		108 0	3 6	1 6	696	
Cross wall ...	1	24 6	3 6	1 6	126	
Verandah wall ...		35 6	2 4	1 6	42	
Steps ...		12 0	3 6	1 0		
					C. feet.	864
Brick-work in foundations and basement—						
Outer walls footing course ...		108 0	2 7	1 6	522	
Cross wall do. ...		24 5	2 7	1 6	82	
Verandah wall do. ...		36 5	1 6	1 6	749	
Outer wall above footing course ...		108 0	1 10	3 0	84	
Cross wall do. ...		25 1	1 10	3 0	4	
Verandah wall do. ...		37 1	0 9	3 0	10	
Steps do. ...	1	7 6	1 0	0 6	17	
Do. do. ...	1	9 6	2 0	0 6		
Do. do. ...	1	11 6	3 0	0 6		
					C. feet.	1,468
Brick-work in superstructure—						
Outer walls ...		108 0	1 6	13 0	2,106	
Cross wall ...	1	25 6	1 6	13 9	526	
Parapet ...		109 6	1 1	1 0	123	
Coping ...		117 0	0 9	0 9	66	
Deductions—						2,821
Doors ...	2	4 0	1 6	8 0	96	
Windows ...	8	3 6	1 6	5 0	210	
Arch-work as per details ...					86	
						392
					C. feet.	2,429
Arch-work over doors and windows—						
Over doors ...	2	5 6	1 6	1 1	86	
Windows ...	8	5 0	1 6	1 1		
Stone-work—						
Under posts ...	4	0 10	0 10	0 6	2	
Teakwood wrought and put up—						
Joists ...	42	13 6	0 3	0 7	83	
Verandah posts ...	4	0 6	0 6	7 6	8	
Do. bressummers ...	1	28 0	0 6	0 6	7	
Do. rafters ...	22	8 6	0 3	0 4	16	

Detail measurements—cont.

Detail of work.	Number.	MEASUREMENTS IN FEET.			Area or contents.	Total quantity of each description of work.
		Length.	Breadth.	Depth.		
Teakwood wrought and put up—cont.		FT. IN.	FT. IN.	FT. IN.		
Verandah pieces at ends ...	2	7 0	0 3	0 4	1	
Do. planks at ends ...	2	7 0	0 1	1 6	2	
Railing in clerks' room—						
Hand rail ...	1	9 6	0 3	0 2	1	
Bottom piece ...	1	9 6	0 3	0 2		
Uprights ...	17	3 0	0 1	0 1	1	
Do. at end ...	1	3 6	0 3	0 3		
					C. feet.	119
Venetian and panel door with frames, &c., complete ...	1	4 0		8 0	32	S. feet.
Batten door with frames complete ...	1	4 0		8 0	32	S. feet.
Venetian windows with frames complete—						
For office ...	2	3 6		5 0	35	S. feet.
Venetian windows with frames and glazed inner shutters complete ...	2	3 6		5 0	35	S. feet.
Batten windows with frames, iron bars $\frac{3}{4}$ " square and inner glazed shutters complete—						
For record room ...	4	3 6		5 0	70	S. feet.
Galvanised iron wire-netting to cover holes between joists ...	40	0 6		0 8	13	S. feet.
Sun-shades complete ...						2 in number.
Terrace roofing—						
For office and record room ...	1	27 0		27 0	729	S. feet.
					Squares.	7.29
Bengal terrace—						
For verandah ...	1	27 6		8 0	220	S. feet.
					Squares.	2.20
Plastering with chunam interior walls—						
Office and record room ...	2	75 0		9 0	1,350	
Door jambs ...	2	14 0		1 6	42	
Window jambs ...	8	17 0		1 6	204	
Top of parapet ...		109 0		1 3	136	
Inside of parapet ...		104 0		1 0	104	
						1,836
Deductions—						
Doors ...	3	4 0		5 0	60	
Windows ...	8	3 6		5 0	140	
						200
					S. feet.	1,636
					Squares.	16.36
Plastering with Portland cement $\frac{1}{2}$ an inch thick—						
Office and record room ...	2	75 0		3 0	450	
Plinth exterior ...		128 0		2 3	288	

Detail measurements—cont.

Detail of work.	Number.	MEASUREMENTS IN FEET.			Area or contents.	Total quantity of each description of work.
		Length.	Breadth.	Depth.		
Plastering with Portland cement $\frac{1}{2}$ an inch thick—cont.		FT. IN.	FT. IN.	FT. IN.		
Sides of steps	2	2 0	...	1 6	6	
Door jambs	2	6 0	...	1 6	18	
Deduct—						
Doors	3	4 0	...	3 0	...	762
						36
					S. feet.	726
					Squares.	7-26
Pointing exterior—						
Walls	...	114 0	...	15 6	...	1,767
Deduct—						
Door	1	4 0	...	8 0	32	
Windows	8	3 6	...	5 0	140	
						172
					S. feet.	1,595
					Squares.	15-95
Flooring with 8 inches square bricks—						
Office	1	25 6	...	12 0	306	
Door piece	1	4 0	...	1 6	6	
Verandah	1	26 0	...	6 6	169	
Steps	1	11 6	...	3 0	35	
						516
					S. feet.	5-16
					Squares.	
Flooring with asphalt $\frac{3}{4}$ inch thick over a bed of concrete 4 inches thick—						
Record room	1	25 6	...	12 0	306	
Door piece	1	4 0	...	1 0	4	
						310
					S. feet.	3-10
					Squares.	
Painting with three coats—						
Joists	42	13 6	...	1 5	803	
Verandah posts	4	2 0	...	7 6	60	
Bressummers	1	27 6	...	2 0	55	
Rafters	22	8 6	...	1 3	234	
Planking at ends	2	7 0	...	3 0	42	
Railing	1	18 0	...	3 0	54	
Venetian and panel door	3	4 0	...	8 0	96	
Batten door	2	4 0	...	8 0	64	
Venetian windows	2	3 6	...	5 0	140	
Do. with glazed shutters $5 \times$	2	3 6	...	5 0	175	
Batten windows with glazed shutters and iron bars $4 \times$	4	3 6	...	5 0	280	
Sun-shades	4	5 0	...	5 0	160	
Do.	2	2 0	...	2 0	8	
						2,111
					S. feet.	21-11
					Squares.	

ABSTRACT.

Quantity.	Description of work.	Rate.	Per	Amount.	Total.
		RS.		RS.	RS.
2,234 C. feet.	Excavation for foundations		1,000 C. ft.		
1,243 "	Earth filling in basement		100 C. ft.		
864 "	Concrete in foundations				
1,468 "	Brick-work in foundations and basement				
2,429 "	Brick-work in superstructure				
86 "	Arch-work		C. ft.		
2 "	Stone-work under posts				
119 "	Teakwood wrought and put up				
32 Sq. ft.	Venetian and panel door with frames, hooks and rim lock, complete		Sq. ft.		
32 "	Batten door do do				
35 "	Venetian windows with frames, hooks, &c., complete				
35 "	Venetian windows with frames and glazed inner shutters, hooks, &c., complete				
70 "	Battened windows with frames, iron bars and inner glazed shutters, hooks, &c., complete				
13 "	Galvanised iron wire-netting		Each.		
2 No.	Sun-shades		Square.		
7-29 Sqs.	Terrace roofing				
2-20 "	Bengal terrace				
16-36 "	Plastering interior walls with two coats of chunam				
7-26 "	Plastering with Portland cement $\frac{1}{2}$ an inch thick		Square.		
15-95 "	Pointing exterior walls				
5-16 "	Flooring with 8 inches square bricks laid in mortar over a levelling course of wall bricks				
3-10 "	Flooring with asphalt $\frac{3}{4}$ inch thick over a bed of concrete 4 inches thick				
21-11 "	Painting with three coats of Carson's paint				
	Petty supervision at $2\frac{1}{2}$ per cent.				
	Contingencies at 5 per cent.				
	Grand Total of estimate				

MADRAS,
8th June 1888.

(Signed) J. W. BRASSINGTON,
Consulting Architect to Government.

Revised standard design for a Sub-Registrar's office with tiled roofing.

Descriptive Specification.

Foundations.—A depth of 4 feet is provided in the quantities, but this should be settled locally in accordance with the nature of the soil.

Walling.—The walls should be carried up in English bond 2 bricks thick, verandah wall 1 brick thick.

Stone-work.—The stone-slabs under verandah posts should be $10\frac{1}{2}'' \times 10\frac{1}{2}'' \times 6''$ with mortice holes 2 inches square and 2 inches deep into which the posts will be tennoned. The steps may also be of stone-slabs if easily procurable.

Wood-work.—The verandah posts should be of Burma or Indian teakwood, well seasoned. The rafters and other roof timbers may be of approved country wood.

Doors.—Provide a venetian and panel door for the entrance and a strong battened door for the record room, both doors to be provided with a good Europe rim lock.

Windows.—Venetian windows to be provided for the office, and windows with glazed inner shutters, batted outer shutters, and iron bars $\frac{3}{4}$ inch square set diagonally for the record room. The sills of all windows should slope outwards with a small opening under the frame to allow water to flow out. All doors and windows to be provided with strong iron bolts and hinges and hooks for fastening when opened and the venetians to have wooden buttons for securing when closed.

Sun-shades.—Sun-shades to be provided for each of the end windows of the office.

Roofing.—The roof will be of the usual flat and pan-tiles or Mangalore tiles; in the latter case, the rafters should be spaced about 2' 6" apart centre to centre and a ceiling of $\frac{1}{2}$ inch planking provided.

Flooring.—The floor may be of square bricks or stone-slabs if the latter are easily procurable. The record room should be floored with asphalt $\frac{3}{4}$ inch thick.

Interior and exterior finishing.—The interior of the building should be plastered and rubbed smooth or plastered and whitewashed. Where good bricks or stone is obtained, the exterior should be pointed, otherwise plastered.

If the soil is damp, river sand to a depth of 1 foot at least should be laid below the flooring, and the interior walls to a depth of about 3 feet all round plastered with Portland cement half an inch thick. The exterior plinth should also be plastered with cement.

Painting.—The roof timbers, sun-shades, doors and windows to be painted with three coats of Carson's oak paint.

Ventilation.—For ventilation, the spaces between the rafters measuring about 15" x 6" and sloping outwards may be left open and galvanised iron wire-netting of $\frac{3}{4}$ inch mesh nailed in between to prevent birds and bats entering.

(Signed) J. W. BRASSINGTON,
Consulting Architect to Government.

Detail measurements.

Detail measurements.						
Detail of work.]	Number.	MEASUREMENTS IN FEET.			Area or contents.	Total quantity of each description of work.
		Length.	Breadth.	Depth.		
<hr/>						
Excavation for foundations—		FT. IN.	FT. IN.	FT. IN.		
Outer walls						
Cross wall	1	108 0	3 6	4 0	} 1,855	
Verandah wall		24 6	3 6	4 0		
Steps		35 6	2 4½	4 0		337
		12 0	3 6	1 0	42	
					C. feet.	2,234
<hr/>						
Earth filling in basement—						
Record room						
Clerks' room		25 6	12 0	1 6	} 747	
Registrar's room		16 0	12 0	1 6		
Verandah		9 6	12 0	2 6		285
		24 6	5 9	1 6	211	
					C. feet.	1,243
<hr/>						
Concrete—						
Outer walls						
Cross wall	1	108 0	3 6	1 6	} 696	
Verandah wall		24 6	3 6	1 6		
Steps		35 6	2 4½	1 6		126
		12 0	3 6	1 0	42	
					C. feet.	864
<hr/>						
Brick-work in foundations to floor level—						
Outer wall footing course						
Cross do. do.		108 0	2 7½	1 6	} 522	
Verandah do. do.		24 5½	2 7½	1 6		
Outer wall above footing course..		36 5½	1 6	1 6		82
Cross wall		108 0	1 10½	3 0	} 749	
		25 1½	1 10½	3 0		

Detail measurements—cont.

Detail of work.	Number.	MEASUREMENTS IN FEET.			Area or contents.	Total quantity of each description of work.
		Length.	Breadth.	Depth.		
<hr/>						
Brick-work in foundations to floor level— <i>cont.</i>		FT. IN.	FT. IN.	FT. IN.		
Verandah wall above	...	37 1½	0 9	3 0	84	
Steps	...	7 6	1 0	0 6	4	
Do.	...	9 6	2 0	0 6	10	
Do.	...	11 6	3 0	0 6	17	
					C. feet.	1,468
<hr/>						
Brick-work in superstructure—						
Outer walls	...	108 0	1 6	12 6	2,025	
Cross wall	1	25 6	1 6	21 6	822	
Gables	2	28 6	1 6	4 9	406	
						3,253
<hr/>						
Deductions—						
Doors	2	4 0	1 6	8 0	96	
Windows	8	3 6	1 6	5 0	210	
Arch-work as per details...	...	...	...	...	86	
						392
					C. feet.	2,861
<hr/>						
Arches over doors and windows—						
Over doors	2	5 6	1 6	1 1½	86	C. feet.
Windows	8	5 0	1 6	1 1½		
<hr/>						
Stone-work—						
Under posts	4	0 10½	0 10½	0 6	2	C. feet.
<hr/>						
Wood-work—						
Wall-plates	3	26 0	0 4	0 3	7	
Rafters	36	18 6	0 3	0 7	97	
Railing in clerks' room—						
Hand rail	1	9 6	0 3	0 2½	1	
Bottom piece	1	9 6	0 3	0 2½		
Uprights	17	3 0	0 1½	0 1½	1	
Do. at end	1	3 6	0 3	0 3		
Verandah—						
Posts	2	0 6	0 6	8 0	7	
Do.	2	0 6	0 6	6 6		
Brackets	2	1 0	0 6	0 4	1	
Do.	2	0 7½	0 6	0 6		
Bressummers	2	10 0	0 6	0 6	5	
Do. piece at ends	2	7 0	0 3	0 4	1	
Valley rafters	2	11 0	0 3	0 5	3	
Do. ridge	1	8 6	0 3	0 5		
Rafters	16	9 6	0 2½	0 4	15	
Do. small rafters	10	6 0	0 2½	0 4		
		average length.				
Collar piece	1	6 0	0 3	0 3	1	
Finial	1	4 6	0 3	0 3		
Barge planks	2	7 0	0 6	0 1	1	
Do.	2	2 6	1 6	0 1	1	
Planking at ends	2	7 0	0 1	2 6	3	
					C. feet.	144
<hr/>						
Venetian and panel doors with frames complete	1	4 0	...	8 0	32	Sq. feet.

Detail measurements—cont.

Detail of work.	Number.	MEASUREMENTS IN FEET.			Area or contents.	Total quantity of each description of work.
		Length.	Breadth.	Depth.		
		FT. IN.	FT. IN.	FT. IN.		
Batten door with frames complete ...	1	4 0	...	8 0	32	Sq. feet.
Venetian windows with frames complete for office ...	2	3 6	...	5 0	35	Sq. feet.
Venetian windows with glazed inner shutters for office ...	2	3 6	...	5 0	35	Sq. feet.
Batten windows with frames, iron bars, and inner glazed shutters for record room ...	4	3 6	...	5 0	70	Sq. feet.
Galvanised iron wire-netting between joists ...	2	26 0	...	0 8	35	Sq. feet.
Sun-shades ...	2	29 6	...	37 6	2,213	
Tiled roofing—	1	22 9	...	8 0	242	
Office and record room	1	7 6	...	8 0		
Verandah	1	7 6	...	8 0		
Do.	1	7 6	...	8 0		
Plastering—					Sq. feet.	2,455
Office and record room	2	75 0	...	14 6	2,175	
Door jambs	2	14 0	...	1 6	42	
Window jambs	8	17 0	...	1 6	204	
Deductions—						2,421
Doors	3	4 0	...	5 0	60	
Windows	8	3 6	...	5 0	140	
						200
Plastering with Portland cement $\frac{1}{2}$ inch thick—					Sq. feet.	2,221
Office and record room	2	75 0	...	3 0	450	
Door jambs	2	6 0	...	1 6	18	
Plinth exterior	2	128 0	...	2 3	288	
Sides of steps	2	2 0	...	1 6	6	
Pointing exterior—					Sq. feet.	762
Walls	2	114 0	...	12 0	1,368	
Gables	2	28 6	...	4 9	271	
Deduct—						1,639
Door	1	4 0	...	8 0	32	
Windows	8	3 6	...	5 0	140	
					Sq. feet.	1,467
					Squares.	14'67

Detail measurements—cont.

Detail of work.	Number.	MEASUREMENTS IN FEET.			Area or contents.	Total quantity of each description of work.
		Length.	Breadth.	Depth.		
		FT. IN.	FT. IN.	FT. IN.		
Flooring with 8 inches square bricks—	1	25 6	...	12 0	306	
Office ...	1	4 0	...	1 6	6	
Door piece ...	1	26 0	...	6 6	169	
Verandah ...	1	11 6	...	3 0	35	
Steps ...	1	11 6	...	3 0	35	
					Sq. feet.	516
					Squares.	5'16
Flooring with asphalt $\frac{3}{4}$ inch thick over a bed of concrete 4 inches thick—	1	25 6	...	12 0	306	
Record room ...	1	4 0	...	1 0	4	
Door piece ...	1	4 0	...	1 0	4	
					Sq. feet.	310
					Squares.	3'10
Painting with three coats of Carson's paint—	36	18 6	...	1 5	944	
Rafters ...	...	18 0	...	3 0	54	
Railing ...	...	18 0	...	3 0	54	
Verandah—	2	2 0	...	7 6	54	
Posts ...	2	2 0	...	6 0	3	
Do. ...	2	1 0	...	1 3	3	
Brackets ...	2	1 0	...	1 6	3	
Do. ...	2	10 0	...	2 0	40	
Bressummers ...	2	7 0	...	0 6	7	
Piece at end ...	2	30 0	...	1 0	30	
Valley rafter and ridge ...	...	212 0	...	0 10 $\frac{1}{2}$	186	
Rafters ...	...	10 6	...	1 0	11	
Collar piece and finial ...	2	7 0	...	1 1	15	
Planks ...	4	2 6	...	1 6	15	
Do. ...	4	7 0	...	2 6	70	
Do. ...	3	4 0	...	8 0	96	
Venetian and panel door ...	2	4 0	...	8 0	64	
Batten door ...	2	3 6	...	5 0	140	
Venetian windows ... 4 x	2	3 6	...	5 0	175	
Do. with glazed shutters 5 x	2	3 6	...	5 0	175	
Batten windows with shutters and iron bars ... 4 x	4	3 6	...	5 0	280	
Sun-shades ...	4	5 0	...	5 0	100	
Do. ...	4	2 0	...	2 0	16	
					Sq. feet.	2,303
					Squares.	23'03

ABSTRACT.

Quantity.	Description of work.	Rate.	Per	Amount.	Total.
2,234 C. feet.	Excavation for foundations	RS.	1,000 C. feet.	RS.	RS.
1,243 "	Earth filling in basement ...				
864 "	Concrete in foundations		100 C. feet.		
1,468 "	Brick-work in foundations and base-ment				
2,861 "	Brick-work in superstructure		"		
86 "	Arch-work		"		
2 "	Stone-work under posts		"		
144 "	Teakwood wrought and put up		C. feet.		
32 Sq. feet.	Venetian and panelled door with frames, hooks and rim lock, complete		"		
32 "	Batten door with frames, hooks, and rim lock, complete		Sq. feet.		
35 "	Venetian windows with frames, hooks, &c., complete		"		
35 "	Venetian windows with frames and glazed inner shutters, hooks, &c., complete		"		
70 "	Battened windows with frames, iron bars, and inner glazed shutters, hooks, &c., complete		"		
35 "	Galvanised iron wire-netting fixed.		"		
2 No.	Sun-shades		"		
24.55 Squares.	Tiled roofing with flat and pan-tiles and teak reapers		Each.		
22 21 "	Plastering interior walls with two coats of chunam		Square.		
7.62 "	Plastering interior walls with Portland cement $\frac{1}{2}$ an inch thick		"		
14.67 "	Pointing exterior walls		"		
5.16 "	Flooring with 8-inch square bricks laid in mortar over a levelling course of wall bricks		"		
3.10 "	Flooring with asphalt $\frac{3}{4}$ inch thick over a bed of concrete 4 inches thick		"		
23.03 "	Painting with three coats of Carson's paint		"		
	Petty supervision at $2\frac{1}{2}$ per cent.		"		
	Contingencies at 5 per cent		"		
	Grand Total of Estimate ...				

MADRAS,
8th June 1888.

(Signed) J. W. BRASSINGTON,
Consulting Architect to Government.

21st JULY 1888, No. 2230 W., PUBLIC WORKS.

GOVERNMENT OF MADRAS.

PUBLIC WORKS DEPARTMENT.

Buildings and Roads.
Civil Works.

READ—the following papers:—

From J. W. BRASSINGTON, Esq., Consulting Architect to the Government of Madras, to the Chief Engineer, Public Works Department, dated Chepāk, 8th June 1888, No. 414.

With reference to the orders of Government marginally noted, I have the honor to submit revised standard designs for Sub-Registrars' offices, with tiled roof and terraced roof, with specifications and schedules of quantities.

G.O. No. 879 W., dated 16th March 1888.
" " 1333 W., " 7th May "

No. 334 D.

Forwarded for the approval of Government in the Judicial Department.

(Signed) J. O. HASTED, Colonel, R.E.,
Ootacamund, 16th June 1888. Secretary to Govt., P.W.D.

Referred to the Inspector-General of Registration for remarks.

(By Order.)

22nd June 1888.

(Signed) A. G. CARDEW,
Ag. Under-Secretary.

From G. HAMNETT, Esq., Inspector-General of Registration, to the Chief Secretary to Government, dated Madras, 28th June 1888, G. No. 2700.

With reference to endorsement, Judicial, (returned with plans and papers), dated the 22nd June 1888, on a letter from the Consulting Architect to the Government, submitting revised designs for Sub-Registry offices with tiled roof and terraced roof, I have the honor to state that the accommodation provided in the revised design is precisely the same as that provided in the design sanctioned in 1885, and that so far as departmental needs are concerned, I have no remarks to make.

2. As regards artistic appearances, I am no judge, but I should not omit to mention, for the information of the Government, that in the tiled roof design the "dormer" has been omitted, apparently because it was difficult to build, and still more difficult to keep from leaking.

3. The terraced roof design is about the same. It is to be hoped that wherever this design is adopted by the Public Works Department, the terrace will be carefully and substantially built to prevent it from leaking.

21st JULY 1888, No. 2230 W., PUBLIC WORKS.

4. The estimate for the two designs does not make provision for any lightning conductors. They may, or may not, be required in some places.
Transferred to the Public Works Department with papers received under endorsement No. 334 D., dated 16th June 1888, returned, and with an intimation that Government in this department approve of the revised type-designs.

(By Order.)

7th July 1888.

(Signed)

A. G. CARDEW,
Ag. Under-Secretary.

ORDER—dated 21st July 1888, No. 2230 W., Public Works.

The revised type-designs, with descriptive specifications and estimates of quantities for Sub-Registrars' offices will be circulated to officers of the Public Works Department in supersession of previous type-designs for similar buildings.

2. Lightning conductors are not considered necessary for these buildings.

(True Extract.)

Captain, R.E.,
Under-Secy. to Govt., P.W.D.

To Superintending Engineers.
To the Consulting Architect to Government.
" Judicial Department.

Exd. F. R. Bantleman.
Spare Copies

1859

10

BUILDINGS AND ROADS.
CIVIL WORKS.

Govt. of (1888) Madras.
PUBLIC WORKS.

Dated July, 21st.

Recd.

Encl.

G.O., 21st July 1888, No. 2230 W.

JULY.

Type-designs

Circulating the revised — with descriptive specifications and estimates of quantities for Sub-Registrars' offices in supersession of previous type-designs.

20TH SEPTEMBER 1888, No. 2958 W., PUBLIC WORKS.

GOVERNMENT OF MADRAS.

PUBLIC WORKS DEPARTMENT.

Buildings and Roads.
Civil Works.

READ—the following paper:—

From J. W. RUNDALL, Esq., M.I.C.E., Superintending Engineer, VI Circle, to the Chief Engineer, Public Works Department, dated Trichinopoly, 7th September 1888, No. 276 R.N.

In G.O., No. 101 W., dated 11th January 1888, an estimate, amounting to Rs. 13,400, was sanctioned for the construction of the District Munsif's Court-house at Paramakudi, in the Madura district, and in this estimate Rs. 1,306 is provided for the construction of a latrine in accordance with the former type design. But in G.O., No. 3019 W., of 10th November 1887, it is ordered that the plan of jail latrine for taluk cutcherries, issued with G.O., No. 1014, dated 20th April 1874, should be adopted instead of the former design as it is on a more expensive scale than is necessary.

2. As the estimate framed on the design circulated with G.O., No. 3019 W., dated 10th November 1887, amounts to only Rs. 599 (*vide* abstract estimate attached) instead of Rs. 1,306, I have the honor to request that you will be good enough to obtain sanction of Government for the following:—

	RS.
Constructing a District Munsif's Court-house at Paramakudi in the	
Madura district	12,094
Constructing a latrine for do. do.	599

Total ... 12,693

in lieu of Rs. 13,400 sanctioned in G.O., No. 101 W., dated 11th January 1888.

ORDER—dated 20th September 1888, No. 2958 W., Public Works.

Sanctioned for the reduced amount, Rs. 12,693.

2. This sanction has been registered as Provincial No. 87 W. of 1888-89 and classified as Civil Buildings, Original Works.

(True Extract.)

(Signed) J. O. HASTED, Colonel, R.E.,
Secretary to Govt., P.W.D.

To the Superintending Engineer, VI Circle.
" Examiner, Public Works Accounts, with the abstract estimate.
" Judicial Department.

Exd. J. Henrius.
Spare Copies

BUILDINGS AND ROADS.
CIVIL WORKS.

Govt. of {1888} Madras.

PUBLIC WORKS.

Dated September, 20th.

Recd.

Encl.

G.O., 20th Sept. 1888, No. 2958 W.

SEPTEMBER.

District Munsif's Court-house at
Paramakudi, Madura District

Estimate, amounting to Rs. 12,693, for
constructing a —, sanctioned in lieu of
the one for Rs. 13,400 sanctioned in G.O.,
No. 101 W., dated 11th January 1888.

[25]

Judicial Department.



1859

PROCEEDINGS OF THE MADRAS GOVERNMENT.

Read the following paper

From the Inspector General of Registration dated
24th October 1888. P. No. 3236.

Order thereon 14th November 1888 No. 2354

The Government approve of the construction
of a Sub-Registrar's office at Paramakudi and the
papers will, accordingly, be transferred to the Public
Works Department.

(True Extract)

A. G. Cordeiro.

Under Secretary



To

The Public Works Department,

with C. Leves.

—u— Inspector General of Registration

12

No 5332

154.

Paramakudi Sub Registry office

8th September 1888.

From *St.*

Mahomed Hussein Khatunigar
Sub Registrar, Paramakudi.

Sub-Registrar, Paramakudi.

The Registrar of Kaduna.

Sept.

With reference to your docket No 3686 dated
H' Luskah, I beg to state that the office is located
in a rented building and though it is tenaced it is
inconmodious and inconvenient. There is no separate
room for the records except a small hall. The
Clerks are obliged to sit on a small pial inside
the office and the parties that come for
registration find it very difficult to find
sufficient place in the two small pials on
side the office.

2. It is not very safe to presume valuable important records in a place like this where incendiarism and burglaries are every day occurrences.

3. They also to point out that the foundations of the District Commissioner's Court of Parama-Kudi has been laid and work commenced and there is enough of space near the site of the new Court house I think it very desirable that a pueka tetraed building

13

For

14 V. Rajagopalakrishnan
Registrar.

Registrar.

the Sub Registrar's office may also be con-
sidered there.

I have the honor to be

Yours most obedient servant
S. Sub Registrar

1888
Registration No. 4306
To
The Sub Registrar
of the Registrar
Madras
Recd. 1888
2/12/88
Recd. 1888
Sub Registrar
to a building for
the Sub Registrar's
Office.

MADURA REGISTRAR'S OFFICE,
Dated 8. October 1888.

No. 4306

From V. Rajapalechiar
REGISTRAR OF

MADURA.

To

THE INSPECTOR GENERAL OF
REGISTRATION,
MADRAS.

SIR,

With reference to your Prop. No. 2837 dated 26
April/88 I have the honor to submit for orders
the enclosed letter of the Sub Registrar of Paracumari
applying for a new building to his office.

2. His office is now held in a rented building
and the Sub Registrar thinks that it is neither a
convenient nor a safe place.

3. It would seem that a Mansiff's Court
is in course of erection and that this will be
an appropriate moment to build up a
registration office also, with the Court house,
building.

4. The Registrations and Collections were in 1887-8
2454 and Rs 2846 respectively.

I have the honor to be,

Sir,

Your most obedient servant,

V. Rajapalechiar
Registrar.

7. N. 3235. 24. October 1888.
Obtained

The Government will be satisfied.

By the Registrar of Madras -

Substantiating letter from the
Sub-Registrar of Paramara-
Kudi stating that a
new office building

Dated 8. October 1888.
Received 11. }
R. No. 9272
No. 4306
ENCLOSURES. only
Subject: -

THE INSPECTOR GENERAL OF
REGISTRATION,
MADRAS.

Registration (1888) Department.
From (Official Account)
THE REGISTRAR OF
MADRAS.

Registration Department.
T. N. 3236.

From,

Gen. Stannett Esq.
Inspector General of Registration
Madras.

To,

The Honble. J. F. Price
Acting Chief Secretary to the
Government.
Fort St. George
Obtained 24. October 1888.

Sir,

In G.O. Judicial dated
the 19th September 1885. No. 2506, the
Government were pleased to sanction
the opening of a sub registry office
at Paramatandi in the Madurai
district from the 1st November 1885.

The office was opened accordingly,
and it is now self-supporting.

The Sub Registrar reports:
"The office is located in a
rented building and though it is
serviced it is incommodious and
inconvenient. There is no separate
room for the records except a small
hall. The clerks are obliged to sit
on a small stool inside the office,
and the parties that come for
registration find it very difficult
to find sufficient place in the

* For 1887-88
Registration Rs. 2454.
Receipts Rs. 2846.
Expenditure Rs. 1620.

256. 4681/88

Two small pials outside the office."

"It is not very safe to
preserve valuable important records
in a place like this where incendiarism
and burglaries are every day occurrences."

3. Under the circumstances,
I have the honor to recommend that the
sanction of the Government may be
granted for the preparation of
plans and estimate, on the revised
standard design, for the construction
of a Sub-Registrar's Office in the
same compound in which the
District Munsiff's Court is being
built.

I have the honor to be,
Sir,

Your most obedient servant,

W. Hammett
Supr. Genl. of Repts.
JH

1859

16

1221

31
1844/76

27

1859

Commenced by
the 25th Sept 1859
for admission of the
residents of the

the 25th Sept 1859
for admission of the
residents of the

17

295-8 w 7 20/4/00
101 w 7 11/1/00

Obt. of 188) Madras.

B No 3703 Wd/23. XI. 88

Communicated to
the Supt. Engr. II Circle
for submission of the
requisite estimate

Wm
17/11/00

Wm

17/11/00

The M.D.

Proceedings, dated 14-11-1888
No. 2354

Subject.

No 3703 Wd/23. XI. 88

Ref the construction
of a Sub Registrars
Office at Parama-
gudi Madurai
District

S. & T. Circle
S. & T. Circle
Judd Deptt.

27/11/00
23/11/00
30/11/00

No 93 B.M.

1859 1P

Report by the Superintending Engineer on the
Estimate amounting to Rs. 3220 for Constructing a
Sub Registrars Office at Paramakudi

Reference - G. O. No 3703. D. of 23rd October 1888.

Enclos: 3.
1. site plan.
1. Estimate.
1. Abstract in
duplicate

Per Mr. Engr. II Circle
14-11-00

The Estimate was called for in G. O.
quoted above and it is prepared in accordance
with the revised Standard Design for the Sub
Registrars Office with tiled roof circulated
with G. O. No. 2230. D. dated 21st July 1888,
with the exception of a slight deviation in the
following sub heads of works which are found
unavoidably necessary.

(a) Substitution of plastering for pointing
exterior walls, as bricks to be used in the structure
are made unavoidably of salt earth.

(b) Substitution of flooring with concrete 4"
thick and plastered with cement, for flooring
of 8" square bricks as good round bricks are
not obtainable.

(c) Substitution of Wood oiling to treat wood
work unexposed to weather, in place of painting.

2. In his letter No. 3236. dated 24th
October 1888. embodied the above G. O. the
Inspector General of registration suggested
to have the building in the same compound
in which the District Munsiff's Court is being
built, but as a reference being made, the
District Judge remarked that the construction
of the building within the District Munsiff's
Court

Court Compound is objectionable as it is very small.

3. The new site now proposed in communication with the Sub. Registrar is contiguous to the Compound above alluded to and so it is a very suitable one. The site being private property a Compensation of Rs: 294 is allowed in the Estimate as reported by the Head Assistant Collector.

4. The rates are fair and the Estimate is submitted for the sanction of Government through the Inspector General of Registration under para 989 of the D. in. Code.

Camp: Hadikaul
7th June 1889.
8th 10th

A Smith Lt. Col: DR.
Superintg. Engineer

2P

7. N. 2894 14 June 1889
Advise

Submitted for the sanction of the Govern.

G. O. No. 1054, approved of the construction of the Office -

W. H. Bennett
Super. Secy. P. & S.

To the Chief Secretary
to the Government.

1859

19

44908/88

T 2781/88

1281

From

The Supt. Engineer
VI circle.

No 9319 R

Dated 7th

Sept. 10

Rec. 12th

3 June 1889.

R No. 4935

Report on estimate for
constructing sub. Registrar's
office at Paramakandi.

1859

20

to be unsuitable -
 It was suggested by
 the Inspector General
 of Registrations that the
 Sub Registrar's office should
 be built in the same
 compound in which
 the Dist. Munsiff Court
 is being constructed,
 but the Dist. Judge
 considers the compound
 too small for both
 buildings, it is
 therefore proposed
 to build the Sub
 Registrar's office on a
 suitable site contiguous
 to the Dist. Munsiff
 Court, and compensation
 for the land which
 amounts to Rs 294
 is provided for in
 the Est.
 The estimates as far as can
 be checked are fair -
 The plinth area of the
 building is 996 sq ft
 and the cost per sq
 foot is Rs 3.3.9 -
 The site plan and
 estimate have been
 countersigned by
 the Inspector General
 of Registrations and
 approved in the judicial
 Dept. - Cmt 3/7/89

Hm/A

No 1859 W
 1889

B & R
 works

PUBLIC WORKS DEPARTMENT.

PROCEEDINGS OF THE MADRAS GOVERNMENT.

Under date the 12th July 1889

Read the following

From the Inspectors -
 General of Registrations - No 2894 dated 14th June 1889
 Endorsement thereon
 in the judicial department - dated 22nd June 1889 -

LP

The estimate
 amounting to Rs 3,220 for
 constructing a Sub Registrar's
 office at Paramakudi in the
 Madurai District is sanctioned
 for execution when funds are
 available.

445
 9/1/89

20 - This sanction has been
 registered as Provincial No 34. W
 of 1889-90 and classified as
 Civil Buildings, Original works.

Dec
 20/7

WCM
 5.7.89

Prasad
 8.7.89

The Suptg Engineer VI Circle
 with 3 enclosures.
 Examined P.W. accounts
 with duplicate abstract estimate.
 in judicial department.

CM

may

28

in 1721-15-1-88.
in 2354-14-11-88.
mem 5888

By Rev 370348 22-11-88.
" 29584 20-9-88.
" 23306 21-7-88.

MM

310

Approved and transferred to the
Public Works Department.

By Garden.

Under Secy.

By 26/6/89

in 5 (1/1/89)



Judicial (1889) Department.
Registration.

From,
The Inspector General
of Registration,
Madras.

To, The Chief Secretary
to the Government,
Madras.

Dated 14th June 1889
Received.

S.N. 2894
14 JUN 89
UNDER SECRETARY
PUBLIC WORKS DEPT.

Enclosure (3)

N.

Submitting the report from
the Superintending Engineer
in Madras on the estimate of Rs 3220.
for constructing a Sub. Registrar's
office at Parangankudi.

By 26/6/89
MM

Public Works Department.

Current No. 5888
Letter No. 1859
Dated 22nd June 1889
From the Judicial Dept.

NOTE OF REMARKS.

The estimate under
review amounting to
Rs 3,220, provides for
constructing a Sub-
Registrar's Office at
Parangankudi in the
Madras Dist.

The building is to be
constructed in wood,
under with the work
designs approved
in G.O. No 2230 W.
of 26th July 1888 with
the following exceptions

- (1) Substitution of
plastering for painting
interior of walls.
- (2) Substitution of
concrete flooring
4" thick for 8" square
bricks.
- (3) Substitution of
woodwork for painting
under paint work.

These deviations from
the Standard Est. are stated.

1821



5-1859

1821-89

1821

Oct 3677 Hm 877-7
12.12.7-89

23

Gobt. of Madras.

PUBLIC WORKS.

13/7/89

Dated

Recd.

Encl.

G.O. 12 July 1889 No. 18596

Sub-Registrar's Office
at Paramakudi,
Madura Dist.

Sub-Registrar, sanctioned

100/-

(23)

27/12/89