GOVERNMENT OF MADRAS.

REVENUE DEPARTMENT.

READ—the following G.O., dated 14th June 1889, No. 373, Financial :—

Read—the following papers :—

From the Accountant-General, dated 4th May 1889, No. 1420.

The Madras Municipality include in the bill for assessment on the buildings classed as the "Chepauk Palace and Garden" the cricket pavilion on the Chepauk grounds, and the proportionate assessment paid to the municipality by the Secretary to the Board of Revenue on account of the pavilion for the official year 1888-89 was Rs. 50-4-0.

2. The Consulting Architect to Government having reported that he believed the building to be the property of the Madras Cricket Club, by whom it is used, a reference was made to the Honorary Secretary of the Club, and I enclose for the information of Government copies of the replies from Dr. Thurston, No. 117, dated 14th February and 15th April 1889, from which it will be seen that the building was erected by the members of the club on land which is the property of Government. As the site was not leased by Government to the club, the pavilion would appear to be the property of Government, which is, therefore, technically liable for the assessment, but I have thought it right to lay the facts before Government, as it seems probable that, under the circumstances stated, it may see fit to require the members of the club to pay the assessment as a condition to their using the pavilion.

ENCLOSURES.

From Mr. E. Thurston, Honorary Secretary, Madras Cricket Club, to the Accountant-General, dated 14th February 1889, No. 117.

With reference to your No. 189, dated 24th January 1889, I have the honor to inform you that the "cricket pavilion" was built by subscription among the members of the Cricket Club and is the property of the Cricket Club, except in so far as it is built on ground belonging to Government.

From the Honorary Secretary, Madras Cricket Club, to the Accountant-General, dated 15th April 1889.

With reference to your letter, No. 655, dated 5th March 1889, I have the honor to inform you that, so far as I am aware, the ground used by the Madras Cricket Club was simply lent by Government, and I do not know of the existence of any lease or agreement referring to the cricket pavilion.

Note by the Chief Engineer, Public Works Department (General Buildings and Roads Branch), dated 1st June 1889, No. 261-D.

I do not think that the Madras Cricket Club can consider it a hardship to be called upon to pay the annual municipal assessment on the pavilion as a set-off for the use of the same. As regards the history of this pavilion and the ground on which it stands, attention is invited to a memorandum, dated 16th October 1887, by the Honorary Secretary of the Cricket Club, which will be found in the file of G.O., dated 29th October 1879, No. 2721 W. (enclosed to be kindly returned).

Order—dated 14th June 1889, No. 373, Financial.

Orders will be issued in the Revenue Department, declaring the tenure of the land used as the cricket ground, viz., that it is Government land, granted free of rent or land-tax to the Madras Cricket Club for a cricket ground, and that, if the club ceases to exist, the land will revert to Government.

2. The tenure being such, it is for the Madras Cricket Club to pay the municipal assessment on the pavilion.

(True Extract.)

(Signed) J. F. PRICE,
Chief Secretary.

To the Accountant-General.
" Public Works Department.
" Revenue Department, with the file of papers to be returned to the Public Works Department when done with.

ORDER—dated 19th July 1889, No. 605, Revenue.

Land Revenue, No. 66.

The land in the occupation of the Madras Cricket Club is Government land granted free of rent or assessment for a cricket ground subject to reversion when it ceases to be used for that purpose.

(True Extract.)

(Signed) C. A. GALTON,
Secretary to Government.

To the Public Works Department,
with one enclosure returned.
" the Financial Department.
" the Board of Revenue (Land Revenue).

Exd. A. D. Xavier.

60 Copies.

Govt. of {1889} Madras.

REVENUE.

Issued.

Recd. *Encl.*

G.O., 19th July 1889, No. 605.

JULY.

Cricket Ground at Chepauk.

Declared to be Government land granted to the Madras Cricket Club free of rent or assessment, subject to reversion when it ceases to be used as such.

GOVERNMENT OF MADRAS.

REVENUE DEPARTMENT.

READ—the following letter from the Government of India, Department of Finance and Commerce, dated 18th June 1889, No. 3040 :—

I am directed to acknowledge the receipt of your letter, No. 325, Revenue, dated 30th April 1889, forwarding the Proceedings of the Government of Madras in which it is proposed that the ruling in paragraph 9 of the Resolution of this department, No. 1648, dated the 28th March 1888, may be modified so as to admit of the grant of compensation for the dearness of provisions being regulated with reference to the prices not of the cheapest staple food-grain of the district, but of the cheapest staple food of the servants to whom it is intended to afford relief.

2. In reply, I am directed to explain that the basis of the rule which was laid down in 1870, and the strict observance of which is directed in the Resolution of 28th March 1888, is that if in any district the common food of the people has risen in price beyond a certain point, the fact indicates a general scarcity and pressure in the district causing such distress to Government servants there employed as to warrant an increase to their pay sufficient to mitigate the hardship caused by high prices. The change proposed by the Government of Madras would render admissible the grant of compensation before such general scarcity had occurred.

3. The Governor-General in Council does not consider that the necessity for thus extending the grant of compensation has been established, and therefore regrets that he is unable to accept the proposal, which would, moreover, complicate the rule and might lead to the result that in the same district and at the same time some Government servants of the class for whose relief the rule is intended would be in receipt of compensation for dearness of provisions while others were not.

ORDER—dated 16th July 1889, No. 597, Revenue.

Miscellaneous.

Recorded.

2. With reference to paragraph 3 of the above letter, it is observed that as in this Presidency all classes of Government servants are habitually rice-eaters, the difficulty anticipated by the Government of India cannot arise.

3. So far as the Ganjam district is concerned, the inquiries made by His Excellency the Governor during his late tour in that district showed beyond doubt that rice, not ragi, is the staple cultivation of the district and the staple food of the people, five-sixths of whom, including many of the very poorest, eat nothing but rice. The percentage of the acreage under rice to total cultivation is also 67, whereas the percentage as regards ragi is only 19. In these circumstances, His Excellency the Governor in

Council is pleased to declare, in modification of previous orders, that rice shall be considered to be " the common staple food " of the people of the Ganjam district under paragraph 9 of the Resolution of Government of India, dated 28th March 1888, No. 1648.

(True Extract.)

(Signed) C. A. GALTON,
Secretary to Government.

To the Commissioner of Revenue Settlement, Land Records and Agriculture.
„ the Commissioners of Land Revenue.
„ the Accountant-General.
„ the Public, &c., Departments.
„ the Local and Municipal Department.
„ the Public Works Department.
„ the Military Department.

Exd. A. Aubert.

120 Copies.

Govt. of {1889} Madras.

REVENUE.

Issued

Recd. *Encl.*

G.O., 16th July 1889, No. 597.

JULY.

Famine Batta.

Rice declared to be the common staple food of the people of the Ganjam district for the purpose of regulating the grant of —.

GOVERNMENT OF MADRAS.

REVENUE DEPARTMENT.

READ—the following letter from the Government of India, Department of Finance and Commerce, dated 18th June 1889, No. 3040 :—

I am directed to acknowledge the receipt of your letter, No. 325, Revenue, dated 30th April 1889, forwarding the Proceedings of the Government of Madras in which it is proposed that the ruling in paragraph 9 of the Resolution of this department, No. 1648, dated the 28th March 1888, may be modified so as to admit of the grant of compensation for the dearness of provisions being regulated with reference to the prices not of the cheapest staple food-grain of the district, but of the cheapest staple food of the servants to whom it is intended to afford relief.

2. In reply, I am directed to explain that the basis of the rule which was laid down in 1870, and the strict observance of which is directed in the Resolution of 28th March 1888, is that if in any district the common food of the people has risen in price beyond a certain point, the fact indicates a general scarcity and pressure in the district causing such distress to Government servants there employed as to warrant an increase to their pay sufficient to mitigate the hardship caused by high prices. The change proposed by the Government of Madras would render admissible the grant of compensation before such general scarcity had occurred.

3. The Governor-General in Council does not consider that the necessity for thus extending the grant of compensation has been established, and therefore regrets that he is unable to accept the proposal, which would, moreover, complicate the rule and might lead to the result that in the same district and at the same time some Government servants of the class for whose relief the rule is intended would be in receipt of compensation for dearness of provisions while others were not.

ORDER—dated 16th July 1889, No. 597, Revenue.

Miscellaneous.

Recorded.

2. With reference to paragraph 3 of the above letter, it is observed that as in this Presidency all classes of Government servants are habitually rice-eaters, the difficulty anticipated by the Government of India cannot arise.

3. So far as the Ganjam district is concerned, the inquiries made by His Excellency the Governor during his late tour in that district showed beyond doubt that rice, not ragi, is the staple cultivation of the district and the staple food of the people, five-sixths of whom, including many of the very poorest, eat nothing but rice. The percentage of the acreage under rice to total cultivation is also 67, whereas the percentage as regards ragi is only 19. In these circumstances, His Excellency the Governor in

Council is pleased to declare, in modification of previous orders, that rice shall be considered to be " the common staple food " of the people of the Ganjam district under paragraph 9 of the Resolution of Government of India, dated 28th March 1888, No. 1648.

(True Extract.)

(Signed) C. A. GALTON,
Secretary to Government.

To the Commissioner of Revenue Settlement, Land Records and Agriculture.
" the Commissioners of Land Revenue.
" the Accountant-General.
" the Public, &c., Departments.
" the Local and Municipal Department.
" the Public Works Department.
" the Military Department.

Exd. A. Aubert.

120 Copies.

(R^e 7385-

Gobt. of {1889} Madras.

REVENUE.

Issued

Recd. Encl.

G.O., 16th July 1889, No. 597.

R. 8922/11 W. 14-8-89

JULY.

Famine Batta.

Rice declared to be the common staple food of the people of the Ganjam district for the purpose of regulating the grant of —.

N^o 2211 W 14-8-89

Communicated to the Superintending Engr. I circle in continuation of G.O. 1866 W 22-6-88

(sd) R R E D 13

SE I circle
EX Or Accounts

Gobt. of {1889} Madras.

REVENUE.

Issued

Recd. Encl.

Encl 1
DW 9/7/89

G.O., 25th July 1889, No. 638.

JULY.

Famine Batta.

The grant of an extra allowance of one rupee per mensem to certain classes of Government servants in the Ganjam district, sanctioned.

25th July 1889, No. 638, Revenue.

GOVERNMENT OF MADRAS.

REVENUE DEPARTMENT.

Order—dated 25th July 1889, No. 638, Revenue.

Miscellaneous.

As the price of rice which forms the common staple food of the people of the Ganjam district is now higher than 12 seers per rupee, His Excellency the Governor in Council is pleased to direct, under paragraph 7 of the Resolution of the Government of India, dated 28th March 1888, No. 1648, that all servants of Government on civil establishments in the district, whose pay does not exceed Rs. 16 per mensem, or in the case of officials required to keep a horse, Rs. 25 per mensem, shall, as a temporary measure, and until further orders, be paid an extra allowance of one rupee per mensem, provided that the aggregate monthly pay shall in no case be less than Rs. 6.

(True Extract.)

(Signed) C. A. GALTON,
Secretary to Government.

To the Financial Department.
„ the Collector of Ganjam.
„ the Commissioner of Revenue Settlement, &c.
„ the Accountant-General.
Copy to the Commissioners of Land Revenue.

Exd. A. D. Xavier.

85 Copies.

16th July 1889, No. 597, Revenue.

GOVERNMENT OF MADRAS.

REVENUE DEPARTMENT.

Read—the following letter from the Government of India, Department of Finance and Commerce, dated 18th June 1889, No. 3040 :—

I am directed to acknowledge the receipt of your letter, No. 325, Revenue, dated 30th April 1889, forwarding the Proceedings of the Government of Madras in which it is proposed that the ruling in paragraph 9 of the Resolution of this department, No. 1648, dated the 28th March 1888, may be modified so as to admit of the grant of compensation for the dearness of provisions being regulated with reference to the prices not of the cheapest staple food-grain of the district, but of the cheapest staple food of the servants to whom it is intended to afford relief.

2. In reply, I am directed to explain that the basis of the rule which was laid down in 1870, and the strict observance of which is directed in the Resolution of 28th March 1888, is that if in any district the common food of the people has risen in price beyond a certain point, the fact indicates a general scarcity and pressure in the district causing such distress to Government servants there employed as to warrant an increase to their pay sufficient to mitigate the hardship caused by high prices. The change proposed by the Government of Madras would render admissible the grant of compensation before such general scarcity had occurred.

3. The Governor-General in Council does not consider that the necessity for thus extending the grant of compensation has been established, and therefore regrets that he is unable to accept the proposal, which would, moreover, complicate the rule and might lead to the result that in the same district and at the same time some Government servants of the class for whose relief the rule is intended would be in receipt of compensation for dearness of provisions while others were not.

Order—dated 16th July 1889, No. 597, Revenue.

Miscellaneous.

Recorded.

2. With reference to paragraph 3 of the above letter, it is observed that as in this Presidency all classes of Government servants are habitually rice-eaters, the difficulty anticipated by the Government of India cannot arise.

3. So far as the Ganjam district is concerned, the inquiries made by His Excellency the Governor during his late tour in that district showed beyond doubt that rice, not ragi, is the staple cultivation of the district and the staple food of the people, five-sixths of whom, including many of the very poorest, eat nothing but rice. The percentage of the acreage under rice to total cultivation is also 67, whereas the percentage as regards ragi is only 19. In these circumstances, His Excellency the Governor in

Council is pleased to declare, in modification of previous orders, that rice shall be considered to be "the common staple food" of the people of the Ganjam district under paragraph 9 of the Resolution of Government of India, dated 28th March 1888, No. 1648.

(True Extract.)

(Signed) C. A. GALTON,
Secretary to Government.

To the Commissioner of Revenue Settlement, Land Records and Agriculture.
" the Commissioners of Land Revenue.
" the Accountant-General.
" the Public, &c., Departments.
" the Local and Municipal Department.
" the Public Works Department.
" the Military Department.

Exd. A. Aubert.

120 Copies.

Govt. of {1889} Madras.

REVENUE.

Issued

Recd. Encl.

G.O., 16th July 1889, No. 597.

JULY.

Famine Batta.

Rice declared to be the common staple food of the people of the Ganjam district for the purpose of regulating the grant of —.

№ 2211 tr dy 14th August 1889

Communicated to the Superintending Engineer I Circle in Continuation of Go 1866 tr dy 22 June 1888

(sd) R R E & B

S E I circle
Ex. P. W.a

20TH SEPTEMBER 1882, No. 2440 W., PUBLIC WORKS.

GOVERNMENT OF MADRAS.

PUBLIC WORKS DEPARTMENT.

Buildings and Roads.
Civil Works.

READ—the following papers :—

From J. W. RUNDALL, Esq., Superintending Engineer, II Circle, to the Chief Engineer, Public Works Department, dated Bezváda, 5th August 1882, No. 440 N.L. :—

I have the honor to forward, herewith, a revised estimate for the Kandukur sub-jail, amounting to Rs. 12,325, together with a comparative statement and explanatory memorandum by the Executive Engineer and two reports.

2. If the Executive Engineer's proposition be accepted and the unfinished latrine be converted into a ryot's shed, only Rs. 350 more than the present sanction will be required to complete the building.

3. As far as my experience goes, numerous latrines have been constructed throughout the Presidency in connection with these cutcherries which are never used, nor can they be used, unless an establishment is maintained to keep them clean. There are still many cutcherries on the standard plan to be built in various districts, and I would suggest district officers being called on to report whether it is necessary to continue building latrines which are never used.

No. 608 E.

Referred to the Judicial Department for approval and for consideration whether the ryot's shed may be omitted as suggested, the latrine being finished off to serve as such.

(By Order.)

(Signed) ROSS THOMPSON, Lieut.-Colonel, R.E.,
21st August 1882. Ag. Under-Secy. to Govt., P.W.D.

Proceedings of the Board of Revenue, dated 2nd September 1882, Mis. No. 6818.

Read—official memorandum from the Acting Under-Secretary to Government, Judicial Department, dated 25th August 1882, No. 810.

Resolution—dated 2nd September 1882, Mis. No. 6818.

The Board agree with the Superintending Engineer. The construction of latrines is generally unnecessary, considering the small number of prisoners usually confined in sub-jails, and it is believed that such buildings are but rarely used for the purpose for which they are intended.

(A true Extract.)

(Signed) E. GIBSON,
Acting Secretary.

No. 892, Judicial.

Approved and transferred to the Public Works Department, with reference to endorsement in that department, dated 21st August 1882, No. 608 (returned).

(By Order.)

OOTACAMUND,
8th September 1882.

(Signed) G. S. FORBES,
Ag. Under-Secretary.

ORDER—dated 20th September 1882, No. 2440 W., Public Works.

The proposal to finish off the partly-built latrine at the Kandukur sub-jail, Nellore district, to serve as a ryot's shed, having been approved in the Judicial Department, the building provided for in the estimate for the latter purpose need not be constructed. The excess over the original estimate, sanctioned in G.O., Judicial Department, No. 1488, dated 11th August 1874, will thus be only Rs. 350, and this can be dealt with by the Superintending Engineer under para. 293, clause (*e*), of the Public Works Code.

2. The Proceedings of the Board of Revenue, communicated with the foregoing endorsement from the Judicial Department, will be communicated to all Superintending Engineers for information and guidance.

(True Extract.)

(Signed) J. SHAW-STEWART, Colonel, R.E.,
Secretary to Government, P.W.D.

To the Superintending Engineer, II Circle, with six enclosures.
To other Superintending Engineers.
To the Examiner, Public Works Accounts.
„ Judicial Department.

Exd. F. R. Bantleman.
Spare Copies

BUILDINGS AND ROADS.
CIVIL WORKS.

Govt. of {1882} Madras.

PUBLIC WORKS.

Dated September, 20th.

Read. *Encl.*

G.O., 20th Sept. 1882, No. 2440 W.

SEPTEMBER.

Kandukur Sub-Jail, Nellore District

Passing orders regarding the conversion of the latrine at the —, to serve as a ryot's shed.

GOVERNMENT OF MADRAS.

PUBLIC WORKS DEPARTMENT.

Buildings and Roads.
Civil Works.

Read—the following papers:—

Proceedings of the Board of Revenue, dated 30th July 1885, Mis. No. 6929.

Read—the following letter from C. S. CROLE, Esq., Collector of Madura, to the Secretary to the Board of Revenue, dated Madura, 25th July 1885, No. 437 :—

With reference to the Proceedings of the Board of Revenue, dated 10th March 1884, No. 839, communicating G.O., dated 21st February 1884, No. 483 W., Public Works Department, I have the honor to submit, for the sanction of Government, estimate, &c., for constructing a taluk cutcherry with outhouses, &c., at Tirumangalam, received from the Superintending Engineer, VI Circle, Trichinopoly.

Resolution—dated 30th July 1885, Mis. No. 6929.

Submitted for the sanction of Government.

(A true Copy and Extract.)

(Signed) E. GIBSON,
Secretary.

Mis. No. 4222, Revenue.

Approved and transferred to the Public Works Department.

Ootacamund,
12th August 1885.

(Signed) W. WILSON,
Ag. Secretary to Government.

Order—dated 31st August 1885, No. 2013 W., Public Works.

The estimate, amounting to Rs. 25,110, for constructing a tahsildar's office with outhouses at Tirumangalam, in the Madura district, is sanctioned for execution when funds are available.

2. This sanction has been registered as Provincial No. 114 W. of 1885-86, and classified as Civil Buildings, Original Works.

(True Extract.)

(Signed) J. SHAW-STEWART, Colonel, R.E.,
Secretary to Govt., P.W.D.

To the Superintending Engineer, VI Circle, with five enclosures.
" Examiner, Public Works Accounts, with duplicate abstract estimate.
" Revenue Department.

Exd. J. Henricus.
Spare Copies

BUILDINGS AND ROADS.
CIVIL WORKS.

Govt. of {1885} Madras.

PUBLIC WORKS.

Dated August, 31*st*.

Recd. *Encl.*

G.O., 31st Aug. 1885, No. 2013 W.

AUGUST.

Tahsildar's Office at Tirumangalam, Madura District

Estimate for —, sanctioned.

Annexure to G.O., No. 1495 *W., dated* 3*rd June* 1887.

ESTIMATE FORM—Detail Measurements.

Detail of work.	No.	Measurements in Feet. Length.	Breadth.	Depth.	Area or contents.	Total quantity of each description of work.
EXCAVATION FOR FOUNDATIONS.						
Court, outer walls	..	92 0	4 0	4 6	1,656	
Property and private room, end walls	3	5 4½	3 7½	4 6		
Do. do. outer walls	..	45 7½	3 7½	4 6	1,007	
Cashier's, sheristadar's, clerk's room, longitudinal walls	2	70 0	4 0	4 6		
Do. do. partition	3	15 6	4 0	4 6		
Record room, outer walls	..	95 6	4 0	4 6	5,076	
Treasury and inspector's room, &c., outer walls	..	115 9	4 4½	4 6		
Do. do. inner walls	2	20 4½	4 4½	4 6		
Do. do.	1	9 6	4 4½	4 6	3,268	
Jail wards, outer walls	..	173 0	4 0	4 6	3,114	
Do. partitions	4	12 6	3 7½	4 6	816	
Verandah and covered way walls near jail	..	89 0	3 3	4 6		
Do. in front	..	130 0	3 3	4 6	5,404	
Do. in rear and sides of record room	..	150 6	3 3	4 6		
Extra thickness at verandah posts	32	1 1½	0 4½	4 6		
Do. do. at corners	5	0 4½	0 4½	4 6	64	
Do. do.	4	1 10½	0 4½	4 6	13	
Steps	2	12 6	3 0	1 6		
Do.	1	11 6	3 0	1 6	214	
Do.	2	5 6	3 0	1 6		
Total, Cubic feet	..	..	..	..	..	20,632
CONCRETE IN FOUNDATIONS.						
Court, outer walls	..	92 0	4 0	1 6	552	
Property and private room, end walls	3	5 4½	3 7½	1 6		
Do. do. outer walls	..	45 7½	3 7½	1 6	336	
Cashier's, sheristadar's and clerk's room, longitudinal walls	2	70 0	4 0	1 6		
Do. do. partitions	3	15 6	4 0	1 6		
Record room, outer walls	..	95 6	4 0	1 6	1,692	
Treasury and inspector's room, outer walls	..	115 9	4 4½	1 6		
Do. do. inner walls	2	20 4½	4 4½	1 6		
Do. do.	1	9 6	4 4½	1 6	1,089	
Jail wards, outer walls	..	173 0	4 0	1 6	1,038	
Do. partitions	4	12 6	3 7½	1 6	272	
Verandah and covered way walls near jail	..	89 0	3 3	1 6		
Do. in front	..	130 0	3 3	1 6	1,800	
Do. in rear and sides of record room	..	150 6	3 3	1 6		
Extra thickness at verandah posts	32	1 1½	0 4½	1 6		
Do. do. at corners	5	0 4½	0 4½	1 6	26	
Do. do.	4	1 10½	0 4½	1 6		
Steps	2	12 6	3 0	1 6		
Do.	1	11 6	3 0	1 6	214	
Do.	2	5 6	3 0	1 6		
Total, Cubic feet	..	..	..	..	..	7,019
BRICKWORK IN FOUNDATIONS.						
Footings.						
Court, outer walls	..	92 0	2 3	1 0	207	
Private and property room end walls	3	7 1½	1 10½	1 0		
Do. do. outer walls	..	43 10½	1 10½	1 0	122	
Cashier's, sheristadar's and clerk's room, longitudinal walls	2	71 9	2 3	1 0		
Do. do. partitions	3	17 3	2 3	1 0	658	
Record room, outer walls	..	97 3	2 3	1 0		
Treasury and inspector's room, outer walls	..	115 9	2 7½	1 0		
Do. do. inner walls	2	22 1½	2 7½	1 0	450	
Do. do.	1	11 3	2 7½	1 0		
Jail wards, outer walls	..	173 0	2 3	1 0	389	
Do. partitions	4	14 3	1 10½	1 0	107	
Verandah and covered way near jail	..	92 6	1 6	1 0		
Do. in front	..	131 9	1 6	1 0	565	
Do. in rear and sides of record room	..	152 3	1 6	1 0		
Extra thickness at verandah posts	32	1 1½	0 4½	1 0		
Do. do. at corners	5	0 4½	0 4½	1 0	17	
Do. do.	4	1 10½	0 4½	1 0		
Above footings to ground level, court, outer walls.	..	92 0	1 6	2 0	276	
Private and property room, end walls	3	7 10½	1 1½	2 0		
Do. do. outer walls	..	43 1½	1 1½	2 0	150	

Estimate Form—Detail Measurements—*cont.*

Detail of work.	No.	Measurements in Feet. Length.	Breadth.	Depth.	Area or contents.	Total quantity of each description of work.
BRICKWORK IN FOUNDATIONS—*cont.*						
Footings—cont.						
Cashier's, sheristadar's and clerk's rooms, longitudinal walls	2	72 6	1 6	2 0		
Cashier's, sheristadar's and clerk's rooms, longitudinal partitions						
Record room, outer walls	3	18 0	1 6	2 0	891	
		98 0	1 6	2 0		
Treasury and Inspector's room.						
Outer walls		116 9	1 10½	2 0		
Do. inner walls	2	22 10½	1 10½	2 0		
Do. do.	1	12 0	1 10½	2 0	654	
Jail wards, outer walls		173 0	1 6	2 0	519	
Do. partitions	4	15 0	1 1½	2 0	135	
Verandah and covered ways near jail		94 0	0 9	2 0		
Do. in front		132 6	0 9	2 0	569	
Do. in rear and sides of record room		153 0	0 9	2 0		
Extra thickness at verandah posts	32	1 1½	0 4½	2 0		
Do. at corners	5	0 4½	0 4½	2 0		
Do. do.	4	1 10½	0 4½	2 0	34	
Extra thickness for plinth		199 7½	0 3	2 0	100	
Dais walls		20 9	1 1½	1 6	35	
Steps		36 6	3 0	0 6	55	
Do.		30 6	2 0	0 6	31	
Do.		24 6	1 0	0 6	12	
Do. near jail	2	5 6	3 0	1 0	33	
Deduct—						3,494
Stone in steps						72
Total, Cubic feet						3,422
BRICKWORK IN SUPERSTRUCTURE.						
Court, outer walls		92 0	1 6	13 3	1,829	
Do. dais walls		20 9	1 1½	1 6		
Private and property room end walls	3	7 10½	1 1½	8 0	35	
Do. do. half gables	3	7 10½	1 1½	3 0	292	
Do. do. outer walls		43 1½	1 1½	8 0	388	
Cashier's, sheristadar's and clerk's room, longitudinal walls	2	72 6	1 6	13 3		
Cashier's, sheristadar's and clerk's room, longitudinal partitions	3	18 0	1 6	13 3	3,955	
Cashier's, sheristadar's and clerk's room, longitudinal gables	4	21 0	1 6	3 6		
Record room, outer walls		98 0	1 6	12 0	441	
Do. gables	2	18 0	1 6	3 0	1,764	
Treasury and inspector's room, outer walls, including battlement					162	
Treasury and inspector's room, inner walls		116 9	1 10½	20 0		
Do. do. do.	2	22 10½	1 10½	15 0	4,378	
Jail wards, outer walls	1	12 0	1 10½	15 0	1,624	
Do. partitions		173 0	1 6	12 0		
Do. gables at ends	4	15 0	1 1½	12 0	3,114	
Do. do. for partitions	2	18 0	1 6	3 0	810	
	4	18 0	1 1½	3 0	162	
					243	
						19,179

Estimate Form—Detail Measurements—*cont.*

Detail of work.	No.	Measurements in Feet. Length.	Breadth.	Depth.	Area or contents.	Total quantity of each description of work.
BRICKWORK IN SUPERSTRUCTURE—*cont.*						
Deductions—						
Doors in treasury	8	4 0	1 10½	8 0	750	
Windows do.	6	4 0	1 10½	6 0		
Archway in treasury square portion	1	12 0	1 10½	4 0	90	
Do. semi-circular do.		56 6	Area.	1 10½	106	
Doors in court, &c.	17	4 0	1 6	8 0	861	
Do. do.	1	4 0	1 6	7 6		
Do. in private and property room	2	4 0	1 1½	7 6	104	
Windows in do.	2	4 0	1 1½	4 0		
Doors in jail	5	4 0	1 6	7 6	225	
Ventilators in jail	7	4 0	1 6	2 0	84	
Record-room windows	18	1 9	1 6	5 6	260	
Archwork as per details					535	
Total, Cubic feet						3,015
ARCHWORK.						16,182
Over treasury doors and windows						
Do. arch semi-circular	14	5 0	1 10½	1 1½	148	
Over doors in court, &c.	1	21 6	1 10½	1 6	60	
Do. and windows in private and property room	18	5 0	1 6	1 1½	152	
Over doors and end ventilators in jail	4	5 0				
Over record-room windows	7	5 0	1 1½	1 1½	25	
	18	3 0	1 6	1 1½	150	
Total, Cubic feet						535
CUT STONEWORK.						
Slabs under posts	48	1 0	1 0	0 6	24	
Steps		143 0	1 0	0 6	72	
Slabs under trusses	22	2 0	1 6	0 4	22	
Total, Cubic feet						118
EARTH FILLING IN BASEMENT.						
Court	1	25 0	18 0	1 6	675	
Dais	1	5 10½	6 9	1 0	40	
Private and property rooms		30 9	7 10½	1 6	363	
Clerk's, sheristadar's, &c., rooms	1	68 0	18 0	1 6	1,836	
Treasury and verandah	1	21 0	12 0	1 6	378	
Arms and inspector's room	2	22 10½	8 0	1 6	549	
Jail wards		64 0	15 0	1 6	2,340	
Record room	1	40 0	15 0	1 6		
Verandahs		170 0	8 3	1 6	2,104	
Do.		167 0	5 9	1 6	1,440	
Covered way	1	18 0	13 6	1 6	365	
Total, Cubic feet						10,090
TEAKWOOD WROUGHT AND PUT UP.						
Court, clerk, sheristadar's, &c., room—						
Five trusses to span 18 feet. Tie beams	5	21 0	0 4	0 7	20	
Principal rafters	10	11 9	0 4	0 6	20	
Struts	10	5 9	0 4	0 4	6	
Purlins allowing for halving		196 0	0 4	0 6	33	
Wall purlins do.		206 0	0 3	0 4	17	
Ridge do.		94 0	0 3	0 9	18	
Hip rafters for court	5	17 0	0 3½	0 6	17	
Do. for sheristadar's room	2	15 0	0 3½	0 6		
Common rafters, 18 inches centre to centre	102	12 6	0 3	0 4		
Jack rafters for court	48	9 0	0 3	0 4		
Do. for sheristadar's room	20	Average length. 7 0	0 3	0 4	154	
Record-room—		Average length.				
Three trusses to span 15 feet. Tie beams	3	18 0	0 4	0 6	9	
Principal rafters	6	9 9	0 4	0 5	8	
Struts	6	4 9	0 4	0 4	3	
Purlins (allowing for halving)	2	49 0	0 4	0 5	14	
Wall purlins	2	44 0	0 3	0 3	6	
Ridge	1	53 0	0 3	0 8	9	
Common rafters, 18 inches centre to centre	58	10 9	0 3	0 3	42	
Do. do. at ends	4	12 6	0 3	0 3		
Treasury, inspector and arms' room—						
Joists, 18 inches centre to centre	16	14 0	0 3½	0 8	44	
Do. do.	32	9 6	0 3	0 6	38	

Estimate Form—Detail Measurements—*cont.*

Detail of work.	No.	Measurements in Feet. Length.	Breadth.	Depth.	Area or contents.	Total quantity of each description of work.
TEAKWOOD WROUGHT AND PUT UP—*cont.*						
Jail wards.						
Three trusses to span 15 feet. { Tie beams	3	18 0	0 4	0 6	9	
Principal rafters	6	9 9	0 4	0 5	8	
Struts	6	4 9	0 4	0 4	3	
Purlins allowing for halving	2	75 6	0 4	0 5	21	
Wall purlins do.	2	75 6	0 3	0 3	9	
Ridge	1	75 6	0 3	0 8	13	
Common rafters, 18 inches centre to centre	56	12 6	0 3	0 3	} 76	
Do. do. do.	48	10 9	0 3	0 3		
Covered way.						
One truss to span 15 feet. { Tie beam	1	16 6	0 4	0 6	3	
Principal rafters	2	9 9	0 4	0 5	3	
Struts	2	4 9	0 4	0 4	1	
Purlins	2	20 0	0 4	0 5	6	
Do. over posts	2	20 0	0 4	0 4	4	
Ridge	1	20 0	0 3	0 8	3	
Hip rafters	2	15 0	0 3	0 5	3	
Common rafters	18	12 6	0 3	0 3	} 17	
Jack rafters	8	6 6	0 3	0 3		
Verandah.						
Posts	48	0 6	0 6	7 4	88	
Breastsummers for 9 feet verandah	..	187 0	0 6	0 7½	58	
Do. for 6½ feet do.	..	222 0	0 6	0 6	56	
Hip rafters	4	12 6	0 3	0 6	}	
Do.	1	18 6	0 3	0 6		
Do.	1	15 6	0 3	0 6	} 18	
Ridges	3	12 6	0 3	0 6		
Common rafters for 9 feet verandahs and private and property room 18″ centre to centre.	2	11 0	0 3	0 6	}	
Jack rafters for do. do.	122	13 6	0 3	0 5		
	24	5 6	0 3	0 5		
		Average length.				
Do.	4	7 6	0 3	0 5	} 199	
		Average length.				
Do.	12	8 6	0 3	0 5		
Common rafters for 6½′ verandah 18″ centre to centre	102	10 0	0 3	0 4	} 98	
Jack rafters	28	5 6	0 3	0 4		
Boarding at ends of Jail.						
Verandahs	2	8 0	0 1	3 0	4	
Barge boards for jail and record room gables	6	13 0	0 1	0 9	5	
Do.	6	3 0	0 1	1 0	2	
Do. collar piece	3	9 0	0 3	0 4	2	
Barge boards for finials	3	6 6	0 3	0 3	1	
Do. do.	3	1 0	0 8	0 8	1	
Do. do.	6	4 0	2 0	0 1¼	5	
Front Verandah gables.						
Barge boards	4	7 6	0 1	0 7½	2	
Collar pieces	2	7 0	0 2	0 4	1	
Finials	2	6 0	0 3	0 3	1	
Planks	2	2 6	0 1¼	1 6	1	
Weather boards for Jail.						
Brackets	4	3 6	0 2	0 2½	}	
Struts	4	3 0	0 2	0 2½		
Breastsummers	2	6 0	0 2	0 2½	} 1	
Rafters	8	4 6	0 1½	0 2		
Planks including overlap	12	6 3	0 3¼	0 9	1 4	
Total, Cubic feet	..	..	..	..	..	1,185
VENETIAN AND PANEL DOORS WITH FRAMES COMPLETE.						
Outer doors of court, clerk's, sheristadar's, &c., rooms	11	4 0	..	8 0	352	
Private room	1	4 0	..	7 6	30	
Total, Square feet	..	..	..	..	..	382
PANELLED DOORS WITH FRAMES.						
Inner doors of court, clerk's, sheristadar's, &c., room	6	4 0	..	8 0	192	
Do. do. do.	1	4 0	..	7 6	30	
Total, Square feet	..	..	..	..	..	222

Estimate Form—Detail Measurements—*cont.*

Detail of work.	No.	Measurements in Feet. Length.	Breadth.	Depth.	Area or contents.	Total quantity of each description of work.
WROUGHT IRON GRATED DOORS WITH WOODEN FRAMES.						
For jail wards	5	4 0	..	7 6	150	
Treasury, &c.	8	4 0	..	8 0	256	
Total, Square feet	..	..	..	..	..	406
Strong battened shutters for treasury doors without frames	4	3 6	..	7 6	105	Sq. ft.
Strong battened door with frame for property room	1	4 0	..	7 6	30	Sq. ft.
VENETIAN WINDOWS WITH FRAMES AND IRON BARS.						
For private and property room	2	4 0	..	4 0	32	Sq. ft.
BATTENED WINDOWS WITH FRAMES AND IRON BARS.						
For arms and inspector's room	6	4 0	..	6 0	144	
For record room	18	1 9	..	5 6	173	
Total, Square feet	..	..	..	..	..	317
Teak frames with iron bars for jail ventilators	7	4 0	..	2 0	56	Sq. ft.
WROUGHT IRON WORK IN TRUSSES.						
1″ diar. king rods for 18 feet trusses	5	8 0	= 40 0	× 2·62	= 105	
1″ hex. nut and bolt head for do.	15	..	..	× 1·10	= 17	
3″ diar. ⅛″ thick washers for do.	10	..	..	× 0·32	= 3	
1¾″ × ½″ heel straps for do.	10	2 9	27 6	× 2·50	= 69	
1½″ × ½″ bearing plates for 18 feet trusses	10	0 6¾	= 5 3¾	× 2·50	= 13	
⅝″ hex. nuts for do. do.	20	..	..	× ·267	= 5	
Caps of ⅜″ plate 6″ wide	5	2 0	= 10 0	× 7·51	= 75	
⅞″ diar. kingrod for 15 feet trusses	7	6 7½	= 46 4½	× 2·01	= 93	
⅞″ hex. nut and head for trusses	21	..	..	× 0·73	= 15	
3″ diar. ⅛″ thick washers for trusses	14	..	..	× 0·32	= 4	
1½″ × ⅜″ heel straps for trusses	14	2 3	= 31 6	× 1·87	= 58	
1½ × ⅜ bearing plate for trusses	14	0 6¾	= 7 10½	× 1·87	= 15	
⅝″ hex. nut for trusses	28	..	..	× ·267	= 7	
Caps of ⅜″ plate 6″ wide	7	1 6	= 10 6	× 7·51	= 79	
Total, lb.	..	..	..	..	..	558
TERRACE ROOFING.						
For treasury, inspector's and arms' rooms	..	32 9	..	23 10½	782	Sq. ft.
Squares	..	..	..	..	..	7·82
TILED ROOFING.						
Court room	..	28 0	..	26 0	} 2,808	
Clerk's, sheristadar's, &c., rooms	..	80 0	..	26 0		
Record room	..	49 0	..	23 0	1,127	
Jail	..	74 6	..	24 6	1,825	
Covered way	..	15 3	..	25 0	381	
Verandah 9 feet wide	..	210 0	..	12 0	2,520	
Do. 6½ do.	..	182 0	..	9 0	1,638	
Square feet	..	..	..	..	..	10,299
Total, Squares	..	..	..	..	..	103
FLOORING WITH 8″ SQUARE BRICKS.						
Court	1	25 0	..	18 0	450	
Private room	1	7 10½	..	18 9	} 242	
Property room	1	7 10½	..	12 0		
Clerk's, sheristadar's, &c., room	..	68 0	..	18 0	1,244	
Treasury and verandah	..	22 10½	..	12 0	} 641	
Inspector's and arms' room	2	22 10½	..	8 0		
Covered way	1	18 0	..	15 0	270	
Verandah 9 feet wide	..	175 0	..	9 0	1,575	
Do. 6½ do.	..	167 0	..	6 6	1,086	
Door pieces	18	4 0	..	1 6	108	
Do.	8	4 0	..	1 10½	60	
Do.	2	4 0	..	1 1½	9	
Square feet	..	..	..	..	..	5,685
Total, Squares	..	..	..	..	..	56·85

Estimate Form—Detail Measurements—*cont.*

Detail of work.	No.	Measurements in Feet. Length.	Breadth.	Depth.	Area or contents.	Total quantity of each description of work.
FLOORING RECORD ROOM AND JAIL WITH ASPHALTE $\frac{3}{4}$" THICK OVER A BED OF CONCRETE.						
Record room	1	40 0	..	15 0	} 1,560	
Jail	1	64 0	..	15 0		
Door pieces	5	4 0	..	1 6	30	
Square feet ..	..	..	..	..	..	1,590
Total, Squares ..	..	..	..	..	..	15·90
PLASTERING INTERIOR (TWO COATS).						
Court	..	86 0	..	13 3	1,140	
Private room	..	53 3	..	10 6	559	
Property room	..	19 $10\frac{1}{2}$	..	8 0	159	
Do.	2	7 $10\frac{1}{2}$	..	10 6	165	
Clerk's, sheristadar's, &c., room	1	4 $1\frac{1}{2}$	..	13 3	55	
Gables	..	280 0	..	13 3	3,710	
Record room	9	18 0	..	3 0	486	
Gables	..	110 0	..	12 0	1,320	
Treasury	2	15 0	..	2 6	75	
Do. verandah	..	54 0	..	14 0	} 3,073	
Inspector's and arms' room	..	42 0	..	14 0		
Jail wards	2	61 9	..	14 0		
Do. gables	..	278 0	..	12 0	3,336	
Door jambs and soffits	10	15 0	..	2 6	375	
Do. do.	17	20 0	..	1 6	510	
Do. do.	1	19 0	..	1 6	29	
Do. do.	8	20 0	..	1 $10\frac{1}{2}$	300	
Do. do.	2	19 0	..	1 $1\frac{1}{2}$	43	
Arch do.	5	19 0	..	1 6	143	
Window do.	..	27 0	..	1 $10\frac{1}{2}$	51	
Do. do.	6	20 0	..	1 $10\frac{1}{2}$	225	
Do. do.	2	16 0	..	1 $1\frac{1}{2}$	36	
Ventilator jambs	18	14 6	..	1 6	} 488	
Do.	2	12 0	..	1 6		
Deductions—	5	8 0	..	1 6		
Doorways						16,278
Do.	32	4 0	..	8 0	1,024	
Archway, square portion	9	4 0	..	7 6	270	
Do. semi-circular portion	1	12 0	..	4 0	48	
Windows	1	56 6	Area.	..	57	
Do.	2	4 0	..	4 0	32	
Do.	6	4 0	..	6 0	144	
Ventilators	18	1 9	..	5 6	174	
	7	4 0	..	2 0	56	
Square feet ..	..	..	..	..	..	1,805
Total, Squares ..	..	..	..	..	..	14,473
						144·73
POINTING EXTERIOR.						
Court	..	50 9	..	13 3	} 3,028	
Clerk's, sheristadar's, &c., rooms	..	177 9	..	13 3		
Property and private room	..	62 3	..	7 6	467	
Do. half gables	2	9 0	..	3 0	54	
Record room	..	101 0	..	12 0	1,212	
Do. gable	1	18 0	..	3 0	54	
Treasury and inspector's, &c., rooms	..	124 3	..	21 6	2,671	
Do. inside parapet	..	109 3	..	5 0	546	
Jail wards	..	179 0	..	12 0	2,148	
Do. gables	2	18 0	..	3 0	108	
Basement all round	..	609 0	..	2 0	1,218	
Deduct—						11,506
Doorways	16	4 0	..	8 0	512	
Do.	7	4 0	..	7 6	210	
Archway, square portion	1	12 0	..	4 0	48	
Do. semi-circular portion	1	56 6	Area.	..	57	
Windows	2	4 0	..	4 0	32	
Do.	6	4 0	..	6 0	144	
Do.	18	1 9	..	5 6	174	
Ventilators	7	4 0	..	2 0	56	
End wall, cashier's room	1	21 0	..	16 0	336	
						1,569
Square feet ..	..	..	..	..	..	9,937
Total, Squares ..	..	..	..	..	..	99·37
					Per foot lb.	lb.
Lead sheeting for roof valleys	..	184 0	1 6	× 276	× 5	1,380
Mouldings over windows for inspector's and arms' room.	6	6 0	..	..	36	L. ft.

Estimate Form—Detail Measurements—*cont.*

Detail of work.	No.	Measurements in Feet. Length.	Breadth.	Depth.	Area or contents.	Total quantity of each description of work.
Coping for treasury	..	..	..	125	L. ft.	
Railing for dais	..	..	..	23	,,	
Finials over court	..	..	2 in number.			
PAINTING WITH THREE COATS OF CARSON'S PAINT.						
Venetian and panel doors	3	382 0	..	..	1,146	
Panelled doors	2	222 0	..	..	444	
Wrought iron grated doors	2	406 0	..	..	812	
Batten shutters	2	105 0	..	..	210	
Do. do.	2	30 0	..	..	60	
Do. windows	2	317 0	..	..	634	
Ventilators	2	56 0	..	..	112	
Roof timbers including weather boards, &c. ..	..	..	..	..	11,972	
Square feet ..	..	..	..	..	..	15,390
Total, Squares ..	..	..	..	..	..	154
Add extra labor in finishing barge boards and finials.	..	..	5 in number.			
Punkah 10 feet long	..	..	1 ,,			

Estimate Form—Abstract.

Quantity.	Description of work.	Rate.	Per	Amount.	Total.
		Rs.		Rs.	Rs.
20,632 C. feet ..	Excavation for foundation	..	1,000 C. feet.		
7,019 ,, ..	Concrete in foundation	..	100 C. feet.		
5,843 ,, ..	Brickwork in foundations	..	,,		
3,422 ,, ..	Do. in basement	..	,,		
16,182 ,, ..	Do. in superstructure	..	,,		
535 ,, ..	Archwork	..	,,		
118 ,, ..	Cut stonework	..	C. feet.		
10,090 ,, ..	Filling in basement	..	1,000 C. feet.		
1,185 ,, ..	Teakwood wrought and put up	..	C. feet.		
382 Sq. feet.	Venetian and panel doors with frames	..	Square feet.		
222 ,, ..	Panelled doors with frames	..	,,		
406 ,, ..	Wrought iron grated doors with teak frames ..	..	,,		
105 ,, ..	Strong battened shutters for treasury doors without frames	..	,,		
30 ,, ..	Strong battened door with frame for property room ..	..	,,		
32 ,, ..	Venetian windows with frames and iron bars ..	..	,,		
317 ,, ..	Battened do. do. ..	..	,,		
56 ,, ..	Teak frames with iron bars for jail ventilators ..	..	,,		
558 lb. ..	Wrought iron work in trusses	..	,,		
7·82 Squares.	Terrace roofing	..	lb.		
103 ,, ..	Tiled roofing with flat and pan tiles including teak reepers	..	Square.		
56·85 ,, ..	Flooring with 8-inch square pavement tiles	..	,,		
15·90 ,, ..	Flooring record room and jail with asphalte $\frac{3}{4}$ inch thick over a bed of concrete	..	,,		
144·73 ,, ..	Plastering interior (two coats)	..	,,		
99·37 ,, ..	Pointing exterior	..	,,		
1,380 lb ..	Lead sheeting for roof valleys	..	,,		
36 L. feet.	Mouldings over windows	..	lb.		
125 ,, ..	Coping for treasury parapet	..	L. feet.		
23 ,, ..	Hand railing for dais	..	,,		
2 in No.	Finials over court	..	,,		
154 Squares.	Painting with three coats of Carson's paint	..	Each.		
5 in No. ..	Add extra labor in finishing barge boards and finials ..	..	Square.		
1 ,, ..	Punkah 10 feet long	..	Each.		
..	Petty supervision	..	,,		
..	Contingencies	..	..		

MADRAS,
25th April 1887.

(Signed) J. W. BRASSINGTON,
Offg. Consulting Architect to Government.

TAHSILDAR'S CUTCHERRY.

Descriptive Specification.

Foundations.—A depth of 4 feet 6 inches is provided in the quantities, but this should be settled locally in accordance with the nature of the soil.

Walling.—The walls should be carried up in English bond, walls of treasury 2½ bricks thick, court, offices, record room and outer walls of jail 2 bricks thick, jail partitions and verandah rooms near court 1½ bricks. Verandah retaining walls 1 brick thick, except under posts which will be half a brick thicker.

Stonework.—Stone slabs 12″ × 12″ × 6″ with mortice holes 2 inches square and 2 inches deep cut into them into which the verandah posts will be tennoned.

Slabs will also be placed at the bearings of trusses. The steps may also be of stone, if procurable without great expense.

Woodwork.—The doors, windows, weather boards, verandah posts and trusses should be of well-seasoned teakwood, the rafters and other minor roof timbers may be of approved country wood.

Roofing.—The roof of the treasury, arms, and inspector's room will be of pucka terrace. The rest of the building will be covered with flat and pan tiles; if the quality of these are good the usual unsightly "chunam bands" might be dispensed with; all valleys should be protected with sheet lead.

Flooring.—The floor may be of square bricks or stone slabs if the latter are easily procurable. Jail wards and record room floors to be asphalted.

Interior and exterior finishing.—The interior walls will be fine plastered with shell lime or plastered and washed. Where good bricks are obtainable the exterior should be pointed.

Where the soil is damp the space below the flooring should be filled with river sand to a depth of 1 foot at least and the interior walls plastered with Portland cement ½ an inch thick to a height of 3 feet all over above floor level. The exterior plinth should also be plastered with cement.

Finials.—The finials may be of copper, iron or wood.

The different kinds of work to be done will be executed in conformity with the standard specification of the Public Works Department.

CHEPÂK,
25th April 1887.

(Signed) J. W. BRASSINGTON,
Offg. Consulting Architect to Government.

3RD JUNE 1887, No. 1495 W., PUBLIC WORKS.

GOVERNMENT OF MADRAS.

PUBLIC WORKS DEPARTMENT.

Buildings and Roads.
Civil Works.

READ—the following papers:—

From J. W. BRASSINGTON, Esq., Officiating Consulting Architect to the Government of Madras, to the Chief Engineer, Public Works Department, dated Chepâk, 25th April 1887, No. 95.

In continuation of my letter, No. 1530, dated the 12th March last, I have the honor to submit a revised plan and schedule of quantities for tahsildars' cutcherries.

2. The plan and quantities for deputy tahsildars' cutcherries will follow.

No. 72 D.

Forwarded for the approval of Government in the Revenue Department.

2. The design has already been approved in Committee by the Honorable Members and Secretaries to Government.

6th May 1887.

(Signed) J. O. HASTED, Col., R.E.,
Chief Engineer, P.W.D.

G.O., dated 23rd May 1887, No. 2981, Revenue.

Read—endorsement of Public Works Department, dated 6th May 1887, No. 72 D., forwarding, for approval, revised standard design for taluk offices.

Order—dated 23rd May 1887, No. 2981, Revenue.

Approved.

(True Extract.)

(Signed) J. F. PRICE,
Ag. Secy. to Govt.

ORDER—dated 3rd June 1887, No. 1495 W., Public Works.

The revised type design, with schedule of quantities and descriptive specification for a first-class taluk office, will be circulated to officers of the Public Works Department, for information and guidance, in supersession of all previous standard designs for similar buildings.

(True Extract.)

W. B. Baddeley
Captain, R.E.,
Under Secy. to Govt., P.W.D.

To Superintending Engineers.
„ the Consulting Architect to Government.
„ the Revenue Department.

Exd. P. L. Pereira.
Spare Copies

18 & 19 Spare copies & type to designs for taluk offices

BUILDINGS AND ROADS.
CIVIL WORKS.

Govt. of {1887} Madras.

PUBLIC WORKS.

Dated June, 3rd.

Recd. *Encl.*

G.O., 3rd June 1887, No. 1495 W.

JUNE.

Taluk Office

A revised type design for a first-class —, circulated to officers of the department.

GOVERNMENT OF MADRAS.

PUBLIC WORKS DEPARTMENT.

Buildings and Roads.
Civil Works.

Read—the following papers:—

Proceedings of the Board of Revenue, dated 30th July 1885, Mis. No. 6929.

Read—the following letter from C. S. CROLE, Esq., Collector of Madura, to the Secretary to the Board of Revenue, dated Madura, 25th July 1885, No. 437 :—

With reference to the Proceedings of the Board of Revenue, dated 10th March 1884, No. 839, communicating G.O., dated 21st February 1884, No. 483 W., Public Works Department, I have the honor to submit, for the sanction of Government, estimate, &c., for constructing a taluk cutcherry with outhouses, &c., at Tirumangalam, received from the Superintending Engineer, VI Circle, Trichinopoly.

Resolution—dated 30th July 1885, Mis. No. 6929.

Submitted for the sanction of Government.

(A true Copy and Extract.)

(Signed) E. GIBSON,
Secretary.

Mis. No. 4222, Revenue.

Approved and transferred to the Public Works Department.

Ootacamund,
12th August 1885.

(Signed) W. WILSON,
Ag. Secretary to Government.

Order—dated 31st August 1885, No. 2013 W., Public Works.

The estimate, amounting to Rs. 25,110, for constructing a tahsildar's office with outhouses at Tirumangalam, in the Madura district, is sanctioned for execution when funds are available.

2. This sanction has been registered as Provincial No. 114 W. of 1885-86, and classified as Civil Buildings, Original Works.

(True Extract.)

(Signed) J. SHAW-STEWART, Colonel, R.E.,
Secretary to Govt., P.W.D.

To the Superintending Engineer, VI Circle, with five enclosures.
„ Examiner, Public Works Accounts, with duplicate abstract estimate.
„ Revenue Department.

Exd. J. Henricus.
Spare Copies

BUILDINGS AND ROADS.
CIVIL WORKS.

Govt. of {1885} Madras.

PUBLIC WORKS.

Dated August, 31*st*.

Recd.

Encl.

G.O., 31st Aug. 1885, No. 2013 W.

AUGUST.

Tahsildar's Office at Tirumangalam, Madura District

Estimate for —, sanctioned.

GOVERNMENT OF MADRAS.

PUBLIC WORKS DEPARTMENT.

Buildings and Roads.
Civil Works.

READ—the following papers:—

Read—the following Proceedings of the Board of Revenue (Land Revenue), dated 29th February 1888, Mis. No. 1386.

H. S. THOMAS, ESQ., F.L.S., F.Z.S.

Read—the following letter from E. TURNER, Esq., Collector of Madura, to the Acting Secretary to the Commissioners of Land Revenue, dated Madura, 10th February 1888, No. 62:—

In enclosing herein marginally noted papers for constructing a Sub-Magistrate's cutcherry with sub-jail and out-houses at Sivaganga, I have the honor to request you to be so good as to obtain the sanction of the Government for carrying out the work in question.

1. Estimate for the construction of a Sub-Magistrate's cutcherry for Rs. 12,570.
2. Plan.
3. Duplicate abstract.

2. I think that the construction of a new building is highly desirable as the present building is in bad order and unsuitable for the purpose (*vide* paragraph 2 of the Superintending Engineer's report herein enclosed).

3. I further beg to state that the Government have in their Proceedings, dated 27th September 1887, No. 1818 L. (Mis.), approved the Taluk Board's proposal regarding the sale of the piece of land for the construction of the said cutcherry, and ordered that the sale should not take place before the estimate for the work is sanctioned.

Resolution—dated 29th February 1888, Mis. No. 1386.

The plan and estimate for Rs. 12,570, for constructing an office for the Sub-Magistrate at Sivaganga, are submitted for the sanction of Government and for the provision of funds in the budget of the Public Works Department.

2. The necessity for the building is explained by the Collector in paragraph 2 of his letter.

(True Extract.)

(Signed) R. S. BENSON,
Ag. Secretary.

To the Secretary to Government, Revenue Department, with letter and enclosures in original to be returned.

Copy to the Collector of Madura.

No. 1993, Revenue.

The estimate is approved and transferred to the Public Works Department.

2. The Board will report how the value of the site for the proposed building has been fixed and whether it was acquired by the Local Fund Board by purchase.

OOTACAMUND,
4th April 1888.

(Signed) J. F. PRICE,
Secretary to Government.

To the Public Works Department, with four enclosures to be returned.
" Commissioners of Land Revenue.

ORDER—dated 27th April 1888, No. 1243 W., Public Works.

The estimate, amounting to Rs. 12,570, for constructing a Sub-Magistrate's office with sub-jail and out-houses at Sivaganga in the Madura district, is sanctioned for execution when funds are available.

2. This sanction has been registered as Provincial No. 7 W. of 1888-89, and classified as Civil Buildings, Original Works.

(True Extract.)

(Signed) J. O. HASTED, Colonel, R.E.,
Secretary to Govt., P.W.D.

To the Superintending Engineer, VI Circle, with nine enclosures.
" Examiner, Public Works Accounts, with the duplicate general abstract estimate.
" Revenue Department.

Exd. L. Passaigne.
Spare Copies

BUILDINGS AND ROADS.
CIVIL WORKS.

Govt. of {1888} Madras.

PUBLIC WORKS.

Dated April, 27th.

Recd. *Encl.*

G.O., 27th Apr. 1888, No. 1243 W.

APRIL.

Sub-Magistrate's Office at Sivaganga

Estimate for constructing a — with sub-jail and out-houses, Madura district, sanctioned.

GOVERNMENT OF MADRAS.

PUBLIC WORKS DEPARTMENT.

Buildings and Roads.
Civil Works.

READ—the following paper :—

Proceedings of the Board of Revenue (Land Revenue), dated 25th April 1888, Mis. No. 2646.

HON'BLE W. S. WHITESIDE.

Read—the following letter from Colonel H. SMALLEY, R.E., Superintending Engineer, III Circle, to the Collector of Bellary, dated Bellary, 9th April 1888, No. 60 :—

I have the honor to forward, for your countersignature and transmission to Government for sanction, an estimate, amounting to Rs. 24,862, for constructing a first-class taluk office at Kúdligi on the standard plan approved in G.O. No. 1495 W., dated 3rd June 1887.

2. An estimate, amounting to Rs. 31,520, was approved for this work in G.O. No. 401, dated 31st May 1886, in the Revenue Department, but the estimate was returned in the Public Works Department for revision in accordance with the standard design above referred to.

Submitted to Government for sanction through the Board of Revenue (Land Revenue).

17th April 1888. (Signed) H. ST. A. GOODRICH,
Collector.

Resolution—dated 25th April 1888, Mis. No. 2646.

The site-plan and the revised estimate for constructing a first-class taluk cutcherry at Kúdligi, at a cost of Rs. 24,862, are submitted for the sanction of Government and the provision of funds in the budget of the Public Works Department.

(True Extract.)

(Signed) H. A. SIM,
Ag. Secretary.

No. 2866, Revenue.

Approved and transferred to the Public Works Department.

OOTACAMUND,
15th May 1888. (Signed) J. F. PRICE,
Secretary to Government.

ORDER—dated 7th June 1888, No. 1681 W., Public Works.

The estimate for constructing a first-class taluk office at Kúdligi, in the Bellary district, reduced to Rs. 23,871 by omission of the cost (Rs. 991) of a ryot's shed, is sanctioned.

2. It is not intended that ryot's sheds should be built in connection with taluk cutcherries on the revised standard plan.

3. The Superintending Engineer will report what sum can be spent on the work during the current official year.

4. This sanction has been registered as Provincial No. 34 W. of 1888-89, and classified as Civil Buildings, Original Works.

(True Extract.)

(Signed) J. O. HASTED, Colonel, R.E.,
Secretary to Govt., P.W.D.

To the Superintending Engineer, III Circle, with six enclosures.
" Examiner, Public Works Accounts, with duplicate abstract estimate.
" Revenue Department.

Exd. F. R. Bantleman.
Spare Copies

BUILDINGS AND ROADS.
CIVIL WORKS.

Govt. of {1888} Madras.

PUBLIC WORKS.

Dated June, 7th.

Recd. *Encl.*

G.O., 7th June 1888, No. 1681 W.

JUNE.

Taluk office at Kudligi

Estimate for constructing a first-class —, in the Bellary district, sanctioned with remarks.

GOVERNMENT OF MADRAS.

PUBLIC WORKS DEPARTMENT.

Buildings and Roads.
Civil Works.

READ—the following papers :—

Proceedings of the Board of Revenue (Land Revenue), dated 14th May 1888, Mis. No. 3022.

HON'BLE W. S. WHITESIDE.

Read—the following letter from S. H. WYNNE, Esq., Acting Collector of South Canara, to the Secretary to the Commissioners of Land Revenue, dated Mangalore, 30th April 1888, No. 1573.

I have the honor to forward, for transmission to Government, plan and estimate for the new taluk cutcherry at Coondapoor, together with a copy of the Superintending Engineer's letter.*

*Dated 10th April 1888, No. 122 M.

2. Sky-lights will be necessary as the monsoon tatties will shut out most of the light at doors and windows, but as there is provision for sundries and contingencies, the cost can be met from this, and it seems unnecessary to return the estimates for this purpose. A public latrine is hardly necessary, as there is a Local Fund latrine close by. If it is omitted, the cook-room can be moved to its site behind the jail, which is a better position than that now assigned.

Resolution—dated 14th May 1888, Mis. No. 3022.

The fresh plans and estimates for Rs. 35,010 for a new taluk cutcherry at Coondapoor are submitted for the sanction of Government with reference to G.O., dated 29th August 1887, No. 5142.

2. The Collector states that the public latrine, provided for in the estimate, is not required, as there is a Local Fund latrine close by, and that the cook-room may be built at the place intended for this latrine. If the former proposal is approved, there will be a saving of Rs. 1,240 on the estimate.

(A true Copy and Extract.)

(Signed) H. A. SIM,
Ag. Secretary.

No. 3742, Revenue.

Transferred to the Public Works Department, with the remark that under G.Os., dated 7th June 1888, No. 1681 W., and 20th September 1882, No. 2440 W.,† the provision of a ryots' shed and sub-jail latrine is unnecessary, and that the alterations suggested by the Collector are approved. It is observed that the approximate cost at Madras rates of a cutcherry on the new type-design is only Rs. 21,000. It is not understood why the present estimate comes to Rs. 35,010.

†*Vide* G.O., Judicial, No. 1430, dated 29th September 1882.

OOTACAMUND,
27th June 1888.

(Signed) J. F. PRICE,
Secretary to Government.

Note by the Chief Engineer, Public Works Department.

Submitted for the sanction of Government.

The provision of a ryots' shed and sub-jail latrine being unnecessary, these items have been struck out of the estimate, reducing it from Rs. 35,010 to Rs. 32,950.

2. With reference to the remarks in the Revenue Department regarding the high cost of the building, it is observed that the approximate cost, Rs. 21,000, of a taluk office on the new type-design at Madras rates represents the cost of the main building only, whereas the present estimate provides for out-houses and subsidiary works, such as dismantling old buildings, levelling site, and constructing drains and sheds for storage of materials, &c. The rates on the West Coast, moreover, are about one-third more than those at Madras.

3. The Superintending Engineer should consider whether the concrete foundation offsets might not be increased to one foot from nine inches, the soil not being good.

4. The suggestions in para. 2 of the Collector's letter should be attended to in carrying out the work.

(Signed) J. O. HASTED, Colonel, R.E.,
Chief Engineer, Public Works Department.

5th August 1888.

Order—dated 14th August 1888, No. 2469 W., Public Works.

The estimate, amounting to Rs. 32,950, as reduced by the Chief Engineer, Public Works Department, for constructing a taluk office with out-houses at Coondapoor in the South Canara District, is sanctioned.

2. A sum of Rs. 6,000 has been provided for the work in the current year's budget.

3. Attention is drawn to the Note by the Chief Engineer, Public Works Department, above recorded.

4. The sanction accorded in para. 1 of these Proceedings has been registered as Provincial No. 65 W. of 1888-89, and classified as Civil Buildings, Original Works.

(True Extract.)

(Signed) J. O. HASTED, Colonel, R.E.,
Secretary to Govt., P.W.D.

To the Superintending Engineer, IV Circle, with eleven enclosures.
„ Examiner, Public Works Accounts, with the general abstract estimate.
„ Revenue Department.

Exd. F. R. Bantleman.
Spare Copies

BUILDINGS AND ROADS.
CIVIL WORKS.

Govt. of {1888} Madras.

PUBLIC WORKS.

Dated August, 14th.

Recd. *Encl.*

G.O., 14th Aug. 1888, No. 2469 W.

AUGUST.

Taluk office at Coondapoor

Estimate, amounting to Rs. 32,950, as reduced by the Chief Engineer, Public Works Department, for constructing a — with out-houses, South Canara District, sanctioned.

22ND JUNE 1889, No. 1638 W., PUBLIC WORKS.

GOVERNMENT OF MADRAS.

PUBLIC WORKS DEPARTMENT.

General.
Account.

READ—the following papers:—

From the Superintending Engineer,			I Circle,	dated	12th May	1889,	No. 83 G.L.
,,	,,	,,	II	,,	23rd ,,	,,	(one statement).
,,	,,	,,	III	,,	7th ,,	,,	(five statements).
,,	,,	,,	IV	,,	10th ,,	,,	No. 201.
,,	,,	,,	IV	,,	13th ,,	,,	,, 212 E.W.
,,	,,	,,	IV	,,	13th June	,,	(telegram).
,,	,,	,,	V	,,	1st ,,	,,	No. 1437.
,,	,,	,,	VI	,,	10th May	,,	,, 279 T.J.
,,	,,	,,	VI	,,	7th June	,,	,, 179 T.C.
,,	Consulting Architect to Government,			,,	21st May	,,	,, 246.

ENCLOSURES.

A.—Statement showing the amounts applied for and those granted under Provincial Civil Works.

Divisions.	AMOUNTS APPLIED FOR							AMOUNTS ALLOTTED.						
	Minor Works.			Repairs.			Tools and Plant.	Minor Works.			Repairs.			Tools and Plant.
	Civil Buildings.	Communications.	Miscellaneous Public Improvements.	Civil Buildings.	Communications.	Miscellaneous Public Improvements.		Civil Buildings.	Communications.	Miscellaneous Public Improvements.	Civil Buildings.	Communications.	Miscellaneous Public Improvements.	
	RS.	RS.	RS.	RS.	RS.	RS.	RS.	RS.	RS.	RS.	RS.	RS.	RS.	RS.
Ganjam	1,000	..	..	4,000	..	..	200	..	..	..	4,000	..	..	200
Rushikulya	..	..	..	..	..	..	..	..	..	..	..	..	..	..
Vizagapatam	500	..	..	3,000	10,000	..	1,000	..	..	..	..	..	..	..
Godávari Eastern	..	..	..	3,000	12,000	500	..	..	..	..	3,000	10,000	..	1,000
Do. Central	300	..	..	300	..	..	..	..	..	..	3,000	12,000	500	..
Do. Western	100	..	..	150	..	..	..	..	..	..	300	..	..	..
Kistna Eastern	..	..	..	1,500	..	500	500	..	..	..	150	..	..	..
Do. Western	..	..	..	500	..	..	..	..	..	..	1,500	..	500	500
Nellore	..	..	..	3,000	..	..	2,000	..	..	..	500	..	..	..
Buckingham Canal	..	..	..	..	..	..	..	..	..	..	3,000	..	..	2,000
Bellary	..	..	..	2,000	3,000	..	1,000	..	..	..	..	..	..	..
Cuddapah	..	..	..	1,500	..	..	2,500	..	..	..	2,000	3,000	..	1,000
Kurnool	..	..	..	3,000	..	..	1,000	..	..	..	1,500	..	..	2,500
Nílgiri	4,000	3,000	1,000	17,500	57,311	1,400	19,250	..	..	..	3,000	..	..	1,000
Coimbatore	1,500	..	..	7,000	..	..	1,000	..	..	..	17,500	55,000	1,400	18,000
West Coast	2,000	..	..	8,000	26,000	..	1,500	..	..	..	7,000	..	..	1,000
North Arcot	..	..	..	1,200	..	..	500	..	..	..	8,000	26,000	..	1,500
South Arcot	2,460	..	..	2,850	..	..	2,197	(a) 2,460	..	..	1,200	..	..	500
Chingleput	..	..	..	7,500	..	..	300	..	..	..	2,500	..	..	2,159
Presidency	..	..	..	60,000	13,500	2,000	1,500	..	..	..	7,500	..	..	300
Public Works Workshops	1,900	..	..	1,500	..	..	2,500	(a) 1,900	..	..	55,000	13,500	2,000	1,500
Do. Stores	..	..	..	450	..	..	7,000	..	..	..	1,500	..	..	2,500
Tanjore	..	..	..	3,000	..	..	600	..	..	..	450	..	..	(c) 7,000
Negapatam	..	..	..	1,000	..	..	100	..	..	..	3,000	..	..	600
Trichinopoly	..	..	..	1,000	..	..	300	..	..	..	1,000	..	..	100
Madura	700	..	..	3,000	..	..	400	(a) 700	..	..	1,000	..	..	300
Tinnevelly	..	..	..	1,660	..	..	200	..	..	..	3,000	..	..	400
Ramnad	..	..	..	800	..	..	100	..	..	..	1,500	..	..	200
Architect	6,000	..	500	25,000	..	12,000	400	(a) 1,000	..	(a) 500	800	..	..	100
Reserve with the Government for Archæological Works ..	..	..	..	..	..	..	..	..	..	..	22,000	..	12,000	400
Total ..	20,460	3,000	1,500	1,63,410	1,21,811	16,400	46,047	6,060	..	500	(b) 7,500	..	..	..
											1,62,400	1,19,500	16,400	44,759

(a) In addition to the budget grants.
(b) Includes Rs. 200 allotted in G.O., No. 1227 W., dated 9th May 1889.
(c) Indian supplies for 1889-90.

B.—Statement of requirements on account of Provincial incomplete works of 1888-89 and of new works sanctioned but not commenced.

Division.	Item No	Name of work.	Amount of estimate.	Number and date of sanction.	Past expenditure.	Balance of estimate.	AMOUNT APPLIED FOR FOR 1889-90		AMOUNT ALLOTTED		Item No.	Remarks.
							For incomplete works.	For new works.	For incomplete works.	For new works.		
1	2	3	4	5	6	7	8	9	10	11	12	13
		Minor Works.	RS.		RS.	RS.	RS.	RS.	RS.	RS.		
Vizagapatam ..	1	Alterations to quarters of the medical subordinate attached to the Lunatic Asylum, Waltair.	1,270	G.O., No. 1796 W., dated 6th July 1887.	..	1,270	..	1,270	..	..	1	No funds are available.
	2	Two iron safes for Koraput treasury.	1,100	Superintending Engineer's Register No. 207 of 1887-88.	..	1,100	..	1,100	..	..	2	
	3	Constructing a dead-house at Chódavaram.	304	Superintending Engineer's Register No. 193 of 1888-89.	..	304	..	304	..	..	3	
	4	Constructing a dead-house at Yellamanchili.	304	Superintending Engineer's Register No. 194 of 1888-89.	..	304	..	304	..	..	4	
	5	Two record-racks for the District Judge's Court at Vizagapatam.	500	Superintending Engineer's Register No. 208 of 1888-89.	..	500	..	500	..	..	5	
	6	Constructing a rest-house for prisoners and guard at Sunki.	780	Superintending Engineer's Register No. 209 of 1888-89.	..	780	..	780	..	..	6	
Godávari Eastern	7	Reroofing northern godown of Custom-house, Cocanada, with corrugated iron.	1,490	Superintending Engineer's Register No. 84 of 1888-89.	490	1,000	1,000	..	1,000	..	7	From the reserve.
	8	Additional accommodation (a treasury room, ryots' shed and record-racks) to the Sub-Magistrate's office at Tuni.	1,180	Superintending Engineer's Register No. 220 of 1888-89.	..	1,180	..	1,180	..	..	8	No funds are available.
Godávari Western.	9	Constructing ryots' shed at Sub-Magistrate's office at Pentapad.	1,180	G.O., No. 2866 W., dated 15th November 1884.	..	1,180	..	1,180	..	..	9	
Kistna Western.	10	Extensions and improvements to the taluk office at Répalle.	1,845	G.O., No. 3235 W., dated 12th October 1888.	792	1,053	1,053	..	1,053	..	10	From the reserve.
	11	Constructing a gallows at the District Jail, Guntúr.	340	G.O., No. 3959 W., dated 18th December 1888.	..	340	..	340	..	..	11	No funds are available.
Kistna Eastern ..	12	Alterations to the Collector's office at Masulipatam.	1,163	Superintending Engineer's Register No. 59 of 1888-89.	68	1,095	1,095	..	1,095	..	12	From the reserve.
Bellary ..	13	Making drains and providing wire-fencing around the compound of the Collector's office at Anantapur.	1,689	Sanctioned by Superintending Engineer.	361	1,328	1,328	..	1,328	..	13	

B.—Statement of requirements on account of Provincial incomplete works of 1888-89, &c.—*cont.*

Division.	Item No.	Name of work.	Amount of estimate.	Number and date of sanction.	Past expenditure.	Balance of estimate.	Amount applied for for 1889-90		Amount allotted		Item No.	Remarks.
							For incomplete works.	For new works.	For incomplete works.	For new works.		
1	2	3	4	5	6	7	8	9	10	11	12	13
		Minor Works—cont.										
Bellary—*cont.* ..	14	Converting the terraced roof of the taluk office at Penukonda into a tiled roof.	Rs. 886	G.O., No. 3149 W., dated 8th October 1888.	Rs. 347	Rs. 539	Rs. 539	Rs. ..	Rs. 539	Rs. ..	14	From the reserve.
	15	Constructing a store-room to the District Jail at Bellary.	2,362	Superintending Engineer's Register No. 55 of 1888-89.	1,291	1,071	1,071	..	1,071	..	15	
Cuddapah ..	16	Constructing a latrine for the Head Assistant Collector's office at Hospet.	521	Superintending Engineer's Register No. 46 of 1888-89.	..	521	..	521	..	..	16	
	17	Constructing a sub-divisional store-shed at Madanapalle.	1,507	Superintending Engineer's Register No. 58 of 1888-89.	..	1,507	..	1,507	..	..	17	
Nilgiri ..	18	Improving the outhouses of Cinchona Villa, Ootacamund.	740	G.O., No. 2728 W., dated 3rd September 1888.	..	740	..	740	..	..	18	
	19	Gravelling the roadway to and around the Roman Catholic church at Wellington.	450	Register No. 74 of 1888-89.	..	450	..	450	..	..	19	
	20	Extending and improving the outhouses of St. Stephen's church at Ootacamund.	535	G.O., No. 2884 W., dated 14th September 1888.	..	535	..	535	..	..	20	
	21	Reflooring St. Thomas' church at Ootacamund.	770	G.O., No. 2991 W., dated 24th September 1888.	..	770	..	770	..	..	21	
	22	Constructing drains to carry off rain water from St. George's church at Wellington.	465	Register No. 103 of 1888-89.	..	465	..	465	..	..	22	
	23	Providing record-shelves for Waterloo House record-room, Adjutant-General's office, Ootacamund.	2,395	Register No. 2 of 1889-90.	..	2,395	..	2,395	..	..	23	No funds are available.
West Coast ..	24	Providing two iron record-racks with two wooden ladders for the District Court at Mangalore.	595	Register No. 61 of 1888-89.	..	595	..	595	..	..	24	
	25	Providing wooden ceiling to the District Munsif's Court at Udipi.	1,266	Register No. 57 of 1888-89.	..	1,266	..	1,266	..	..	25	
	26	Constructing warders' huts at the Mangalore District Jail.	564	Register No. 60 of 1888-89.	..	564	..	564	..	..	26	
	27	Constructing a latrine for the Government College, Calicut.	1,305	Register No. 55 of 1888-89.	..	1,305	..	1,305	..	..	27	
	28	Providing iron record-racks for the District Court, North Malabar.	504	Register No. 65 of 1888-89.	..	504	..	504	..	..	28	
	29	Supplying wrought iron strong rooms for taluk office at Udipi.	769	Register No. 51 of 1888-89.	..	769	..	769	..	..	29	
West Coast ..	30	Supplying wrought iron strong rooms for taluk office at Coondapoor.	769	Register No. 52 of 1888-89.	..	769	..	769	..	..	30	
	31	Supplying wrought iron strong rooms for taluk office at Mangalore.	769	Register No. 53 of 1888-89.	..	769	..	769	..	..	31	
	32	Supplying wrought iron strong rooms for taluk office at Uppinangádi.	769	Register No. 54 of 1888-89.	..	769	..	769	..	..	32	
Coimbatore ..	33	Providing two iron double record-racks and one iron ladder to the District Court-house at Coimbatore.	421	Register No. 49 of 1888-89.	..	421	..	421	..	..	33	No funds are available.
	34	Constructing two new verandahs to the District Court-house at Salem.	1,720	Register No. 51 of 1888-89.	..	1,720	..	1,720	..	..	34	
	35	Alterations and additions to the Huzur treasury at Salem.	1,210	Register No. 55 of 1888-89.	..	1,210	..	1,210	..	..	35	
Presidency ..	36	Providing lightning conductors to the Government Central Museum, Madras.	2,375	Register No. 65 of 1888-89.	20	2,355	2,355	..	2,355	..	36	
	37	Providing two spiral staircases from 1st to ground floor of the Government Secretariat, Fort St. George.	760	Register No. 7 of 1889-90.	..	760	..	760	..	760	37	
	38	Improvements to the chancel at St. Andrew's church, Bangalore.	1,440	G.O., No. 1305 W., dated 3rd May 1888.	507	933	933	..	933	..	38	From the reserve.
	39	Constructing a portico and sun-shade to the quarters of the Superintendent, Government Central Museum, Madras.	890	G.O., No. 95 W., dated 11th January 1888.	328	562	562	..	562	..	39	
	40	Putting up shelves inside the store-room of the straw shed attached to the Medical Stores, Madras.	563	Superintending Engineer's Register No. 17 of 1888-89.	9	554	554	..	554	..	40	
Public Works Workshops.	41	Improving the buildings connected with the Public Works Workshops.	2,048	G.O., No. 2907 W., dated 17th September 1888.	1,708	340	340	..	..	..	41	No appropriation is necessary under Code para. 1908, part III.
Tinnevelly ..	42	Improving English record-room at the Collector's office at Kokarakulam.	1,145	Register No. 2 of 1889-90.	363	782	737	..	737	..	42	From the reserve.
	43	Repairing travellers' bungalow and its outhouses at Virudupati.	2,080	Superintending Engineer's Register No. 17 of 1888-89.	..	2,080	..	2,080	..	..	43	No funds are available.
Architect ..	44	Additions and improvements to the School of Arts, Madras.	1,442	G.O., No. 200 W., dated 25th January 1889.	1,325	117	117	..	..	..	44	No appropriation is necessary under Code para. 1908, part III.
	45	Fixing an electric clock on the northern face of the Public Works Department offices at Chepâk.	444	Consulting Architect's Register No. 62 of 1888-89.	223	221	221	..	..	..	45	
		Total ..	..	....	..	..	11,905	27,842	11,227	760		

B.—Statement of requirements on account of Provincial incomplete works of 1888-89, &c.—*cont.*

Division.	Item No.	Name of work.	Amount of estimate.	Number and date of sanction.	Past expenditure.	Balance of estimate.	Amount applied for for 1889-90		Amount allotted		Item No.	Remarks.
							For incomplete works.	For new works.	For incomplete works.	For new works.		
1	2	3	4	5	6	7	8	9	10	11	12	13
		Major Works.	RS.		RS.	RS.	RS.	RS.	RS.	RS.		
Vizagapatam ..	46	Constructing a 3rd-class Tahsildar's office at Sálúr.	10,230	G.O., No. 1018 W., dated 20th April 1886.	3,485	6,745	6,745	..	6,745	..	46	From the reserve.
	47	Constructing hospital at Ganapuram.	4,020	G.O., No. 421 W., dated 6th February 1888.	3,285	735	735	..	735	..	47	
	48	Reconstructing compound wall of the District Jail, Vizagapatam.	4,290	G.O., No. 3314 W., dated 18th October 1888.	823	3,467	3,467	..	2,396	..	48	From the reserve. Balance of the estimate, exclusive of the value of convict labor, has been provided.
Godávari Eastern	49	Constructing a General Deputy Collector's office at Vizianagrum.	5,000	G.O., No. 491 W., dated 11th February 1888.	..	5,000	..	5,000	..	..	49	No funds are available.
	50	Constructing a church at Cocoanada.	18,380	G.O., No. 586 W., dated 5th March 1886.	17,447	933	933	..	933	..	50	From the reserve. The allotment represents the balance of contribution by Government.
Godávari Western.	51	Additions to block No. 4 in the District Jail at Rajahmundry to adapt it for the office of the Sub-Collector.	5,020	G.O., No. 668 W., dated 7th March 1889.	..	5,020	..	2,000	..	..	51	No funds are available.
Kistna Western ..	52	Constructing 1st-class taluk office at Narsápur.	23,770	G.O., No. 1536 W., dated 25th May 1888.	20,797	2,973	2,973	..	2,973	..	52	From the reserve.
Kistna Eastern ..	53	Constructing taluk office at Sattenapalle.	21,880	G.O., No. 94 W., dated 15th January 1889.	6,848	15,032	15,032	..	10,000	..	53	From the reserve. It has not been possible to provide a larger grant.
Bellary ..	54	Repairing Collector's residence at Masulipatam.	14,305	G.O., No. 372 W., dated 1st February 1888.	14,153	152	792	..	792	..	54	From the reserve.
	55	Converting the Apothecary's quarters at Anantapur into a residence for the District Surgeon.	6,538	G.O., No. 1814 W., dated 19th June 1888.	..	6,538	..	6,538	..	..	55	No funds are available.
	56	Alterations and additions to the Collector's office at Bellary.	47,540	G.O., No. 1134 W., dated 6th May 1884.	44,198	3,342	7,000	..	3,342	..	56	From the reserve. The question of supplementing the grant will be considered on receipt of the revised estimate.
Cuddapah ..	57	Improving Christ church at Cuddapah.	3,176	G.O., No. 1019 W., dated 29th March 1888.	2,470	706	706	..	706	..	57	From the reserve.
West Coast ..	58	Improvements to the District Munsif's Court at Kásaragód.	4,700	G.O., No. 2468 W., dated 14th August 1888.	724	3,976	3,270	..	..	..	58	Rs. 3,979 have been provided for the work in the final issue of the budget.
	59	Improvements to the second and third blocks of the Collector's office at Mangalore.	15,060	G.O., No. 2421 W., dated 9th August 1888.	2,658	12,402	4,000	..	4,000	..	59	From the reserve. In addition to the budget grant of Rs. 6,000.
West Coast ..	60	Constructing Law Courts at Calicut.	1,24,439	G.O., No. 199 W., dated 25th January 1889.	1,21,088	3,351	3,350	..	3,350	..	60	From the reserve.
	61	Constructing a Collector's office at Calicut.	1,89,970	G.O., No. 1186 W., dated 21st April 1888.	25,048	1,64,922	10,000	..	..	..	61	It is not at present possible to supplement the grant of Rs. 30,000 provided in the budget.
	62	Constructing 12 cells for lunatics in the District Jail at Calicut.	9,280	G.O., No. 786 W., dated 9th March 1888.	7,491	1,789	1,780	..	1,780	..	62	From the reserve.
	63	Constructing Sub-Judge's and District Munsif's Court at Pálghat.	28,790	G.O., No. 2521 W., dated 17th August 1888.	7,200	21,590	10,000	..	..	..	63	No funds are available to supplement the budget grant of Rs. 10,000.
	64	Constructing a Sub-Judge's Court-house at Tellicherry.	14,440	G.O., No. 2631 W., dated 27th August 1888.	2,000	12,440	4,000	..	4,000	..	64	From the reserve. In addition to the budget grant of Rs. 6,000.
Coimbatore ..	65	Constructing a Deputy Tahsildar's office at Aravakurchi.	9,540	G.O., No. 3287 W., dated 16th October 1888.	..	9,540	..	9,540	..	..	65	No funds are available.
	66	Repairs and improvements to Mountstuart property at Ootacamund.	22,330	G.O., No. 3793 W., dated 1st December 1888.	20,464	1,866	500	..	500	..	66	From the reserve.
	67	Improvements to peons' quarters on Mountstuart, Ootacamund.	2,840	G.O., No. 2834 W., dated 12th September 1888.	1,994	846	846	..	846	..	67	
	68	Improvements to the Collector's office at Ootacamund.	..	....	..	..	..	4,640	..	..	68	No funds are available. Estimate is awaited.
Nílgiri ..	69	Constructing eight cart-stands on road from Kullar to Ootacamund.	6,100	G.O., No. 58 W., dated 7th January 1886.	4,702	1,398	1,348	..	1,348	..	69	From the reserve.
	70	Reconstructing Farewell's bridge at the 14th mile on the Ootacamund-Kullar road.	..	....	..	..	..	10,000	..	..	70	No funds are available. Estimate is awaited.
	71	Improvements to Hobart Park, Ootacamund.	6,540	G.O., No. 2994 W., dated 24th September 1888.	6,540	..	3,365	..	..	..	71	The question of providing funds for the work will be considered on receipt of the revised estimate.
	72	Improving water-supply of that portion of Ootacamund lying north of the lake.	1,71,365	G.O., No. 1545 W., dated 18th June 1886, and G.O., No. 3512 W., dated 5th November 1888.	1,65,107	6,258	3,000	..	3,000	..	72	From the reserve.
Presidency ..	73	Providing iron bars to the exterior doors and windows on the ground floor of the Government Secretariat, Fort St. George.	..	....	1,654	..	2,021	..	2,021	..	73	From the reserve. Estimate is awaited.
	74	Additions and improvements to the Presidency Training School for Mistresses, Madras.	26,370	G.O., No. 1665 W., dated 6th June 1888.	4,310	22,060	10,690	..	..	..	74	Funds are not available to supplement the budget grant of Rs. 11,370.
	75	Constructing an operation room at the General Hospital, Madras.	11,590	G.O., No. 2096 W., dated 25th August 1884.	2,535	9,055	9,055	..	9,055	..	75	From the reserve.
	76	Converting two of the work-sheds at the Lunatic Asylum, Madras, into 16 single rooms and constructing drains.	8,729	G.O., No. 971 W., dated 26th March 1888, and G.O., No. 2617 W., dated 24th August 1888.	3,711	5,018	5,018	..	5,018	..	76	
	77	Constructing quarters for Assistant Matron and for 2nd-class European attendants at the Lunatic Asylum, Madras.	12,445	G.O. No. 1225 W., dated 14th August 1884.	1,197	11,248	11,248	..	6,918	..	77	From the reserve. Allotment has been made to the extent of the balance of the estimate for the quarters of the European attendants for which alone funds were provided in 1888-89.

B.—Statement of requirements on account of Provincial incomplete works of 1888-89, &c.—*cont.*

Division.	Item No.	Name of work.	Amount of estimate.	Number and date of sanction.	Past expenditure.	Balance of estimate.	Amount applied for for 1889-90		Amount allotted		Item No.	Remarks.
							For incomplete works.	For new works.	For incomplete works.	For new works.		
1	2	3	4	5	6	7	8	9	10	11	12	13
		Major Works—cont.	Rs.		Rs.	Rs.	Rs.	Rs.	Rs.	Rs.		
Presidency—*cont.*	78	Improving strong rooms of the Paper Currency office, Fort St. George.	12,500	G.O., No. 240 W., dated 20th January 1883.	..	12,500	..	12,500	..	10,000	78	From the reserve. The Superintending Engineer should explain the circumstances in which the allotment made for the work in 1888-89 was not utilised.
	79	Putting self-acting shutters on three bridges of the Cooum river, Madras.	39,360	G.O., No. 2319 W., dated 31st July 1888.	3,031	36,329	2,000	..	..	..	79	Funds are not available to supplement the budget grant of Rs. 10,000.
South Arcot ..	80	Constructing taluk office at Tirukoilúr.	20,680	G.O., No. 770 W., dated 7th March 1888.	..	20,680	..	6,000	..	..	80	No funds are available.
	81	Constructing taluk office at Tindivanam.	22,640	Do. do.	..	22,640	..	6,000	..	..	81	
Chingleput ..	82	Artesian boring in the Kortalayár valley.	8,745	G.O., No. 3147 W., dated 21st November 1887.	8,564	181	700	..	200	..	82	From the reserve. In addition to Rs. 500 provided in G.O., No. 1213-A W., dated 7th May 1889.
Trichinopoly ..	83	Constructing a District Jail at Trichinopoly.	85,244	G.O., No. 3275 W., dated 1st December 1887.	73,944	11,300	820	..	820	..	83	From the reserve.
	84	Converting the Artillery barracks at Trichinopoly into an office for the Collector.	5,300	G.O., No. 668 W., dated 27th February 1888.	2,537	2,763	7,500	..	7,500	..	84	From the reserve. Revised estimate is awaited.
Negapatam ..	85	District Munsif's Court at Tiruválúr.	14,230	G.O., No. 908 W., dated 27th March 1889.	12,892	1,338	1,338	..	1,338	..	85	
Tinnevelly ..	86	Sub-jail and outhouses to the Deputy Tahsildar's office at Kulasekharapatnam.	3,900	Superintending Engineer's Register No. 2 of 1888-89.	2,778	1,122	1,000	..	1,000	..	86	
Madura ..	87	Completion of road from Cumbum to foot of the Gúdalúr-Peermade ghát.	90,507	G.O., No. 3226 W., dated 7th December 1886.	86,490	4,017	4,017	..	4,017	..	87	From the reserve.
Consulting Architect.	88	Additions to the ophthalmic hospital at Madras.	4,517	G.O., No. 2383 W., dated 6th August 1888.	2,422	2,095	2,095	..	2,095	..	88	
		Total ..	..	....	..	..	1,41,344	62,218	87,428	10,000		
		Police.										
Vizagapatam ..	89	Constructing a stable and wall in the compound of the Police Assistant Superintendent's bungalow at Jeypore.	1,330	Superintending Engineer's Register No. 169 of 1888-89.	..	1,330	..	1,330	..	..	89	No funds are available.
Godávari Eastern..	90	Constructing a well for the Police force at Kota.	1,960	Superintending Engineer's Register No. 183 of 1888-89.	..	1,960	..	1,230	..	..	90	
Godávari Western.	91	Constructing a 2nd-class Police station at Tallapudi.	2,360	Superintending Engineer's Register No. 142 of 1888-89.	..	2,360	..	2,360	..	..	91	
Nellore ..	92	Police huts at Thettu	1,350	G.O., No. 1834 W., dated 19th July 1886.	..	1,350	..	1,350	..	..	92	No funds are available.
	93	Eight Police huts at Náyudupet ..	2,490	G.O., No. 419 W., dated 8th February 1888.	..	2,490	..	2,490	..	..	93	
Bellary	94	2nd-class Police station at Podili	2,100	....	..	2,100	..	2,100	..	..	94	
Kurnool ..	95	Constructing seven Police huts at Muchukottah.	2,224	G.O., No. 1834 W., dated 20th June 1888.	..	2,224	..	2,224	..	..	95	
	96	Constructing an office for the Assistant Superintendent of Police at Nandyál.	1,623	Superintending Engineer's Register No. 94 of 1888-89.	..	1,623	..	1,623	..	..	96	
West Coast ..	97	Constructing a 3rd-class Police station house at Nilambúr.	1,434	G.O., No. 2208 W., dated 19th July 1888.	..	1,434	..	1,434	..	..	97	
	98	Constructing six Police huts at Sultan's battery at Wynaad.	1,920	G.O., No. 894 W., dated 19th March 1888.	..	1,920	..	1,920	..	..	98	
North Arcot ..	99	Constructing seven Police huts at Kuppam.	1,895	Superintending Engineer's Register No. 15 of 1888-89.	920	975	975	..	975	..	99	
South Arcot ..	100	Constructing Police station at Kutteripet.	1,180	G.O., No. 3387 W., dated 9th December 1887.	530	650	650	..	650	..	100	
Chingleput ..	101	Constructing 17 cubicles for the Reformatory school-house at Chingleput.	629	Superintending Engineer's Register No. 3 of 1889-90.	..	629	..	629	..	629	101	From the reserve.
Tinnevelly ..	102	Constructing a 2nd-class Police station-house at Nángunéri.	1,800	G.O., No. 3514 W., dated 5th November 1888.	694	1,106	1,106	..	1,106	..	102	
	103	Constructing a Police station-house at Masarapatty.	1,260	G.O., No. 1185 W., dated 11th May 1886.	759	501	501	..	501	..	103	
Ganjam ..	104	Additions and alterations to Police Superintendent's office at Chatrapur.	4,600	G.O., No. 1700 W., dated 9th July 1884.	3,030	1,570	1,570	..	1,570	..	104	
Nellore	105	Police huts at Mulapet ..	3,300	G.O., No. 1834 W., dated 19th July 1886.	..	3,300	..	3,000	..	..	105	
Bellary ..	106	Constructing a Police hospital at Anantapur.	6,075	G.O., No. 3880 W., dated 10th December 1888.	..	6,075	..	6,075	..	..	106	No funds are available.
	107	Constructing seven Police huts at Vanavole.	2,928	G.O., No. 88 W., dated 11th January 1887.	1,569	1,359	1,359	..	1,359	..	107	
West Coast ..	108	Constructing a residence for the Assistant Superintendent of Police at Malapuram and providing wire-fencing.	14,380	G.O., No. 3034 W., dated 16th December 1885. and G.O., No. 873 W., dated 23rd March 1889.	14,245	135	720	..	720	..	108	From the reserve.
		Total ..	..	....	..	..	6,881	27,765	6,881	629		
		Registration.										
Vizagapatam ..	109	Constructing a Sub-Registrar's office at Chódavaram.	2,285	....	..	2,285	..	2,285	..	..	109	A sum of Rs. 2,620 having been provided for the work in the budget, the excess Rs. 335 will be resumed and credited to the reserve.

B.—Statement of requirements on account of Provincial incomplete works of 1888-89, &c.—*cont.*

Division.	Item No.	Name of work.	Amount of estimate.	Number and date of sanction.	Past expenditure.	Balance of estimate.	Amount applied for for 1889-90		Amount allotted		Item No.	Remarks.
							For incomplete works.	For new works.	For incomplete works.	For new works.		
1	2	3	4	5	6	7	8	9	10	11	12	13
		Registration—cont.	Rs.		Rs.	Rs.	Rs.	Rs.	Rs.	Rs.		
Vizagapatam—*cont.*	110	Converting the canteen in the fort at Vizagapatam into Registrar's office.	897	G.O., No. 805 W., dated 31st March 1885.	..	897	..	897	..	..	110	No funds are available.
	111	Constructing a Sub-Registrar's office at Párvatipur.	2,145	Superintending Engineer's Register No. 143 of 1888-89.	347	1,798	1,798	..	1,798	..	111	From the reserve.
Godávari Eastern.	112	Addition of a room to the Sub-Magistrate's office at Tuni for Sub-Registrar's office.	1,590	Superintending Engineer's Register No. 173 of 1888-89.	..	1,590	..	1,590	..	..	112	No funds are available.
Kistna Eastern ..	113	Improvements to Sub-Registrar's office at Bezváda.	1,520	G.O., No. 3824 W., dated 5th December 1888.	..	1,520	..	1,520	..	..	113	
Bellary ..	114	Constructing a Sub-Registrar's office at Hindupur.	2,483	Superintending Engineer's Register No. 54 of 1888-89.	759	1,724	1,724	..	1,724	..	114	From the reserve.
Cuddapah ..	115	Constructing a Sub-Registrar's office at Peelair.	2,358	Superintending Engineer's Register No. 76 of 1888-89.	..	2,358	..	2,358	..	..	115	No funds are available.
West Coast ..	116	Providing additional accommodation for the Sub-Registrar's office at Vetatapudiyangadi.	1,350	G.O., No. 2926 W., dated 26th November 1884.	601	749	749	..	749	..	116	From the reserve.
Coimbatore ..	117	Adding a record-room to the Sub-Registrar's office at Avanáshi.	880	G.O., No. 2867 W., dated 2nd November 1886.	..	880	..	880	..	..	117	No funds are available.
	118	Additions to the taluk office at Atúr for the Sub-Registrar's office.	2,365	G.O., No. 18 W., dated 6th February 1888.	..	2,365	..	2,365	..	..	118	
Godávari Eastern..	119	Constructing a Sub-Registrar's office at Prattipad.	3,400	G.O., No. 796 W., dated 10th March 1888.	..	3,400	..	1,400	..	..	119	
Godávari Western.	120	Constructing a Sub-Registrar's office at Bhímavaram.	3,420	G.O., No. 3769 W., dated 29th November 1888.	535	2,885	2,885	..	1,465	..	120	From the reserve. In addition to Rs. 1,420 provided in the budget.
	121	Constructing a Sub-Registrar's office at Narsápur.	3,430	Do. do. ..	762	2,668	2,668	..	2,668	..	121	From the reserve.
Nellore ..	122	Constructing a Sub-Registrar's office at Atmakúr.	3,185	G.O., No. 176 W., dated 21st January 1886.	..	3,185	..	1,585	..	1,585	122	From the reserve. In addition to Rs. 1,600 provided in the budget.
Kurnool ..	123	Constructing a Sub-Registrar's office at Giddalúr.	2,761	G.O., No. 3827 W., dated 5th December 1888.	..	2,761	..	2,761	..	..	123	No funds are available.
	124	Constructing a Sub-Registrar's office at Márkápur.	2,828	G.O., No. 3825 W., dated 5th December 1888.	..	2,828	..	2,828	..	..	124	
Coimbatore ..	125	Constructing a Sub-Registrar's office at Gobichettipolliem.	2,680	G.O., No. 278 W., dated 4th February 1887.	..	2,680	..	2,680	..	..	125	No funds are available.
	126	Constructing a Sub-Registrar's office at Sólúr.	2,750	G.O., No. 1587 W., dated 13th June 1887.	..	2,750	..	2,750	..	..	126	
	127	Constructing a Sub-Registrar's office at Thathiangarpet.	2,770	G.O., No. 198 W., dated 25th January 1889.	..	2,770	..	2,770	..	..	127	
North Arcot ..	128	Constructing a Sub-Registrar's office at Kuppam.	2,850	G.O., No. 2944 W., dated 5th November 1887.	..	2,850	..	2,850	..	..	128	
	129	Constructing a Sub-Registrar's office at Arkónam.	2,575	G.O., No. 655 W., dated 24th February 1888.	..	2,575	..	2,575	..	..	129	
South Arcot ..	130	Constructing a Sub-Registrar's office at Merkánam.	3,196	G.O., No. 827 W., dated 13th March 1888.	..	3,196	..	1,000	..	..	130	
	131	Constructing a Sub-Registrar's office at Vanúr.	3,080	Do. do. ..	..	3,080	..	1,000	..	..	131	
Chingleput ..	132	Constructing a Sub-Registrar's office at Uttramallúr.	2,800	G.O., No. 967 W., dated 9th April 1886.	..	2,800	..	2,800	..	2,800	132	From the reserve. The circumstances in which work was commenced without allotment should be explained.
		Total ..	..	....	..	..	9,824	38,594	8,404	4,385		

ORDER—dated 22nd June 1889, No. 1638 W., Public Works.

With the papers above recorded, Superintending Engineers and the Consulting Architect to Government submit statements of demands under Provincial for incomplete works of 1888-89 and for new works, repairs and tools and plant.

2. A sum of Rs. 1,63,549 was reserved in the budget for incomplete works, but the modifications of grants subsequently sanctioned increased the reserve to Rs. 1,64,199. Adding to this amount Rs. 335 resumed from the grant provided in the budget for item No. 109 of the statement B printed with these Proceedings, the reserve will stand at Rs. 1,64,534. Superintending Engineers, I and IV Circles, having applied for less grants under minor works than those provided in the budget, the following sums are resumed and credited to the reserve which will now amount to Rs. 1,83,584 :—

	RS.
Civil Buildings, Minor works, Ganjam division	500
Do. do. Vizagapatam division	2,400
Do. do. Godávari Western division	1,150
Do. do. Nílgiri division	8,000
Do. do. Coimbatore division	500
Do. do. West Coast do.	2,500
Communications, Minor works, Nílgiri division	3,000
Miscellaneous Public Improvements, Minor works, Nílgiri division.	1,000
Total ...	19,050

3. The demands under Original works are detailed in the statement B and they amount to—

	RS.
Incomplete Minor works	11,905
Do. Major do.	1,41,344
Do. Police do.	6,881
Do. Registration works	9,824
Total ...	1,69,954
New Minor works	27,842
New Major do.	62,218
New Police do.	27,765
New Registration works	38,894
Total demands ...	3,26,673

4. The allotments sanctioned under Original works amount to—

	RS.
Incomplete Minor works	11,227
Do. Major do.	87,428
Do. Police do.	6,881
Do. Registration works	8,404
Total ...	1,13,940
New Minor works	760
New Major do.	10,000
New Police do.	629
New Registration works	4,385
Total allotments ...	1,29,714

5. The demands under incomplete works include additions to allotments already provided in the budget, but these demands have not been complied with in the case of items 61, 63, 74 and 79 as the balance of reserve is too small. No allotment has been made for item 71, as outlay to the extent of the sanctioned estimate has already been incurred. The question of providing funds for it will be considered on receipt of a revised estimate. Funds have been provided for all other incomplete works brought forward by Superintending Engineers and the Consulting Architect to Government.

6. In the case of new works, a sum of Rs. 10,000 has been provided for improving the strong rooms of the Paper Currency office, Fort St. George, the early execution of which was urged by the Accountant-General (*vide* G.O., No. 247 W., dated 30th January 1889). The circumstances in which the grant provided for this work in 1888-89 has not been utilised should be explained. Funds have also been provided for three other new works, items 37, 101 and 132 of the statement B, as the Superintending Engineer, V Circle, has reported that they have been already commenced. The circumstances in which these works were put in hand without obtaining allotments should be explained.

7. The marginally-noted works, for which large grants have been applied for, should have been included in the Superintending Engineers' budget estimates for 1889-90. Funds have now been allotted for them with much inconvenience as the small reserve with the Government was chiefly intended for such incomplete works as were expected to be completed in 1888-89, but were delayed owing to unforeseen circumstances.

i. Third-class Tahsildar's office at Sálúr.
ii. Constructing an operation room at the General Hospital, Madras.
iii. Converting two of the work-sheds at the Lunatic Asylum, Madras, into 16 single rooms.

8. An allotment of Rs. 6,560 under Minor works as shown in the statement A has been made from the reserve in addition to the grants already provided in the budget.

9. The demands under Repairs being much in excess of the budget provision, a sum of Rs. 38,300 has been transferred from the reserve as shown below :—

	RS.
Civil Buildings	2,400
Communications	34,500
Miscellaneous Public Improvements	1,400
Total ...	38,300

10. The amounts applied for and those granted under Repairs and Tools and plant are shown in the statement A appended to these Proceedings.

11. As the system of distributing the grants for repairs and tools and plant in the statements of demands is productive of inconvenience, these grants will be finally distributed in the budgets of ensuing years. Superintending Engineers and the Consulting Architect in framing their future budget estimates will carefully consider the requirements under Minor works, Repairs, and Tools and plant and include the same in their budgets. When large amounts are applied for, explanation with details should be furnished.

(True Extract.)

(Signed) R. R. E. DRAKE-BROCKMAN, Lt.-Col., R.E.,
Ag. Joint Secy. to Govt., P.W.D.

To Superintending Engineers.
To the Consulting Architect to Government.
" Examiner, Public Works Accounts.
" Financial Department.
" Judicial Department.
" Educational Department.
" Public Department.
" Ecclesiastical Department.
" Revenue Department.

Exd. J. Henricus.
Spare Copies

GENERAL.
ACCOUNT.

Govt. of {1889} Madras.

PUBLIC WORKS.

Dated June, 22nd.

Recd. *Encl.*

G.O., 22nd June 1889, No. 1638 W.

JUNE.

Funds

Orders on statements of demands under Provincial for incomplete works of 1888-89 and for new works, repairs, and tools and plant.