(1) பக்கங்களின் எண்ணிக்கை 76.

(2) புதுக்கித் திருப்பிய நாள் 8/89

(3) ஆதாரங்குறிப்பவர் சுருக்கொப்பம்

தமிழ்நாடு ஆவணக் காப்பகம்.

தமிழ்நாடு அரசு

P.W.D துறை

அரசாணை எண். / மு. கோப்புத் தாள் எண். 2235 அச்சகம் / பலவகை

நாள் : 16- 16-8-1887 ~~19~~.

கவோ கண்டபடி கையாளவோ கூடாது

38 sheets

கா-1—18,006—15-6-87.

(38)

16th August 1889, No. 2235 W., Public Works.

GOVERNMENT OF MADRAS.

PUBLIC WORKS DEPARTMENT.

Buildings and Roads.
Civil Works.

2231

Read—the following paper:—

From T. M. HORSFALL, Esq., Registrar of the High Court of Judicature, Appellate Side, to the Chief Secretary to Government, dated Madras, 22nd July 1889, No. 1784.

I am directed to forward, for the sanction of Government, the accompanying plan and estimates, amounting in the aggregate, to Rs. 12,360, for the construction of the District Munsif's Court-house at Sómpet, in the district of Ganjam.

Enclosure.

From Major D. McNEIL CAMPBELL, R.E., Superintending Engineer, I Circle, to the District Judge, Ganjam, dated Dowlaishweram, 12th May 1889, No. 191 G.N.

With reference to G.O., No. 2673 W., dated the 29th August 1888, I have the honor to submit herewith estimates, amounting in the aggregate to Rs. 12,360, for constructing a District Munsif's Court-house at Sómpet, in the Ganjam district, and to request that you will be so good as to obtain the sanction of Government to the same.

2. The estimates have been prepared agreeably to the standard design sanctioned in G.O., No. 1098 W., dated 21st April 1887, and the only deviations from it are—

(1) The substitution of sâl for teakwood.
(2) Rough stone in chunam for brickwork.

The former deviation is due to the scarcity of teakwood in the district, and the latter to the request contained in your letter No. 629 of the 6th February 1889 to the Executive Engineer.

3. The following plans accompany the estimates:—

1 Site-plan.
1 Plan of foundations.

Approved and transferred to the Public Works Department.

30th July 1889. (Signed) A. G. CARDEW,
Under-Secretary.

Order—dated 16th August 1889, No. 2235 W., Public Works.

The estimate, amounting to Rs. 12,360, for the construction of a District Munsif's Court at Sómpet, in the Ganjam district, is sanctioned.

2. A sum of Rs. 9,000 has been provided for the work in the current year's Provincial budget.

3. This sanction has been registered as Provincial No. 51 W. of 1889-90 and classified as Civil Buildings, Original Works.

(True Extract.)

Captain, R.E.,
Under-Secy. to Govt., P.W.D.

To the Superintending Engineer, I Circle,
with fifteen enclosures.
„ Examiner, Public Works Accounts,
with duplicate general abstract estimate.
„ Judicial Department.

Exd. J. Henricus.
Spare Copies

1

~~30~~

1

BUILDINGS AND ROADS.
CIVIL WORKS.

Govt. of {1889} Madras.

PUBLIC WORKS.

Dated August, 16th.

Recd. *Encl.*

G.O., 16th Aug. 1889, No. 2235 W.

AUGUST.

District Munsif's Court
at Sompet, Ganjam District

Estimate for —, sanctioned.

GOVERNMENT OF MADRAS.

2235

PUBLIC WORKS DEPARTMENT.

Buildings and Roads.
Civil Works.

Read—the following letter from J. A. DAVIES, Esq., Acting Registrar of the High Court of Judicature at Madras, to the Officiating Chief Secretary to Government, dated 3rd January 1884, No. 13 :—

I am directed to submit, for the orders of Government, copy of a letter, dated the 5th December 1883, No. 1750, from the District Judge of Ganjam requesting that funds may be sanctioned for constructing new court-houses for the district munsifs of Berhampore, Tekkali and Aska.

Enclosure.

From J. R. DANIEL Esq., District Judge, Ganjam, to the Registrar of the High Court of Judicature, Appellate side, Madras, dated 5th December 1883, No. 1750.

I have the honor to request that the High Court will obtain the sanction of Government for funds to construct new court-houses for the district munsifs of Berhampore, Tekkali and Aska.

For several years past the munsifs have been complaining of the want of accommodation, and inconvenience of the present buildings.

The court-house at Berhampore is small and low, with very inadequate accommodation for the officials, pleaders and suitors; in the hot weather it is very trying to carry on work in such a building. The situation is bad, it is at the opposite end of the town from the district court, a distance of about 2 miles, and is, moreover, not conveniently situated for the parties.

The Tekkali court-house is even worse; it is very small and ill-constructed, and on the present site there are no means of improving it. This is an important court, perhaps the most litigious in the district, and the want of adequate accommodation is much felt.

The Aska court-house is similar to the Berhampore court-house; it is in the centre of the town. Some attempts have been made to increase accommodation, but the building itself is low and not adapted to improvements.

I have inspected these courts myself and am satisfied that the complaints which the munsifs have been making during the last few years are well founded. I applied to the Executive Engineer for estimates. He has sent me approximate estimates, but I have requested him to prepare detailed estimates according to the standard plan.

Approved and transferred to the Financial Department for the consideration of funds.

(By Order.)

(Signed) M. HAMMICK,
Ag. Asst. Secy., Judl. Dept.

8th January 1884.

No. 70, Financial.

Transferred to the Public Works Department.

(Signed) E. F. WEBSTER,
Chief Secretary.

12th January 1884.

2

ORDER—dated 16th January 1884, No. 137 W., Public Works.

The Superintending Engineer, I Circle, will submit the necessary plans and estimates as early as practicable.

(True Extract.)

(Signed) J. SHAW-STEWART, Colonel, R.E.,
Secretary to Govt., P.W.D.

To the Superintending Engineer, I Circle.
" Judicial Department.
" Financial Department.

Exd. E. Fernandez.
Spare Copies

2235

3

3

BUILDINGS AND ROADS.
CIVIL WORKS.

Govt. of (1884) Madras.

PUBLIC WORKS.

Dated January, 16th.

Encl.

Recd.

G.O., 16th Jan. 1884, No. 137 W.

JANUARY.

District Munsifs' Court-houses

The Superintending Engineer, I Circle, directed to submit plans and estimates for constructing — at Berhampore, Tekkali and Aska.

2235

GOVERNMENT OF MADRAS.

PUBLIC WORKS DEPARTMENT.

Buildings and Roads.
Civil Works.

Read—the following papers :—

From the Consulting Architect to Government, dated 4th February 1887, No. 1327.

From J. W. BRASSINGTON, Esq., Officiating Consulting Architect to the Government of Madras, to the Chief Engineer, Public Works Department, dated Chepâk, 12th March 1887, No. 1530.

I have the honor to submit a revised plan, with schedule of quantities, for a Sub-Judge or District Munsif's court.

2. This design will supersede the design circulated with G.O., No. 505 W., dated the 6th March 1885.

3. The revised design and quantities for Tahsildars' cutcherries will follow.

No. 970 C.

Forwarded for the approval of Government in the Judicial Department.

2. The design has already been approved in Committee by the Honorable Members and Secretaries to Government.

15th March 1887.

(Signed) J. O. HASTED, Colonel, R.E.,
Secretary to Govt., P.W.D.

Approved and transferred to the Public Works Department.

(By Order.)

Ootacamund,
12th April 1887.

(Signed) H. A. STUART,
Under Secy., J.D.

Order—dated 21st April 1887, No. 1098 W., Public Works.

The revised type design, with schedule of quantities and descriptive specification, for a Sub-Judge's or District Munsif's court-house with tiled roof, will be circulated to officers of the Public Works Department, for information and guidance, in supersession of the design circulated with G.O., No. 505 W., dated 6th March 1885.

2. The Consulting Architect will, as early as practicable, submit a type design affording the same accommodation for a court-house with a terraced roof.

3. The submission of a revised type design for taluk offices is awaited.

(True Extract.)

(Signed) J. O. HASTED, Colonel, R.E.,
Secretary to Govt., P.W.D.

To Superintending Engineers.
,, the Consulting Architect to Government.
,, the Judicial Department.

Exd. P. L. Pereira.

Spare Copies.

8

R 4 –

BUILDINGS AND ROADS.
CIVIL WORKS.

Govt. of 1887 Madras.

PUBLIC WORKS.

Dated April 21st.

Encl.

Recd.

G.O., 21st April 1887, No. 1098 W.

APRIL.

Sub-Judge's or District Munsif's Court-house

A revised type design for a — with tiled roof, circulated to officers of the Public Works Department.

2235

SUB-JUDGE OR DISTRICT MUNSIF'S COURT-HOUSE.

DESCRIPTIVE SPECIFICATION.

Foundation.—A depth of 5 feet is provided in the quantities, but this should be settled locally in accordance with the nature of the soil.

Brickwork.—The walls should be carried up in English bond-walls of central portion being 2½ bricks thick, ends 2 bricks thick, partitions 1½ bricks thick, verandah retaining walls 1 brick thick, except under posts, which will be half a brick thicker.

Where good bricks are obtainable the exterior of the building should be pointed.

Woodwork.—The verandah posts, trusses, doors and windows should be of teakwood, the rafters and other minor roof timbers may be of approved country wood.

Tiled roofing.—The roof will be covered with flat and pantiles; if the quality of these are good the usual unsightly "chunam bands" might be dispensed with.

All valleys should be protected with sheet lead.

Stonework.—Stone slabs 12″ × 12″ × 6″ with mortice holes 2 inches square and 2 inches deep cut into them into which the verandah posts will rest. Slabs will also be placed under the bearings of trusses. The steps may also be of stone if procurable without great expense.

Flooring.—The floor may be of square bricks or stone slabs if the latter are easily procurable.

Interior finishing.—The interior will be fine plastered with shell lime or plastered and washed.

Finials.—The finials may be of copper, iron or wood.

The different kinds of work to be done will be executed in conformity with the standard specification of the Public Works Department.

(Signed) J. W. BRASSINGTON,
Offg Consulting Architect to Government.

ESTIMATE FORM—Detail Measurements.

Detail of work.	No.	Measurements in Feet. Length.		Breadth.		Depth.		Area or contents.	Total quantity of each description of work.
EXCAVATION FOR FOUNDATIONS.									
Court-house, record and property room.									
Outer walls	...	151	3	4	10½	5	0	4,052	
Partition	1	15	0	4	10½	5	0		
Do.	1	19	0	4	1½	5	0	392	
Gumastah's, Head Clerk's, Judge's retiring room, &c.									
Outer walls	2	99	6	4	6	5	0	4,478	
Partitions	3	12	0	4	1½	5	0	743	
Verandah	...	261	9	3	9	5	0	4,908	
Extra for posts	28	4	0	0	3	5	0	146	
Do. at corners	8	0	3	0	3	5	0		
Do. next to walls	4	0	9	0	3	5	0		
Steps	1	14	0	3	0	1	6	252	
Do.	4	10	6	3	0	1	6		
Total, Cubic Feet ...	...	...		...		...		...	14,971
CONCRETE.									
Court-house, record and property room.									
Outer walls	...	151	3	4	10½	1	6	1,216	
Partition	1	15	0	4	10½	1	6		
Do.	1	19	0	4	1½	1	6	118	

4 5 3 4

Estimate Form—Detail Measurements—*cont.*

Detail of work.	No.	Measurements in Feet.			Area or contents.	Total quantity of each description of work.
		Length.	Breadth.	Depth.		
Gumastah's, Head Clerk's, Judge's retiring room, &c.						
Outer walls	2	99 6	4 6	1 6	1,343	
Partitions	3	12 0	4 1½	1 6	223	
Verandah	...	261 9	3 9	1 6	1,472	
Extra for posts	28	4 0	0 3	1 6	44	
Do. at corners	8	0 3	0 3	1 6		
Do. next to walls	4	0 9	0 3	1 6		
Steps	1	14 0	3 0	1 6	252	
Do.	4	10 6	3 0	1 6		
Total, Cubic Feet ...	...	...	...	...	...	4,668
Brickwork in Foundations.						
Footings.						
Court-house, record and property room.						
Outer walls	...	151 3	2 10½	1 6	726	
Partitions	1	17 0	2 10½	1 6		
Do.	1	21 0	2 1½	1 6	67	
Gumastah's, Head Clerk's, Judge's retiring room, &c.						
Outer walls	2	101 6	2 6	1 6	919	
Partitions	3	14 0	2 6	1 6		
Verandah	...	267 9	1 9	1 6	703	
Extra for posts	28	2 0	0 3	1 6	23	
Do. at corners	8	0 3	0 3	1 6		
Do. next to walls	4	0 9	0 3	1 6		
Above footings to ground level.						
Court-house, record and property room.						
Outer walls	...	151 3	1 10½	2 0	567	
Extra thickness for plinth in rear wall and ends	...	43 0	0 3	2 0	22	
Partition	1	18 0	1 10½	2 0	68	
Do.	1	22 0	1 1½	2 0	50	
Gumastah's, Head Clerk's, Judge's retiring room, &c.						
Outer walls	2	102 6	1 6	2 0	615	
Extra thickness for plinth at ends ...	2	18 0	0 3	2 0	18	
Partitions	3	15 0	1 1½	2 0	101	
Verandah	...	270 9	0 9	2 0	406	
Extra for posts	28	1 0	0 3	2 0	17	
Do. at corners	8	0 3	0 3	2 0		
Do. next to walls	4	0 9	0 3	2 0		
Total, Cubic Feet ...	...	...	...	...	...	4,302
Brickwork in Basement.						
Court-house, record and property room.						
Outer walls	...	151 3	1 10½	2 0	567	
Extra thickness for plinth in rear and ends	...	43 0	0 3	2 0	22	
Partition	1	18 0	1 10½	2 0	68	
Do.	1	22 0	1 1½	2 0	50	

22535

Estimate Form—Detail Measurements—*cont.*

Detail of work.	No.	Measurements in Feet.			Area or contents.	Total quantity of each description of work.
		Length.	Breadth.	Depth.		
Gumastah's, Head Clerk's, Judge's retiring room, &c.						
Outer walls	2	102 6	1 6	2 0	615	
Extra thickness for plinth at ends ...	2	18 0	0 3	2 0	18	
Partitions	3	15 0	1 1½	2 0	101	
Verandah	...	270 9	0 9	2 0	406	
Extra for posts	28	1 0	0 3	2 0	17	
Do. at corners	8	0 3	0 3	2 0		
Do. next to walls	4	0 9	0 3	2 0		
Steps	1	12 3	2 0	1 6	139	
Do.	4	8 6	2 0	1 6		2,003
Deductions— Stone under-posts and for steps ...	...	...	...	...	...	105
Total, Cubic Feet ...	...	...	...	...	...	1,898
Brickwork in Superstructure.						
Court-house, record and property room.						
Outer wall	...	151 3	1 10½	18 6	5,871	
Partition	1	18 0	1 10½	18 6		
Gable	1	18 0	1 10½	3 0	101	
Partition	1	22 0	1 1½	24 6	606	
Gumastah's, Head Clerk's, Judge's retiring room, &c.						
Outer walls	2	102 6	1 6	13 5	4,126	
Partitions	3	15 0	1 1½	13 5	806	
Gables	3	15 0	1 1½	2 6		
Dais wall	...	23 6	0 9	1 0	18	11,528
Deductions—						
At hip from partition in record and property room	1	9 0	1 1½	3 0	30	
Doors	9	4 0	1 10½	8 0	540	
Do.	12	4 0	1 6	8 0	576	
Do.	2	4 0	1 1½	8 0	72	
Windows	2	4 0	1 10½	6 0	90	
Do.	2	4 0	1 6	6 0	72	
Ventilators	9	4 0	1 10½	2 9	186	
Archwork as per details	...	...	...	...	247	1,813
Total, Cubic Feet ...	...	...	...	...	...	9,715
Archwork.						
Over doors and windows	11	5 0	1 10½	1 1½	116	
Do. do.	14	5 0	1 6	1 1½	118	
Do. do.	2	5 0	1 1½	1 1½	13	
Total, Cubic Feet ...	...	...	...	...	...	247
Cut-stonework.						
Under-posts	40	1 0	1 0	0 6	20	
Steps	...	169 0	1 0	0 6	85	
Slabs under trusses	4	2 0	1 10½	0 4	5	
Do. do.	10	1 6	1 6	0 4	8	
Total, Cubic Feet ...	...	...	...	...	...	118

~~4~~ 5 6

Estimate Form—Detail Measurements—*cont.*

Detail of work.	No.	Measurements in Feet.			Area or contents.	Total quantity of each description of work.
		Length.	Breadth.	Depth.		
Filling in basement.						
Court-house	1	30 0	18 0	1 6	810	
Court dais	1	7 6	7 3	1 0	54	
Record and property room	2	22 0	8 5¼	1 6	557	
Gumastah's, head clerk's, judge's retiring room, &c.	...	81 1½	15 0	1 6	1,825	
Verandahs	...	218 3	8 3	1 6	2,701	
Total, Cubic Feet ...	...	...	...	...	...	5,947
Teakwood wrought and put up.						
Court-house, record and property room.						
2 Trusses to span 18 feet. Tie beams	2	21 9	0 4	0 7	8	
Principal rafters ...	4	11 9	0 4	0 6	8	
Struts	4	5 9	0 4	0 4	3	
Purlins allowing for halving ...	2	47 0	0 5	0 6	20	
Do. over wall do. ...	2	58 6	0 4	0 4	18	
Do. do. ...	2	22 0	0 4	0 4		
Ridge	1	38 0	0 3	0 9	7	
Principal rafters in record and property room	2	11 9	0 4	0 6	4	
Hip rafters	4	19 6	0 4	0 5	11	
Common rafters (18 inches centre to centre)	46	14 6	0 3	0 5	130	
Do. do. ...	6	13 0	0 3	0 5		
Jack rafters	56	Average length. 9 0	0 3	0 5		
Gumastah's, Head Clerk's, Judge's retiring room.						
5 Trusses to span 15 feet. Tie beams	5	18 0	0 4	0 6	15	
Principal rafters ...	10	9 9	0 4	0 5	14	
Struts	10	4 9	0 4	0 4	5	
Purlins allowing for halving ...	4	41 0	0 4	0 5	23	
Do. over wall	4	45 0	0 3	0 4	18	
Do. do.	2	18 0	0 3	0 4		
Ridge	2	37 0	0 2½	0 7	9	
Hip rafters	4	16 6	0 4	0 4	7	
Common rafters (18 inches centre to centre)	98	11 3	0 3	0 4	112	
Jack rafters	40	Average length. 6 0	0 3	0 4		
Verandahs.						
Posts	40	0 6	0 6	7 6	75	
Breastsummers allowing for halving.	...	282 0	0 6	0 6	71	
Ridge for entrance to court ...	1	11 0	0 3	0 6	1	
Ridge for end gables of verandah ...	4	5 6	0 2½	0 6	2	
Hip rafters	8	17 0	0 4	0 5	19	
Hip for gable at entrance	2	11 6	0 3	0 5	256	
Hip do. at ends	4	8 6	0 3	0 5		
Common rafters	110	13 3	0 3	0 5		
Jack rafters at entrance gable ...	9	9 6	0 3	0 5		
Do. at corners ...	72	9 3	0 3	0 5		
Do. at end gables	8	8 0	0 3	0 5		
Do. do.	24	5 6	0 3	0 5		
Wall plate at front and ends of court.	...	62 0	0 4	0 3	5	

2235

Estimate Form—Detail Measurements—*cont.*

Detail of work.	No.	Measurements in Feet.			Area or contents.	Total quantity of each description of work.
		Length.	Breadth.	Depth.		
Verandahs—cont.						
Barge board at entrance gable ...	2	8 6	0 1½	0 8	1	
Do. do. do. ...	2	3 0	0 1½	1 0	1	
Do. do. knobs ...	2	0 6	0 6	0 9	1	
Collar piece	1	6 6	0 4	0 3	1	
Do. plank	1	5 0	0 1½	1 9	1	
Barge boards at ends	8	6 6	0 1	0 7	3	
Collar pieces	4	5 6	0 2	0 3	1	
Plank	4	1 0	0 2	1 6	1	
Total, Cubic Feet ...	...	...	...	...	...	851
Venetian and panel doors with frames.						
Outer doors	17	4 0	...	8 0	544	
Total, Square Feet ...	...	...	...	...	...	544
Panelled doors with frames.						
Inner doors, and for record and property room	6	4 0	...	8 0	192	
Total, Square Feet ...	...	...	...	...	...	192
Venetian windows with glazed shutters and iron bars	4	4 0	...	6 0	...	
Total, Square Feet ...	...	...	...	...	...	96
Ventilators.						
For court, record and property room.	9	4 0	...	2 9	...	
Total, Square Feet ...	...	...	...	...	...	99
Wrought Iron work in trusses.						
1″ diar. kingrods for 18 feet trusses.	2	8 0	=16 0	× 2·62	= 41·92	
1″ hex. nut and bolt heads for do.	6	...	...	× 1·10	= 6·60	
3″ diar. ⅛″ thick washers for do.	4	...	...	0·32	= 1·28	
1½″ × ½″ heel straps for do.	4	2 9	=11 0	× 2·50	= 27·50	
1½″ × ½″ bearing plates for do.	4	0 6¾	= 2 3	× 2·50	= 5·62	
⅝″ hex. nuts for do.	8	...	...	× ·267	= 2·13	
Caps of ⅜″ plates 6″ wide	2	2 0	= 4 0	× 7·51	= 30·04	
⅞″ diar. kingrods for 15 feet trusses.	5	6 7½	=33 1½	× 2·01	= 66·58	
⅞″ hex. nut and bolt heads for do.	15	...	...	× 0·73	= 10·95	
3″ diar. ⅛″ thick washers for do.	10	...	...	× 0·32	= 3·20	
1½″ × ⅜″ heel straps for do.	10	2 3	=22 6	× 1·87	= 42·07	
1½″ × ⅜″ bearing plates for do.	10	0 6¾	= 5 7½	× 1·87	= 10·51	
⅝″ hex. nuts for do.	20	...	...	·267	= 5·34	
Caps of ⅜″ plate 6″ wide	5	1 6	= 7 6	× 7·51	= 56·32	
Total, lb. ...	...	...	...	...	...	310
Tiled roofing with flat and pan tiles.						
Court-house, &c.	1	61 0	...	30 0	1,830	
Gumastah's, head clerk's and judge's retiring room, &c.	2	46 0	...	25 0	2,300	
Verandahs	...	160 0	...	11 0	1,760	
Do.	...	80 0	...	12 6	1,000	
Square Feet ...	...	...	...	...	6,890	
Total, Squares ...	...	...	...	...	...	70

6 7 5

Estimate Form—Detail Measurements—*cont.*

Detail of work.	No.	Measurements in Feet.			Area or contents.	Total quantity of each description of work.
		Length.	Breadth.	Depth.		
Flooring with 8 inches square pavement bricks.						
Court-house	1	30 0	...	18 0	540	
Record and property room	2	8 5½	...	22 0	371	
Gumastah's, head clerk's, judge's retiring room, &c.	...	81 1½	...	15 0	1,217	
Verandahs	...	237 9	...	9 0	2,140	
Square Feet ...					4,268	
Total, Squares ...	...	...	...	...		43
Plastering interior (2 coats).	...	...	...	...	...	
Court-house	...	96 0	...	18 6	1,776	
Court gables	1	18 0	...	3 0	54	
Dais sides	2	8 0	...	1 0	16	
Record and property rooms... ...	2	60 10½	...	18 6	2,252	
Additional height to partition ...	2	17 6	...	6 0	210	
Gable	1	16 10½	...	6 0	101	
Door and window jambs	11	20 0	...	1 10½	413	
Ventilator jambs	9	9 6	...	1 10½	160	
Gumastah's, head clerk's rooms, &c. ...		302 3	...	13 5	4,055	
Door and window jambs	14	20 0	...	1 6	420	
Do. do.	2	20 0	...	1 1½	45	9,502
Deductions—						
Doors	27	4 0	...	8 0	864	
Windows	4	4 0	...	6 0	96	
Ventilators	9	4 0	...	2 9	99	1,059
Square Feet ...						8,443
Total, Squares ...	...	...	...	...	...	85
Pointing exterior.						
Basement all round	...	352 9	...	2 0	706	
Court-house, &c.	...	118 9	...	18 6	2,197	
Gumastah's rooms, &c.	2	105 6	...	13 5	2,831	5,734
Deductions—						
Doors	19	4 0	...	8 0	608	
Windows	4	4 0	...	6 0	96	
Ventilators	9	4 0	...	2 9	99	803
Square Feet ...						4,931
Total, Squares ...	...	...	...	...	...	50
Lead sheeting for valleys	...	96 0	1 6	=144 0 ×	5	720 lb.
Mouldings over windows (exterior).	4	5 3	...	...	21	L. ft.
Railings for dais	...	...	...	...	25	L. ft.
Finials over court room	...	...	...	2 in number.		
Finials over Gumastah's and Nazarat establishment	...	...	...	2 in number.		
Finials for verandahs	...	...	...	5 in number.		

2235

Estimate Form—Detail Measurements—*cont.*

Detail of work.	No.	Measurements in Feet.			Area or contents.	Total quantity of each description of work.
		Length.	Breadth.	Depth.		
Painting with 3 coats of Carson's paint.						
Venetian and panel doors	3	544 0	...	...	1,632	
Panelled doors	2	192 0	...	...	384	
Venetian and glazed windows ...	5	96 0	...	...	480	
Ventilators	2	99 0	...	...	198	2,694
Roof timbers including reepers and verandah posts	...	...	...	...	..	11,800
Square Feet ...	...	...	...	...	...	14,494
Total, Squares ...	...	...	...	...	...	145
Punkah.						
Over dais	1	10 0	...	...	10	L. ft.

ESTIMATE FORM—Abstract.

Quantity.	Description of work.	Rate.	Per	Amount.	Total.
		RS.		RS.	RS.
14,971 C. feet ...	Excavation for foundations (rate to include refilling of trenches) ...	...	1,000 C. feet.		
4,668 „ ...	Concrete in foundations	...	100 „		
4,302 „ ...	Brickwork in foundations	...	„		
1,898 „ ...	Do. in basement	...	„		
9,715 „ ...	Do. in superstructure	...	„		
247 „ ...	Archwork	...	„		
118 „ ...	Cut stonework	..	C. feet.		
5,947 „ ...	Filling in basement	...	1,000 C. feet.		
851 „ ...	Teakwood wrought and put up ...	...	C. feet.		
544 Sq. feet ...	Venetian and panel doors with frames complete	...	Sq. feet.		
192 „ ...	Panelled doors with frames complete ...	...	„		
96 „ ...	Venetian windows with glazed shutters and iron bars complete	...	„		
99 „ ...	Ventilators	...	„		
310 lb. ...	Wrought ironwork in trusses ...	...	lb.		
70 Squares ...	Tiled roofing with flat and pantiles including teak reepers	...	Square.		
43 „ ...	Flooring with 8-inch square pavement bricks	...	„		
85 „ ...	Plastering interior (two coats) ...	...	„		
50 „ ...	Pointing exterior	...	„		
720 lb. ...	Lead sheeting for roof valleys ...	...	lb.		
21 L. feet. ...	Moulding over windows	...	L. feet.		
25 „ ...	Hand railing for dais	...	„		
2 in No. ...	Finials over court room	...	Each.		
2 „ ...	Do. at ends	...	„		
5 „ ...	Do. for verandah	...	„		
145 Squares ...	Painting with 3 coats of Carson's paint.	...	Square.		
5 in No. ...	Add extra for finishing barge boards ...	...	Each.		
1 „ ...	Punkah 10 feet long	...	„		
	Petty supervision				
	Contingencies				

MADRAS,
12th March 1887.

(Signed) J. W. BRASSINGTON,
Offg. Consulting Architect to Government.

8

29TH AUGUST 1888, No. 2673 W., PUBLIC WORKS.

2235

GOVERNMENT OF MADRAS.

PUBLIC WORKS DEPARTMENT.

Buildings and Roads.
Civil Works.

READ—the following paper :—

From T. M. HORSFALL, Esq., Acting Registrar of the High Court of Judicature at Madras, Appellate Side, to the Acting Chief Secretary to Government, dated Madras, 3rd August 1888, No. 1946.

In G.O., Judicial Department, No. 2593, dated 14th November 1887, reviewing the report of the High Court on the administration of civil justice for 1886, the Government remarked (para. 11) : "Perhaps the most unequal district (as regards the work of the District Munsifs) is Ganjam, where there are but four Munsifs, and the Aska institutions numbered 1,094 O.S. and 864 S.C. against only 408 and 348 at Chicacole."

2. The High Court have accordingly put themselves in communication with the Judge and Collector of Gamjam with a view to remedying these inequalities, and have in the result, under Sections 5 and 11 of the Civil Courts' Act, decided on re-arranging the district in the manner described in the accompanying two notifications.

3. As regards the question of the location of the District Munsifi between the Berhampore and Chicacole munsifis, Tekkali has had to be abandoned, as, under the arrangements proposed, the town of Tekkali will fall within the Chicacole jurisdiction. The choice lay between Sompetta, Mandasa and Palasa, and the High Court on full consideration have fixed on Sompetta as presenting on the whole the most advantages with the fewest disadvantages.

4. The new arrangements, it will be observed, are to come into force from the 1st January next. A rented building will be available for temporary occupation by the Sompetta Munsif, and the High Court request that Government will take early steps to have a District Munsif's Court built at Sompetta instead of at Tekkali (*see* G.O. of 16th January 1884, No. 137 W.)

Approved and transferred to the Public Works Department.

(By Order.)

(Signed) A. G. CARDEW,
Ag. Under-Secretary.

24th August 1888.

ORDER—dated 29th August 1888, No. 2673 W., Public Works.

Communicated to the Superintending Engineer, I Circle, who will submit an estimate for a District Munsif's Court-house at Sompetta instead of at Tekkali as called for in G.O. No. 137 W., dated 16th January 1884.

(True Extract.)

Captain, R.E.,
Under-Secy. to Govt., P.W.D.

To the Superintending Engineer, I Circle.
" Judicial Department.

Exd. S. J. Pereira.
Spare Copies

N 9

BUILDINGS AND ROADS.
CIVIL WORKS.

Govt. of {1888} Madras.

PUBLIC WORKS.

Dated August, 29th.

Encl

Recd.

G.O., 29th Aug. 1888, No. 2673 W.

AUGUST.

District Munsif's Court-house at Sompetta

Communicating to the Superintending Engineer, I Circle, endorsement of the Judicial Department approving of the proposed construction of a —, Ganjam District, instead of at Tekkali; and requesting submission of the required estimate.

P.W.C.L. No 7987

[30]

CHIEF SECRETARIAT, MADRAS.

2235

Recd 14-8-88

SECRETARY TO GOVERNMENT 10 AUG. 8 P.W. DEPARTMENT, MADRAS.

OFFICE NOTE.

D/ 10 Aug/88

From

THE CHIEF SECRETARY,

To the Secy. to Govt., PWD.

Adverting to G.O. 16 Jan. 84, No. 137 W. Public Works the Chief Secy. has the honour to enquire whether any, and if so, what, progress has been made towards the construction of a Dt. Munsif's Court at Tekkali, Ganjam Dt., as the Hon'ble the Judges of the High Court have now proposed to move the Dt. Munsif from that Station.

Chief Secretary

10 ~~8~~

~~9~~ ~~8~~

SKW

OS 19.8

1028 w 11. 4. 86.
137 w 16.1.84

B. No 1649 W of 5.6.88
G.6. 137 W ,, 16.1.84.

1987

2235

B/

Please report ~~either~~ whether any estimate has been sanctioned, or funds allotted.

C
14.8.88

To / [illegible]

S Ar

9

No estimate has been sanctioned nor any funds allotted for the Dt Munsif's Court at Takkali — The SW reported in his memorandum list for the period ending with 12 January 1888 that estimate has not yet been received from

[illegible]
[illegible]

G/1578

6. 15. 8. 88

15. 8. 88

X

P. W. Depts.

Memo.

2235 2235

In reply to Office Note from the Chief Secy. d/ 10 August 1888, the undersigned has the honor to state that the proposed District Munsiff's Court house at Tekkali, Ganjam District, has not yet been commenced, an estimate for the building not having yet been received.

15.8.88

17/8/88

To the Chief Secy.

No. 1649 W of 5-6-88.
137 W .. 16. 1-84.

Rd. 15-8-88 O.S 19. 8
Despd. 18 viii/88.

H.C. 22135

These M.S. papers have been returned to me by the Public dept. They ~~app~~ should be put up with the original of No. 2673 W of 29. viii. 88

21. ix. 88

R. R.

12

12 13

CHIEF SECRETARIAT,

Ootacamund, 15-8-88

OFFICE NOTE.

From 2235

THE CHIEF SECRETARY,

To The Secy to Govt P.W.D.

Adverting to G.O. 16 January 1884 No. 127 P.W. the Chief Secy has the honor to enquire whether any, & if so, what progress has been made towards the construction of a District Munsiff's Court at Tekkali Ganjam Dt., as the Hon'ble the Judges of the High Court have now proposed to move the Dt. Munsiff from that station.

(Sgd) J Price
of Chief Secy.

No.

Notification.

[illegible] 2275

1. Under Section 11 of the Madras Civil Courts' Act, III of 1873, the High Court hereby notifies that on and after the 1st day of January 1889,

the Pubbakhandam or Purushottapur Division, now lying within and forming a portion of the territorial jurisdiction of the District Munsif of Aska, will be transferred to the jurisdiction of the Berhampore District Munsif;

that on and after the same date Budarasingi, Talantra, Jarada and the Itchapur Division, now lying within and forming a portion of the territorial jurisdiction of the Berhampore District Munsif, will be transferred to the jurisdiction of the District Munsif of Sompetta and

that (1) the part of the Chicacole Taluk now under the Tekkali District Munsif's jurisdiction, (2) the South-western portion of the Parlakimedi Zemin consisting of the Kotturu

14 15 14 [illegible] and

and Sarvakota Khandams and (3) the south-west portion of the Tekkali Estate comprising Talagam and Raghunadapuram Khandams and now lying within and forming a portion of the territorial jurisdiction of the Tekkali District Munsif, will be transferred to the jurisdiction of the District Munsif of Chicacole.

2. All suits arising within the limits of the said Pubbakhandam or Purushottapur Division over which the District Munsif of Aska has hitherto exercised jurisdiction will, on and after the above date, be instituted in the Court of the District Munsif of Berhampore,

all suits arising within the limits of the said Budarasingi, Talantra, Tarada and the Itchapur Division over which the District Munsif of Berhampore has hitherto exercised jurisdiction will, on and after the above date, be instituted in the Court of the District Munsif of Sompetta, and

all suits arising within the limits of the said (1) part of Chicacole Taluk, now under the Tekkali Munsif jurisdiction, (2) south-west portion of the Parlakimedi Zemin consisting of Kotturu and Sarvakota Khandams and (3) south-west portion of the Tekkali Estate comprising Talagam and Raghunadapuram Khandams over which the District Munsif of Tekkali has hitherto exercised jurisdiction will, on and after the above date, be instituted in the Court of the District Munsif of Chicacole.

2275

By the Court.

Acting Registrar,
Appellate Side.

F.S.

16

Exd. N.

Enclosure one
to High Court's letter
dated 3rd August 1888,
No. 1946.

E. 2
P.W. 861

J. 3395
of 88

No.

Notification.

2235

Under the provisions of Section 5 of the Madras Civil Courts' Act, — III of 1873, the High Court directs that the Court of the District Munsif of Tekkali in the Ganjam District, now located at Tekkali, be, on and after the 1st January 1889, transferred to Sompetta in the Ganjam District and styled the Court of the District Munsif of Sompetta.

By the Court.

Acting Registrar,
Appellate Side.

X6 17

Exd. W

Enclosure ~~Two~~ Two
to High Court's letter
dated 3d August 1888,
No. 1946.

E. 1
P.W. 8613/88

2673W

No. 1946. High Court of Judicature,
Madras, 3rd August 1888.

CURRENT No 3395 / 1P

From
F. M. Horsfall Esquire,
Acting Registrar of the
High Court of Judicature
at Madras.

2235

To
J. F. Price Esquire,
Acting Chief Secretary
to Government,
Fort Saint George.

Sir,

In G. O., Judicial Department, No. 2593, dated 14th November 1887, reviewing the Report of the High Court on the Administration of Civil Justice for 1886, the Government remarked (para. 11):– "Perhaps the most unequal District (as regards the work of the District Munsifs) is Ganjam, where there are but four Munsifs, and the Aska institutions numbered 1094 O. S. and 864 S. C. against only 408 and 348 at Chicacole."

+not comm'd to P.W.D

2. The High Court have accordingly

-ingly put themselves in communication with the Judge and Collector of Ganjam with a view to remedying these inequalities, and have in the result, under Secs: 5 and 11 of the Civil Courts' Act, decided on rearranging the District in the manner described in the accompanying two notifications.

3. As regards the question of the location of the District Munsifi between the Berhampore and Chicacole Munsifis, Tekkali has had to be abandoned as, under the arrangements proposed, the town of Tekkali will fall within the Chicacole jurisdiction. The choice lay between Sompetta, Mandasa and Palasa, and the High Court on full consideration have fixed on Sompetta as presenting on the whole the most advantages with the fewest disadvantages.

4. The new arrangements, it will be observed, are to come into force from the 1st January next. A rented building will be available for temporary occupation by the Sompetta Munsif; and the High Court request that Government will take early steps to have a District Munsif's Court built at Sompetta instead of at Tekkali (See G. O. of 16th January 1884, No. 137W.)

I have the honor to be,
Sir,
Your most obedient servant,

Acting Registrar,
Appellate Side.

2235

Ed. Wenkataramiahdu

[10]

Jud. DEPARTMENT.

Office Note in
No 3375 of 188

SUBJECT. E.4 / P.W. 8613

For

CURRENT NO. 3601

Public Works Department
Ootacamund 18th August 1888

No. 547 D. 2235

CHIEF SECRETARY 18 AUG 88 GOVERNMENT OF MADRAS

Memorandum.

In reply to Office Note from the Chief Secretary dated 10th August 1888, the undersigned has the honor to state that the proposed District Munsiff's Court-House at Tekkali, Ganjam District, has not yet been commenced, an estimate for the building not having yet been received.

J. Hasted
Colonel R.E.
Secretary to Govt. P.W.D.

21 2d

To
The Chief Secretary

Judicial Dept

CURRENT No 3601

From
The P. W. D.

E-3
P.W. 8617/8

No 549 D.

D/ 18 } August /88
Ry. " }

Stating that the proposed District Munsiff's Court house at Tekkali has not yet been commenced.

See inside on C. No 3395

2235

8613

RENT NO. 75

2593 – 16 – 11 – 87
Pi 137W – 16 – 1 – 84.
Mi 1182 – 23 – 5 – 88
Mi 1130 – 15 – 5
Pi 1028 – 21 – 4

SECRETARY TO GOVERNMENT
24 AUG.
P.W. DEPARTMENT, MADRAS.

547 D d/ 18. 8. 88
1649 W d/ 6. 6. 88

24 aug 3P

approved & transferred to the P.W.D.
(by order)
A. G. Cardew.
Ag. Under Secy

Fr 2nd cl.

Note

The P.W. Office Note states that the estimate for the Tekkali Ct. called for in G.O. 16 Jan 84 No. 137 W. has not yet been recd.!

B.E.P.
C. Wilkes !

4P Communicated to the Supdg. Engr. I Circle who will submit an estimate for a District Munsif's Court house at Sompetta, instead of at Tekkali as called for in G.O. 137 W d/ 16 Jany 1884

15 11/29/18

Fdl.

S.E. I Circle 27/8/88
Judl Dept

O.S. 129/VIII/88 M. 27.8.88

Judicial {1888} Department.

No.

FROM

THE Ag. REGISTRAR OF THE HIGH COURT
OF JUDICATURE AT MADRAS,
APPELLATE SIDE

CHIEF SECRETARIAT
6 AUG 88
GOVERNMENT OF MADRAS

Dated 3d August } 1888.
Received 6th

Ry 29 – 8 – 88
Enclos 4

No. 1946
Encls. 2.

Rearranging the jurisdiction of the District Munsifs in the Ganjam District and requesting that early steps may be taken for the construction of a Munsif's Court at Sompetta instead of at Tekkali.

for the order

2235

23 24

Govt. of {1888} Madras.

PUBLIC WORKS.

Dated

Recd. Encl.

G.O. 29th Augt 1888, No. 2673 W

District Munsiff's Court-house at Sompetta

Communicating to the Superintending Engineer I Circle endorsement of the Judicial Department approving of the proposed construction of a — Ganjam Dt. instead of at Tekkali and requesting submission of the required estimate.

---

[25]

Judicial Department.

CHIEF SECRETARIAT, MADRAS.

2235

PROCEEDINGS OF THE MADRAS GOVERNMENT.

READ the following paper

From the Registrar of the High Court, Appellate side, dated 4th October 1888, No. 2529

Comd. Adverting to G.O. dated 12th September 1888, No. 1945, Judicial, I am directed to forward to you copies of letter dated 13th idem No. 2363, from the District Judge of Ganjam and of the High Court Proceedings thereon, and to request that the Government may be pleased to expedite the construction of the District Munsif's Court-house at Sompeta.

Order:- 22d October 1888, No. 2183

Communicated to the P.W. Department with the request that the construction of the Court-house at Sompeta may be, as far as possible, expedited.

(True Extract)

A. G. Cardew

Ag Undersecretary

SECRETARY TO GOVERNMENT, 24 OCT. 88, P.W. DEPARTMENT, MADRAS.

To,

The P.W. Dept ✓

— High Court.

~~24~~ 25

Copy of Letter from the District Judge, Ganjam, to the Registrar of the High Court of Judicature, Appellate side, dated 13th September 1888, No. 2363.

With reference to para 4 of the Proceedings of the High Court dated the 3rd August 1888, No. 1947, I have the honor to state that the draft notification is correct.

With reference to para 2, I have the honour to enquire whether in case a suitable building cannot be obtained at Sompeta in time to locate the Court in it by the 1st of January 1889, the Court may remain at Tekkali though it is outside the limits of the Sompeta Munsifi till accommodation can be provided at Sompeta.

I ask this as I have been informed that the house recommended by the sub-Magistrate at Sompeta does not contain any room large enough for a Court-room and as the owner the Zemindar of Jalantra only offers a lease for 1 year within which time the new Court-house cannot be built.

I would also like to know whether the High Court would sanction the erection of a temporary building at Sompeta and the location of the Court therein while the new Court house is being erected.

I have the honour to request that the following papers may be returned for reference.

1. The sketch map referred to in para 12 of this Court's letter, dated 23rd February 1888, No. 491.

2. Letter from the 2nd Class Magistrate of Sompeta dated 23rd April 1888, No. 229, with a rough sketch of the house therein referred to.

3. Letter from the District Munsif of Tekkali, dated 27th April 1888.

4. Plan of the Palasa old Court-house.

Forwarded with this Court's letter, dated 28th April 1888, No. 1270.

Copy of Proceedings of the High Court of Judicature at Madras, dated 4th October 1888, No 2528.

Read letter dated 13th September 1888, No 2363, from the District Judge of Ganjam, requesting to know whether the District Munsif's Court of Tekkali may remain at Tekkali in case a suitable building cannot be obtained at Sompeta in time to locate the Court in it.

(Here enter H.C: No 5192 of 1888) 2235

The District Judge is informed that the transfer of the Tekkali Court to Sompeta from January 1st 1889 has been finally sanctioned and that the Government has approved of the arrangements proposed. The Notification will now be published in the Gazettes.

2/. The District Munsif cannot continue after January 1st to hold his Court at Tekkali which will be outside his jurisdiction.

3/. The District Judge should have verified the sub. Magistrate's report as to the house which is available before making his final proposals. The house must be taken for one year and the District Munsif's Court must go into it from January 1st. If it is wanted for a longer time in consequence of the new Court not being ready, the Collector can be requested to represent to the Zemindar the inconvenience which would be caused to Government by turning out the Court and request him to allow its occupation for a short time longer.

4/. The house is no doubt not so large as is desirable, but the District Munsif must put up with it till a new Court can be built. The Government will be requested to expedite the building.

[0]

Govt. of (188) Madras.

B No 3422 W of 26 Oct 88

Communicated in continuation of G.O. No. 2673 W. of 29 August 1888 to the Supdg. Engr. I Circle, who will expedite the submission of the estimate already called for, in view to the inclusion of the work in the Provincial Budget for 1889-90.

Communicated in Continuation of G.O. No. 2673 W. of 29 August 1888 to the Supdg. Engr. I Circle who will expedite the submission of the estimate already called for, in view to the inclusion of the work in the Provincial Budget for 1889-90.

25.10.88

25/10/88

W
26/10

S. E. I Circle

S. E. I Circle

Judl. Deptt

Judl Dept

Ecc 29/10

4th

To

The P.W.D.

Rec 24/10/88

Proceedings, dated 22/10/ 1888.

No. 2183

Subject.

No. 3422 W. of 26 Oct 88

Reg. the construction of the Dt. Munsiff's Court house at Sompeta

---

Judicial Department.

CHIEF SECRETARIAT MADRAS

2235

PROCEEDINGS OF THE MADRAS GOVERNMENT.

Read the following paper

From the Registrar of the High Court of Judicature, Appellate side, Madras dated 15th October 1888 No. 2614.

In continuation of my letter dated 4th instant No. 2529, I am directed to state that the High Court has permitted the District Judge of Ganjam to take a lease of the house at Sompeta for the Munsif's Court-house for three years (which is the utmost the owner will let it for) from the 1st January next; and to request that the construction of a new Court-house may be taken in hand without delay as it must be ready by the 1st January 1892.

Order thereon 31st October 1888 No. 2250

Communicated to the Public Works Department in continuation of G.O. dated 22d October 1888 No. 2183.

(True Extract)

A. G. Cardew.

Ag Under Secretary

To

The Public Works Department. ~~28~~ 29

$\frac{2}{x^4}$ S.D

P.W.C. No 11240

No 3532 W. I/6 Nov 1888

B

[6] Govt. of (188) Madras.

Communicated to the Supdt. Engineer I Circle in continuation of G.O. 3422 W. of 26 October 1888, the estimate called for in which and in previous orders should be expedited.

To

The P.W. Dept

Proceedings, dated 31 Octr 1888

No. 2250

SECRETARY TO GOVERNMENT, P.W. DEPARTMENT, MADRAS. -3 NOV.

Subject.

Re the location of the Dt. Mu. Court at Sompeta, Ganjam

M.C.W. 3.11.88

3/11/88

S.E. I Circle. √ Desptd 6/11

S.E. I Circle

with order

No. 1784. 2235

High Court of Judicature,
Madras, 22nd July 1889

From

T. M. Horsfall, Esquire,
Registrar of the High Court
of Judicature, Appellate Side,
Madras.

To

The Honorable J. F. Price,
Chief Secretary to Government,
Fort Saint George

2235 Sir,

I am directed to forward for the sanction of Government the accompanying plan and estimates amounting in the aggregate to Rs. 12,360 for the construction of the District Munsif's Court-house at Sompet in the District of Ganjam.

I have the honor to be,
Sir,
Your most obedient servant,

Registrar

7031

From,

Major D. Mc. Neel Campbell R.E.
Superintending Engineer,
First Circle.

To,

The District Judge Print
Ganjam District.

2235

Dowlaishweram, 12th May 1889.

Encs: 7.
1. Estimate for Court house.
1. Do. for Latrine.
1. Do for compound wall.
2. General Abstracts.
1. Site plan.
1. Plan of foundations.

Sir,

With reference to G. O. No. 2673 W. dated the 29/8/88, I have the honor to submit herewith estimates amounting in the aggregate to Rs 12,360 for constructing a District Munsiff's Court house at Sompett in the Ganjam District and to request that you will be so good as to obtain the sanction of Government to the same.

2. The estimates have been prepared agreeably to the Standard design sanctioned in G. O. No. 1098 W d/21-4-87 and the only deviations from it are -

(1) The substitution of Sal for Teakwood.

(2) Rough stone in Chunam for brick work, the former deviation is due to the scarcity of Teak wood in the District and the latter to the request contained in your letter No. 629 of the 6th February 1889 to the Executive Engineer.

3. The following plans accompany the Estimates.
1. Site plan
1. Plan of foundation.

I have &c

(Signed) D. Mc. N. Campbell Major R.E.
Supt. Engineer 1st Circle

(True Copy)

G. A. Johnston
Ag. District Judge.

32 33

GR
HC

p 1940 – 12 – 9 – [illegible]
p 2183 – 22 – 10 – [illegible]
p 2250 – 31 – 10 – [illegible]
p 1001 – 10 – 11 – [illegible]

3 P

Judicial {1889} Department.

(1)

No. CHIEF SECRETARIAT 24 JUL 89 GOVERNMENT OF MADRAS

FROM

THE REGISTRAR OF THE HIGH COURT OF JUDICATURE AT MADRAS, APPELLATE SIDE.

E 18 (+2 plans)

Dated 22d July } 1889.
Received 2-8-89

No. 1784
Enc 5. 8.

Submitting for sanction plans and estimates for the construction of the Dist. Munsif's Court-house at Sompet, Ganjam district.

Hw 29 July.

Approved & transferred to the P.W.D.

A. G. Cardew,
Under Secy

29 July.

Se. Bus. 3582 W of 6-11-88
" " 3422 W of 26-10-88
" A 2673 W of 29-8-88
Memo No. 5147 B of 18-8-88
Pr. Bus 137 W a/ 10-1-84
" " " 1098 W of 21-4-87

0/11/8

0/857/8

Public Works Department.

Current No. 7163 2235 W

Letter No. Nil.

Dated 29th July 1889

From the Judicial Depts.—

Sanction [illegible]

2235

2235 W

B/

NOTE OF REMARKS.

The Estimate under review, amounting to Rs 12,360, provides for the construction of a Dist: Munsiff's Court House at Sompet in the Ganjam District and is divided as follows.

Main Building	Rs	10,450
Latrine	"	510
Compound Wall	"	1,400
Total	Rs	12,360

The building is to be constructed in accordance with the type design approved in G.O. No 1098 W of 21-4-87 with the exceptions of Salwood being substituted for Teakwood and rough stone for facing the building where

3 A
35
34

to be used are the same as those provided in the type Est:-

The following rates are in excess of the rates given in the Schedule for the Berhampore Sub Dn in the Ganjam Division -

1 Earthwork - Rs 3-.-. per 1000 c.ft against Rs 2-4-.- -
2 Concrete, broken stone in Chunam Rs 11-8-. per 100 c.ft against Rs 9-.-.
3 Painting, 3 coats of [illegible] Paint Rs 4/- per 100 Sq ft against Rs 3/-

The Est: would have lowered by Rs 275 if the rates in force had been used, but it is probable the high rates are due to the famine in Ganjam and [illegible] may be accepted -

The following lump sum provisions are made in the Est:-

Shed for materials	Rs 25
Clearing site	" 25
Scaffolding	" 40
Land Compensation	" 155

The plinth area of the building is 4,970 sq feet and will cost Rs 2-1-7 per sq. foot -

Contingencies and Petty Supervision are provided for at 5 per cent each -

The plans and Estimate have been countersigned by the Dist. Judge and are approved in the Judicial Deptt:-

5/8/89

2235

Ro 2235 W

BKR
Clarke

PUBLIC WORKS DEPARTMENT.

PROCEEDINGS OF THE MADRAS GOVERNMENT.

UNDER date the 16th August 1889

READ the following

2235

From the Registrar of the High Court of Judicature at Madras, Appelate side — No. 1784 d/ 22d July 1889. —

Endorsement thereon in the Judicial Department. — d/: 30 July 1889. —

LP

The estimate amounting to Rs 12,060 for the construction of a District Munsiff's Court at Sompet in the Ganjam District is sanctioned.

2. A sum of Rs 9,000 has been provided for the work in the current year's Provincial Budget.

3. This sanction has been registered as Provincial No. 57 W of 1889-90 and classified as Civil Buildings, Original Works.

13 Aug.

To
The Supt. Engineer I Circle with 15 Enclosures
" Examr. P. W. Accounts with duplicate general abstract estimate
" Judicial Department.

9.8.89

36
37

12.8.89

① V

P
10/10/189

7
15.0

Ag. 57/8. Hm. 12/8.

0/10/8

5

2235

~~37~~ 38

Govt. of 18 Madras.

PUBLIC WORKS.

Dated 17/8/8 5-30

Recd. Encl.

G.O., 16 Augt 1889 No. 2235W

District Munsiff's Court at Sompet, Ganjam District, sanctioned

90/6

B7

9 17/8 - 17/8