

- (1) பக்கங்களின் எண்ணிக்கை 8
 (2) புதுக்கித் திருப்பிய நாள் 3/90
 (3) ஆதாரங்குறிப்பவர் சுருக்கொப்பம் 10/9

தமிழ்நாடு ஆவணக் காப்பகம்.

தமிழ்நாடு அரசு

P. W. D. துறை

அரசாணை எண். மு. கோப்புத் தாள் எண்.	2902	அச்சகம் பலவகை
நாள் :	16-10-1889	198

மடிக்கவோ கண்டபடி கையாளவோ கூடாது

4. Sheets

ஆவண. கா-1-18,006-15-6-87.

செ.பி.பி.

106 N.S.W.

No. 420
E.W.

2982
Supg. Engrs office, 4th Circle
Palghat 30th Sept 1889

From

Col. H. M. Vibart R.E.

Supg. Engineer, 4th Circle

To

The Chief Engineer

P.W. Department.

Sir,

Enclosures 2
1 Estimate
with abstract
1 Tracing

I have the honor to forward
for sanction of Government, a plan
and estimate amounting to Rs. 370
for constructing a Night Latrine
for servants of Government House
at Cotacamund.

2. The estimate has been prepared
at the request of the Military Secretary
to His Excellency the Governor, who
suggests that the cost of the work be
met from the sub head Item A 17 to
the large estimate for Government
House sanctioned in G.O. No. 24,591 of
3rd September 1883.

3.

I have the honor to be

Your Most Obedt Servt

Supg. Engineer 4th fire.

18

2202

2

From
The Supg. Engineer
4th Circle

J.W. No. 9270

Dated 30th Septer/89
Desd 2nd October/89

2384-561 of 29.8.85

2683 W of 25.9.85

279.80 W of 1.2.89

2459 W of 3.9.83

1915 W of 9.7.83



Recd 4.10.89

No. 2902 W of October 16, 1889

Enc. 3
2

Consd. a night latrine
for servants of Govern-
ment House Co. taramund

Forwards for sanction
of Government a plan &
estimate amounting to
Rs. 370 for—

Public Works Department.

Current No. 9270

Letter No. 420

Dated 30th Septer/89

From the S. E. IVth Circle

To S. E. IVth Circle, point
out that the work is not
included in the bill with C. H. S.

NOTE OF REMARKS.

The plan & estimate
under review amounting
to Rs 370 provide for
constructing a night
latrine for servants of
Government House, Co. taramund.

The estimate has been
prepared at the request
of the Military Secretary
to H. E. the Governor.

The particulars of
construction are as follows—

Floor, around posts &
under cistern are to be
of brick concrete in
chunam. Seats & cistern
walls are to be of country
bricks in chunam.

Floor,

Floor, Cistern walls all sides
are to be plastered with Portland
Cement 2 coats & tressed.

The roof, walls & cisterns
are to be of corrugated
iron & painted with 2
coats of Carson's lead paint.

The roof timbers are to be
of Bentuck & the scantlings
are correct.

The rates are fair.

The total area of the building
is 94 Sft or cost \$3-15-
per Sft.

The estimate has been
counter signed by the Military
Secretary to H. E. the
Governor.

M.

7.10.89.

Note. This is not one of
the works mentioned in
Circular No 8748. C.

B/2

No 2902W

PUBLIC WORKS DEPARTMENT

2902

PROCEEDINGS OF THE MADRAS GOVERNMENT

October 16, 1889

Read the following

From the Superintending
Engineer IV Circle.

No 420 Est of 30th Sept 1889.

The estimate
amounting to Rs 370,
for constructing a night
latrine for ~~the~~ servants
of Government House,
Ootacamund, is sanctioned
against the savings on
Item No 17 of the general
estimate for the Government
House sanctioned in G.O.
No 2459 W dated 3rd Sept
1883.

1480
13 Oct
2. It is observed
that the present estimate
was not included in the
list of works appended
to letter from the Supt of
Engineers IV Circle No 444 Est,
dated 16th September 1889.

3. This sanction
has been registered as
Provincial

222
~~222~~

Provincial No 74 W
of 1889-90, and classified
as Civil Buildings,
Original Works.

10.10.89
10.10.89

7th 16-10-89
No 2902 W of Oct. 16, 1889

(18)

To
The Suptg Engr. IV Civil W.
with 2 copies
Examined P. W. Accounts
with the abstract of funds for the 1st 12 months
of the year 1888-89
H. E. the Governor.

Recd
17-11-89

Cs
11.11.89
R.H.