

(1) பக்கங்களின் எண்ணிக்கை 12

(2) புதுக்கித் திருப்பிய நாள் 1/90

(3) ஆதாரங்குறிப்பவர் சுருக்கொப்பம் 10/90

தமிழ்நாடு ஆவணக் காப்பகம்.

தமிழ்நாடு அரசு

P. W. D துறை

5

அரசாணை எண். 8
மு. கோப்புத் தாள் எண்.

அச்சகம்
பலவகை

நாள் : 5-1-1891 198

மடிக்கவோ கண்டபடி கையாளவோ கூடாது

6 Sheets

ஆவண, கா-1-18,006-15-6-87.

Q. B.

8
5TH JANUARY 1891, No. 8 W., PUBLIC WORKS.

GOVERNMENT OF MADRAS.
PUBLIC WORKS DEPARTMENT.

Buildings and Roads.
Civil Works.

READ—the following paper:—

From Colonel H. SMALLEY, R.E., Superintending Engineer, III Circle, to the Chief Engineer, Public Works Department (through the Collector of Cuddapah), dated Bellary, 20th October 1890, No. 2129.

I have the honor to forward, for the sanction of Government, a comparative statement and revised estimate, amounting to Rs. 23,150, for constructing a Taluk Cutcherry at Badvel, in the Cuddapah district, in lieu of the original estimate of Rs. 21,330 sanctioned in G.O., No. 2236 W., dated 21st July 1888.

2. The building has been completed with the exception of the well, and the excesses on the following items have been explained in the comparative statement:—

1. Teakwood wrought and put up including iron for trusses.
2. Doors and windows of several kinds.
3. Glass shutters to record-room.
4. Cut stone work.
5. Store shed.
6. Culvert.
7. Well.

Forwarded.

(Signed) K. V. LAKSHMANA RAO,
for Collector.

ORDER—dated 5th January 1891, No. 8 W., Public Works.

The revised estimate, amounting to Rs. 23,150, for constructing a Taluk office at Badvel, in the Cuddapah district, is sanctioned in supersession of the estimate of Rs. 21,330 sanctioned in G.O., No. 2236 W., dated 21st July 1888.

2. This sanction has been registered as Provincial No. 91 W. of 1890-91, and classified as Civil Buildings, Original Works.

(True Extract.)

Major, R.E.,
Under-Secy. to Govt., P.W.D.

To the Superintending Engineer, III Circle, with five enclosures.
" Examiner, Public Works Accounts.
" Revenue Department.

Exd. J. Moses.
Spare Copies

BUILDINGS AND ROADS.
CIVIL WORKS.

Govt. of {1891} Madras.
PUBLIC WORKS.

Dated January, 5th.

Recd.

Encl.

G.O., 5th Jan. 1891, No. 8 W.

JANUARY.

Taluk Office

Revised estimate of Rs. 23,150 for constructing a — at Badvel in the Cuddapah district, sanctioned.

No. 2129

Superintending Engineer's Office,
3RD CIRCLE,

Bellary 20 October 1890.

FROM,

Col W. Smalley, R.E.

SUPERINTENDING ENGINEER,

IIIrd CIRCLE.

To,

THE Chief Engineer

P. W. Deptt

Sir,

through the Taluk Office, Cuddapah.

Enclosures. 5

1 Comparative statement.

1 Plan of well.

1 Detail of Abutment

for do -

1 Data list.

Forwarded

Memorandum

for Collection

I have the honor to forward for the sanction of Government a comparative statement and revised estimate amounting to Rs 23,150 for constructing a Taluk butcherry at Badvel in the Cuddapah district in lieu of the original estimate of Rs 21,330 sanctioned in G. O. No 2236 W dated 21st July 1888.

2. The building has been completed with the exception of the well and the excesses on the following items have been explained in the comparative statement.

1. Teakwood brought & put up including iron for trusses.
2. Doors & windows of several kinds.
3. Glass shutters to record room.
4. Cut stone work.
5. Store shed.
6. Bulwark.
7. Well.

I have the honor to be
Your most obed^t servant

W. Smalley, Col. R.E.

Suptg Engineer 3rd Circle

From
The Supt Engineer
3872

From,
The Superintending Engineer,
IIIrd Circle,
Bellary

To,
The _____

28 OCT 90
GODDAPAH

The Chief Engineer
P.W. Dept

Dated _____
Received _____ 18

Enclosures.
No. _____
Subject. _____

Date 20/9
Recd 1/10
Encls 5
Hudrais
October 1890

No 2129
Salary Cutcherry
at Budvail Cuddapah
District.

Forwarding for sanction
a revised estimate for
No 23150 for constructing
a L

Public Works Department.

Current No. 11721
Letter No. 2129
Dated 20th October 1890
From the Supt. Engr. III Circle
Sanction 11.12.90

NOTE OF REMARKS.

The revised estimate
under review amounting
to Rs 23,150 for constructing
a first class tele. office
at Budvail in the
Cuddapah District
is submitted for
sanction in pursuance
of the estimate of
Rs 21,330 sanctioned
in G.O. No 2236 M
of 21st July 1888.

The excess with Rs 82
is principally due
to the following items
being increased.

(4) Teak wood 3
r put up. Excess Rs 12.
The quantity & cost
provided in the

original Estimate
were found to be
insufficient and
the timber had to be
obtained from the
S.M. Store -

(6) Wrought iron grates
doors - Excess Rs 152 -
The above remark
applying to the woodwork
in this item & the
rate had to be increased
from Rs 1-12- to Rs 2-2-
per Sq. foot -

(15) Cut Stonework - Excess
Rs 262 due to the
basement being topped
with stone & the quantity
thereby increased.

(18, 19, 20, 21, 22) Woodwork
in doors & windows &
appurtenant Excess Rs 335
The remarks against
item (4) is applicable
in this case also -

4 has doors & windows
for the resort room -
Excess Rs 200 - Omitted
in the original Est.

(23) Wrought iron work
on trusses - Excess Rs 131 -
Obtained from M. Watch.

Spouts & Stone Slabs - Excess
Rs 35 - Omitted in original
Estimate

(34) Prisoner Dock - Excess
Rs 85 - Omitted in the
original Est. -

(39) Store Shed - Excess
Rs 250 - It is explained
that it was found
necessary to construct
a shed for the storage
of articles received
from Madras -

Labour at Gateway -
Excess Rs 78 - Omitted
in the original
Estimate -

4
Well - The amount
provided in the
original Est. for
this item was Rs 412
as it was assumed
the soil was of an
ordinary kind, but
it has been subsequently
found to be gravel
& rocks, and the
estimate for this

work has accordingly
been increased to
Rs 1859 or by Rs 1447.

The comparative
Statement shows
other minor excesses
& also savings effected
in the items of the
original estimate.

It is stated that
the building has
been completed
with the exception
of the wall.

The estimate has
been countersigned
by the Collector
but apparently
it has not been
passed by the
Revenue Dept.:-

Cm
11.11.90

No. 8 W of 5th Jan'y 1891. B.P.R.
Civil Works
PUBLIC WORKS DEPARTMENT.

PROCEEDINGS OF THE MADRAS GOVERNMENT.

8

Read the following

From the ^{Joint} S. & E. Circle No 2129, of 20th Oct 90

The revised
estimate amounting
to Rs 23,150 for
constructing a Taluk
office at Badvel in
the Cuddapah Dh. is
sanctioned in supers-
session of the estimate
of Rs 21,350 sanctioned
in G.O. No 2236 W, dated
21st July 1888.

This sanction
has been registered
as No 91 W of
1890-91 & classified
as Civil Buildings,
Original Works.

16.12.90

17/12

S. & E. Circle
with 5 enclos
Ex: P. W. Accts.
Revenue Dept.

Cm

The Honorable the Secy

T. C. Cull
B. 5. 1. 91

The Secy to the
Revenue Dept
of the County of

R. S.
H. 16. 11. 90
H. 18. 11. 90
R. 5. 1. 91

8

(J)

3

6

11721.

Govt. of Madras.

PUBLIC WORKS.

Dated

6

Recd.

Encl.

G.O. 5th Jan 1891 No 810.

Survey Office

Revised estimate
of Rs 23150 for constg.
a — at Badvel in
the Cuddapah Dist.
Sanctioned.

82
14

30
Secy. 2/6/11