(1) பக்கங்களின் எண்ணிக்கை 18

(2) புதுக்கித் திருப்பிய நாள் 25.10.90

(3) ஆதாரங்குறிப்பவர் சுருக்கொப்பம்

தமிழ்நாடு ஆவணக் காப்பகம்.

தமிழ்நாடு அரசு

PWD துறை

48

அரசாணை எண். — மு. கோப்புத் தாள் எண். 2985

அச்சகம் பலவகை

நாள் : 10-11-1891

198 .

மடிக்கவோ கண்டபடி கையாளவோ கூடாது

9 Sheets

ஆவண. கா-1—18,006—15-6-87.

(b)

10th November 1891, No. 2985 W., Public Works.

2985/1

GOVERNMENT OF MADRAS.

PUBLIC WORKS DEPARTMENT.

Buildings and Roads.
Civil Works.

Read—the following paper:—

From Colonel H. SMALLEY, R.E., Superintending Engineer, III Circle, to the Inspector-General of Registration, dated Bellary, 14th August 1891, No. 1317.

With reference to G.O., No. 1242 W., dated 4th May 1891, I have the honour to forward, for obtaining sanction of Government, an estimate, amounting to Rs. 3,170, for constructing a Sub-Registrar's office at Badvél prepared as per standard design circulated with G.O., No. 2230 W., dated 21st July 1888.

No. 4898 G.

Submitted for the sanction of Government.

2. The necessity for the construction of an office for the Sub-Registrar of Badvél, in the Cuddapah district, was brought to the notice of Government in my letter No. 761 G., dated 7th April 1891, and approved in its order, dated 21st idem, No. 760, Judicial.

3. The building appears from the plan to face the west, but the District Registrar suggests that it should face the north and I agree with him.

17th October 1891. (Signed) S. SRINIVASA RAGHAVAIYANGAR,
Inspector-General of Registration.

Approved and transferred to the Public Works Department, the attention of which is invited to the Inspector-General's remarks.

(By Order.)

27th October 1891. (Signed) A. BUTTERWORTH,
Ag. Under-Secretary.

Note by the Chief Engineer, Public Works Department.

The estimate amounting to Rs. 3,170, for the construction of a Sub-Registrar's office at Badvél, in the Cuddapah district, is submitted for the sanction of Government with the following remarks.

2. The site plan should be amended so that the building may face north instead of west as at present shown.

(Signed) J. PENNYCUICK, Colonel, R.E.,
Chief Engineer, P.W.D.

ORDER—dated 10th November 1891, No. 2985 W., Public Works.

The estimate, amounting to Rs. 3,170, for constructing a Sub-Registrar's office at Badvél, in the Cuddapah district, is sanctioned.

2. Attention is drawn to the note by the Chief Engineer, Public Works Department, above recorded.

3. The necessary allotment of funds for the work will be made on application by the Superintending Engineer.

4. This sanction has been registered as Provincial No. 86 W. of 1891-92, and classified as Civil Buildings, Original Works.

(True Extract.)

(Signed) J. PENNYCUICK, Colonel, R.E.,
Secretary to Govt., P.W.D.

To the Superintending Engineer, III Circle, with six enclosures.
" Examiner, Public Works Accounts.
" Judicial Department.

Exd. C. M. Brisson.
Spare Copies

2985/2

BUILDINGS AND ROADS.
CIVIL WORKS.

Govt. of {1891} Madras.

PUBLIC WORKS.

Dated November, 10th.

Recd. *Encl.*

G.O., 10th Nov. 1891, No. 2985 W.

NOVEMBER.

Sub-Registrar's office

Estimate of Rs. 3,170, for constructing a — at Badvél, in the Cuddapah district, sanctioned with remarks.

No.1317. Superintending Engin
3d Circle, Bellary, 14th August

2285/3

From,

Col. H. Smalley R.E.
Superintending Engineer
3d Circle.

To,

The Inspector General of Registration
Madras.

Enclosures (6)
1 Site plan
1 Report
1 Specification
1 Data
1 Detailed Estimate
1 abstract — do —

Sir,

With reference to G.O. No.1242 W. dated 4th May 1891, I have the honor to forward for obtaining sanction of Government an Estimate amounting to Rs. 3170 for constructing a sub registrar's office at Badvel prepared as per standard design circulated with G.O. No. 2230 W. dated 21st July 1888.

I have the honor to be,
Sir,
Your most obedient Servant,
(Signed) H. Smalley Col. R.E.
Supdg. Engineer, 3d circle

G. no. 4898 - 17th October 1891
Madras.

Submitted for the sanction of Government.

2. The necessity for the construction of an office for the Sub Registrar of Badvel in the Cuddapah district was brought to the notice of Government in

G. O. No. 761 dated 7th April 1891
roved in its order dated 21st idem
o. Judicial.

The building appears from the
ion to face the west, but the district
Registrar suggests that it should
face the North and I agree with him.

Inspr. Genl. of Regn.

To,

The Chief Secretary to Government,
Fort St. George.

Exd. mtd

2985/4

Judicial (1891) Department
"Registration"

From,
The Inspector General of
Registration
Madras

To The Chief Secretary to
Government,
Fort St George

Dated 17 } October 1891
Received }

26 OCT 91

G.no. 4898.

Enclosures (Six)

No

Submitting letter from the Superintending Engineer forwarding for sanction plan & Estimate for the construction of a Sub Registrar's office at Badvel, Cuddapah district.

R. 25/10
R. 27/10

21 – u – 88 – 360 km
21 – 7 – 88 – 2230 w.P.W.
15 – 6 – 83 – 1606 J.S.R.

P. W. CURRENT No. 11366

H. M. 28

Dy 27 October 1891
Mo 26 Oct

Approved and transferred to

The Public Works Department the attention of which is invited to the Inspector-General's remarks.
(By order)

A. Butterworth
Ag. Under Secretary

23 Oct.

Enclos^d^ (Six)

Recd: 28 10. 91

No. 735 W – 17-3-86
– 1064 C – 16-3-86
– 2230 W – 21-7-88

C. 24/10
R. 27/10

---

3 P

2285/6

Note by the Chief Engr. P. W. D.

The estimate amounting to Rs. 3,170, for the construction of a sub-registrar's office at Badvel in the Cuddapah District, is submitted for the sanction of Govt. with the following remarks:-

The site plan should be amended so that the building may face north instead of west as at present shown.

2. ~~There is no necessity for the [illegible] on Stoney's patent"~~

E. W.

6.11.91

Public Works Department.

Current No. 11366 2985½

Letter No. ..

Dated 29th October 1891

From the Judicial Dept. "Registration"

2985/6

TECHNICAL NOTE.

Constructing Sub. Registrar's Office at Badvel. Cuddapah Dist.
Amount of Estimate Rs 3170

This estimate was called for in G.O. No. 1242 W dated 4th May 1891. it provides for constructing a Sub Registry Office as per type design circulated in G.O. No. 2230 W dated 21st July 1888. The above design is adopted as the office ~~is said~~ is said to contain less than 3 clerks. The Office is proposed to be located in the compound of the new Taluq Office, vide site plan accompanying the estimate.

The sub soil is stated to be hard gravel 4 ft below ground surface, hence the depth of foundations are proposed to be

Car

The site plan ould be amended hat the building may face North instead of West as at present shown.

There is no necessity for the use of such expensive punkah wheels as "Stoney's patent"

OU13
5.11.91

carried 4 feet, the lower 1'6" being of concrete.

The foundation & basement will be built of rough stone in mortar, hammer dressed and the superstructure walls of table moulded bricks in chunam, plastered with 2 coats of lime in the interior and pointed exterior. The flooring of the building will be of 18" square stone slabs set on 4" of concrete bed, except the record room which will be of 3/4" asphalte laid over a bed of concrete 4" thick. The roof will be tiled with flat and pan tiles laid on teak reepers; doors & windows will be of teakwood and of the descriptions provided in the estimate and painted with 3 coats of Carsons chocolate paint.

The scantlings of the roof timbers are correct; timbers will be painted with 3 coats of Carsons Chocolate paint.

The following rates are high when compared with the Schedule for the Hd. Quarter sub Division, Cuddapah, but in the data list submitted, it is stated that the rates are the same as that sanctioned for the Taluq Office at Badvel:

	Estimate	Schedule
Teakwood wrought & fixed.	Rs 4.9.9	4.. ..
Plastering 2 coats	4.1.6	3.10.6
Flooring with asphalte	19.12..	19.6..

The following rates cannot be checked as they are not provided in the schedule but data is furnished for some items and the others are stated to be the same rates as those sanctioned for the Badvel Taluq Office:

	Rs.
Table moulded brick in mortar	18.1..
—do— archwork —do—	22.4..
Venetian & panel doors %	1.12..
Batten doors %	1.10..
Venetian windows	1.10..
Batten windows with iron bars & glazed inner shutters	3.2..
Venetian windows with inner glazed shutters %	2.7.3
~~Glazes~~ Galvanized wi[illegible]tting	..8..
Roofing with flat & pan tiles.	15.13..
Flooring with 18" sq. stone slabs	16.9..

The other rates [illegible] provided in the estimate are fair, as far as can be checked.

The rate for Punkah 8 ft. long with Stoney's patent wheel cannot be fairly checked, the Schedule rates allow Rs 2.8.. per Rft but Govt: prohibit the purchase of such expensive a[illegible]ticles as Stoney's patent whe[illegible] G.O. No. 735 W dated [illegible] 10th [illegible]

2285/7

6

…inth area of the building is 1,005 Sq ft and the cost per superficial foot will be Rs 3-2-5. This rate seems a little too high, due chiefly to extra height of basement, proposed height 3 feet against 2 ft allowed in the standard plan.

The site plan and estimate have been countersigned by the Inspr. Genl. of Registration with the remark that the building should be made to face the north instead of the west as shown in the site plan. The Judicial dept in approving the estimate in:vite the attention of this dept. to the remarks of the Inspr. Genl. of Registration

4-XI-91

No. 2985-W d/ 10th Nov/91

PUBLIC WORKS DEPARTMENT.

PROCEEDINGS OF THE MADRAS GOVERNMENT.

READ the following

From the Inspector General of Registration G. No: 4898 d/17th October 1891
Endorsement by the Judicial Department d/27th October 1891
Note by the Chief Engineer P. W. Dd/

The estimate amounting to Rs. 3,170, for constructing a sub-registrar's office at Baduel in the Cuddapah District, is sanctioned.

2. Attention is drawn to the note by the Chief Engineer, P. W. Department above recorded.

3. The necessary allotment of funds for the work will be made on application by the Supty. Engr.

Ins 7 Nov

4. This sanction has been registered as Provincial No: 86 W of 1891-92, and classified as Civil Buildings, Original Works.

To The Supty. Engr. III Circle with 6 enclos.
" Examiner of P. W. Accts
" Judicial Department

6.11.91

6.11

7 Mos. 10-XI-91

N

6-11-91 R 10-XI-91

KW

2985/9

5

P

C No. 11366

Govt. of (1891) Madras.

PUBLIC WORKS.

10.xi. 91 No. 2985W

Sub Registrar's Office

Estimate of Rs 3,170 for constg a —— at Badvel in the Cuddapah District, sanctioned with remarks

9

10
4

J.C. 11.xi

3/11/11

2-30 PM

1-8