

(1) பக்கங்களின் எண்ணிக்கை 8

(2) புதுக்கித் திருப்பிய நாள் 9/91

(3) ஆதாரங்குறிப்பவர் கருக்கொப்பம்

தமிழ்நாடு ஆவணக் காப்பகம்.

தமிழ்நாடு அரசு

PWD துறை

184

அரசாணை எண்.

மு. கோப்புத் தாள் எண். 2401

அச்சகம்
பலவகை

நாள் : 29-8-1882 198

மடிக்கவோ கண்டபடி கையாளவோ கூடாது

4 Shas

ஆவண. கா-1-18,006-15-6-87.

L. J. Subrah



240/1

PROCEEDINGS OF THE MADRAS GOVERNMENT.

Read the following paper:—

From the Inspector General of Police,
 of 15 July 1892 N^o 4546:—

2. Plans.

1 detailed estimate

1 Abstract estimate

1 report

1 Schedule of land
to be taken up under
the Act.

I have the honor to forward, for sanction,
 the Public Works Department plans and estimates re-
 amounting to Rs 1750, for the construction of 8 huts
 at Tagalore, Tanjore District, together with a schedule
 for the acquisition of site under Act X of 1870.
 The want of lines at this station has long been
 felt.

Order, 6 August 1892 N^o 1429.

The plans and estimate are approved
 and will be transferred to the Public Works Department.

(True extract)

W. Lewis

Under Secretary to Govt P. W. D.
 For Chief Secretary.

To

The Public Works Department. (with plans & estimate.)
 Inspector General of Police.

P. W. CURRENT No. 8147

Gobt. of Madras.

To

The Public Works Dept.

Encls 6 (2 plans)

Recd: 11-8-92

Proceedings, dated 6th August 1892,
No. 1429.

Subject.

Approving & transferring to the
Public Works Dept. plans and
estimate for the construction
of 8 Police huts at Tagatire,
Tanjore district.

19/8 11-8-92

Public Works Department.

TECHNICAL NOTE.

Current No. 8147
Letter No. 1429
Dated 6th August 1892
From the Indian Dept.
Name of Work Constructing 8 Police huts at Tagatire
District Tanjore
Taluk Tiruthurai
Amount of Estimate Rs. 1950
Do. of Revised Estimate ---
G.O. sanctioning original estimate No. ---
dated ---

Difference. More ---
Less ---

PARTICULARS OF ESTIMATE.

Main Building	Rs.	1750
Subsidiary Buildings	"	---
Contingencies 5%	"	87
Petty Supervision 5%	"	88
Land compensation	"	25

Total Rs. 1950

PARTICULARS OF CONSTRUCTION.

Surface soil Sandy alluvial
Sub soil Sandy loam 3 feet below
Foundations are to be sunk 4 feet deep. The
lower 2 1/2 feet is to be of concrete & the
upper 1 1/2 feet of brick in clay
Basement is to be raised 12 inches & built of
brick in clay.
Walls raised 7.5 ft high & built of brick
in clay.

Plastering nil.
Pointing with chunam both exterior & interior
faces generally.
Flooring with the of mud.
Roofing the of pan tiles on bamboo rafters
Roof timbers are the of jangewood
Scantlings are correct
Doors and Windows are the of jangewood
batten with frames
Lightning Conductors nil.
Rates are fair

The plinth area of the main building is
square feet and the cost per square hut

without compensation for land
will be Rs. 240.10.0 which is fair.
+ with land compensation Rs 247.4.0 per hut.

The Plan and Estimate have been
countersigned by the Imp. General of Police
and approved in the Judicial Dept.

Department.

REMARKS.

This estimate has been framed at
the request of the Supt. of Police, Tan-
javur, it provides for constructing 8
Police huts as per Standard plan
approved in G.O. No. 954 dated 14th Jan.
1880 on the site marked, as per
site plan, at a cost of Rs 25.

19. VIII. 1880

B² N^o 2401. Wd/29 August 1892

PUBLIC WORKS DEPARTMENT.

PROCEEDINGS OF THE MADRAS GOVERNMENT.

Read the following

Pro. in the Judicial Dept. No: 1429 d/6th Aug. 1892

The estimate, amounting
to Rs. 1950, for constructing
8 police huts at Tagatole
in the Tanjore District,
is returned to the Suptg.
Engineer, VI circle, for
sanction and execution
when funds are
available.

Note The budget allotment
to the Megapalam Division
under Civil Building, Minor
Original Works, is only Rs. 1,000.

To
The S.E.V. circle
with 6 enclos
Judicial Dept.

✓ 2401. Wd/29 Aug 72

✓ Tho

(4)

MS 147-8
= MS 23-8
MS 25-8

2-31/8

J.C. 8/8