(1) பக்கங்களின் எண்ணிக்கை 12

(2) புதுக்கித் திருப்பிய நாள் 9/91

(3) ஆதாரங்குறிப்பவர் சுருக்கொப்பம்

தமிழ்நாடு ஆவணக் காப்பகம்.

தமிழ்நாடு அரசு

PWD துறை

(110)

அரசாணை எண்.
மு. கோப்புத் தாள் எண். 2594

~~அச்சகம்~~
~~பல்வகை~~

நாள் : 19-9-1892

~~198~~ .

மடிக்கவோ கண்டபடி கையாளவோ கூடாது

6 Sheets

ஆவண. கா-1—18,006—15-6-87.

2594/1

GOVERNMENT OF MADRAS.

PUBLIC WORKS DEPARTMENT.

Buildings and Roads.
Civil Works.

READ—the following paper:—

From Lieut.-Colonel D. McNEIL CAMPBELL, R.E., Superintending Engineer, V Circle, to the Inspector-General of Registration, dated Chepâk, 13th July 1892, No. 208 M.

In continuation of my letter, No. 195 M., dated 1st July 1892, I have the honour to forward, herewith, plan and estimate of Rs. 2,860 for constructing Sub-Registrar's office at Pápanásam for your approval and transmission to Government for sanction.

T. No. 3209.

Submitted for the sanction of Government.

2. The construction of an office building for the Sub-Registrar has been sanctioned in G.O., No. 2521, Judicial, dated 10th December 1891.

COIMBATORE, 10th August 1892.

(Signed) S. SRINIVASA RAGHAVAIYANGAR,
Inspector-General of Registration.

No. 1397.

Approved and transferred to the Public Works Department.

(By Order.)

31st August 1892.

(Signed) N. S. BRODIE,
Acting Under-Secretary.

ORDER—dated 19th September 1892, No. 2594 W., Public Works.

The estimate, amounting to Rs. 2,860, for constructing a Sub-Registrar's office at Pápanásam, in the Tanjore district, is sanctioned for execution when funds are available.

2. This sanction has been registered as Provincial No. 59 W. of 1892–93 and classified as Civil Buildings—Original Works.

(True Extract.)

Major, R.E.,
Under-Secy. to Govt., P.W.D.

To the Superintending Engineer, V Circle, with four enclosures.
" Examiner, Public Works Accounts.
" Judicial Department.

Exd. C. M. Brisson.

Spare Copies

BUILDINGS AND ROADS.
CIVIL WORKS.

Govt. of (1892) Madras.

PUBLIC WORKS.

Dated September, 19th.

Read. *Encl.*

G.O., 19th Sept. 1892, No. 2594 W.

SEPTEMBER.

Sub-Registrar's office at Papanasam

Estimate of Rs. 2,860 for constructing a —, in the Tanjore district, sanctioned for execution when funds are available.

CURRENT NO. 335

Superintending Engineer's Office,
V Circle, Madras.
Chepak, 13th July 1892.

No: 208 Dr.

From
Lieut Col. D. McNeil Campbell R.E.
Superintending Engineer, V Circle,

To
The Inspector General
of Registration,
Madras.

Sir,

In continuation of my Letter No: 195 Dr dated 1st July 1892, I have the honor to forward herewith plan and estimate of Rs 2860 for constructing Sub-registrar's office at Papanasam for your approval and sanction to Government for sanction.

I have the honor to be,
Sir,
Your most Obedient Servant
(Signed) D. McNeil Campbell Lieut. Col. RE.
Superintending Engineer. V Circle

Enclosures 4
1 site plan
1 Detail Estt.
1 Gl. abstract do
1 Report
4

———"———

T. No: 3209 10 August 1892
Coimbatore

Submitted for the sanction of Government.

2

2594
3

No. The construction of an office building for the Subregistrar has been sanctioned in G.O. Judicial dated 10th December 1891 No. 2521.

Inspector General of Registration.

To

The Chief Secretary
to Government.

Ootacamund.

Encl 5

P. W. CURRENT No. 8949

CURRENT No. 3397

Judicial (1892) Department

Registration

Gen 12-9: 252

From

The Inspector General
of Registration,
Madras

To

The Chief Secretary
to Government,
Ootacamund.

CHIEF SECRETARIAT GOVERNMENT
12 AUG 92

Dated 10 August 1892

Received 12

Regd 3-9-92

T. No: 3209

Enclosures. Four (without plan)

No:

Submitting letter from the Superintending Engineer Vcicle together with plan & estimates for a Sub. registrar's office at Papanaseam (Tanjore dt:)

2.8.18/8

no

No 2318-3rd) 20-8-92

Encl: 1397 dt 31-8-92

Rect 30 August

Approved & transferred to the Public Works Department

dt 29 aug.

(By order).

W. Brodie

Offg. Under Secretary

To the Public Works dept. with enclos.

17/8.

C. 29/8
R 31/8

Public Works Department.

TECHNICAL NOTE.

Current No. 8949

Letter No. 1397

Dated 31st August 1892

From the Judicial Dept.

Name of Work Sub Registrar Office at Papanaseam

District Tanjore.

Taluk Kumbakonam

Amount of Estimate Rupees 2860

Do. of Revised Estimate — " —

G.O. sanctioning original estimate No. — " —

dated — " —

Difference. More — " —
Less — " —

PARTICULARS OF ESTIMATE.

Main Building	Rs.	2250.
~~Subsidiary Buildings~~ Compound wall & well	"	350.
~~Contingencies~~	"	100.
~~Petty Supervision~~	"	"
Land compensation	"	160
Total Rs.		2860.

PARTICULARS OF CONSTRUCTION.

Surface soil } alluvial for a depth of 6 feet.
Sub soil }

Foundations are 4 in cmnt 4 feet deep the lowest 15 inches the bricks in cement & the upper portion of bricks in chunam.

Basement is 4 in raised 2 feet high & built of bricks in chunam.

Walls The outer walls are 4 in raised 12½ high & the cross wall 19 feet & 4 in with table moulded bricks in chunam

Plastering interior faces of walls are 1 thick with 2 coats of chunam

Pointing exterior faces of walls with chunam

Flooring 1/ thick of cement concrete laid over 3" of concrete for the office & verandah & 3/4" asphaltic over 4" of cement for the record room

Roofing is 1 thick of mangalore tiles laid on teak rafters & the main rooms ceiled with 1/2" teak battens.

Roof timbers are 1 thick of teakwood

Scantlings are correct, rafters are proposed 1 thick placed 2 1/2 feet from centre to centre.

Doors and Windows are 1 thick of teakwood & of the descriptions noted in the estimate.

Lightning Conductors nil.

Rates are fair

The plinth area of the main building is 996 square feet, and the cost per square foot will be Rs. 2-8-2.

The Plan and Estimate have been countersigned by the Inspector General of Registration and approved in the Judicial Dept

Department.

REMARKS.

This estimate is framed with reference to G.O. No. 3389 dated 16th March 1891 and it provides for constructing an office for the sub-Registrar at Papanasam in Tanjore Dist as per type design approved in G.O. No 2230 dated 21st July 1888 with the exception that the slope of the roof has been altered from 1/3 to 1/4 the span so as to suit Mangalore tiles. The rafters are placed 2'6" apart instead of 1'6" & the roof ceiled with 1/2" teak planks.

Provision is made in the estimate for a compound wall with wooden gate shutters

Shutters for sinking a well in the enclosed also compensation for land.

The dimensions of doors & windows are for interior measurements as per appending G.O. Standard specification, hence they differ for the printed estimate.

10-IX-92

PUBLIC WORKS DEPARTMENT.

No 2594 W Dated 19 September 1892

PROCEEDINGS OF THE MADRAS GOVERNMENT.

55/6

READ the following

From the Inspector Genl of Registration No 3209 d/10-8-92

Endorsement thereon in the Judicial Dept No 897 d/31-8-92

Re estimate, amounting to Rs. 2,860, for constructing a Subregistrar's office at Papanasam in the Tanjore District, is sanctioned for execution when funds are available

2. This sanction has been registered as Provincial No 59 W of 1892-93 and classified as Civil Original Works Buildings.

Do

To the S. E. Tanjore with 4 encls.

" Exam. P.W. Accts

" Judicial Dept

Cy

C No. 8949

Govt. of 1892 Madras.

PUBLIC WORKS.

2 Mar 92

Dated

Read. Encl.

G.O., 19 September No. 2594-98

Sub-Registrar's Office at Papanasam

Estimate of Rs 2,860 for constructing a —— in the Tanjore District, sanctioned for execution when funds are available

6

80
4+2=

1—4

22/9

JC 21/9