

- (1) பக்கங்களின் எண்ணிக்கை 16
 (2) புதுக்கித் திருப்பிய நாள் 10/9/
 (3) ஆதாரங்குறிப்பவர் சுருக்கொப்பம் [Signature]

தமிழ்நாடு ஆவணக் காப்பகம்.

தமிழ்நாடு அரசு

PWD துறை

(113)

அரசாணை எண். மு. கோப்புத் தாள் எண்.	<u>2598</u>	அச்சகம் பஸ்ஸைக்
நாள் :	<u>19-9-1892</u>	198.

மடிக்கவோ கண்டபடி கையாளவோ கூடாது

8 Sheet

[Signature]

2598/1

GOVERNMENT OF MADRAS.

PUBLIC WORKS DEPARTMENT.

Buildings and Roads.
Civil Works.

READ—the following papers:—

From C. J. PETERS, Esq., Officiating Superintending Engineer, III Circle,
to the Inspector-General of Registration, dated Bellary, 30th July 1892,
No. 1323.

I have the honour to forward an estimate, amounting to Rs. 2,750, for constructing Sub-Registrar's office at Ráyadrug, prepared in accordance with standard design approved in G.O., No. 2230 W., dated 21st July 1888, and to request that you will please obtain the necessary sanction of Government.

T. No. 3309.

Submitted for the sanction of Government. The necessity for an office building for the Sub-Registrar was explained in my letter recorded in G.O., dated 15th January 1892, No. 93, Judicial.

COIMBATORE, (Signed) S. SREENIVASA RAGHAVAIYANGAR,
14th August 1892. Inspector-General of Registration.
To the Chief Secretary to Government.

No. 1402.

Approved and transferred to the Public Works Department.

(By Order.)

1st September 1892.

(Signed) N. S. BRODIE,
Ag. Under-Secy. to Govt.

Note by the Chief Engineer, Public Works Department.

The dimensions of doors and windows, as provided for in the estimate, are from outside to outside of frames and not in accordance with appendix G to the standard specification. If the dimensions be taken within frames, there will be a saving of Rs. 85, as the rates allowed include apparently the value of the frames on measurements thus taken.

15th September 1892.

(Signed) J. PENNYCUICK, Colonel, R.E.,
Chief Engineer, P.W.D.

ORDER—dated 19th September 1892, No. 2598 W., Public Works.

The estimate, amounting to Rs. 2,750, for constructing a Sub-Registrar's office at Rayadug in the Bellary district, is sanctioned for execution when funds are available.

2. The attention of the Superintending Engineer, III Circle, is drawn to the note by the Chief Engineer above recorded.

3. This sanction has been registered as Provincial No. 60 W. of 1892-93 and classified as Civil Buildings, Original Works.

(True Extract.)

Major, R.E.,
Under-Secy. to Govt., P.W.D.

To the Superintending Engineer, III Circle,
with six enclosures.
" Examiner, Public Works Accounts.
" Judicial Department.

Exd. C. A. Muniswamy.
Spare Copies

2598
2

BUILDINGS AND ROADS.
CIVIL WORKS.

Gobt. of {1892} Madras.
PUBLIC WORKS.

Dated September, 19th.

Recd.

Encl.

G.O., 19th Sept. 1892, No. 2598 W.

SEPTEMBER.

Sub-Registrar's office at
Rayadurg

Estimate of Rs. 2,750 for constructing a
— in the Bellary district sanctioned for
execution when funds are available.

N: 1323.

3rd Circle
Bellary 30th July 1892.

CURRENT NO. 3488

From

to: J. Peters Esquire
offg. Suptg. Engineer
3rd Circle.

To

The Inspector General of
Registration
Madras.

Sir,

Enclosures

1. Data list
2. Detailed Estimate.
3. Abstract do.
- 1 Report
- 1 Specification
- 1 Site plan

6

I have the honor to forward an
Estimate amounting to Rs 2750 for constructing
Sub Registrar's office at Rayadurg prepared
in accordance with standard design approved
in G.O. N: 2230 W, dated 21st July 1888 and to
request that you will please obtain the
necessary sanction of Government.

I have the honor to be

Sir

Your most obedient servant

(Signed), J. Peters.

offg. Suptg. Engineer
3rd Circle.

J. N: 3309, 14th August 1892
Coimbatore.

Submitted for the sanction of Government.

The necessity for an office building for the Sub
Registrar was explained in my letter recorded in
G.O. dated 15th January 1892, N: 93. Judicial.

Shunmugam Raghunayag

To The Chief Secretary to Government Super Secy of Legn.
Pattanamund

From
The Inspector General of
Registration
Madras

To
The Chief Secretary to
Government
Coatacamund.

Est. No. 1402 of 1st September 1892
Approved and transferred to
The Public Works Department.

Dated 14th August 1892.
Received 18th August 1892.
By 5-9-92
J. A. 3309.

(By order)
W. W. B. B. B.
J. Under Secretary

Enclosures 6

To The Public Works Dept.
19/8.

Subject.

Submitting for sanction an
estimate from the Superintending
Engineer 3 Circle for the construction
of a Sub Registrar's office
at Rayachoti.

20/9/92
J. A. 3309
W. W. B. B. B.
J. Under Secretary

19/9-9-92
J. A. 3309
W. W. B. B. B.
J. Under Secretary

Note by the Chief Engineer, P. W. D.
— 98/

The dimensions of doors
and windows as provided
for in the estimate, are
from outside to outside
of frames and not in
accordance with
Appendix G to the Standard
specification. If the
dimensions be ^{taken} within frames,
there will be a saving of
Rs 85. as the rates
allowed include apparently
the value of the frames on
measurement thus taken.

15-9-92
J. A. 3309
W. W. B. B. B.
J. Under Secretary

Public Works Department.

TECHNICAL NOTE.

Current No. 9027Letter No. 1802Dated 18 September 1932From the Public Works DeptName of Work Sub Registration office at Rayachur.District BellaryTaluk Rayachur.Amount of Estimate Rs. 2750Do. of Revised Estimate —G.O. sanctioning original estimate No. —dated —Difference.

More	<u>—</u>
Less	<u>—</u>

PARTICULARS OF ESTIMATE.

Main Building	Rs.	<u>2527</u>
Subsidiary Buildings	"	<u>—</u>
Contingencies	<u>5%</u>	<u>123</u>
Petty Supervision	"	<u>100</u>
Land compensation	"	<u>—</u>

Total Rs. 2750

PARTICULARS OF CONSTRUCTION.

Surface soil } Black & red sandy loam, hard
 Sub soil } for a depth of 5-10".

Foundations are proposed to be 5 feet deep. The lower one foot to be built of concrete & the upper 4 feet of concrete rubble in chunnam.

Basement is to be raised 2 feet high & built of concrete rubble in chunnam.

Walls are to be raised 12 feet high to top of first & built with concrete rubble in chunnam.

2598W

Plastering the interior faces of walls with 2 coats
of Chumam 3 lbs. above floor & the remaining
Pointing the exterior faces with chumam
the building with 18 square stone slabs
laid out of cement & the second row with 3/4 asphalt
Roofing is the pulley frame for the main
rooms & Ranges for the verandah
Roof timbers are 5 in. of timber
Scantlings are correct (as per printed schedule)

Doors and Windows are 1/2 in. of timberwork & of the
descriptions noted in the schedule
Lightning Conductors none.

Rates a few of the rates are high but data in
support of the high rates are submitted.
The plinth area of the main building is
996 square feet, and the cost per square
foot will be Rs. 2. 13. 3.

The Plan and Estimate have been
countersigned by the Inspector General
of Registration and approved in the
Judicial Dept.
Department.

REMARKS.

This estimate was called for in
G.O. No. 222 W dated 22nd July 1892
1892 & it provides for constructing
a Sub Registrar's Office at Rayadrug
in the Bellary District, on the type
design circulated in G.O. No. 2230
W dated 2nd July 1892 for District
works.

The following rates are high when
compared with the Government Schedule

Cement	13.000	against Rs. 12.000
Concrete rubble 2 nd sort	14.800	do - 12.800
do - archwork	25.000	do - 23.000
Smearing pulley	35.000	do - 30.000
3/4 asphalt flooring	23.000	do - 20.000

Data in support of the high rates
are furnished hence they may
be passed.

The compensation for land is
provided in the estimate as the
site selected is situated on the
Govt. land.

The dimensions of doors &
windows are from outside to
outside of frames & not in
accordance with Appendix G
if the dimensions are to be with
in frames, the saving will be
Rs. 85 on the estimate.

10.1.92



PUBLIC WORKS DEPARTMENT.

PROCEEDINGS OF THE MADRAS GOVERNMENT.

Read the following

From the Inspector G. of Registration No 3309 d/14th Aug 1892
Endorsed. Thereon in the Judicial Dept. No 1402 d/1st Sept 1892
Note by the Chief Engineer, P.W. D d/15th 11 92

The estimate, amounting
to Rs. 2750, for constructing
a Sub Registrar's office
at Rayadrug in the
Bellary District, is
Sanctioned for execution
when funds are available.

2. The attention of the Suptg.
Engineer III Circle is drawn
to the Note by the Chief
Engineer above recorded
3. This sanction has been
registered as Provincial
No. 60 W of 1892-93 and
classified as Civil
Buildings, original works.

The S.E. III circle
with 6 each
Exar. P.W. Dept.
Judicial Dept.

May

2598
8

$\frac{27.00}{1}$ $\frac{1}{2}$

0
12/19

Imaging pulley - 35.000 - 00 - 30.000
1/2" asphalt flooring 23.000 - 00 - 20.000

C. No. 9027.

GOVT. OF INDIA

PUBLIC WORKS.

24/11/1902

19th September 2 25986

Sub-Registrar's Office
at Rayachur.

Estimate of Rs. 2,750 for
constructing a — in
the Bellary District,
sanctioned for execution
when funds are available

(8)

90
✓
4

Barth

7/12/19