

- (1) பக்கங்களின் எண்ணிக்கை 14
 (2) புதுக்கித் திருப்பிய நாள் 8/91
 (3) ஆதாரங்குறிப்பவர் சுருக்கொப்பம் ay

தமிழ்நாடு ஆவணக் காப்பகம்.

தமிழ்நாடு அரசு

Pw. துறை

அரசாணை எண்.	2829	அ. ப.
மு. கோப்புத் தாள் எண்.		ப. வகை
நாள் :	12.10.1892	198

மடிக்கவோ கண்டபடி கையாளவோ கூடாது

7 sheet

ஆவண. கா-1-18,006-15-6-87.

Lukfeller.

12TH OCTOBER 1892, No. 2829 W., PUBLIC WORKS.

GOVERNMENT OF MADRAS.
PUBLIC WORKS DEPARTMENT.

Buildings and Roads.
Civil Works.

READ—the following papers:—

From Colonel H. W. H. COX, Commissioner of Police, Madras, to the Chief Secretary to Government, dated Madras, 19th September 1892, No. 55.

I have the honour to submit, for sanction of Government, plan and estimate, amounting to Rs. 2,755, for improvements to the Egmore police station, and to request that orders be issued in the Public Works Department to commence the work at an early date.

No. 1536, Judicial.

Approved and transferred to the Public Works Department.

(By Order.)

28th September 1892.

(Signed) N. S. BRODIE,
Acting Under-Secretary.

Note by the Chief Engineer, Public Works Department.

It is observed that each end of the girder in the Inspector's room comes over an opening. If a girder is necessary, it should span the room the longest way and thus rest on solid supports. The span of the room being only 15', the girder may be omitted and joists 3" $\times$ 8½" used instead.

6th October 1892.

(Signed) J. PENNYCUICK, Colonel, R.E.,
Chief Engineer, P.W.D.

ORDER—dated 12th October 1892, No. 2829 W., Public Works.

The estimate, amounting to Rs. 2,755, for improvements to the police station at Egmore, Madras, is sanctioned.

2. No funds are available at present for appropriation to the work. An allotment will be made later in the year if practicable.

3. This sanction has been registered as Provincial No. 72 W. of 1892-93 and classified as Civil Buildings, Original Works.

4. Attention is directed to the note by the Chief Engineer.

(True Extract.)

To the Consulting Architect to Government, with three enclosures.
" Examiner, Public Works Accounts.
" Judicial Department.

Major, R.E.,
Under-Secy. to Govt., P.W.D.

Exd. A. D. Xavier.
Spare Copies

BUILDINGS AND ROADS.
CIVIL WORKS.

Govt. of {1892} Madras.
PUBLIC WORKS.

Dated October, 12th.

Recd.

Encl.

G.O., 12th Oct. 1892, No. 2829 W.

OCTOBER.

Police Station at Egmore,
Madras

Estimate of Rs. 2,755 for improvements
to the —, sanctioned with remarks.

No. 55.

City Police Office.

Madras, 19th September 1892.

From

Colonel H. H. Fox,
THE COMMISSIONER OF POLICE,
MADRAS.

To

The Chief Secretary to Government,
With the Governor,
Stouhouse Hill.

Sir,

I have the honor to
submit for sanction of
Government Plan and
Estimates amounting to
Rs 2755/- for improvements
to the Egmore Police Station
and to request that orders
be issued in the Public
Works Department to
commence the work at an
early date.

I have the honor to be,
Sir,
Your most obedt. Servt.

H. H. Fox,
Commissioner of Police.

4024
1. 8. 92-1086

From
The Commissioner of Police,
Madras,
To The Chief Secretary to Govt,
With the Encl.
Stores & Equip.
1. 8. 92

Encl. 28 September 1892, No. 1536
1st
27th
Approved & transferred to
The Public Works Department.
(By order)
W. Brodie
Sd/- Under Secretary.

No. 55.

Dated 19th Sept/92.
Recd: 23
Regd: 30. 9. 92
Encl: 3.4
1 plan

To The Public Works Dept.
23/9

Enure Police Station.

Submitting for
Sanction Plan and
Estimate for improvements
to the

21/9
22/9
23/9
24/9
25/9
26/9
27/9
28/9
29/9
30/9
1. 10. 92
43-9
20-9
6-10
26/9
27/9
30-10-92

From the Commissioner of Police, Madras, No. 55 of 19. 9. 1892.
Encl. thereon in the Judicial Dept. No. 1536 of 28. 9. 1892.

Note by Chief Engineer P. W. D.

It is observed that
each end of the girder in
the Inspector's room comes
over an opening. If a girder
is necessary it should span
the room the longest way
and thus rest on solid
supports. The span of the
room being only 15', the
girder may be omitted
and joists 3" x 8 1/2" used
instead.

21/9
22/9
23/9
24/9
25/9
26/9
27/9
28/9
29/9
30/9
1. 10. 92
43-9
20-9
6-10
26/9
27/9
30-10-92

W. 2829
L. H. by J. W.

His Honor said that
each end of the Prison
in the Inspector's room
comes over an
opening. If a Prison
is necessary it should
span the room the
largest way & then
rest on solid supports.
The span of the room
being only 15' the
Prison may be divided
2 parts 3" & 8 1/2" and
united.

W. 2829
6.10.29

Public Works Department.

Current No. 9839

Letter No. 1536

Dated 28 September 1892

From the Inspector's Dept.

Sanitation

TECHNICAL NOTE

Improvements to the Square Police
Station - Madras.

Amount of Estimate Rs 2,755

This estimate provides for the following
alterations & additions to the
Square Police Station.

The existing constables' room is
to be converted into 2 cells by
building a partition wall 9" thick
so as to make each room 12 1/2' x 8' 10"
& the two small front rooms & ver-
andah removed. The present
doorway leading to the constables'
room is to be built up & two iron
grated doors each 2' 9" x 6' 6" opened
one to each cell. A front room
for the Inspector 15' 0" x 17' 6" is to be
thrown out & immediately in rear
a guard room 13' 0" x 17' 6" with
side rooms for the constables &
station house officer, as per plan.

The walls are to be built of
stock bricks in chunam on a
foundation 4 feet deep. The walls
are to be plastered interior with
2 coats of chunam polished & the
exterior

exterior faces pointed with lime & sand. The floor is to be of Cuddalore chert laid on a inches of concrete & pointed with asphaltic to the roof terrace throughout with bricks on edge & supported on teakwood joists. The doors & windows are to be of teakwood. Doors paneled except the cell doors which are to be iron barred & the windows iron barred with wooden shutters outside & glazed shutters inside.

The scantlings of roof timbers cannot fairly be checked as no details are furnished but from the dimensions noted in the plan, the scantlings are correct.

The plan shows a beam with a section of 9" x 13" in the Inspectors room just over the doorways. This appears to be objectionable unless provision is made for retaining arches over the flat arches of doors but space will not permit of this, the span being only 15 ft. Joists may be provided throughout.

The rates are fair.

The plan & estimate have been countersigned by the Commissioner of Police & approved in the Judicial Dept.

[Signature]
30.11.92

"Am 6-10"

X P 2829 Wd / 12th October 1892

B. H. civil works
PUBLIC WORKS DEPARTMENT.

PROCEEDINGS OF THE MADRAS GOVERNMENT.

Read the following

From the Commissioner of Police, Madras No 55 d/19.9.92
Endorsed thereon in the Judicial Dept. No 1536 d/28.9.92
Note by the Chief Mag. P.W.D. d/6 Oct. 92

The estimate, amounting to Rs. 2,755, for improvements to the Police Station at Egmore, Madras, is sanctioned.

1. No funds are available at present for appropriation to the work. An allotment will be made later in the year, if practicable.
2. This sanction has been registered as Provincial No. 72 W of 1892-93 and classified as Civil Buildings, Original Works.
3. Attention is directed to this note by the Chief Mag. P.W.D.

The C.A. to Govt
with 3 Encl.
Exar. P.W. Accts.
Judicial Dept.

2

6.10.92

C No 9839

Govt. of (1892) Madras.

PUBLIC WORKS.

15/11/92

David

Recd.

Recd.

G.O. 12th October 1892 No 1829

Police Station at
Egmore, Madras

Estimate of Rs 2755 for
improvements to the
—, sanctioned with
remarks.

80/5

13/10

12/10