

(1) பக்கங்களின் எண்ணிக்கை

14

(2) புதுக்கித் திருப்பிய நாள்

3192

(3) ஆதாரக் குறிப்பவர் சுருக்கொப்பம்

3

தமிழ்நாடு ஆவணக் காப்பகம்.

தமிழ்நாடு அரசு

மதுரை

அரசாணை எண்.	3284 W	அச்சகம்
மு. கோப்புத் தாள் எண்.		பலவகை
நாள் :	1-12-1892	199

மடிக்கவோ கண்டபடி கையாளவோ கூடாது.

1st DECEMBER 1892, No. 3284 W., PUBLIC WORKS.

GOVERNMENT OF MADRAS.
PUBLIC WORKS DEPARTMENT.

Buildings and Roads.
Civil Works.

READ—the following paper:—

G.O., dated 9th November 1892, No. 2098, Judicial.

Read—the following letter from the Inspector-General of Registration, Madras, dated 21st October 1892, No. 4951:—

In submitting, herewith, for sanction of Government, the plans and estimates for constructing a sub-registrar's office on the standard design for smaller offices sanctioned in G.O., No. 2230 W., dated 21st July 1888, at Sattenapalle, Kistna district, I have the honour to state that the said office could not be built in the same compound as the taluk cutcherry as directed in G.O., Judicial, dated 27th August 1888, No. 1798, for want of sufficient accommodation to the east of the cutcherry; that, moreover, a special magistrate having been sanctioned for Sattenapalle, the necessary extension has to be provided for him to hold his office; that the site selected for the proposed sub-registrar's office, though situated outside the compound of the taluk cutcherry, is quite close to it and conveniently situated and that a compound wall round the proposed building being absolutely necessary, the necessary provision has been made for it in the estimate.

Order—dated 9th November 1892, No. 2098, Judicial.

The provision made for constructing a well is unnecessary as one will be constructed close at hand when the new taluk cutcherry, is built; with this exception, the estimate is approved and transferred to the Public Works Department.

(True Extract.)

(Signed) N. S. BRODIE,
Ag. Under Secretary.

ORDER—dated 1st December 1892, No. 3284 W., Public Works.

The estimate, amounting to Rs. 5,200, for constructing a sub-registrar's office at Sattenapalle in the Kistna district, is reduced to Rs. 4,530 by certain alterations shown thereon and the omission of the provision for a well which is considered unnecessary. The estimate, as thus reduced, is sanctioned for execution when funds are available.

2. This sanction has been registered as Provincial No. 79 W. of 1892-93 and classified as Civil Buildings, Original Works.

(True Extract.)

Major, E.E.,
Under-Secy. to Govt., P.W.D.

To the Superintending Engineer, II Circle, with plan and estimate.
" Examiner, Public Works Accounts.
" Judicial Department.

Exd. A. D. Xavier.
Spare Copies

BUILDINGS AND ROADS.
CIVIL WORKS.

Gobi. of {1892} Madras.
PUBLIC WORKS.

Dated December, 1st.

Recd.

Encl.

G.O., 1st Dec. 1892, No. 3284 W.

DECEMBER.

Sub-Registrar's Office at
Sattenapalle

Estimate for constructing a — in the
Kistna district sanctioned for execution
when funds are available.

N. 1292 No. Superintending Engineer's Office
II Circle, P. Coy. No. 22, Aug 1892.

To.

J. W. Martin Esq.
Superintending Engineer, II Circle

To.

The Inspector General of Registration
Madras.

Sir,

With reference to your letter
N. G. 2482 of 20. 6. 91, I have the
honor to forward herewith plans and
Estimates for constructing a sub
Registrar's office at Sattenapalle
for your approval and obtaining
the necessary sanction of Government
therein, as also to an allotment of
Rs 2,000 for expenditure during the
current year.

2. The rates entered in the
abstract Estimate are the same
as those allowed for the Taluk
Office in the same locality, the
Estimate for which was already
sanctioned.

Encls

1. Tracing
1. Report
2. Estimates

4

Have the honor to be,

Br.

Yours most obedt servant,
/ signed / J. W. Martin.
Superintending Engineer
U. S. Circle.

Stimulus Newspaper
Luzerne Co. Pa.

[25]



PROCEEDINGS OF THE MADRAS GOVERNMENT.

READ the following paper :—

Amritsar
Order, 19th November 1892. No 2098. Judicial.

The provision made for constructing a well is unnecessary as one will be constructed close at hand when the new Taluk Cutchery is built, with this exception, the estimate is approved and transferred to the Public Works Department.

[True Extract]

W. B. D. C.

Asy. Under Secretary.

To

The Public Works Department (with plan & estimate)
" Inspector General of Registrations.

Govt. of Madras.

To

The Public Works Dept.

Encls. 4 (Plans)

Recd. 17.11.92

Proceedings, dated 9 Nov 1892
No. 2098

Subject.

Approving the plans
and Estimate for Sub
Regis. office at Sattenapalli
Kistna Dist.

No. 2703 Wd/12-10-87 ✓
 " 1696 Wd - 8-6-88 ✓
 " 2251 Wd - 24-7-88 ✓
 " 2879 Wd - 4-9-88 ✓
 " 3199 Wd - 10-10-88 ✓
 " 3440 Wd - 30-10-88 ✓
 " 3634 Wd - 16-11-88 ✓

T.
 Include least
 Meeting with C.E.
 P.W.
 Wd/12

End sheeting has now been
 included (1/8" thick & 18 inches wide)
 The cost of this is Rs 36 more.
 The estimate altered from Rs 5200
 to Rs 5030. This includes deduction in
 the cost of sheeting.

Sanction - Meeting
 No provision for a
 work.

PWB

21.11.92

Current No. 11439

Letter No. 2098

Dated 9th November 1892

From the Public Works Dept.

TECHNICAL NOTE.

Name of Work Constructing Sub-Registration
Office at Sattenapalli, Krishna Dist.

Amount of Estimate, Rs. 5200

PARTICULARS OF ESTIMATE.

Main Building	Rs. 5010
Compound wall & gate	140
Subsidiary Buildings - Store shed	40
Culvert over side drain	300
Contingencies	50
Petty Supervision	20
Land compensation	200
Wall - 6' dia.	500

Total Rupees 4990

PARTICULARS OF CONSTRUCTION.

Surface soil } Granular
 Sub soil }
 Foundations are to be made 3 feet deep
 in two footings of 18" each & built
 of rough stone in Channarayana
 Basement is to be raised 2 feet high &
 built of rough stone in Channarayana
 Walls are to be raised as per type
 design & built of rough stone in
 Channarayana with brick arches over
 door windows

Plastering or Pointing The walls are to be plastered
interior & painted exterior with chunam
Flooring is to be 2" kuper stones laid on 4" of
concrete throughout except for the record
room which is to be asphalted 3/4" thick & cement
Roofing is to be of flat & pan tiles laid over
truss system, rafters etc.

Doors and Windows are to be of teakwood & of the
description noted in the estimate.

Roof timbers are to be of teakwood.

Scantlings are correct as per printed estimate.

Rates are high. They are stated to be similar
to the rates sanctioned for the Taluk Office at
Sattenapatti, hence no data sheet is submitted.

The plinth area of the main building is
196 square feet, and the cost per square
foot will be Rs. 3.0.4.

The plans and estimates have been countersigned
by the Inspector General of Registration
and approved in the Judicial Dept.
Department, with the remark that the provision
for sinking a well is unnecessary.

REMARKS.

This estimate provides for construct-
ing a Sub-Registrar's office at Sattenapatti
in the Kistna Dist. as per type design
appended in G.O. No. 2230 in dated 20th
July 1892 (Tiled roof) also for erecting
a compound wall for a length of 300 feet
with the wooden gate shutters, culvert on
each side, sinking a well 6 feet
in dia. & for compensation for land.

The compound wall is stated to be
absolutely necessary, but the provision
of a well has been disallowed by G.O.
in the Judicial Dept. as it is proposed
to sink a well near by where the
Taluk Office is built.

The area of doors & windows provided
in the estimate are for internal

diminution from outside to on
of frames & not in accordance
appending G.O. standard spec.
No provision is made for heat-
ing under valleys, ~~which~~ ^{this} ~~is~~ ^{is}
to be absolutely necessary.

The amount of the estimate has
been altered from Rs. 5,200 to Rs.
owing to an error in the item of
roofing. The area of roofing shown
is 1,348 sq. against 2,455 sq. per
in the estimate, the correction in
the printed estimate & amount
is noted in G.O. No. 2015 in dated 29th
1891. By omitting the cost of
sinking a well in Rs. 500 the
estimate amount requiring
will be Rs. 4,490.

The Sub-Registrar's office is
constructed outside the Taluk
boundary as per site plan.

19-11

PUBLIC WORKS DEPARTMENT.

PROCEEDINGS OF THE MADRAS GOVERNMENT.

Read the following

Pro. in the Judicial Dept. No. 2098 of 9th November 1892

3 Pro.

The estimate, amounting
to Rs. 5,200, for Constructing a
Sub-Registrar's office at
Sattenapatti in the Kistna
District, is reduced to
Rs. 4,530 by certain altera-
tions shown thereon and
the omission of the provision
for a well which is con-
sidered unnecessary. The
estimate, as thus reduced,
is sanctioned for execution
when funds are available.

2. This sanction has been
registered as Provincial
No. 79 of 1892-93 and

Classified as Civil
Buildings, Original Works.
The S.E. Circle with plan & estimate
Esar. P.W. accts.
Judicial Dept.

C No 11439

Govt. of Madras.
PUBLIC WORKS.

1/12/92

G.O. 1st December 1892 No. 3284 E

Sub-Registrar's Office
at Sattenapalle

Estimate for constructing
a — in the Krishna D.,
Sanctioned for execution
when funds are available

70
—
4

9/1/12

8/1/12