

(1) பக்கங்களின் எண்ணிக்கை 12

(2) புதுக்கித் திருப்பிய நாள் 8/92

(3) ஆதாரங் குறிப்பவர் சுருக்கொப்பம்

தமிழ்நாடு ஆவணக் காப்பகம்.

தமிழ்நாடு அரசு

துறை

அரசாணை எண்.

மு. கோப்புத் தாள் எண்.

அச்சகம்

பலவகை

நாள் :

3.12.1892

199

மடிக்கவோ கண்டபடி கையாளவோ கூடாது.

ஆவண. கா. 1-18,006-6-9-90.

GOVERNMENT OF MADRAS.
PUBLIC WORKS DEPARTMENT.

Buildings and Roads.
Civil Works.

READ—the following paper:—

From H. M. WINTERBOTHAM, Esq., President, District Board, Tanjore, to the Chief Secretary to Government (through the Chief Engineer, Public Works Department), dated Vallam, 9th November 1892, No. 189.

Under section 36 of the Local Fund rules sanctioned in G.O., No. 721 L.F., dated 26th June 1886, I have the honour to submit, for the sanction of Government, an estimate (with 13 enclosures as per margin) for Rs. 12,600 for improving and metalling the road from Arantangi to Pudukota limits, for which a provision of Rs. 2,000 has been made in the current year's budget (*vide* item 5, Communications, Statement III-A.).

- 1 detailed estimate for earthwork.
- 1 do. for gravel collection.
- 1 data for gravel collection.
- 1 abstract for masonry works.
- 1 detailed for do.
- 1 report.
- 1 specification.
- 1 sketch.
- 4 sheets survey longitudinal and cross sections.
- 1 sheet masonry plans.

13 (with an abstract estimate).

2. The necessity for the work has been explained in para. 27 of my budget report (for 1892-93) embodied in G.O., No. 749 L., dated 25th March 1892. The estimate has been scrutinized by the Superintending Engineer, V Circle, and approved of by the District Board in its Resolution No. 20, dated 29th October 1892 (*vide* copy enclosed).

ORDER—dated 3rd December 1892, No. 3325 W., Public Works.

The estimate, amounting to Rs. 12,600, for improving and gravelling the road from Arantangi to Pudukota in the Tanjore district, is sanctioned.

2. This sanction has been registered as Local No. 26 W. of 1892-93.

(True Extract.)

Major, R.E.,
Under-Secy. to Govt., P.W.D.

To the Superintending Engineer, V Circle.
Local and Municipal Department, with plans and estimates.

Exd. A. D. Xavier.
Spare Copies

BUILDINGS AND ROADS.
CIVIL WORKS.

Govt. of {1892} Madras.
PUBLIC WORKS.

Dated December, 3rd.

Recd.

Encl.

G.O., 3rd Dec. 1892, No. 3325 W.

DECEMBER.

Road from Arantangi
to Pudukota

Estimate of Rs. 12,600 for improving
and gravelling the — in the Tanjore dis-
trict, sanctioned.

Local Fund Department.

Tanjore District Board Office.

Camp, Vallam 9 November 1892.

No.

From

H. M. Winterbottom ESQUIRE,

PRESIDENT DISTRICT BOARD,
TANJORE.

To

THE HONORABLE MR. J. J. Price,
CHIEF SECRETARY TO GOVERNMENT,

LOCAL AND MUNICIPAL DEPARTMENT,

Through the Chief Engineer,
P. W. Department, MADRAS.

Sir,

Under section 36 of the Local
Fund Rules sanctioned in G.O.
No. 721 L.D., dated 26th June 1886,
I have the honor to submit for
the sanction of Government an
estimate (with 13 enclosures as

per margin) for
Rs 12,600 for im-
proving and
mettalling the
road from
Arantangi to Pudukota limits
for which a provision of Rs 2,000
has

- 1. Detailed estimate for earth work.
- 2. Do for gravel collection.
- 1. Data for Do Do.
- 1. Abstract for masonry works.
- 1. Detailed for Do Do.
- 1. Report.
- 1. Specification.
- 1. Sketch.
- 4. Sheets survey longitudinal and cross sections.
- 1. Sheet masonry plans.
- 13. (with an abstract estimate).

has been made in the current
year's Budget (vide Item 5,
communications, statement IIIA)

2. The necessity for the work
has been explained in para
27 of my Budget report (for
1892-93) embodied in G.O. No
749L, dated 25th March 1892.

The estimate has been ser-
viced by the Superintending
Engineer Vth circle and approved
of by the District Board in
its resolution No 20, dated
29th August October 1892. (vide
copy enclosed)

I have the honor to be

sir,

Your most obedient servant

President

W

L

3325

1892.

Local Fund Department.

From

The President District Board

TANJORE.

To

The Chief Secretary to Government

Local and Municipal Department

Through the Chief of P.W.D. Madras
P.W.D. Department
Madras.

Dated

Despatched

Received //

9 November 1892

No. 189

ENCLOSURES.

14 (5 Plans)

Subject.

Submitting for sanction an estimate for Rs 12,600 for improving and metalling the road from Arantangi to Pudukota limits

No 152 SW 418-5-92

Public Works Department.

Current No.

11243

Letter No.

189

Dated

9 November 1892

From the

President District Board, Tanjore.

Sanctioned

Technical Note.

Improving & metalling the road from Arantangi to Pudukota limits in Tanjore Dist.

Amount of Estimate Rs 12,600

The existing road is shown to be a mere earth track running through dry waste land in hard red soil. It is therefore proposed to raise this road, on the levels noted on the tracing plans submitted.

The top width of the proposed road is to be 8 feet with side slopes $1\frac{1}{2}$ to 1. The earth for the formation of the road is to be obtained by digging side channels 2 ft wide at bottom & with side slopes $1\frac{1}{2}$ to 1. The road is to be gravelled throughout to a width of 12 feet with 6 inches of good hard gravel & consolidated to a hard surface.

Provision is made for 14 tunnels of varying spans from $1\frac{1}{2}$ ft to 4 feet and

Sanctioned

and for 5 road drains varying
in length from 40 to 60 feet, to dis-
charge the surface drainage

The amount of the estimate is
made up as follows:-

Earthwork	Rs 2604
Graveling & consolidating	5676
14 masonry tunnels	1730
5 Road drains	1620
Compensation for land	400
Contingencies @ 5%	570
Water Rates	12600

The rates cannot be checked
but data in support of graveling
&c. are submitted. The rates
for printing & plastering are slightly
in excess of the Divisional rates
but if schedule rates be applied
the saving will only be Rs 25

The length of the proposed road
is 7 miles 5 furlongs & 30 feet & the
cost per mile of roadway, includ-
ing masonry works, will be Rs 1600.

The estimate has been examined
and approved by the President & approved
in Dist. Board proceedings dated
29th Oct 1892.

[Signature]
23.11.92

N^o 3325-V of 3rd December 1892

PROCEEDINGS OF THE MADRAS GOVERNMENT.

Read the following

Print From the President, District Board, Tanjore. N^o 189d/9.11.92

The estimate, amounting
to Rs. 12,600, for improving
and graveling the road
from Arantangi to Pudukotah
in the Tanjore District, is
sanctioned.

2. This sanction has been
registered as local N^o.
26 W of 1892-93

[Signature]

5013
29.11.92

To
The S.E. V Circle
" L. & M. Dept.
with plans & estimates

[Signature]

HW

41 DEC 2

3725
6

LB King

T. L.

To

The Honorable Mr. [unclear]
[unclear] a [unclear]
for [unclear] of [unclear]

cs. 30/11.

4/12 R 3/12.

C No 11243

Govt. of Madras.
PUBLIC WORKS.

Dated

Recd.

Encl.

6/7/92
6/

G.O. 3rd December 1892, No. 3325 R

Road from Arantangi
to Padukotah.

Estimate of Rs 12,600 for
improving and gravelling
the _____ in the Tanjore Dt.,
sanctioned

76
3

9th 5/12

8th 5/12