

- (1) பக்கங்களின் எண்ணிக்கை 16
 (2) புதுக்கித் திருப்பிய நாள் 5/9/2
 (3) ஆதரவ் குறிப்பவர் சுருக்கொப்பம் 3

தமிழ்நாடு ஆவணக் காப்பகம்.

தமிழ்நாடு அரசு

R. V. V. துறை

அரசாணை எண். மு. கோப்புத் தாள் எண் <u>3841</u>	அச்சகம் பலவகை
<u>இலக்கணத்தினை</u>	
நாள்: <u>24. 12. 1892</u>	199

மடிக்கவோ தண்டபடி கையாளவோ கூடாது.



ஆவண. கா. 1-18,006-6-9-90.

24TH DECEMBER 1892, No. 3541 W., PUBLIC WORKS.

GOVERNMENT OF MADRAS.
PUBLIC WORKS DEPARTMENT.

Buildings and Roads.
Civil Works.

READ—the following paper:—

From Lieut.-Colonel A. C. SMITH, R.E., Superintending Engineer, VI Circle,
to the Inspector-General of Registration, Madras, dated Trichinopoly, 25th
October 1892, No. 694 T.N.

With reference to G.O., No. 3283 W., dated 7th December 1891, I have the
honour to forward, for your approval and submission to Government for sanction, an
estimate, amounting to Rs. 4,850, for constructing a Sub-Registrar's office with tiled
roof at Koilpati, Tinnevely district, prepared on the standard design for larger
offices, approved in G.O., dated 13th May 1891, No. 1320 W.

2. The site plan enclosed has been approved by the Collector and the District
Registrar. Provisions of Rs. 370 for compensation for the land and Rs. 550 for the
compound wall and culvert are made in the estimate.

3. All other details are given in the report attached to the estimate.

4. The work is included in the Provincial Service budget for the year 1893-94
sent up by me to Government.

T. No. 5354 (a).

Submitted for the sanction of Government.

2. The necessity for the construction of a building for the Sub-Registry office at
Koilpati was brought to the notice of Government in this office letter, dated 13th
November 1891, G. No. 5402, recorded in G.O., dated 2nd December 1891, No. 2460,
Judicial.

SHOLINGHUR,
24th November 1892.

(Signed) S. HARI ROW,
Ag. Inspector-General of Registration.

To the Chief Secretary to Government.

No. 1975, Judicial.

Approved and transferred to the Public Works Department.

(By Order.)

(Signed) A. BUTTERWORTH,
Ag. Under-Secretary.

12th December 1892.

ORDER—dated 24th December 1892, No. 3541 W., Public Works.

The estimate, amounting to Rs. 4,350, for constructing a Sub-Registrar's office at Koilpati in the Tinnevely district, is reduced to Rs. 4,330 by omitting the provision made for padlocks, which, not being fixtures, will not be supplied by the Public Works Department. The estimate, as thus reduced, is sanctioned for execution when funds are available.

2. It is observed that, while it is stated in the report accompanying the estimate that the *inside* measurements of doors and windows have been taken, the dimensions given in the detailed estimate for those items include the frames.

3. This sanction has been registered as Provincial No. 89 W. of 1892-93 and classified as Civil Buildings, Original Works.

(True Extract.)

Major, R.E.,
Under-Secy. to Govt., P.W.D.

To the Superintending Engineer, VI Circle, with plans and estimates.
" Examiner, Public Works Accounts.
" Judicial Department.

Exd. A. D. Xavier.
Spare Copies

No. 694 T.W.

Trichinopoly

Dated 25 October 1892

From

Lt. Col. A. C. Smith R.E.,
Superintending Engineer, 6th Circle,

Trichinopoly.

To

The Inspector General
of Registration,

Madras.

Sir, With reference to G.O. No. 3283 W d/7th December 1891, I have the honor to forward for your approval and submission to Government for sanction, an estimate amounting to Rupees 4,350 for constructing a Sub-Registrar's office with tiled roof at Koilpaty, Tinnevely District, prepared on the standard design for larger offices, approved in G.O. dated 13 May/91 No. 1320 W.

2. The site plan enclosed has been approved by the Collector and the District Registrar. Provisions of Rs. 370 for compensation for the land and Rs. 550 for the compound wall and culvert are made in the estimate.

3.

All other details are given in the report

Encl. 3
Estimate with report
Tracing of site plan
do - of culvert
and compound wall

report attached to the estimate.

4. The work is included in
the Provincial Service Budget for the year
1893-94 sent up by me to Government.

I have the honor to be,

Sir,

Your most Obedient Servant

(Signed) A. C. Smith Lt. Col. R.E.

Supg: Engineer, V Circle.

T. No. 5354 (a) dt 24 November 1892

Sholinghur

Submitted for the sanction of
Government.

2. The necessity for the construction of
a building for the Subregional office at
Koilpatti was brought to the notice of Govern-
ment in this office letter dated 13th Novem-
ber 1891, G. No. 5402, recorded in G. O dated
2nd December 1891 No. 2400 Judicial.

S. H. S. M. S.
Ag. Insp. Genl. of Regn.

To The Chief Secretary to Government,
Fort St. George
E. India

BUILDINGS AND ROADS.
CIVIL WORKS.

Govt. of {1892} Madras.
PUBLIC WORKS.

Dated December, 24th.

Recd.

Encl.

G.O., 24th Dec. 1892, No. 3541 W.

DECEMBER.

Sub-Registrar's Office at
Koilpati

Estimate reduced to Rs. 4,330 for constructing a — in the Tinnevely district, sanctioned.

No. 3541 W/24 Dec 1892

PUBLIC WORKS DEPARTMENT.

PROCEEDINGS OF THE MADRAS GOVERNMENT.

Read the following

From the S. E. VI circle No. 694 J. W/25 Oct
Endorsed by the Inspector G. & Registrar No. 5354 (a)
Endorsed thereon in the Judicial Dept. No. 7975 d/12 Dec 1892

The estimate, amounting to Rs. 4,350, for constructing a Sub-registrar's office at Koilpati in the Tinnevely Dist. is reduced to Rs. 4,330 by omitting the provision made for padlocks which, not being fixtures, will not be supplied by the P. W. Dept.

H/1
23 Dec

The estimate, as thus reduced, is sanctioned for execution when funds are available.

2. It is observed that while it is stated that in the report accompanying the estimate that the inside measurements of doors and windows have been taken, the dimensions given in the details

detailed estimate for
those items include the
frames.

3. This sanction has been
registered as Provincial
S. No. 1892-93 and
as Civil
original works.

for 22/3/92

well
n. n. n.

for 22/3/92

The Suptg. Engr. VI Circle
with plan (9)
" Exar. P. V. Accts.
" Judicial Dept.

Public Works Department

Current No. 12,327
Letter No. 1975
Dated 12 December 1892
From the Judicial Dept.

TECHNICAL NOTE.

Name of Work Constructing a Sub-Registration
Office at Kailpatti, Tinnamully Dist.

Amount of Estimate, Rs. 4350

PARTICULARS OF ESTIMATE.

Main Building	Office	Rs. 3430
Subsidiary Buildings	Chamber	60
Compensation wall		490
Contingencies	5% Rs. 191	191
Petty Supervision	5% Rs. 192	192
Land compensation		370

Total Rupees 4350.

PARTICULARS OF CONSTRUCTION.

Surface soil ground
Sub soil Kumbhar one foot & 2 inches below
Foundations are 4 feet deep. The lower
18 inches the concrete & the upper
2 1/2 feet the brick with rough stone
in chunnam
Basement is the raised 2 feet & built
with curved rubble in chunnam
Walls are the raised 13 feet high, as per
type design & built with curved
masonry in chunnam except the
verandah pillars, partition wall
& the gables which are the built
with brick in chunnam.

Plastering or Pointing The walls are to be plastered

both interior & exterior with chunnam

Flooring is to be of concrete & cement plaster

except for the record room which is
to be of concrete & $\frac{3}{4}$ " asphalt.

Roofing is to be tiled with flat & pane tiles

laid over lime resins & supported
by teakwood rafters.

Doors and Windows are to be of teakwood & of the

descriptions noted in the estimate &
painted with 2 coats of Silicate paint.

Roof timbers are to be of teakwood & wood dried.

Scantlings are correct, as per printed estimate

Rates a few of the rates are high vide remarks
here.

The plinth area of the main building is

1274 square feet, and the cost per square
foot will be Rs. 2. 10. 10.

The plans and estimates have been countersigned

by the Inspector General of Registration
and approved in the Judicial Department.

REMARKS.

This estimate has been framed with
reference to G.O. No. 3283 dated 7th
December 1891. It provides for the
construction of a Sub-Registration Office at
Koilpatta in the Tinnamully District on the
type design circulated with G.O. No. 1300
dated 13th May 1891 for larger accom-
modation (tiled roofing). Provision
is also made in the estimate for erect-
ing a compound wall & for a masonry
cutwater.

The site selected is on private land
for which compensation to the extent of
Rs. 375 has been provided in the estimate.

The walls are chiefly built with
concrete rubble in chunnam owing to
the bricks being expensive as they
have to be raised in from immediately

The following rates are high

Brickwork 18.000 against 26.000

Archwork 20.000 do. 27.000

Flooring with asphalt 19.000 do. 28.000

- do. with concrete & 12.400 do. 17.000

Cement plaster 17.000 do. 18.000

Roofing with pane tiles 17.000 do. 18.000

data for the first 3 items are only

submitted & not for flooring &

roofing. If schedule rates be

applied for flooring with concrete

plaster & with cement &

for roofing the saving will be Rs.

50-

Provision is made to supply

2 brass pad locks of Hindigul

pattern at a cost of Rs. 10 each.

This item appears to be objection-

able, as they do not come in:

the fixture they should be

purchased by the office con-

cerned under their contingent

expenditure. If the locks & doors

are necessary, Rines or mortice

locks may be fitted to the doors

which will then come under

fixtures.

In the report accompanying

the estimate mention is

made as to the dimensions

of the doors being within frame

they are not the case, the

dimensions noted in the

the estimate is from outside
to outside of frames.

[Signature]

19-XII-92

Past racks, not being
six lines, should
not be supplied by
this Dept., and the
cost of 2 brass
pandracks will
therefore be
omitted from the
estimate -

It is stated in
the report accompanying
the bill that the
inside measurements
of doors & windows
have been taken -

The dimensions given
in the detailed estimates
for doors & windows
include the frames.

Lambert

[Signature]

20-XI-92

12327
CURRENT NO.

Judicial (1892) Department

"Registration"

328310-17-12-91
1920-11-12-91
From 1920-11-12-91

The Inspector General
of Registration,
Madras.

To The Chief Secretary
to Government,
Fort St. George

Dated 24 Nov. }
Dept. 2 December } 1892
Received 13 Dec

T. No. 5354 (a)

Enclosures Three (10)
No.

Submitting for sanction plan
estimates for a Subregistration
Office Building at Kailpatti,
Tinnevely Dt.

11288: 16.6.87^{SC}
1118: 10.6.91^{mic}
2460: 2.12.91
1184: 2.11.92^{SC}

H. M. 9/12 Dec 1892 to 1975
M. S. S.

Approved and transferred to
the Public Works Department.

S. S. S.

(By order)
A. S. S.
Chief Secretary

To the Public Works Dept.
with enclos.

1/11

No 13205 d/13-5-91
32835 - 7-12-91

C. 10/12
R. 12/12

14-11-92

8

C No 12327

Govt. of Madras.

PUBLIC WORKS.

24/12/92

No. 24 December 2 No. 3541-W

Sub-Registrar's Office at
Koilpati

Estimate reduced to Rs. 330
for constructing a
in the Tirunelveli Dist.,
sanctioned.

80/5
80/5

J.C. 24/12