(1) பக்கங்களின் எண்ணிக்கை 14

(2) புதுக்கித் திருப்பிய நாள் நவம்பர் 91-91

(3) ஆதாரங்குறிப்பவர் சுருக்கொப்பம்

# தமிழ்நாடு ஆவணக் காப்பகம்.

தமிழ்நாடு அரசு

பொது துறை

| | |
|---|---|
| அரசாணை எண். —<br>மு. கோப்புத் தாள் எண். 1179 | அச்சகம்<br>பலவகை |
| நாள் : 28-4-1883 | 198- |

மடிக்கவோ கண்டபடி கையாளவோ கூடாது

ஆவண. கா-1—18,006—15-6-87.

GOVERNMENT OF MADRAS.

PUBLIC WORKS DEPARTMENT.

11787/1

**Buildings and Roads.**
**Civil Works.**

READ—the following paper :—

G.O., dated 14th March 1893, Mis. No. 1039, Revenue.

*Read*—the following Proceedings of the Board of Revenue (Land Revenue), dated 18th January 1893, Mis. No. 297 :—

Read—the following letter from the Superintending Engineer, IV Circle, to the Collector of Coimbatore, dated 16th December 1892, No. 433 M. :—

With reference to your letter, Mis. No. 1652, dated 10th October 1892, to the address of the Executive Engineer, Coimbatore division, I have the honour to forward, for transmission to Government, for sanction and provision of funds an estimate, amounting to Rs. 37,650, for constructing a first-class taluk cutcherry at Kollegal.

2. Provision has been made in the estimate for a cook-room, latrine, compound wall with a wooden gate, and sinking a well in the compound.

---

Endorsement by the Collector, dated 21st December 1892, Ref. on Mis. No. 2066.

Submitted.

2. In my letter recorded with G.O., dated 1st August 1891, No. 2076 W., I recommended the construction of a combined office for the Deputy Collector and Tahsildar ; but as I find it will be much more expensive than I anticipated, I think it will be sufficient to build a new taluk cutcherry. The existing Munsif's Court with a few additions will suffice for the Deputy Collector.

---

Resolution—dated 18th January 1893, Mis. No. 297.

The plan and estimate for Rs. 37,650 for constructing a first-class taluk cutcherry with out-houses at Kollegal are submitted for the sanction of Government and for the provision of funds in the Public Works budget with reference to G.O., dated 26th August 1891, No. 828 R.

2. In view of the remarks now made by the Collector with which the Board concurs, the construction of a combined office for the Deputy Collector and Tahsildar at Kollegal, approved in G.O., dated 10th July 1891, No. 3938, Revenue, becomes unnecessary.

---

*Order*—dated 14th March 1893, Mis. No. 1039, Revenue.

The Government considers that a barbed wire fence should be substituted for the proposed compound wall. Subject to this alteration the plan and estimates are approved and will be transferred to the Public Works Department for the necessary action.

(True Extract.)

(Signed) E. GIBSON,
Ag. Secretary to Government.

Order—dated 28th April 1893, No. 1179 W., Public Works.

The estimate, amounting to Rs. 37,650, for constructing a first-class taluk office at Kollegal in the Coimbatore district, is reduced to Rs. 33,140 by omitting the provision for a compound wall. The estimate as thus reduced is sanctioned for execution when funds are available.

2. The Superintending Engineer, IV Circle, will submit a supplemental estimate for a barbed wire fence.

3. This sanction has been registered as Provincial No. 11 W. of 1893–94 and classified as Civil Buildings, Original Works.

(True Extract.)

Major, R.E.,
Under-Secy. to Govt., P.W.D.

To the Superintending Engineer, IV Circle, with plans and estimate.
" Examiner of Public Works Accounts.
" Revenue Department.
Editors' Table.

Exd. C. A. Munisawmy.
Spare Copies

BUILDINGS AND ROADS.
CIVIL WORKS.

# Govt. of {1893} Madras.

## PUBLIC WORKS.

*Dated April, 28th.*

*Read.* *Encl.*

**G.O., 28th April 1893, No. 1179 W.**

**APRIL.**

---

**Taluk Office at Kollegal,**
**Coimbatore District**

Estimate of Rs. 33,140 for constructing a first-class —, sanctioned, and the Superintending Engineer, IV Circle, directed to submit a supplemental estimate for a barbed wire fence.

1179/3

DEPARTMENT.

## PROCEEDINGS OF THE MADRAS GOVERNMENT.

Read the following proceedings of the Board of Revenue (Land Revenue) d/ 18 January 1893 No 297 Mis. on the following letter from the Superintending Engineer IV Circle to the Collector of Coimbatore d/ 16 December 1892 No 433 M:—

Enclosures 5
2 Plans
1 Estimate
1 Abstract
1 Report

With reference to your letter No 1652 Mis d/ 10 October 1892 to the address of the Executive Engineer Coimbatore Division, I have the honor to forward for transmission to Government for sanction and provision of funds an Estimate amounting to Rs 37,650 for constructing a first Taluk cutcherry at Kollegal.

2 Provision has been made in the Estimate for a Cook room, Latrine, Compound Wall with a Wooden Gate, and Sinking a well in the Compound.

(2) Abstract Endorsement of the Collector thereon d/ 21 December 1892, Ref: on No 2066 Mis:—

Submitted.

2 In my letter recorded with G.O. d/ 1 August 1891 No 2076 W, I recommended the construction of a combined Office for the Deputy Collector and Tahsildar, but as I find it will be much more Expensive than I anticipated, I think it will be sufficient to build a new Taluk Cutcherry. The Existing Munsiff's Court with a few additions will suffice for the Deputy Collector.

---

Order Resolution:— dated 1st January 1894 No 197.

The plan and Estimate for Rs 37,650 for constructing a first Class Taluk Cutchery with out houses at Kollegal are

Submitted

submitted for the sanction of Government & for the provision of funds in the Public Works budget with reference to G.O. d/ 26. August 1891, No 828 R.

2. In view of the remarks now made by the Collector with which the Board concurs, the construction of a combined Office for the Deputy Collector and Tahsildar at Kollegal approved in G.O. d/ 10. July 1891 No 3938 Revenue, becomes unnecessary.

returned.

2076 W 8
1.8.91

Order dated 14. March 1893 No 1039. Revenue

The Government considers that a barbed wire fence should be substituted for the proposed Compound Wall. Subject to this alteration the plan & estimate are approved & will be transferred to the Public Works Department for the necessary action.

(True Extract)

G. Gibbons
Offg. Secretary to Govt.

To

The Public Works Dept.
with 4 Enclosures
a Commr. of Land Revenue

P. W. CURRENT No. 2555

Govt. of {1893} Madras.

REVENUE.

To

The Public Works Depte

No. 1167 W dy 19-4-90
" 4120 C - 16-9-89
" 2076 W - 1-8-91
" 1088 W - 4-4-92

Dated

Recd. 16-3-93

Encl. 5 (2 plans)

Mis. G.O., 14 March 1893, No. 1039.

SUBJECT.

Approving & transferring to the P. W. D. for the necessary action plan & estimates for constructing a First class Taluk Cutcherry at Kollegal Coimbatore Dt with certain alteration.

103

0/14/4 - 28-4-93

D-5

1179/5

Sanction - Nothing to comprised with a Cutcherry at Kollegal for a sum of Rs. 37,650 - Nine years.

Public Works Department.

Current No. 2555

Letter No. 1039

Dated 14th March 1893

From the Revenue Depte.

TECHNICAL NOTE.

Name of Work Constructing a First Class Taluk Office with subordinate at Kollegal, Coimbatore Dist.

Amount of Estimate, Rs. 37,650

PARTICULARS OF ESTIMATE.

| | | | |
|---|---|---|---|
| Main Building | Office | Rs. | 27347 |
| Record racks & ladder | | " | 460 |
| Subsidiary Buildings | Cycle room | " | 482 |
| | Public latrine | " | 603 |
| Sinking a well | | " | 450 |
| Contingencies | 5% | " | 1752 |
| Petty Supervision | 2½% | " | 859 |
| Land compensation | | " | 500 |
| Gate & compound wall | | " | (4197) |
| Total Rupees ... | | | 37650 / 33140 |

PARTICULARS OF CONSTRUCTION.

Surface soil red earth

Sub soil hard red ground

Foundations are 4 in the centre 3 feet deep & built of coked concrete throughout

Basement is 4 in the rear 2 feet high & built of table moulded bricks in chunam

Walls are 4 in the rear as per heights noted on the upper drawing & built of table moulded bricks in chunam with flat & cumbrambam arches over doors & windows.

Plastering or Pointing The interior faces of walls are two plastered with 2 coats of Chunam & the exterior faces pointed with tar & asphaltic.

Flooring in Two of 8" Cuppam bricks laid over 6 inches of Concrete & pointed with Portland cement except for the Jail wards & record room which are to be asphalted 3/4" thick on 6" of concrete

Roofing in Two of mangalore tiles laid over teak rafters & ceiled with 1/2" teak planks

Doors and Windows are Two of the description noted in the estimate of teakwood & painted with 3 coats of Silicate paint

Roof timbers are Two of teakwood for the trusses & posts & jungle wood for rafters &c

Scantlings are correct

Rates In few of the rates are in excess of the Divisional schedule.

The plinth area of the main building is 10747 square feet, and the cost per square foot will be Rs. 3-13-4.

The plans and estimates have been countersigned by the Collector Coimbatore District and approved in the Revenue Dept with the exception that a barbed wire fence should be substituted for the proposed compound wall.

Remarks

An estimate for a combined office both for the Deputy Collector & Tahsildar was called for in G.O. No. 2076 R dated 1st August 1892.

The Supdg Engineer IV Circle in submitting a special design for the work to the Collector of Coimbatore stated that the cost of constructing the same would be Rs 50000 The Collector considers this sum an expensive one for the combined office & recommends the construction of only a Taluq office.

The estimate under review provides for constructing a First Class Taluq office as per type design circulated with G.O. No. 3023 R dated 11th Novr 1891 also for a circle room, public latrine, compound wall & for sinking a well

The circle room & public latrine will be in accordance with the design approved in G.O. No. 1609 R dated 28 May 1889.

The following rates are in excess of the Divisional Schedule.

| | Rate bid | Schedule |
|---|---|---|
| Table moulded brickwork | Rs. 4.. | against Rs. 3-8.. |
| Jungle woodwork | 3-4.. | do 2-8 |
| Sanitary arrangements | 6..... | do 7... |
| 3/4" asphaltic flooring | 16..... | do 18... |
| Wood oiling 3 coats | 2..... | do 3... |
| Counting brick in chunam | 18-8... | do 25... |
| Plastering 2 coats | 2-4... | do 2-8... |
| Stone work | 8..... | do 10... |

If schedule rates be adopted the saving will be Rs 1230.

By omitting the masonry compound wall as suggested by the Revenue Deptt the saving will be Rs 4510 & the total amount of estimate reduced from Rs 37650 to Rs 33140.

A supplemental estimate may be sanctioned for a barbed wire fence with gate shutters complete

30. III. 93

A

No 1179 Irdy 28th April 1893

1179/6

PUBLIC WORKS DEPARTMENT,

IRRIGATION BRANCH.

# PROCEEDINGS OF THE MADRAS GOVERNMENT.

UNDER date the

READ the following

Revl Proc. in the Revenue Dept. No. 1039 dy 14th March 1893

The estimate, Amounting to Rs. 37650, for constructing a first class Taluk Office at Kollegal in the Coimbatore District, is reduced to Rs. 33140 by omitting the provision for a Compound wall. The estimate, as thus reduced is sanctioned for execution when funds are available.

2. The Suptg. Engineer IV Circle will submit a supplemental estimate for a barbed wire fence.

3. This sanction has been registered as Provincial No. 11 W of 1893-94 and classified as Civil Buildings, Original Works.

3 Rs

w 264 pc.

Note It is proposed to place this G.O. on the Editor's Table

To
The S.E. IV Circle
with plans & estimate (5)
" Exar. P.W. Accts
" Revenue Dept.
" Editor's Table

P.M.-G—1,000—10-2-93.

C No. 2535

Govt. of {1893} Madras.

PUBLIC WORKS.

Dated

Rcvd. Encl.

G.O. 28 April 93 No. 1179W.

Taluk office at
Kollegal, Coimbatore
District

=

Estimate for Rs 33140
for only a first class
sanctioned, and the
S.E. is also invited
to submit a supplemental
estimate for a barbed
wire fence.

10/6

17/3/93

J.C. 28/4
28/4