(1) பக்கங்களின் எண்ணிக்கை 12

(2) புதுக்கித் திருப்பிய நாள் 11/90

(3) ஆதாரங்குறிப்பவர் சுருக்கொப்பம்

தமிழ்நாடு ஆவணக் காப்பகம்.

தமிழ்நாடு அரசு

P.W.D துறை

அரசாணை எண்.	அச்சகம்
மு. கோப்புத் தாள் எண். 1181 W	பலவகை

நாள் : 1.12.1893 198 .

மடிக்கவோ கண்டபடி கையாளவோ கூடாது

ஆவண. கா-1—18,000—15-6-87.

1181
1

1st May 1893, No. 1181 W., Public Works.

GOVERNMENT OF MADRAS.

PUBLIC WORKS DEPARTMENT.

Buildings and Roads.
Civil Works.

Read—the following paper:—

From G. D. WYBROW, Esq., Superintending Engineer, I Circle, to the Chief Engineer, Public Works Department, dated Palkonda, 6th March 1893, No. 1195 G.N.

I have the honour to submit, herewith, a revised estimate with plans, &c., for Rs. 11,300 for the construction of a Local Fund road from Tekkali to Gopalpur in Ganjam district, and to request that you will be so good as to obtain the sanction of Government to the same.

2. The original estimate for this road (hitherto styled a road from the 20th milestone on the Malapeta road to Gopalpur; the change in the name has been explained to be due to a slight alteration in the original alignment), which was sanctioned in Proceedings of the Madras Government No. 1345 W., dated 28th April 1892, amounts to Rs. 6,980 exclusive of the cost of masonry works, and the excess of Rs. 4,320 therefore requires the sanction of Government.

3. From the accompanying comparative statement it will be observed that masonry works and land compensation, not provided in the original sanctioned estimate, constitute the chief item of excess.

4. The revised estimate, &c., have been scrutinized in my office.

5. A copy of the District Board's resolution sanctioning the revised estimate is enclosed.

Order—dated 1st May 1893, No. 1181 W., Public Works.

The revised estimate, amounting to Rs. 11,300, for constructing a road from Tekkali to Gopalpur in the Ganjam district, is sanctioned in supersession of the estimate of Rs. 6,980, sanctioned in G.O., No. 1345 W., dated 28th April 1892.

2. This sanction has been registered as Local No. 2 W. of 1893–94.

(True Extract.)

Major, R.E.,
Under-Secy. to Govt., P.W.D.

To the Superintending Engineer, I Circle.
" Local and Municipal Department,
with plans and estimates (8).
Editors' Table.

Exd. A. D. Xavier.
Spare Copies

BUILDINGS AND ROADS.
CIVIL WORKS.

Govt. of {1893} Madras.

PUBLIC WORKS.

Dated May, 1st.

Recd. *Encl.*

G.O., 1st May 1893, No. 1181 W.

MAY.

Road

Revised estimate of Rs. 11,300 for constructing a — from Tekkali to Gopalpur in the Ganjam district, sanctioned.

1181

Public Works Department.

Current No. 2996
Letter No. 1195 GN.
Dated 6th March 1893
From the Supdg Engineer I Circle.

1181/93

Technical Note.

Name of work Constructing a road from Tekkali to Gopalpore in the Ganjam District
Amount of Estimate Rs 11,300

In G.O. No. 1345 W dated 28th April 92 an estimate amounting to Rs 6980 was sanctioned for the construction of masonry works. The Supdg Engineer I Circle now submits for the sanction of Govt. a revised estimate amounting to Rs 11,300 in lieu of the original sanction.

The original estimate for the road was styled "Road from 20 mile stone on the Srikakulam road to Gopalpore" but the accompanying estimate is worded as road from "Tekkali to Gopalpore" The change is stated to be due to slight alteration in the original alignment.

The excess of Rs 4,320 over the original sanction is due chiefly to the provision of masonry works, compensation for land, Temporary roads &c. viz:-

14 masonry culverts varying from

from 2 to 6 feet 6 pcm — Rs 3150
Compensation for land — " 1070.
Compensation sheds — " 70.
Total excess Rs — 4320

The length of road provided in the original estimate was 3 miles 4 furlongs & 310 feet with a top width of 18 feet & side slopes 1½ to 1, metalled in the centre to a width of 12 feet with 4" of stone metal & gravelled to a width of 15 feet with 3 inches of gravel. The revised estimate provides for a length of 3 miles 3 furlongs & 466 feet with a top width of 21 feet & side slopes 1½ to 1, metalled to a centre width of 15 feet with 6 inches of stone metal & gravelled to a width of 18 feet with 3" of gravel. By increasing the width of roadway, the items of earthwork, metalling & gravelling have been increased but the rates have been reduced to normal rates as the original estimate provided for famine rates, & hence the excess is mid under these items.

The revised estimate & plans have been countersigned by the President Dist. Board & approved in Dist. Board Proceedings dated 30th July 92.

The estimate has been examined & the rates provided are fair.

15.IV.93

118/3

No. 1195 G.N

FROM

G. D. Wybrow Esq

SUPERINTENDING ENGINEER

FIRST CIRCLE.

TO

THE CHIEF ENGINEER

PUBLIC WORKS DEPARTMENT.

Enclosures. 8
3 Sheets of sections
1 Sketch of land required
1 Survey plan
1 Book of Detail & Abstract estimate
1 Comparative statement
1 Extract from the Board's resolution

Camp Palkonda, 6th March 1893.

SIR,

I have the honor to submit herewith a revised estimate with plans &c^a for Rs 11300 for the construction of a Local fund road from Tekkali to Gopalpur in Ganjam District, and to request that you will be so good as to obtain the sanction of Government to the same.

2. The original estimate for this road (hitherto styled a road from the 20th mile stone on the Allalapeta road to Gopalpore) (The change in the name has been explained to be due to a slight alteration in the original alignment) was sanctioned in P.W.D. No. 1345 dated 28th April 1892, amounts to Rs 6980 exclusive of the cost of masonry works & the excess of Rs 4320 therefore requires the sanction of Government.

3. From the accompanying Comparative

statement it will be observed that masonry works & land compensation, not provided in the original sanctioned estimate, constitute the chief item of excess.

4- The revised estimate we have been scrutinized in my office.

5. A copy of the District Boards Resolution sanctioning the revised estimate is enclosed.

I have the honor to be,
Sir,
your most Obedient Sv.
[illegible]
Supdg Engr 1st Circle.

5/0
13-3

1181/4

P. W. CURRENT No. 2996

P. Acc. 1345 W dt 28.4.92

FROM

G. D. Wyberow Esq.
SUPERINTENDING ENGINEER
FIRST CIRCLE.

TO

THE CHIEF ENGINEER
PUBLIC WORKS DEPARTMENT.

DATED 6th
DESPATCHED 24th } March 1893.
RECEIVED 28th

No. 1195 G.N.

ENCLOSURES 6 & (5 plans)

SUBJECT.

Tekkali Gopalpur road.
Submits an estimate for Rs. 11300 for the construction of & requests to obtain the sanction of Govt to the same.

7
20
1
3
17 0

1/20/4 R. 5. 93

15.IV.93

No. 1181 W dt 1st May 1893

PUBLIC WORKS DEPARTMENT.

1181/4

PROCEEDINGS OF THE MADRAS GOVERNMENT.

B. & C. Works

READ the following

Proceedings from the S.E. I Circle No: 1195 G.N dt 6 Mar. 1893

2 Encl

The revised estimate, amounting to Rs. 11300. for Constructing a road from Tekkali to Gopalpur in the Ganjam District, is sanctioned in supersession of the estimate of Rs. 6980 sanctioned in G.O. No. 1345 W dt 28th April 1892.

2. This sanction has been registered as Local No. 2 W of 1893-94.

Note

It is proposed to place this G.O. on the Editor's Table.

DESPATCHED
12 MAY. 93

To

The S.E. I Circle
" Local and Municipl. Dept. with plans & estimate (8)
" Editor's Table

12.4.93

24.4.93

CM.

40—800-23-3-92.

(7)

To

The Hon. the Chief Secy. Govt
Local and Municipal Dept
for Legislative Council

C.W. 2996

Govt. of Madras.
PUBLIC WORKS.

Dated

Rcd. Rpd.

G.O. Ft. May 1893 No. 1181W

Road
=

Revised estimate
of Rs 11,300 for
continuing a ——
from Sekkalitta
to Gopalpur in the
Ganjam district,
sanctioned.

9/5

G.O. 2/5
2/5 1-3