

- (1) பக்கங்களின் எண்ணிக்கை 12
 (2) புதுக்கித் திருப்பிய நாள் 4.9.11
 (3) ஆதரங்குறிப்பவர் சுருக்கொப்பம் 10/2

தமிழ்நாடு ஆவணக் காப்பகம்.

தமிழ்நாடு அரசு

P.W.D. துறை

அரசாணை எண். மு. கோப்புத் தாள் எண்.	அச்சகம் பலவகை
1197	
நாள் : 3.5.1893	198.

மடிக்கவோ கண்டபடி கையாளவோ கூடாது

(Handwritten signature)

1/1197

GOVERNMENT OF MADRAS.
PUBLIC WORKS DEPARTMENT.

Buildings and Roads.
Civil Works.

READ—the following paper :—

Proceedings of the Board of Revenue (Land Revenue), dated 6th March 1893, Mis. No. 1500.

Read—the following letter from W. G. UNDERWOOD, Esq., Collector of Anantapur, to the Secretary to the Commissioners of Land Revenue, dated 20th February 1893, Ref. on C. No. 424 :—

I have the honour to forward, herewith, an estimate received from the Superintending Engineer, Bellary, for the construction of a new taluk cutcherry at Madakasira and to request that sanction of Government may be obtained for the same.

Resolution—dated 6th March 1893, Mis. No. 1500.

The site plan and estimate for Rs. 32,080 for constructing a new taluk cutcherry at Madakasira are submitted for the sanction of Government with reference to G.Os., dated 9th August 1889, No. 687, and 27th September 1889, No. 6155.

2. The estimate includes a provision for fencing the compound with aloes or korkapally plants. As they harbour snakes, the Board suggests a barbed wire fence instead.

(A true Copy and Extract.)

(Signed) F. LEVY,
for Ag. Secretary.

No. 1249, Revenue.

The plan and estimate are approved and will be transferred to the Public Works Department, in which the Board's suggestion in para. 2 of its Proceedings read above will be considered.

FORT ST. GEORGE,
2nd April 1893.

(Signed) E. GIBSON,
Ag. Secretary to Government.

ORDER—dated 3rd May 1893, No. 1197 W., Public Works.

The estimate, amounting to Rs. 32,080, for constructing a first-class taluk office at Madakasira in the Anantapur district, is reduced to Rs. 31,883 by omitting the provision for enclosing the compound with aloes or korkapally plants. The estimate, as thus reduced, is sanctioned for execution when funds are available.

2. The Superintending Engineer, III Circle, will submit a supplemental estimate providing for record racks and a barbed wire fence.

3. This sanction has been registered as Provincial No. 16 W. of 1893-94 and classified as Civil Buildings, Original Works.

(True Extract.)

Major, R.E.,
Under Secy. to Govt., P.W.D.

To the Superintending Engineer, III Circle, with plan and estimate.
" Examiner, Public Works Accounts.
" Revenue Department.
Editors' Table.

Exd. C. A. Muniswamy.
Spare Copies

2
1197

BUILDINGS AND ROADS.
CIVIL WORKS.

Gobt. of {1893} Madras.
PUBLIC WORKS.

Dated May, 3rd.

Recd.

Encl.

G.O., 3rd May 1893, No. 1197 W.

MAY.

Taluk Office at Madakasira,
Anantapur District

Estimate of Rs. 31,883 for constructing a first-class —, sanctioned for execution when funds are available, and the Superintending Engineer, III Circle, directed to submit a supplemental estimate providing for record racks and a barbed wire fence.

Proceedings of the Board of Revenue -
(Land Revenue)

Dated 6 March 1893. $\frac{3}{1197}$

No. 1500 Ins: -

Read the following letter from W. G. Underwood Esq. Collector of Anantapur, dated 20 February 1893, Ref. no C. W. 424 to the Secretary to the Commissioners of Land Revenue.

I have the honor to forward herewith an estimate received from the Superintending Engineer Bellary for the construction of a new Taluk Cuckery at Madakasira and to request that sanction of Government may be obtained for the same.

Resolution -

The site plan and estimate for No. 32080, for constructing a new Taluk Cuckery at Madakasira are submitted for the sanction of Government with reference to Government orders dated 7-8-89 No. 187 and 27-9-89, No. 655.

2. The estimate includes a provision for fencing the compound with allos or Korkapally plants. As they have been used the Board suggests a barbed wire fence instead -

(See Copy and extract)

(Signed) J. Levy

For Secy

To The Secretary to Govt. P.D.
with the plan & estimate -
to The Collector of Anantapur -

(1893.)

REVENUE DEPARTMENT.

No. 1882;

ABSTRACT.

R. No. 1778 W 924. 7. 71

2507 W 910. 7. 89

355 W 922. 73

From

The Board of Revenue
(Land Revenue)

Inst. No. 1249.

Recd: 7.4.93

Dated 1st 3 March/93.
Received 8th

Enclosures 5. (Plan)

No. 1500, M.S.

SUBJECT.

Submitting with
remark for the sanction
of Government plan &
estimate for constructing
a new Subk. Cutchery
at Madakaira in
Anantapur Dist.The plan and
estimate are approved,
& will be transferred
to the Public Works
Department in which
the Board's suggestion
in para 2 of its Proved.
ings read above will
be considered.

Secretary to Govt.

For Mr. George &
2nd April/93To the Public Works Dept.
Cantonment of Madakaira

Public Works Department.

Current No. 333

Letter No. 1249

Dated 2nd April 1893

From the Revenue Department

TECHNICAL NOTE.

Name of Work Constructing a first class Subk.
Office at Madakaira, Anantapur Dist.

Amount of Estimate, Rs. 32,080

PARTICULARS OF ESTIMATE.

Main Building	Office	Rs. 30,159
	Cook house	606
Subsidiary Buildings	Public latrine,	788
	Gate & compound wall for 10 feet.	130
Contingencies	5% Rs. 1,483.	"
Petty Supervision	for 32/10 months at Rs. 600	"
Land compensation	for 32/10 months at Rs. 600	200
	also bridge fencing	197
Total Rupees		32,080

PARTICULARS OF CONSTRUCTION.

Surface soil earth about 2 1/2 feet deep.
 Sub soil hard white & red gravel.
 Foundations are the same as depth of 3 feet
 the lower one foot to be of concrete & the
 upper 2 feet of rough stone in chunam
 as per footing, noted on sketch in the
 report.
 Basement is the raised 2 feet high & built
 of hammer dressed stone in chunam.
 Walls are the raised to the height noted on
 the type design & built with hammer
 dressed stone (chunam rubble) in chunam
 & have with flat & concave windows
 & work over doors & windows.

Plastering or Pointing *The interior faces are to be plastered with 2 coats of chunam & the interior faces primed.*

Flooring *is to be of granite slabs laid on 3" of concrete below and except for the girdle roads & roads near which will be of 3/4" asphalt.*

Roofing *is to be covered with brick on edge & asphalt.*

Doors and Windows *are to be of teakwood & of the descriptions noted in the estimate & primed with 3 coats of Canso oak.*

Roof timbers *are to be of teakwood & of the descriptions noted in the estimate.*

Scantlings *are correct, as per primed estimate.*

Rates *are fair, those for doors & windows cannot be checked from the District rate list.*

The plinth area of the main building is 10842 square feet, and the cost per square foot will be Rs. 2.12.6.

The plans and estimates have been countersigned by the *Collector of the District* and approved in the *Revenue Dept.* with the *Remarks* that the suggestion of the Board regarding the above hedge be considered in this Dept.

Remarks

This estimate has been framed with reference to G.O. No. 368 dated 10th Feb. 1891. It provides for construction of a first class Taluk office with out-houses at Madakavira in the Anantapur District.

The Taluk office will be built as per the design approved in G.O. No. 3023 dated 11th March 1891 & the out-houses, as per design approved in G.O. No. 1409 dated 28th May 1889.

The site selected is private land & compensation to the owners of the 200 has been provided for in the estimate. The Board of Revenue in submitting

The plans & estimates for same. I am suggesting that the fencing of the compound with above be substituted by a barbed wire fence, as the former has been made & one of which protection against trespass if the above fence be omitted the whole estimate of the estimate will be reduced by Rs. 197.

no provision has been made for record racks, but from the first note in the General abstract, a supplementary estimate for this work is headed *Record Racks* is stated to follow hereafter. With the record racks & barbed wire fence may be submitted together.

15.11.92

4
1197

1197

No. 1197. Wd/3rd May 1893
PUBLIC WORKS DEPARTMENT.

PROCEEDINGS OF THE MADRAS GOVERNMENT.

5
1197
Read the following

Proc. of the Bd. of Rev. (Chand Rev.) No. 1500 mis d/6 Mar 73
Endorsed thereon in the Rev. Dept. No. 1249 d/2 Apr 93

The estimate, amounting to Rs. 32,080, for constructing a first class Taluk office at Madakavira in the Anantapur District, is reduced to Rs. 31,883 by omitting the provision for enclosing the compound with above or Korkapally plants. The estimate, as thus reduced, is sanctioned for execution when funds are available.

2. The Suptg. Engineer III Circle will submit a supplemental estimate providing for record racks and a barbed wire fence.

3. This sanction has been

W
29 Apr.

W
29 Apr.

been registered as Pro-
vincial No. 16 W of
1893-94 and classified
as Civil Buildings.
Original Works.

(1) His Excellency the Governor
(2) The Hon. Secy. of State, K.C.S.

1073
12-17-93

1073
12-17-93

Note: It is proposed to place
this on the Editor's
Table.

DESPATCHED
17 MAY. 95

8. The S.E. III Circle
with plan & estimate
Exar. P.W. a/ccts.
Rev. Dept.
Editor's Table

On
1073
12-17-93

6
1197

CW^o 3313

Gobt. of Madras.
PUBLIC WORKS.

Dist.

Recd.

Encl.

G.O. 3 May 1893 No. 11976

Salut office at
Mada Kasira
Mantapur 1st

2

31,883

Estimate of ~~Rs. 22,000~~
for constructing a
first class
sanctuary for
execution when funds
are available, and
the S.E. III Circle directed
to submit a supplemental
estimate providing
for record rack & a
barbed wire fence

90/
100/
6

G.O. 3/5/93