(1) பக்கங்களின் எண்ணிக்கை 12

(2) புதுக்கித் திருப்பிய நாள் 4.91

(3) ஆதாரங்குறிப்பவர் சுருக்கொப்பம்

# தமிழ்நாடு ஆவணக் காப்பகம்.

## தமிழ்நாடு அரசு

P.W.D. துறை

அரசாணை எண். —
மு. கோப்புத் தாள் எண்.

அச்சகம்
பலவகை

1198

நாள் : 3.5.1833 198 .

மடிக்கவோ கண்டபடி கையாளவோ கூடாது

இவண. கர-1—18,006—15-6-87.

1/1198

GOVERNMENT OF MADRAS.

PUBLIC WORKS DEPARTMENT.

**Buildings and Roads.**
**Civil Works.**

Read—the following paper:—

From G. D. WYBROW, Esq., Superintending Engineer, I Circle, to the Chief Engineer, Public Works Department, dated Dowlaishweram, 10th March 1893, No. 2498 G.D.

I have the honour to submit, herewith, plans and estimates, amounting to Rupees 6,200, received from the President, District Board, Gódávari, for constructing a road to connect Ralli village with Amalápur and Gunnaram canals in the Gódávari district, and to request that you will be so good as to obtain the sanction of Government to the same.

2. The estimate has been scrutinized by this office and bears the countersignature of the President, District Board.

3. A copy of the Taluk Board's resolution sanctioning the estimate is enclosed.

Order—dated 3rd May 1893, No. 1198 W., Public Works.

The estimate, amounting to Rs. 6,200, for constructing a road to connect the Ralli village with the Amalápur and Gunnaram canals in the Gódávari district, has been increased to Rs. 6,510 by the correction of an arithmetical error under the item "Gravelling." The estimate, as thus amended, is sanctioned.

2. This sanction has been registered as Local No. 3 W. of 1893–94.

(True Extract.)

Major, R.E.,
Under Secy. to Govt., P.W.D.

To the Superintending Engineer, I Circle.
" Local and Municipal Department,
with plans and estimate (11).
Editors' Table.

Exd. C. A. Munisawmy.
Spare Copies

BUILDINGS AND ROADS.
CIVIL WORKS.

Govt. of {1893} Madras.

PUBLIC WORKS.

Dated May, 3rd.

Read.

Encl.

G.O., 3rd May 1893, No. 1198 W.

MAY.

Road

Estimate of Rs. 6,540 for constructing a -- to connect the Ralli village with the Amalápur and Gunnaram canals in the Gódávari district, sanctioned.

No. 2498 G.D

2/1198

FROM

G. D. Wybrow Esq:
SUPERINTENDING ENGINEER

FIRST CIRCLE.

TO

THE CHIEF ENGINEER

PUBLIC WORKS DEPARTMENT.

DOWLAISHWERAM, 10th March 1893.

Enclosures. 11
2 Plans
1 Survey
1 Longitudinal section
2 Report & specification
1 Detailed & Abstract estimate of road
1 — 00 — 00 Culvert 3 span
1 — 01 — 00 — 0 — 00 — 6 — do
1 Data list
1 Extract of the Taluq Board's Proceedings
11

SIR,

I have the honor to submit herewith plans and estimates amounting to Rs 6200 received from the President District Board Godavari for constructing a road to connect Ralli village with Amalapur and Gunnaram Canals in the Godavari District, and to request that you will be so good as to obtain the sanction of Govt. to the same.

2. The estimate has been scrutinized by this office and bears the countersignature of the President District Board.

3. A copy of the Taluq Board's Resolution sanctioning the estimate is enclosed.

J

I have the honor to be
Sir
Your most obedt servt

H. Mohs
Asst Engr Jpr

Supg. Engineer I Circle
20-3-93

Se
20-3

3/
1198

P. W. CURRENT No. 2940

FROM

G. D. Hyberson Esq:
SUPERINTENDING ENGINEER

FIRST CIRCLE

TO

THE CHIEF ENGINEER

PUBLIC WORKS DEPARTMENT.

DATED 10th
DESPATCHED 21st } March 1893.
RECEIVED

No. 2498 GD

ENCLOSURES 11 (Eleven)

SUBJECT.

Road to connect Ralli village with Amalapur & Gunnaram canals in the Godavari Dist
Submits plan & estimate of Rs 6200 for construction & requests to obtain the sanction of Govt to the same

Public Works Department.

Current No. 2940 4/1198

Letter No. 2498 GD

Dated 10 March 1893

From the Superintending Engineer 1 Circle

TECHNICAL NOTE.

Name of work Constructing a road to connect Ralli village with Amalapur & Gunnaram Canals in the Godavari Dist. Amount of estimate Rs 6540

In the report accompanying the estimate it is stated that this road is necessary, as during the wet weather water stands between the Canals & the village & the village becomes an island. It is therefore proposed to construct a road one mile three furlongs & 330 feet in length from the Amalapur canal to Gunnaram canal passing through the village of Ralli as per accompanying plan.

The road will be embanked throughout with a top width of 21 feet & with side slopes 1½ to 1. The centre portion of the roadway will be gravelled to a width of 12 feet with 6 inches of gravel & the sides of embankment turfed. There will be 4 ma

masonry culverts to pass the cross drainage, one culvert of 6 feet span at the first furlong & three of 3 feet span each at the 5½, 6 & 7th furlongs.

The amounts of the estimate is made up as follows:

| | |
|---|---|
| Roadwork embanking & gravelling | 4440 |
| One masonry culvert 6 feet span. | 350 |
| Three - do - of 3 feet span each at Rs. 400 each | 1200 |
| Compensation for land | 500 |
| Incidental charges | 50 |
| Total estimate Rs. | 6540 |

The ratio cannot be checked but detailed lists are submitted.

The amount of the estimate has been increased from Rs. 6200 to Rs. 6540 owing to an error in calculation under the item gravelling (2nd mile) by which the total estimate has been increased by Rs. 340. The correction has been made in red ink.

The estimate has been countersigned by the President Distt Board & approved in Rajahmundry Taluq Board's proceedings dated 19. Oct 93.

18.11.93

with 4 plans.

11984

A

No. 1198 Rdy 3rd May 1893

PUBLIC WORKS DEPARTMENT.

B.P.W. Circular

# PROCEEDINGS OF THE MADRAS GOVERNMENT.

5/1198

READ the following

Print from the S.E.I Circle No: 2498 G.D dy 2nd Mar: 93

The estimate, amounting to Rs. 6200, for constructing a road to connect the Ralli village with the Amalapur and Gunnaram canals in the Godavari District has been increased to Rs. 6540 by the correction of an arithmetical error under the item 'gravelling'. The estimate, as thus amended, is sanctioned.

2. This sanction has been registered as Local No. 3 of 1893-94.

Two 304/pa

Note

It is proposed to place this G.O. on the Editor's Table

DESPATCHED 6 MAY. 95

To

The S.E.I Circle

" Local and Municipal Dept. with plans estimate

" Editor's Table

10—800-23-3-93.

(11)

24.4.93

25/4/93

maj

6/1158

HSD1054
CA 264
Rem 1 of 1
PO: 3/5

cd°-2940

Govt. of {1893} Madras.

PUBLIC WORKS.

Dated

Read

Rect.

G.O. 2nd Sitting 1893, No. 1198 W.

Road.

6540

Estimate of Rs ~~62000~~

for constructing a

to connect the Kalli

village with the Amalapa

and Gunaram roads

in the Godavari Dt

sanctioned

90/