(1) பக்கங்களின் எண்ணிக்கை 12

(2) புதுக்கித் திருப்பிய நாள் 12/90,

(3) ஆதாரங்குறிப்பவர் சுருக்கொப்பம்

தமிழ்நாடு ஆவணக் காப்பகம்.

தமிழ்நாடு அரசு

பொதுப்பணி துறை

அரசாணை எண். மு. கோப்புத் தாள் எண்.	1610 (W.)	அச்சகம் பலவகை
நாள் :	16-6-1893	198 .

MSP.

மடிக்கவோ கண்டபடி கையாளவோ கூடாது

ஆவண. கா-1—18,006—15-6-87.

16th June 1893, No. 1610 W., Public Works.

1610
1-

GOVERNMENT OF MADRAS.

PUBLIC WORKS DEPARTMENT.

Buildings and Roads.
Civil Works.

Read—the following paper :—

G.O., dated 1st June 1893, Mis. No. 2006, Revenue.

Read—the following paper :—

Proceedings of the Board of Revenue (Land Revenue), dated 8th May 1893, Mis. No. 2813.

Read—the following letter from E. TURNER, Esq., Collector of Madura, to the Secretary to the Commissioners of Land Revenue, dated Kodaikánal, 27th April 1893, No. 120.—

I have the honour to report that the Deputy Tahsildar's office at Mudukulattúr built by the Department of Public Works in 1875 is badly in need of repair. The roof of the building is quite unsafe and likely to fall, the beams and posts thereof having become rotten. The wood work that has given way in some places now stands on supports recently fixed at a small cost.

2. The Department of Public Works was addressed on the matter and the Superintending Engineer forwarded with his letter No. 864 M.D., dated 12th November 1891, an estimate for Rs. 2,[illegible]90 for countersignature, which was approved of and returned to him with this office letter No 2394, dated 20th November 1891. He has now forwarded with his letter No. 1302, dated 20th March 1893, a revised estimate for Rs. 2,780 for my approval and submission to Government for sanction, as the present estimate is to be treated as for original work.

3. I request, therefore, that you will be so good as to obtain the sanction of Government for repairing and improving the Deputy Tahsildar's cutcherry at Mudukulattúr at a very early date.

4. Copy of the Superintending Engineer's letter No. 1302, dated 20th March 1893, with estimate and plan is herewith submitted.

Resolution—dated 8th May 1893, Mis. No. 2813.

The estimate for Rs. 2,780 for repairing and improving the Deputy Tahsildar's cutcherry at Mudukulattúr is submitted for the early sanction of Government. The building is stated to be in an unsafe condition.

Order—dated 1st June 1893, Mis. No. 2006, Revenue.

The estimate is approved and transferred to the Public Works Department.

(True Extract.)

(Signed) R. H. CAMPBELL,
Ag. Under Secretary.

Order—dated 16th June 1893, No. 1610 W., Public Works.

The estimate, amounting to Rs. 2,780, for repairing and improving the Deputy Tahsildar's office at Mudukulattúr in the Madura district, is sanctioned for early execution in supersession of the estimate of Rs. 2,490 sanctioned by the Superintending Engineer under "Repairs."

2. The Superintending Engineer will report the amount required for expenditure on the work during the current official year.

3. The sanction accorded in para. 1 has been registered as Provincial No. 41 W. of 1893-94 and classified as Civil Buildings, Original Works.

(True Extract.)

Major, R.E.,
Under Secy. to Govt., P.W.D.

To the Superintending Engineer, VI Circle, with plan and estimate.
" Examiner, Public Works Accounts.
" Revenue Department, with two enclosures returned.
Editors' Table.

Exd. A. D. Xavier.
Spare Copies

1610/2.

BUILDINGS AND ROADS.
CIVIL WORKS.

Govt. of {1893} Madras.

PUBLIC WORKS.

Dated June, 16th.

Recd. *Encl.*

G.O., 16th June 1893, No. 1610 W.

JUNE.

Deputy Tahsildar's Office at Mudukulattur

Revised estimate of Rs. 2,780 for repairing and improving the — in Madura district sanctioned for early execution and the Superintending Engineer, VI Circle, requested to report the amount required for expenditure during the current official year.

F/17 1,000—8-3-93.

Read the following [illegible] No 2006 [illegible]
[illegible] 1 June 1893 [illegible]

REVENUE DEPARTMENT.

1610/3

PROCEEDINGS OF THE MADRAS GOVERNMENT.

Read the following Proceedings of the Board of Revenue Land Revenue dated 8 May 1893 No. 2813 Mis on letter from the Collector of Madura dated 27 April 1893 No 120.

Resolution

The estimate for Rs 2780 for repairing and improving the Deputy Tahsildar's Cutcherry at Mudukulathur is submitted for the early Sanction of Government. The building is stated to be in an unsafe Condition.

Order thereon: 1 June 1893 No 2006.

The estimate is approved and transferred to the Public Works Department.

True Extract
[illegible]
Ag under secretary

To
The Public Works Dept
with the enclos
Comms of L R

~~Govt. of {1893} Madras.~~

P. W. CURRENT No. 5253

~~REVENUE.~~

To

The Public Works Dept.

Dated
Recd. 8-6-93

Encl. 10 (1 plan)

Mis. G.O., 1st June 1893, No. 2006

SUBJECT.

pproving and
ransferring the
stimate for repairing
nd improving the
eputy Tahr's Cutcherr
t Madukulatur
Madura Dt

Public Works Department.

1610/4

Current No. 5253
Letter No. 2006
Dated 1st June 1893
From the Revenue Dept.

TECHNICAL NOTE.

Name of work Repairing & improving the Deputy Tahsildars Office at Madukulatur in the Madura District

Amount of revised estimate Rs 2780

The roof of this building is reported to be unsafe & likely to fall in as the roof timbers have decayed & in many places given way, an estimate amounting to Rs 2490 was sanctioned by the Supg Engineer for repairing & improving the building. The revised estimate amounting to Rs 2780 exceeds the original estimate by Rs 290 or 11.5% This excess is due to the following items:

(a) Cement plastering	Rs	59
(b) Teakwood work —	"	20
(c) Tiled roofing —	"	254
(d) Treasury cell —	"	90
(e) Other petty items —	"	45
Total —		468
Deduct savings —		17

Total excess

b) is due substitution of cement pla
:ter for ordinary chunam plast-
) due to provision of new ridge pol
& 2 rafters to replace decayed
~~old~~ ones

(c) original rate found inadequate
as a larger quantity of repairs
had to be renewed than anti-
:cipated.

(d) original lump sum provision
of Rs 40 for the treasury cell was
found inadequate

The savings are chiefly due
to the omission of a latrine as
being found unnecessary for Sub
Magistrates offices & to the item
of contingencies not required.

The estimate has been classi-
:fied under original works vide
para 2 Chap VII of the P. W. Cod
as the amount exceeds 1/4 th
book value of the building.

The estimate has been cou-
:ntersigned by the Collector & ap-
:proved in the Revenue ~~Judicial~~ Dep

10.VI.93

1610 W

Public Works Department.

B.41

№ 1610 W d/ 16th June 1893.

1610

PROCEEDINGS OF THE MADRAS GOVERNMENT.

5

Read the following

~~Procd. in the Rev. Dept.~~ No. 2006 d/ 1st June 1893.

Print letter from the Collr. of Madura d/ 27 April 93 No. 120

The estimate, amounting to Rs. 2780, for repairing and improving the Deputy Tahsildar's office at Muttukulatur in the Madura District is sanctioned, for early execution, in supersession of the estimate of Rs. 2490 sanctioned by the Superintending Engineer under 'Repairs'.

2. The Superintending Engineer will report the amount required for expenditure on the work during the current official year. The

work appears to
been put in hand already

(40—2,000—13-5-93.)

3. The sanction accorded in para 1 has been registered as Provincial No. 4/W of 1893-94 and classified as Civil Building Original Works.

HW
12/6

HW
13/6

Revised Estimate for repairing and improving the Dep. Tahsildar's office at Mullukulateer, Madura Dt.

—

Note

It is proposed to place [illegible]

the [illegible]

DESPATCHED

To

The S. E. VI Circle
with plan & estimate (8)

.. Exas. P.W. accts.

.. Rev. Dept. with two [illegible]

Ch

1610/6

C No. 5253

Govt. of (1893) Madras.
PUBLIC WORKS.

Dated 17/0

Recd. Reply

G.O. 16th June 1893, No. 1610 W.

Deputy Tahsildars' office at Muttukulatur.

Revised estimate of Rs 2780 for repairing and improving the — in Madura Dt, sanctd. for early execution & the S.E. VI Circle requested to report the amount required for expenditure during the c/o year

110/5

G.O. 16/VI
1610