

6

- (1) பக்கங்களின் எண்ணிக்கை 12
(2) புதுக்கித் திருப்பிய நாள் 17-2-92
(3) ஆதாரக் குறிப்பவர் சுருக்கப்படும்

தமிழ்நாடு ஆவணக் காப்பகம்.

தமிழ்நாடு அரசு

துறை

அரசாணை எண். மு. கோப்புத் தாள் எண்.	3298 P. W. D.	அச்சம் பலவகை
நாள் :	18. 12. 1893	199

மடிக்கவோ சுண்டப்படிக் கையாளவோ கூடாது.



ஆவண. கா. 1—18,006—6-9-90.

GOVERNMENT OF MADRAS.
PUBLIC WORKS DEPARTMENT.

Buildings and Roads.
Civil Works.

3298

READ—the following papers:—

From H. FARRER, Esq., Postmaster-General, Madras, to the Secretary to Government, Public Works Department, dated Madras, 22nd November 1893, No. 18607/ E.S. 2 No. 4.

With reference to letter No. 10123, dated 11th November 1893, from the Director-General of Post Office to your address, I have the honour to forward, herewith, the plan and estimate of the proposed Post and Telegraph office building at Vániyambádi and to request that the sanction of Government may be accorded for the execution of the work, and the Executive Engineer, Salem, instructed in the matter at the earliest date convenient in order that the work may be carried out within the official year.

Note by the Chief Engineer, Public Works Department.

In the estimate of Rs. 2,480 for constructing a combined Post and Telegraph office at Vániyambádi in the Salem district, the superstructure walls are proposed to be built of brick in clay; but as it is desirable that a depth of 9 inches around doors and windows and the top of walls near the roof should be built with chunam to prevent the attack of white-ants, the necessary alterations have been made and the estimate increased to Rs. 2,530. The estimate as thus modified is recommended for the sanction of Government.

15th December 1893.

(Signed) J. PENNYQUICK, Col., R.E.,
Chief Engineer, P.W.D.

ORDER—dated 18th December 1893, No. 3298 W., Public Works.

The estimate, amounting to Rs. 2,530, as modified by the Chief Engineer, Public Works Department, for the construction of a combined Post and Telegraph office at Vániyambádi in the Salem district, is sanctioned for early execution.

2. A sum of Rs. 2,480 has been allotted for the work in G.O., No. 2964 W., dated 16th November 1893.

3. This sanction has been registered as Imperial No. 3 W. of 1893-94 and classified as Civil Buildings, Original Works.

(True Extract.)

Major, R.E.,
Under Secy. to Govt., P.W.D

To the Superintending Engineer, IV Circle, with six enclosures.

„ Examiner, Public Works Accounts.

„ Postmaster-General, Madras.

Editors' Table.

Exd. C. A. Munisawmy.

Spare Copies

BUILDINGS AND ROADS.
CIVIL WORKS.

Govt. of {1893} Madras.
PUBLIC WORKS.

Dated December, 18th.

Recd.

Encl.

G.O., 18th Dec. 1893, No. 3298 W.

DECEMBER.

Combined Post and Telegraph
Office

Estimate of Rs. 2,530 for the construction
of a — at Vaniyambadi in Salem district,
sanctioned.

Post Office Department.

From

H. FARRER, Esq.,
POSTMASTER GENERAL, MADRAS,

To

THE SECRETARY

TO THE GOVERNMENT OF MADRAS,

Public Works DEPARTMENT.

No. 1867 dated Madras, the 11th November 1893.
E.S. 2 he 4

SIR,

2964 W 16.12.93
With reference to letter No. 10128 dated
11th November 93 from the Director General
of Post office to your address, I have the
honour to forward herewith the plan
and estimate of the proposed Post and
Telegraph office building at Vaniyambadi,
and to request that the sanction of
Government may be accorded for the
execution of the work, and the
Executive

Executive Engineer Salem instructed
in the matter at the earliest date is
convenient in order that the work
may be carried out within the official
year.

I have the honor to be,
Sir,

Your most obedt. servant,

Dec: 27. 11. 93

Encls: 6 (3 Plans)

H. J. J. J.

Postmaster General

No. 2964 of 16-11-93

Public Works Department.

Current No. 10069 *26 32906*
Letter No. 18609 *18 12 93*

Dated 22. November 1893

From the *Postmaster General.*

Caution

NOTE BY TECHNICAL SECTION.

Name of Work *Constructing a Combined
Post & Telegraph Office at Varianambady.
Salem Dist.*

Amount of Estimate, Rs. *2480*
2530

PARTICULARS OF ESTIMATE.

Main Building	Rs. <i>2178</i> <i>2180</i>
Subsidiary Buildings	" "
Contingencies <i>3%</i>	" <i>71</i> <i>65</i>
Petty Supervision <i>4%</i>	" <i>26</i> <i>80</i>
Land compensation	" <i>185</i>

Total Rupees ... *2530*
2480

PARTICULARS OF CONSTRUCTION.

Surface soil } *soft loam*
Sub soil }
Foundations *are to be sunk 2 feet deep
& built of concrete throughout.*
Basement *is to be raised 18 inches & built
with brick in chunam.*
Walls *are to be raised as per heights
noted on the plan & built of brick
in chunam with flat archwork over
doors & windows.*

*a. The plan submitted is not
on the standard design. The
only standard design available
is the one now submitted put
up.*
*b. The necessary alterations
have now been made in the
estimate for brick in chunam
for top of walls & around doors
& windows which has in-
creased the estimate by Rs
50.*

H. J. J. J.
11. 11. 93

3
3298

Plastering on Painting the walls are to be plastered with inferior & exterior with one coat of chunnam.
Flooring is to be of 6" concrete with summer
Roofing The office room is to be tiled with flat & pan tiles laid over ver: -
-teak rafters & the out-houses tiled with pan tiles laid over bamboo mats & rafters.
Doors and Windows to be of the descriptions noted in the estimate of materials.
Roof timbers are to be of suitable for the office room & palanquin for the quarters.
Scantlings are correct.
Rates are fair.

The plinth area of the main building is 1980 square feet, and the cost per square foot will be Rs. 1-2-6.

The plans and estimates have been countersigned by the Director General of Port Office India and approved in the Port Master General Department. Madras, for the sanction of Govt.

REMARKS.

In the report accompanying the estimate it is stated that the Combined Port & Telegraph office are at present located in a low dark room out of mud chanku, which is inadequate in size & incapable of permanent repairs. It is therefore proposed to construct a new building on the site of the ruined building. Deputy Tahsildars Office by acquiring a small strip of private land, as shown on site plan.

The accommodation proposed is an office room 30' x 15' with front verandah 8 feet wide & two rooms each 14'3" x 13'0" as Port Masters quarters with out-houses of a kitchen 12' x 9', store room 9' x 9' and

and a latrine 8' x 6'. A court yard 7'6" wide is to separate the quarters from the out-houses, as per plan.

The superstructure walls are proposed to be built of brick in clay. It is submitted that for a depth of 9 inches around doors & windows to the top of walls near roof, may be built in chunnam to prevent the attacks of white ants.

The verandah rafters are proposed to be let into the masonry at one end. It is submitted that the rafters may be carried on wall purlins supported by stone & wooden corbels.

8.11.93

(a) Is this design a standard one?

(b) The verandah rafters may be left as proposed, but the 9' x 6' in quarters round some dimensions 2 lts of female masonry substituted for 6 lts - T can do this. 8.11.93

Note by the Chief Engineer Public Works Department

4/3298

In the estimate of Rs 2,480 for constructing a combined Port and Telegraph office at Vainambady in the Salem District, the superstructure walls are proposed to be built of brick in clay, but as it is desirable that a depth of 9 inches around doors and windows and the top of walls near roof should be built with chunnam to prevent the attack of white ants, the necessary alterations have been made and the estimate increased to Rs 2,530. The estimate as thus modified is recommended for the sanction of Government.

L.S. 13.12.93 S. E.W.

No. 3298 W. d/18 December 1893.

PUBLIC WORKS DEPARTMENT.

PROCEEDINGS OF THE MADRAS GOVERNMENT.

5/298

READ the following

From the Post Master General, Madras (H.E. No. 1867 of 122-11-93)
Note by the Chief Engineer P.W. Dept. d/15 Decr. 1893

W
16 Dec.

1. The estimate amounting to Rs 2,530, as modified by the Chief Engineer P.W. Dept. for the construction of a combined Post and Telegraph office at Vaniambady in the Salem District, is sanctioned for early execution.

2. A sum of Rs 2,480 has been allotted for the work in G.O. No. 2964 W d/16 November 1893.

3. This sanction has been registered as Imperial No. 3 W of 1893-94 and classified as Civil Buildings Original Works.

Note. It is proposed to place this in the Editors' Table

DESPATCHED
8- JAN. 94

To The S.E. & Circle with enclosures.
... Examiners P.W. Dept.
... Post Master General, Madras.
... Editors' Table

13-12-93

Combined Post and
Telegraph Office at
Lansdowne, Salem St.

6
5298

Case 10069

Govt. of (1883) Madras.
PUBLIC WORKS

20/12/93

18 Dec 1893 No. 32984

Combined post and
telegraph office

=

Estimate of Rs 2530
for the construction
of a — at Vaniam-
bady in Salem
district sanctioned

20/

2.C. 19.84

20/12