~~உ3411~~/OBR.

(1) பக்கங்களின் எண்ணிக்கை 28

(2) புதுக்கித் திருப்பிய நாள்

(3) ஆதாரங் குறிப்பவர் சுருக்கொப்பம் 1/9/95

தமிழ்நாடு ஆவணக் காப்பகம்.

தமிழ்நாடு அரசு

பொதுப்பணி (P W) துறை

அரசாணை எண். / மு. கோப்புத் தாள் எண். 358 W அச்சகம் / பலவகை

358

நாள் : 9-2-1893

அ. பாண்டி

மடிக்கவோ கண்டபடி கையாளவோ கூடாது.

ஆவண. கா. 1—18,006—6-9-90.

செப்பனிடுபவர் பெயர் அ. மாணிக்
செப்பனிடுவதற்காக எடுத்துக்
கொள்ளப்பட்ட நாள் ஆகஸ்ட் 95
செப்பனிட்டு முடித்த நாள்
ஆகஸ்ட் 95
சரிபார்த்த மு. பா. கையொப்பம் [illegible]
ஆராய்ச்சி உதவியாளர் கையொப்பம் [illegible] 95

GOVERNMENT OF MADRAS.

PUBLIC WORKS DEPARTMENT.

358/1

Buildings and Roads.
Civil Works.

Read—the following paper :—

G.O., dated 27th December 1892, Mis. No. 5692, Revenue.

Read—the following Proceedings of the Board of Revenue, Land Revenue, dated 18th August 1892, Mis. No. 5157 :—

Read—letter from the Collector of Trichinopoly, dated 10th June 1892, No. 285/4.

Reference thereon, dated 11th July 1892.

In the revised standard design the estimate for a taluk office with terraced roofing is given as Rs. 28,910. Adding to this amount the estimated expenditure for the marginal items which have not been included in the above estimate, the total comes to Rs. 32,048. The difference between this amount and the estimate for the new taluk cutcherry sent with the letter read above is Rs. 5,652. The difference is large and is due mainly to increase in the rates under the following heads :—

	RS.
Record racks	1,320
Cook room	448
Latrine	600
Gate and compound wall	200
Well	270
Lightning conductor	300
Total ...	3,138

	Rate as in the standard estimate.			As in the estimate of the Executive Engineer.			
	RS.	A.	P.	RS.	A.	P.	
1. Concrete	14	0	0	17	10	0	per 100 c. ft.
2. Foundation and basement with stock bricks in chunam ...	19	8	0	23	8	0	„ „
3. Superstructure do. do. ...	20	8	0	24	12	0	„ „
4. Teakwood wrought and put up.	3	8	0	4	4	0	per c. ft.
5. Cuddapah slabs for cornice ...	24	8	0	27	8	0	per 100 sq. ft.
6. Teakwood panel and venetian doors	1	1	0	1	12	0	per sq. ft.
7. Teakwood panel doors	0	14	0	1	8	0	„ „
8. Flooring with 8″ square brick, &c.	7	13	0	13	0	0	per 100 sq. ft.

The increase under item 5 above has been explained. The Collector is requested to call upon the Executive Engineer to explain the increases in the remaining items. The Board observes that teak is largely imported at Negapatam.

Read—letter from the Collector of Trichinopoly, dated 10th August 1892, No. 385/4.

Resolution—dated 18th August 1892, Mis. No. 5157.

The estimate for building a new taluk cutcherry at Jayankondacholapuram at a cost of Rs. 37,700, received with the first letter read above, is submitted for the early sanction of Government.

2. The rates given for certain items appearing large, the Collector was called upon to furnish an explanation. This is submitted with the second letter read above. The explanation appears satisfactory.

3. A portion of the compound wall is proposed to be fenced with aloes. As these plants are not considered a sufficient protection against cattle and are, moreover, supposed to harbour snakes, the Board suggests that a barbed wire fence may be substituted therefor.

Read—Proceedings of the Board of Revenue, Land Revenue, Nos. 7710 and 7894, dated 24th November and 1st December 1892, respectively, on certain petitions regarding the transfer of taluk head-quarters from Jayankondacholapuram to Udayárpálaiyam.

Order—dated 27th December 1892, Mis. No. 5692, Revenue.

The Government is unable to accept the Board's recommendation in the second paper read above. As regards central situation, there is little to choose between Udayárpálaiyam and Jayankondacholapuram, and the Deputy Collector's description of the superior advantages of the former place seems somewhat exaggerated. The Government is unable to agree with the Board in thinking that the fact that Udayárpálaiyam is the head-quarters of a large zemindari is a point in its favour. On the contrary, it appears to be a serious objection to the location of the cutcherry there. Moreover, a contract has already been given for the construction of the building at Jayankondacholapuram and a change at this juncture cannot but cause loss and extra expenditure. On these grounds the proposed transfer appears undesirable.

2. The plan and estimates are accordingly approved and transferred to the Public Works Department for sanction. Orders will issue in that department on the Board's suggestion in para. 3 of its Proceedings, dated 18th August 1892.

(True Extract.)

(Signed) C. A. GALTON,
Secretary to Government.

ORDER—dated 9th February 1893, No. 358 W., Public Works.

In the estimate for constructing a first-class taluk office at Jayankondacholapuram in the Trichinopoly district received with the foregoing proceedings, provision has been made for enclosing a portion of the compound with aloes. This item will be omitted with reference to para. 3 of the Resolution of the Board of Revenue, Mis. No. 5157, dated 18th August 1892. The estimate, as thus reduced, amounts to Rs. 37,660 and is sanctioned.

2. The Superintending Engineer, VI Circle, will submit a supplemental estimate for a barbed wire fence in lieu of the aloe hedge.

3. The current year's grant for the work is Rs. 6,000.

4. This sanction has been registered as Provincial No. 107 W. of 1892–93 and classified as Civil Buildings, Original Works.

(True Extract.)

Major, R.E.,
Under-Secy. to Govt., P.W.D.

To the Superintending Engineer, VI Circle,
with plan and estimates (7).
" Examiner, Public Works Accounts.
" Revenue Department.
Editors' Table.

Exd. C A. Munisawmy.
Spare Copies

350/2

BUILDINGS AND ROADS.
CIVIL WORKS.

358/2

Govt. of {1893} Madras.
PUBLIC WORKS.

Dated February, 9th.

Recd. *Encl.*

G.O., 9th Feb. 1893, No. 358 W.

FEBRUARY.

Taluk Office at Jayankonda-cholapuram

Estimate reduced to Rs. 37,660 for constructing a first-class —, Trichinopoly district, sanctioned with remarks.

C. No: 43.

S.A.W. 358 W

358/3

The following information is submitted in reply to DW's queries on T's note on the estimate for the Taluk office at Jeyankondasholapuram.

(1) There is an allotment of Rs 6000 for the work in the current year's budget

(2) No schedule contract has been accepted for the work. The tender for the supply of materials was approved by the Supdg. Engr and this was informed to this office vide No: 285 C of 18th January 1892.

Maj
25/1/93

DW

Submitted with reference to your pencil queries on the back of T's note.

Ch
25.1.93

358/3

358/4

(1) Is there any allotment for this work this year?

(2) The Revenue [illegible] [illegible]

Sanction

The suggestion in para 2 of the Revenue Dept's letter that a barbed wire fence should be substituted for an live hedge will be given effect to.

[illegible]
24.1.93

Revised [illegible] in [illegible] of [illegible] & paint [illegible] for asphalting. The amounts has been [illegible]

[illegible]

B 24.1.93

Public Works Department.

Current No. 43
Letter No. 5612
Dated 27th December 1892
From the Revenue Dept.

TECHNICAL NOTE.

Name of Work Const. a Taluq office at Jiam:Kondasolapuram. Trichinopoly Dist.

Amount of Estimate, Rs. 37,700

PARTICULARS OF ESTIMATE.

Main Building	Office	Rs. 34,862
Record racks & ladder		1,320
Subsidiary Buildings	Cook room	448
	Public latrine	600
Gate & fence		(200)
Contingencies	5% Rs. 1626	..
Petty Supervision	3% Rs. 1030	..
Land compensation		..
Sinking a well		270
Total Rupees ...		(37,700)
amount to be sanctd. omitting fence.		37,500

PARTICULARS OF CONSTRUCTION.

Surface soil ordinary earth to a depth of 18 inches

Sub soil hard earth mixed with gravel

Foundations are to be sunk 5 feet deep, the lower 2 feet to be of concrete & the upper 3 feet of brick in chunam.

Basement is to be raised 2 feet & built of brick in chunam.

Walls are to be raised to the heights noted on the type design & built of brick in chunam with flat & semicircular arches over door & window ways &

Plastering or Pointing the interior faces of walls are to be plastered with 2 coats of chunam & the exterior pointed with tar & asphalte

Flooring is to be of 6" square bricks laid on 6" of concrete & pointed with cement except for the record room & jail wards which are to be asphalted 3/4" on 6" of concrete.

Roofing is to be terraced with brick on edge 3" of concrete & 3 courses of flat tiles &c complete

Doors and Windows are to be of teakwood & of the descriptions noted in the estimate & painted with 3 coats of Canara oak paint.

Roof timbers are to be of teakwood & painted with 3 coats of zinc white paint.

Scantlings are correct - as per printed estimate

Rates as far as can be checked are fair with the exception of those detailed below.

The plinth area of the main building is 10,842 square feet, and the cost per square foot will be Rs. 3-3-5.

The ~~plans and~~ estimates have been countersigned by the Collector, Trichinopoly Dist. and approved in the Revenue Dept. with the ~~Department~~. remark that action will ensue in this Dept. on the Board's suggestion in para 3 of its ~~Remarks.~~ proceedings dated 18th Aug. 1892.

Remark

This estimate has been framed with reference to G.O. No. 2917 W dated 4th November 1890. It provides for constructing a first class Taluq office with outhouses at Jayankondacholapuram Udayarpalayam Taluq Trichinopoly Dist.

The estimate for the main building is based on the type design circulated with G.O. No. 3023 W dated 11th November 1891 for terraced roofing & the out houses as per design approved in G.O. No. 1409 W dated 28th May 1889.

Provision has been made in the estimate for fitting the record room with 24 record racks & a wooden moveable ladder as per the design circulated with G.O. No. 802 W dated 19th March 1891 also for sinking a well 7 feet in diameter at a cost of Rs 270 & for providing lightning conductors to the main building for a lump sum of Rs 300.

358/5

The following rates are in excess of the Divisional schedule.

	Rate list		Estimate
Concrete work	14....	against	19-10-..
Brickwork in mortar	20-10-..	- do -	23-10-
- do - superstructure	21-14-..	- do -	24-12-..
Archwork flat & circular	23-14-..	- do -	24-12-..
Teak woodwork	3-8-..	- do -	4-4-..
Terracing	22-....	- do -	28-....
Panel & venetian doors	1-10-..	- do -	1-12-..
Asphalting floor	16-5-4	- do -	22-....

Of these high rates, data are furnished for the items of concrete, brickwork, archwork & terracing. The increased rates for teak wood, panel & venetian doors & for 3/4" asphalting may be sanctioned. The rate for asphalting provides for 4" of concrete, the bed of concrete has already been calculated separately. If schedule rates for items not provided with data are applied the saving will be Rs 1210. This saving is chiefly due to the decrease in the rate for woodwork.

Compound wall of brick in chunam

Spaces on each side with [illegible] & wooden shutters are provided to-gether with a ditch & aloe edge but the Board in para 3 of its resolution dated 18th Augst 1892 suggest that as aloe hedges are not of sufficient protection against cattle & that they are supposed to harbour snakes, a barbed wire fencing may be substituted therefor.

The site proposed is Govt. land hence no compensation has been provided in the estimate.

The Taluq Office is proposed in [illegible]

20.1.93.

The proposed Taluq Office is made to face the East, as per site plan.

Trichinopoly Collector's Office.

10th June 1892.

Enc. 1.

No. 285/4

163 OF 1892

FROM

W. H. Welsh Esquire.

~~AG~~ COLLECTOR OF

TRICHINOPOLY.

358/6

TO

THE SECRETARY TO THE COMMISSIONERS

OF LAND REVENUE,

MADRAS.

SIR, With reference to Boards' Progs. No. 7498/24.11.90 mis, I have the honour to forward an estimate amounting to Rs. 37700, with report and site plan for constructing a 1st class Taluk Cutcherry at Jayankondasholapuram and request that the Board will be pleased to obtain the sanction of Government at an early date.

2. The Collection of materials was put in hand last official year and is being proceeded with. An allotment of Rs. 6000 has also been provided for the work in the current year's budget.

I have the honour to be,

Sir,

Your most obedient Servant,

A. Krishnaswamaiyar

For Collector.

[illegible]

Reg 13/6

1892

BOARD'S GEN. REC. LAND 1632 of 1892 Department

FROM

The Collector of
Trichinopoly

To

The Secretary to the
Commissioners of
Land Revenue
MADRAS.

11 JUN 92

Dated 10th
Despd. 10th
Recd.
} June 1892

No. 285/4

Enclosures 1.

Subject

Forwarding an estimate for Rs 37700 with report & site plan for constructing a 1st class Taluk cutcherry at Jayankondasholapuram & requesting to obtain the sanction of Government at an early date.

Office of the Supg. Engineer
III Circle

No. 635 P.C. Trichinopoly 1st August 1892

From

Lt. Col. A. C. Smith R.E.
Superintending Engineer, III Circle,

To

The Collector of
Trichinopoly

Sir,

With reference to your letters
No: 113/12 & 117/12 dated respectively 21st and
23rd July 1892, forwarding copies of
the Proceedings No. 4203 Mis dated
9th July 1892 and Reference dated 11th
July 1892 on G.O. No. 1632 of 1892 of the Board
of Revenue calling for an explanation
of the increase in the rates provided for
certain items in the estimates for con-
-structing first class Taluk cutcherries at
Jayankondacholapuram and at Musiri,
I have the honor to observe that the
Board appear to have compared the
rates in the above estimates with
those in the schedule or estimate
circulated with G.O. No. 3023 W. dated
11th November 1891, by Government with
the revised type designs, taking the
latter as a standard estimate in

every respect, and thus arrived at the conclusion that certain rates in the former are in excess of those in the latter. This conclusion is incorrect.

2. The estimate which accompanied the type design, must be considered as standard only so far as the quantities, (except in foundations) are concerned. The rates entered therein must on no account be taken as standard rates for the whole presidency. Rates for materials and labour must as a matter of course, be fluctuating according to the local demands, and for several other causes. There was in fact, no necessity for entering rates and amount in the standard estimates, unless they were intended to give an approximate idea of the cost of the building at the rates that prevailed at the Presidency town at the time it was prepared. It will be also seen from the G.O. above quoted that only "the Schedules of quantities" and not the whole estimates were circulated for guidance.

3. Schedules of ordinary rates in each district are prepared and submitted to the Chief Engineer every year, and the rates in our estimates are generally based on these schedules. Whenever the rates of the former are appreciably or by 10 per cent exceeded, they are required to be supported by data.

4. In the case of the two estimates in question, data have been attached in support of the rates that were considered to be much in excess of the schedule rates, and the Board do not appear to have taken into consideration these data. As regards the items specially noticed by them the following table and explanation will show that the excesses are not so high as considered by them.

Item Number	Items noted by the Board of Revenue	Unit	Taluk cutchery at Jankondachola-puram		Taluk cutchery at Musiri	
			Schedule rates	Estimated rates	Schedule rates	Estimated rates.
1	Concrete	100 cft.	14 - -	17 10 -		
2	Foundation and basement with stock bricks in chunam	100 cft.	20 10 -	23 8 -		
3	Superstructure Do	100 cft.		24 12 -		
4	Teak wood - wrought and put up	1 cft.	3 8 -	4 4 -	3 8 -	4 - -
5	Teak wood Panel & Venetian doors	1 sft.	1 10 -	1 12 -	1 10 -	1 12 -
6	Do Panel doors	Do	- - -	1 8 -	- - -	1 8 -
7	Flooring with 8" square bricks &c	100 sft.	12 - -	13 - -	12 - -	12 - -
8	Teak wood. Strong battened doors	1 sft.	- - -	- - -	1 2 -	1 8 -
9	Do - Venetian window with glazed shutters inside frames &c	Do	- - -	- - -	- - -	1 14 -
10	Do - battened windows &c	Do	- - -	- - -	- - -	1 12 -
11	Do - Venetian window with glazed top frame &c	Do	- - -	- - -	- - -	2 - -
12.	Flooring with asphalte	100 sft.	- - -	- - -	21 - -	21 - -

5. (a) Items No: 1, 2 & 3 – Data accounting for the excess in each case have been attached to the estimate. Bricks required for these items are to be brought to the work spot from a distance of eleven miles; hence the excess in the estimate rate.

(b) Item No: 4 – As observed by the Board, teak wood is, at times largely imported at Negapatam, but the distance of its carriage by rail and land is to be taken into consideration. In the present case, teak wood for the Musiri cutchery is to be brought down by rail from Negapatam to Trichinopoly and from the latter place to the workspot – a distance of 24 miles – by land. Teak wood for the cutcherry at Jayankondacholapuram is to go by rail to Kumbakonam and thence to the workspot – a distance of 18 miles – by land. Again in the case of the latter work skilled labour to a large extent is to be imported from Kumbakonam.

(c) The other items of wood work call for no special explanation; the foregoing will account for the slight excesses.

(d) Item No: 7 vide explanation against items 1, 2 & 3.

(6) With reference to the Board's proposal to have a wire fencing to the Musiri cutchery, instead of aloe fencing provided in the estimate, I think a supplemental estimate may, if necessary, be submitted for the same hereafter, or it may be sanctioned in a deviation statement.

(7) I am sending a copy of this letter to the Chief Engineer, D.P.W. and request that you will be good enough to ask the Board to submit to Government at once the estimates for the cutchery at Jayankondacholapuram, as outlay is being incurred on the 2 works since the last year in anticipation of sanction to the estimates.

I have &c

(Sd) A. C. Smith
Lt. Col. R.E.
Superintending Engineer III Circle

358/9

True copy

A. Krishnaswamaiyer
for Collector

[Enc]losure No. 1

to letter No. 385/4 dated 16-8-92

from the Collector of Trichinopoly

cee:

ent. 43 of 93

Trichinopoly Collector's Office.

16th August 1892.

Enc. 1.

No. 385/4

BOARD'S GEN. REG. No. 2281 OF 1892
LAND REVENUE.

From

W. H. Welsh Esquire.

COLLECTOR OF

TRICHINOPOLY.

358/10

To

THE SECRETARY TO THE COMMISSIONERS

OF LAND REVENUE,

MADRAS.

SIR, Adverting to Board's Reference dated 11th Ultimo on General Register No. 1632 and Board's Procs. No. $\frac{4203}{9.7.92}$ Mis, calling for an explanation of the increase in the rates provided for certain items in the estimate for the Construction of first class Taluk Cutcherris at Jayankondasholapuram and at Musiri, I have the honour to enclose copy of letter from the Superintending Engineer VI. Circle No. $\frac{635.\ T.C}{1.8.92}$ furnishing the explanation called for.

I have the honour to be,

Sir,

Your most obedt. Servant,

A. Krishnaswamaiyar

For Collector.

JH

Before a.m. 13/8

EMERGENT.

G

Wt 13/8.

BOARD'S GEN. REG. No. 2281 OF 1892
LAND REVENUE

1892

Department.

FROM

The Collector of
Trichinopoly.

BOARD OF REVENUE 12 AUG. 92 MADRAS

To

The Secretary to the
Commissioners of
Land Revenue
MADRAS.

Dated 10th
Despd. 10th August 1892
Recd.

No. 285/4

Enclosures. One

Submitting copy of letter from the Supdg Engr. VI Circle No. 635-Pe / 1-8-92 regarding increase of rates provided for certain items in the Estimate for the Construction of 1st Class Taluk cutcheries at Jayankondasholapuram & Musiri

1/ f.w. C.P. 43 of 93

Recd 13-8-92 at 3-50

[illegible] 13/8

13/8

Read the following papers

G.O. dated 27 Dec 1892, No 5692 Rev

REVENUE DEPARTMENT.

PROCEEDINGS OF THE MADRAS GOVERNMENT.

Read the following Proceedings of the Board of Revenue, Land Revenue dated 18th August 1892 No. 5157 Mis on letter from the Collector of Trichinopoly dated 10th June 1892 No. 285/4 and on ~~the~~ the following reference thereon dated 11th July 1892:—

358/11

In the revised standard design, the estimate for a taluk office with terraced roofing is given as Rs 28,910. Adding to this amount, the estimated expenditure for the marginal items which have not been included in the above estimate, the total comes to Rs 32,048. The difference between this amount and the estimate for the new taluk cutchery sent with the letter read above is Rs 5,652. The difference is large and is due mainly to increase in the rates under the following heads:—

	Rs
Record racks	1,320
Cook room	448
Latrine	600
Gate room & ground walls	200
Well	270
[illegible]	300
	3138

	Rate as in the standard estimate Rs	as in the estimate of the Executive Engineer Rs.
1. Concrete	14- 0- 0	17- 10- 0 per 100 c. ft.
2. Foundation and basement with stock bricks in chunam	19- 8- 0	23- 8- 0 Do.
3. Superstructure Do.	Do. 20- 8- 0	24- 12- 0 Do.
4. Teak wood wrought & put up.	3- 8- 0	4- 4- 0 per c. ft.
5. Cuddapah slabs for cornice	24- 8- 0	27- 8- 0 per 100 Sq. ft.
6. Teak wood panel & Venetian doors	1- 1- 0	1- 12- 0 per Sq. ft.
7. Teak wood panel doors	„ 14- 0	1- 8- 0 Do.
8. Flooring with 8" Sq. brick &c.	7- 13- 0	13- 0- 0 per 100 Sq. ft.

The increase under item 5 above has been explained

The

The Collector is requested to call upon the executive Engineer to explain the increases in the remaining items. The Board observes that teak is largely imported at Negapatam.

Also on letter from the Collector of Trichinopoly dated 10th August 1892 No. 385/4.

Resolution dated 18 Aug 1893, Mis. No. 5115

The estimate for building a new taluk Cutcherry at Jayankondasholapuram at a cost of Rs 37,700 received with the first letter read above is submitted for the early sanction of Government.

2. The rates given for certain items appearing large, the Collector was called upon to furnish an explanation. This is submitted with the second letter read above. The explanation appears satisfactory.

3. A portion of the compound wall is proposed to be fenced with aloes. As these plants are not considered a sufficient protection against cattle and are, moreover, supposed to harbour ~~sn~~ snakes, the Board suggests that a barbed wire fence may be substituted therefor.

—:—

Read also Proceedings of the Board of Revenue, Land Revenue No. 7710 and 7894 dated 24th November and 1st December 1892, respectively, on certain petitions regarding the transfer of Taluk head-quarters from Jayankondasholapuram to Udayarpalayam.

Order

Order thereon dated 27th December 1892 No. 5692

38
3/12

The Government is unable to accept the Board's recommendation in the second paper read above. As regards central situation, there is little to choose between Udayarpalayam and Jayankondasholapuram and the Deputy Collector's description of the superior advantages of the former place seems somewhat exaggerated. The Government is unable to agree with the Board in thinking that the fact that Udayarpalayam is the head quarters of a large Zemindari is a point in its favor. On the contrary it appears to be a serious objection to the location of the Cutcherry there. Moreover a contract has already been given for the construction of the building at Jayankondasholapuram and a change at this juncture cannot but cause loss and extra expenditure. On these grounds the proposed transfer appears undesirable.

2. The plan and estimates are accordingly approved and transferred to the Public Works Department for sanction. Orders will issue in that Department on the Board's suggestion in para 3 of its Proceedings dated 18th August 1892.

(True Extract)

Secretary to Government.

To
The Board of Rev. L. R with 2 letters from Collr. & their enclosures returned.
" Public Works Department with six enclosures (to be returned)

P. W. CURRENT No. 43

Govt. of (1892) Madras.

REVENUE.

To

The Public Works
Dept.

Dated
Recd. 3rd January 1893 Encl. 10 + (+1 sketch)

Mis. G.O., 27th Dec 1892, No. 5692

SUBJECT.

Transferring for sanction papers re: to the construction of a Taluk cutchery at Jayankondacholapuram. Trichinopoly Dt.

No. 358 W. d/19 February 1893. PUBLIC WORKS DEPARTMENT.

PROCEEDINGS OF THE MADRAS GOVERNMENT.

39

READ the following

Pros. in the Rev. Dept. No. 5692 d/27th December 1892

75/17

W
8 Feb

H.O.
15 Feb

In the estimate for constructing a first class taluk office at Jayankondacholapuram in the Trichinopoly District received with the foregoing proceedings, provision has been made for enclosing a portion of the Compound with aloes. This item will be omitted with reference to para 3 of the Resolution of the Board of Revenue No. 5157 mis d/18th August 1892. The estimate, as thus reduced, amounts to Rs. 37,660 and is sanctioned.

2. The Superintending Engineer VI Circle will submit a Supplemental estimate for a barbed wire fence in

in lieu of the aloe hedges

3. The current year's grant for the work is Rs. 6000.

4. This Sanction has been registered as Provincial No. 107 W of 1892-93 and classified as Civil Buildings, Original Works.

~~(2) His Excellency the~~

~~(1) The Hon. Sir Henry Stokes~~

4/2/93

2-2-93

[illegible] communicate.

thus G.O. to the Editor's Table. 15 [illegible] 4/2/93

28/2

To

The S.E. VI Circle with plan & estimates

" Exar. P.W. acct.

" Rev. Dept.

Editor's Table

H.M. 4/2/93

Rw H.E. 6/2 R 9/2

35/14

C [illegible] 43

27-3-18

Govt. of (1893) Madras.
PUBLIC WORKS.

Dated

Recd.

Encl.

G.O., 9th February 1893 No. 358. W.

Taluk Office at
Jayankondacholapuram

Estimate reduced to Rs 37,660
for constructing a first
class ——, Trichinopoly
District, sanctioned with
remarks.

97/6

3/10/2