26

(1) பக்கங்களின் எண்ணிக்கை 24

(2) புதுக்கித் திருப்பிய நாள் 1/94

(3) ஆதாரங் குறிப்பவர் சுருக்கொப்பம்

தமிழ்நாடு ஆவணக் காப்பகம்.

தமிழ்நாடு அரசு

P-W துறை

அரசாணை எண்.
மு. கோப்புத் தாள் எண். 367

அச்சகம்
பலவகை

நாள் : 9-2-1853 199

13

மடிக்கவோ கண்டபடி கையாளவோ கூடாது.

ஆவண. கா. 1—18,006—6-9-90.

The estimates may
be sanctioned
omitting the amounts
provided for cement
washes sealing for
supplementary rates
for barbed wire
fencing — 367/7

Separate memo
to go to S.E. regarding
increase of rates,
pointing out that
there is no reason
to take increase into
account for the
rates of asphalte
flooring, as it is
already provided

and further
point out the
necessary for
submitting a
General Abstract
for each project
which should
now be done

11/2/93

B 21/1/93
23/1/93

9th February 1893, No. 367 W., Public Works.

367/2

GOVERNMENT OF MADRAS.

PUBLIC WORKS DEPARTMENT.

Buildings and Roads.
Civil Works.

Read—the following paper :—

G.O., dated 19th December 1892, Mis. No. 5574, Revenue.

Read—the following paper :—

Proceedings of the Board of Revenue (Land Revenue), dated 28th October 1892, Mis. No. 6977.

Read—the following letter from Lt.-Col. R. R. E. DRAKE-BROCKMAN, R.E., Superintending Engineer, IV Circle, to the Collector of Salem, dated 6th October 1892, No. 348.

As called for in G.O., No. 1733 W., dated 21st June 1890, embodied in Revenue Department endorsement No. 3519, dated 9th idem, I have the honour to forward, for your approval and transmission to Government for sanction and provision of funds, plans and estimates for the following works :—

		RS.
1.	Constructing a 1st-class taluk office at Tiruchengód	38,280
2.	Do. do. at Tirupatúr	40,980

2. Revised standard design with tiled roof approved of in G.O., No. 3023 W., dated 11th November 1891, has been adopted for the above offices.

3. No provision was made in the printed estimate circulated with the above quoted Government order for record racks, &c., which, however, have been provided in these estimates, as they are absolutely necessary.

Endorsement by the Collector of Salem, dated 15th October 1892, No. 3509.

Submitted to the Board of Revenue (Land Revenue) with the estimates and plans countersigned.

2. Accommodation is provided in both the plans for the Stationary Sub-Magistrate's Court, although at present it is only for Tirupatúr that one has been sanctioned.

Resolution—dated 28th October 1892, Mis. No. 6977.

The plans and estimates for constructing two first-class taluk cutcherries, one at Tiruchengód and another at Tirupatúr, at a cost of Rs. 38,280 and Rs. 40,980, respectively, received with the letter read above, are submitted for the sanction of Government (subject to the modification proposed in para. 4 below) with reference to G.O., No. 4027, dated 30th June 1890.

2. In his report accompanying the estimate for the Tirupatúr taluk office, the Executive Engineer says that he has provided for a latrine for prisoners. This is unnecessary with reference to G.O., dated 8th September 1882, No. 892, J.D. No provision, however, has been made for public latrines in either of the buildings as required in G.O., dated 28th May 1889, No. 1409 W. The latrine intended for prisoners may, however, be used by the taluk officials and the public.

and further
forward the
necessary for
submitting a
General Abstract
for each project
which would
now be done
—
HMW
11/1/93

B 21/1/93
23/1/93

9th February 1893, No. 367 W., Public Works.

367/2

GOVERNMENT OF MADRAS.

PUBLIC WORKS DEPARTMENT.

Buildings and Roads.
Civil Works.

Read—the following paper :—

G.O., dated 19th December 1892, Mis. No. 5574, Revenue.

Read—the following paper :—

Proceedings of the Board of Revenue (Land Revenue), dated 28th October 1892, Mis. No. 6977.

Read—the following letter from Lt.-Col. R. R. E. DRAKE-BROCKMAN, R.E., Superintending Engineer, IV Circle, to the Collector of Salem, dated 6th October 1892, No. 348.

As called for in G.O., No. 1733 W., dated 21st June 1890, embodied in Revenue Department endorsement No. 3519, dated 9th idem, I have the honour to forward, for your approval and transmission to Government for sanction and provision of funds, plans and estimates for the following works :—

				RS.
1. Constructing a 1st-class taluk office at Tiruchengód		...	...	38,280
2. Do.	do.	at Tirupatúr	... ...	40,980

2. Revised standard design with tiled roof approved of in G.O., No. 3023 W., dated 11th November 1891, has been adopted for the above offices.

3. No provision was made in the printed estimate circulated with the above quoted Government order for record racks, &c., which, however, have been provided in these estimates, as they are absolutely necessary:

Endorsement by the Collector of Salem, dated 15th October 1892, No. 3509.

Submitted to the Board of Revenue (Land Revenue) with the estimates and plans countersigned.

2. Accommodation is provided in both the plans for the Stationary Sub-Magistrate's Court, although at present it is only for Tirupatúr that one has been sanctioned.

Resolution—dated 28th October 1892, Mis. No. 6977.

The plans and estimates for constructing two first-class taluk cutcherries, one at Tiruchengód and another at Tirupatúr, at a cost of Rs. 38,280 and Rs. 40,980, respectively, received with the letter read above, are submitted for the sanction of Government (subject to the modification proposed in para. 4 below) with reference to G.O., No. 4027, dated 30th June 1890.

2. In his report accompanying the estimate for the Tirupatúr taluk office, the Executive Engineer says that he has provided for a latrine for prisoners. This is unnecessary with reference to G.O., dated 8th September 1882, No. 892, J.D. No provision, however, has been made for public latrines in either of the buildings as required in G.O., dated 28th May 1889, No. 1409 W. The latrine intended for prisoners may, however, be used by the taluk officials and the public.

3. The Board observes that the compound wall for Tiruchengód cutcherry is estimated at Rs. 4,197 and for Tirupatúr at Rs. 3,982. The estimate seems high, but the large amount is probably required for walling the whole of the compound.

4. With reference to para. 2 of the Collector's letter, the Board considers that as no Stationary Sub-Magistrate has been sanctioned for Tiruchengód, no accommodation need be provided for such an officer in the proposed taluk cutcherry at that place.

Order—dated 19th December 1892, Mis. No. 5574, Revenue.

The plans and estimates will be transferred to the Public Works Department with an expression of concurrence in the Board's remarks in para. 2.

2. With reference to the last sentence of para. 3, the Government considers that a barbed wire fence with at least four strands of wire is preferable to a compound wall.

3. The Government does not concur in the Board's remark in para. 4. Before long every taluk will have a Stationary Sub-Magistrate and it will be much cheaper to build a court for him at once than to add it on two or three years hence. Moreover, a new cutcherry on the standard plan will be lopsided if the Stationary Sub-Magistrate's Court is omitted. In any case, two courts will be wanted, as, if there is no Stationary Sub-Magistrate, there will be a Sheristadar exercising magisterial powers and when he is trying cases there must be some accommodation for the Tahsildar.

(True Extract.)

(Signed) C. A. GALTON,
Secretary to Government.

Order—dated 9th February 1893, No. 367 W., Public Works.

The estimates received with the foregoing Proceedings have been reduced with reference to para. 2 thereof by omitting the provision for compound walls and sanction is accorded to the reduced amounts as shown below :—

Provincial.

	RS.	
1. Constructing a first-class taluk office at Tiruchengód in the Salem district	33,660	No. 108 W. of 1892–93.
2. Constructing a first-class taluk office at Tirupatúr in the Salem district	36,600	No. 109 W. of 1892–93.

2. The Superintending Engineer, IV Circle, will submit a supplemental estimate for enclosing each of the offices with a barbed wire fence.

3. The current year's grant for each of the works is Rs. 6,000.

(True Extract.)

Major, R.E.,
Under-Secy. to Govt., P.W.D.

To the Superintending Engineer, IV Circle,
with plans and estimates (16).
„ Examiner, Public Works Accounts.
„ Revenue Department.
Editors' Table.

Exd. C. A. Munisawmy.
Spare Copies

367/93

BUILDINGS AND ROADS.
CIVIL WORKS.

Govt. of {1893} Madras.
PUBLIC WORKS.

367/2

Dated February, 9th.

Recd. *Encl.*

G.O., 9th Feb. 1893, No. 367 W.

FEBRUARY.

Taluk Offices at Tiruchengod and Tirupatur

Estimates reduced respectively to Rs. 33,660 and Rs. 36,600 for constructing first-class — in the Salem district, sanctioned with remarks.

No 348

Superintending Engineer's Office
6th October 1892

From
Lieut. Col: R. R. E. Drake Brockman R.E.
Superintending Engineer
4th Circle.

To,
The Collector of
Salem District 367/3 10

L.B.P. 12.7.90 / 4406

Sir,

[illegible] dated 30 June 1890 No 409

Enclosures
4. Estimates with Abstracts
4. Sheets of levels of sites of buildings
5. Plans.
2. Reports
2. Data

As called for in G.O. No 1733 W dated 21st June 1890 embodied in Revenue Department endorsement No 3519 dated 9th idem, I have the honor to forward, for your approval and transmission to Government for sanction and provision of funds, plans and estimates for the following works.

1. Constructing a 1st Class Taluq Office at Tiruchengod Rupees -- -- -- -- -- — -- --38280

2 Constructing —do— do —at Tirupatur 40,980

2. Revised Standard design with tiled roof approved of in G.O. No 3,023 W, dated 11th November 1890 has been adopted for the above Offices.

3. No provision was made in the printed estimate, circulated with the above quoted G.O. for Record racks &c., which however have been provided

in

[illegible] **Department.**

From the Collector

and District Magistrate,

Salem.

BOARD'S GEN. REG. No 3226

To

The Secretary to the
Commissioners of
Land Revenue, Madras

Dated 15th October 1892

No. 3509/4

Enclosure.

Subject.

Submitting copy of Superintending Engineer's letter forwarding for approval and transmission to Government for sanction estimates for constructing Taluq Cutcherries at Tiruchengod and Tirupatur Salem District

in these estimates, as they are absolutely necessary.

I have &c.
(Signed) R. Col. Drake Brockman
Lieut Col: R.E.
Supg Engineer 4th Circle

BOARD OF REVENUE
17 OCT. 92
MADRAS.

Endorsement
No 3509/4 d/15-10-92

Submitted to the Board of Revenue (Land Revenue), with the Estimates and plans countersigned.

2. Accommodation is provided in both the plans for the Stationary Sub Magistrate's Court although, at present, it is only for Tirupatur that one has been sanctioned.

For Ag Collector
E K.

BOARD'S GEN. REG. No 3226

13/10

Read the following paper: G.O., dated 19th Dec. 1892, Mis No. 5574, Rev.

REVENUE DEPARTMENT.

367/4

PROCEEDINGS OF THE MADRAS GOVERNMENT.

Read the following ~~Proceedings~~ paper of the Board of Revenue (Land Revenue) d/28 October 1892 No 6977 Mis. on the following Endorsement of the Collector of Salem, d/15 Oct 92 No 350 on letter from the Superintending Engineer IV Circle d/6 October 1892 No 348.

As called for in G.O. No 1733 W. d/21 June 1890 embodying in Revenue Department Endorsement No 3519 dated 9: idem, I have the honor to forward for your approval and transmission to Government for Sanction and provision of funds, plans and Estimates for the following works.

1. Constructing a 1 Class Taluk Office at Tiruchengod Rupees ...... 38280.
2. Constructing Do Do at Tirupatur. 40,980.

2. Revised Standard design with tiled roof approved of in G.O. No 3023 W. dated 11 November 1891, has been adopted for the above Offices.

3. No provision was made in the printed Estimate, circulated with the above quoted G.O. for Record racks &c which however have been provided in these Estimates, as they are absolutely necessary.

Endorsement.

Submitted to the Board of Revenue (Land Revenue) with the Estimates and plans countersigned.

2. Accommodation is provided in both the plans for the Stationary Sub Magistrates' Court, although at present it is only

only for Tirupatur that one has been sanctioned.

Resolution:– Dated 28th Oct. 1892, Mis No. 6977

The plans and Estimates for constructing two first Class Taluk Cutcherries one at Tiruchengod and another at Tirupatur at a cost of Rs 38280 and Rs 40980 respectively, received with the letter read above, are submitted for the sanction of Government (subject to the modification proposed in para 4 below) with reference to G.O. $\frac{30-6-90}{1027}$.

2. In his report accompanying the Estimate for the Tirupatur Taluk Office, the Executive Engineer says that he has provided for a latrine for prisoners. This is unnecessary with reference to G.O. 8. Septr. /82 No 892, J.D. No provision, however, has been made for public latrines in either of the buildings as required in G.O. 22. May 1889 No 1409 W. The latrine intended for prisoners may however be used by the Taluk Officials and the public.

3. The Board observes that the Compound Wall for Tiruchengod Cutcherry is Estimated at Rs 4197, and for Tirupatur at Rs 3982. The Estimate seems high; but the large amount is probably required for walling the whole of the Compound.

4. With reference to para 2 of the Collector's letter, the Board considers that as no Stationary Sub Magistrate has been sanctioned for Tiruchengod, no accommodation need be provided for such an Officer in the proposed Taluk Cutcherry at that place.

Order thereon, 19 December 1892 No 5574.

The plans and Estimates will be transferred to the Public Works Department with an expression of concurrence in the Board's remarks in para 2.

2. With reference to the last sentence of para 3, the Government considers that a barbed wire fence with at least four strands of wire is preferable to a Compound wall.

3. The Government does not concur in the Board's remark in para 4. Before long every taluk will have a Stationary Sub-Magistrate and it will be much cheaper to build a Court for him at once than to add it on two or three years hence. Moreover a new Cutcherry on the Standard plan will be lopsided if the Stationary Sub Magistrate's Court is omitted. In any case, two Courts will be wanted as, if there is no Stationary Sub Magistrate there will be a Sheristadar exercising magisterial powers and when he is trying cases there must be some accommodation for the Tahsildar.

(True Extract)

Secretary to Government

To

The Public Works Deptt. with 17 Enclosures

" Commr. of Land Revenue.

367/9

367/[illegible]

P. W. CURRENT No. 12733

Govt. of {1892} Madras.

REVENUE.

To

The Public Works Depts

Dated }
Recd. 23.12.92 }

Encl. 17 ×
(9 plans ×)

Mis. G.O., 19: Decr 1892, No. 5574

SUBJECT.

Transferring to the P.W.D. plans & Estimates for constructing two 1. Class Taluk cutcherries in the Salem Dt.

1609 W d/ 28-5-89 ×
1733 W d/ 21-6-90 ×
4262 13. C d/ 20-10-90 ×
2895 C d/ 3-7-90 ×
3023 W d/ 11-11-91 ×

367/6

Public Works Department.

367/6

Current No. 12733
Letter No. 5574
Dated 19th December 1892
From the Revenue Dept.

TECHNICAL NOTE.

Name of Work Constructing a Taluq Office at Tiruchengode. Salem District

Amount of Estimate, Rs. 38,280

PARTICULARS OF ESTIMATE.

Main Building	Office	Rs.	30,440.
Record racks & ladders.		"	1,300
Subsidiary Buildings	Cook house	"	380
	Public latrine.	"	540
Gate & compound wall		"	(4,620)
Contingencies	5% Rs 1680	"	..
Petty Supervision	5% Rs 1693	"	..
Land compensation		"	1,000
Total Rupees ...			38,280.
To be sanctioned by omitting the compound wall &c			(33,660)

PARTICULARS OF CONSTRUCTION.

Surface soil soft earth to a depth of 4 feet.

Sub soil hard gravel.

Foundations are to be sunk 5 feet deep the lower 2 feet to be laid with concrete & the upper 3 feet of burnt stone in chunam.

Basement is to be raised 2 feet & built of burnt stone in chunam.

Walls are to be raised as per heights noted on the type design & built of burnt stone in chunam with flat & semi-circular arches over door & window ways &c.

~~Plastering or~~ Pointing is that of chunam to both faces of the walls, interior & exterior.

Flooring of all the rooms is that of cut granite stone laid on 6" of concrete & pointed with cement except for the jail wards & record rooms which are to be asphalted 3/4" thick on a bed of concrete 6" thick.

Roofing is that of flat & pan tiles laid on teak reapers, rafters, purlins, trusses &c.

Doors and Windows are that of teakwood & of the descriptions noted in the estimate & painted with 3 coats of silicate paint.

Roof timbers are that of teakwood.

Scantlings are correct as per printed estimate rates.

Rates as far as can be checked are fair except those detailed below.

The plinth area of the main building is 10842 square feet, and the cost per square foot will be Rs. 2-13-0.

The plans and estimates have been countersigned by the Collector, Salem District and approved in the Revenue Dept. ~~Department~~ with the remark that barbed wire fence is preferable to a compound wall.

REMARKS.

This estimate has been framed with reference to G.O. No. 1733 W dated 26th June 1890. It provides for constructing a First class Taluq office with outhouses at Tiruchengode in the Salem Dist.

The estimate for the main building is based on the type design approved in G.O. No. 3033 W dated 11th November 1891 & the outhouses as per design circulated with G.O. No. 1409 W dated 28th May 1889.

The site selected for the building is on private land & for which Rs 1000 has been provided in the estimate for compensation.

The necessity for building the walls with burnt stone in chunam is owing to no suitable clay being available for good bricks.

367
(19)

Provision has been made in the estimate for fitting the record room with 24 racks each 6 × 2½ × 9 11/12 ft & a moveable ladder as per design circulated with G.O. No. 80 W dated 19th March 1891 together with arm racks, accoutrement pegs & a moveable shelf to the Inspector's room. The latter 3 items have not been provided for in the printed estimate for Taluq offices. The racks & pegs in the existing office may be utilized but the cost of these items as provided in the estimate is trifling, viz Rs 10. hence they may be passed.

The following rates are in excess of the Divisional Schedule.

	Estimate		Rate list
Burnt stone in mortar	18....	against	17...
Teak woodwork ——	4.8..	do	4...
Batten doors ——	1.5...	do	..14..
Concrete bed for floor	7....	do	6..
3/4" asphalting ——	20....	do	16....
Pointing with chunam	1.8..	do	1.4..

Data are submitted only for the first item of burnt stone in mortar. If schedule rates be adopted for the other items, the saving will be Rs 1220.

In this case also the rate for asphalting floor 3/4" thick is included at Rs 20 per square as per schedule rate. The schedule rate of Rs 20 provides for 4" of concrete & 3/4" of asphalte, the thickness of concrete having been already estimated under the item of 7" levelling course to the rooms 6" in depth, it is thought that the value of 6" of concrete included in the schedule rate should be deducted, leaving Rs 16 for 3/4" asphalting only.

No general abstract accompanies the estimate as required by Code rules vide para of Chap VII. Vol 1.

The site plan shews the building to face the East. This appears to be objectionable as it will be open to the [illegible] full force of the sun. It may be made to face the north.

19-1-93.

Public Works Department.

Current No. 12,733

Letter No. 5,574

Dated 19th December 1892

From the Revenue Dept

TECHNICAL NOTE.

Name of Work Constructing a Taluq Office at Tirupatur, Salem District

Amount of Estimate, Rs. 40,980

PARTICULARS OF ESTIMATE.

Main Building Office	Rs.	34,230
Record racks & ladder	"	1,300
Subsidiary Buildings { Cook house	"	460
Public latrine	"	610
Gate & compound wall		(4,380)
Contingencies 5% (Rs 1801)	"	
Petty Supervision 5% (Rs 1809)	"	
Land compensation	"	
Total Rupees ...		40,980
Ex. excluding compound wall		36,600

PARTICULARS OF CONSTRUCTION.

Surface soil Hard gravel to a depth of 2 feet

Sub soil soft rock 2½ feet below.

Foundations are to be made 5 feet deep, the lower 2 feet to be laid with concrete & the upper 3 feet of rubble stone in chunam.

Basement is to be raised 2 feet & built of rubble stone in chunam.

Walls are to be raised as per heights noted on the type design & built of rubble stone in chunam with flat & semicircular archwork over doors & windows

~~Plastering or~~ Pointing is to be of chunam to both faces of the walls, interior & exterior.

Flooring / of all the rooms is to be of cutstone laid on 6" of concrete & pointed with portland cement except for the Jailrooms & record room which are to be of 3/4" asphalte.

Roofing is to be of flat [illegible] tiles laid on teak reapers, rafters, purlins, trusses &c.

Doors and Windows are to be of teakwood & of the descriptions noted in the estimate & painted with 3 coats of silicate paint.

Roof timbers are to be of teakwood

Scantlings are correct as per printed estimate.

Rates as far as can be checked are fair except those detailed below

The plinth area of the main building is 1842 square feet, and the cost per square foot will be Rs. 3-2-6.

The plans and estimates have been countersigned by the Collector, Salem Dist and approved in the Revenue Dept with the ~~Departmen~~t. remark that barbed wire fencing is preferable to a compound wall.

REMARKS.

This estimate has been framed with reference to G.O. No 1733 W dated 26th June 1890. it provides for constructing a first class Taluq office with out-houses at Tirupatur in the Salem Dist.

The estimate for the main building is based on the type design approved in G.O. No 3023 W dated 11th November 1891 & the out houses, as per design circulated with G.O. No 1409 W dated 28th May 1889.

The estimate provides for 24 wooden record racks & one moveable wooden ladder, as per design approved in G.O. No 802 W dated 19th March 1891.

The necessity for constructing the walls with burnt stone in chunam is owing to no good brick earth

367/11B

This possibly might do, but the greater depth had better be allowed to stand.

[illegible] [illegible] [illegible] table & the flooring with cutstone obtained from Munikolam tank under orders from this office vide Memo No. 4263 C dated 20th October 1890.

The building is to be constructed on Govt land, hence no provision is made for compensation.

The depth of foundations proposed, viz 5 feet appears to be excessive, the surface soil being hard gravel to a depth of 2 feet & the sub soil soft rock. it is thought that a depth of 3½ or 4 feet of solid concrete bed, 4 feet in width will be sufficient & much cheaper.

The following rates are in excess of the Divisional schedule

	Estimate		Rate list
Burnt stone in mortar	26-6--	against	17----
Teakwood	4-8--	do	4----
Teak batten doors	1----	do	-14--
Levelling course of concrete	7----	do	6----
3/4" asphalting	20----	do	16----
Pointing with chunam	1-8--	do	1-4--

Data for the item of burnt stone in chunam are submitted. if schedule rates be applied for the other items the saving will be Rs 132[illegible]

The frontage of the proposed building is made to face the S.E. parallel to the road.

In the report accompanying the estimate, the Executive Engineer mentions that provision is made for a latrine for prisoners in a

but the estimate
not provide for such a latrine, the Board of Revenue remark on this point & state that the latrine for prisoners is necessary & that the latrine estimated may however be used for the Taluq officials & the public. The plan & estimate for the latrine now submitted, though designated "Jail latrine" is of the area & of the number of seats, as provided in the standard design for public latrines, vide plan circulated with G.O. No. 1409 W dated 28th May 1889.

No general abstract accompanies the estimate as required by para 7, Chap VII, Vol I of the Code.

19.1-93.

367 W/

No. 367 W. d/9th February 1893. PUBLIC WORKS DEPARTMENT.

PROCEEDINGS OF THE MADRAS GOVERNMENT.

367/1893

READ the following

Print

Pro. S. in the Rev. Dept. No. 5574 d/19th December 1892

The estimates received with the foregoing proceedings have been reduced with reference to para 2 thereof by omitting the provision for compound walls and sanction is accorded to the reduced amounts as shown below:—

W / 8 Feb

Ulo 5 Feb

Provincial

1. Constructing a first class taluk office at Tiruchengod in the Salem District –	Rs. 33660	No. 108 W of 1892-93
2. — Do — Do — at Tirupatur — Do —	Rs. 36,600	No. 109 W of 1892-93.

2. The Superintending Engineer IV Circle will submit a supplemental estimate for enclosing each of the offices with a barbed wire fence.

3. The current year's grant for

for each of the works is
Rs. 6000.

A.M.
2.2.93

Fr. 3/2/93

Note

It is proposed to communicate the G.O. to the Editor's Table

H.M. 4/2

~~2) His Excellency the Governor~~
~~1) The Hon'ble Henry Stokes~~

I/12/95

16

To
The S.E. IV Circle with plans & estimates
" Exar. P.W. Accts.
" Revenue Depty.
" Editor's Table

1/3/93

367/17

C No. 12733/92

Govt. of 1893 Madras.
PUBLIC WORKS.

18/2/93

367/17

Dated

Recd. Encl.

G.O., 9th February 1893, No. 367: W

Taluk offices at
Tiruchengod & Tirupatur

Estimates reduced respective
to Rs 33,660 and Rs 36,600 for
constructing first class —
in the Salem District,
sanctioned with remarks.

10/6

101

S 10/2

J.C. 10/2