(1) பக்கங்களின் எண்ணிக்கை 14

(2) புதுக்கித் திருப்பிய நாள்

(3) ஆதாரங் குறிப்பவர் சுருக்கொப்பம் 1/9/95

தமிழ்நாடு ஆவணக் காப்பகம்.

தமிழ்நாடு அரசு

பொதுப்பணி துறை

அரசாணை எல்.
மு. கோப்புத் தாள் எண். 454 W

அச்சகம்
பலவகை

நாள் : 21 – 2 – 1893 199 .

அ. பாண்டி

மடிக்கவோ கண்டபடி கையாளவோ கூடாது.

ஆவண. கா. 1—18,006—6-9-90.

செப்பனிடுபவர் பெயர் அ. பாண்டு
செப்பனிடுவதற்காக எடுத்துக்
கொள்ளப்பட்ட நாள் ஆகஸ்டு 95
[illegible] ஆகஸ்டு 95
சரிபார்க்கும்
மு. எ. 1/9/95
கையொப்பம்
ஆராய்ச்சி
[illegible]
கையொப்பம்

21st February 1893, No. 454 W., Public Works.

454
1

GOVERNMENT OF MADRAS.

PUBLIC WORKS DEPARTMENT.

Buildings and Roads.
Civil Works.

Read—the following paper:—

From J. C. LARMINIE, Esq., Superintending Engineer, IV Circle, to the Inspector-General of Registration, dated 29th November 1892, No. 405-M.

With reference to Proceedings of Government, dated 19th October 1892,* No. 2145, in the Judicial Department, I have the honour to forward, for your approval and transmission to Government for sanction and provision of funds, plans and estimates, amounting to Rs. 4,220 for constructing a Sub-Registrar's office at Kuttipuram in Ernád taluk, Malabar district.

* *Sic.*

2. The estimate for a Sub-Registrar's office at Tanur will be submitted when received from the Executive Engineer to whom a reminder has been sent.

G. No. 50.

Submitted for the sanction of Government.

2. The necessity for the construction of an office building for the Sub-Registrar of Kuttipuram was brought to the notice of Government in this office letter recorded in G.O., dated 19th October 1891, No. 2145, Judicial.

(Signed) S. HARI ROW,
Ag. Inspector-Genl. of Registration.

Madras,
10th January 1893.

To the Chief Secretary to Government.

No. 189, Judicial.

Approved and transferred to the Public Works Department.

(By Order.)

(Signed) A. BUTTERWORTH,
Acting Under-Secretary.

30th January 1893.

Order—dated 21st February 1893, No. 454 W., Public Works.

The estimate, amounting to Rs. 4,220, for constructing a Sub-Registrar's office at Kuttipuram in the Malabar district, is sanctioned.

2. A sum of Rs. 4,000 has been provided for the work in the Provincial Civil Works Budget for 1893-94.

3. This sanction has been registered as Provincial No. 112 W. of 1892-93 and classified as Civil Buildings, Original works.

(True Extract.)

Major, R.E.,
Under-Secy. to Govt., P.W.D.

To the Superintending Engineer, IV Circle,
with plans and estimates
,, Examiner, Public Works Accounts.
,, Judicial Department.
Editors' Table.

Exd. T. K. Narayana Aiyangar.
Spare Copies

454/2

BUILDINGS AND ROADS.
CIVIL WORKS.

Govt. of {1893} Madras.

PUBLIC WORKS.

Dated February, 21st.

Recd. Encl.

G.O., 21st Feb. 1893, No. 454 W.

FEBRUARY.

Sub-Registrar's Office

Estimate of Rs. 4,220 for constructing a—at Kuttipuram in the Malabar district, sanctioned.

No. 405/M.

Superintending Engineer's Office
4th Circle, 29th November 1892.

454

From
J. C. Larminie, Esq.,
Superintending Engineer,
4th Circle.

Enclo: 6.
1 Plan of building
1 Site plan
1 Estimate
1 Report
1 Specification
1 abstract.

To
The Inspector General of Registration,

Sir,

With reference to Proceedings of Government dated 19th October 1892× No. 2145 in the Judicial department, I have the honor to forward for your approval and transmission to Government for sanction and provision of funds, plans and estimates amounting to Rs 4220 for constructing a Sub Registrar's Office at Kuttipuram in ~~Erode~~ Ernad taluq, Malabar District.

× sic

Ernád

2. The estimate for a Sub Registrar's Office at Tanur will be submitted when received from the Executive Engineer to whom a reminder has been sent.

I have the honor to be,
Sir,
Your most obedient Servant,
(Signed) J. C. Larminie
Superintending Engineer,
4th Circle.

J. No.

G. No. 50, dated 10 January 1893,
Madras.

Submitted for the Sanction of Government.

2. The necessity for the Construction of an office building for the Sub Registrar of Kuttipuram was brought to the notice of Government in this office letter recorded in G.O. dated 19 October 1891, No. 2145. Judicial

S. H[illegible] Row
Ag. Inspr. [illegible] of Registration.

To
The Chief Secretary to Government,
Fort Saint George.

Exmd.

~~CURRENT NO. 122~~

~~JUDICIAL (1893) DEPARTMENT.~~

"REGISTRATION."

P. W. CURRENT No. 877

[illegible]
28[illegible] : 7.10.92 S

From

THE Ag. INSPECTOR-GENERAL OF
REGISTRATION,
Madras,

To

THE Ag. CHIEF SECRETARY
TO GOVERNMENT,
Fort St. George.

Recd 31-1-93

Dated 10
~~Desp~~ Received 11 } January 1893.

No. 50.

ENCLOSURES six (2 plans)

No.

14 JAN 93
GOVERNMENT

Submitting for approval and sanction plan and estimates for the Construction of an office building for the Sub Registrar of Kuttiparam in the Malabar District.

(Est. Rs. 4220)

1134 : 3-11-91 R
2145 : 19.10.91 Mis
1622 : 21.10.90 Sc

H. M. Dy 30 January (93 No 189)
Recd 27/Jan

Approved & transferred to the Public Works Department.
(By order)
A. B. Huttemorth.
Ag. Under Secretary.
C 23 Jan

To the Public Works Dept with enclos.
17/1

No. 2837 W d/27-10-91 ✓
" 1320 W " 13-5-91 ✓

C. 23/1
R. 27/1

Public Works Department.

Current No. 877
Letter No. 189 ~~454~~
Dated 30th January 1893
From the Judicial Dept.
~~Sanitary~~ ~~Old~~

TECHNICAL NOTE.

Name of Work Constructing a Sub Registrar Office at Kuttiparam, Malabar Dist.

Amount of Estimate, Rs. 4220

3/2/93

PARTICULARS OF ESTIMATE.

Main Building	Office	Rs.	3450
~~Subsidiary Buildings~~	Compound wall	"	770
Contingencies	3/4 % Rs 101	"	—
Petty Supervision	3/4 % Rs 98	"	—
Land compensation		"	—
Total Rupees ...			4,220.

PARTICULARS OF CONSTRUCTION.

Surface soil } Red loam
Sub soil }

Foundations are to be sunk 4 feet deep the lower 18 inches to be of concrete & the upper 2½ feet of laterite stone in chunam.

Basement is to be raised 2 feet & built of laterite stone in chunam.

Walls are to be raised 13 feet high as per type plan & built of laterite stone in chunam with arches over doors & windows. The top of basement is to be asphalted so as to form a damp proof course.

Plastering ~~or Pointing~~ the interior faces are to be plastered with 2 coats of chunam & the exterior faces plastered with surki mortar

Flooring is to be of 9" square bricks laid on 4" of concrete except for the record room which is to be asphalted 3/4" thick on 4" concrete

Roofing is to be of Mission tiles laid over teak reapers, jungle wood rafters &c. & the roof ceiled with 3/4" cedar wood planks

Doors and Windows are to be of the descriptions noted in the estimate of teakwood & painted with 3 coats of silicate paint.

Roof timbers are to be of jungle wood ([illegible] or [illegible]) & wood oiled 3 coats.

Scantlings slightly in excess to those provided in the printed estimate but they are correct for jungle wood.

Rates are fair.

The plinth area of the main building is 1,374 square feet, and the cost per square foot will be Rs. 3. 1. 0.

The plans and estimates have been countersigned by the Inspector General of Registration and approved in the Judicial Dept. ~~Department.~~

REMARKS.

This estimate has been framed with reference to G.O. No. 2837 W dated 27th October 1891 and it provides for constructing a Sub-Registrar's office at Kuttipuram in the Malabar Dist. as per type design approved in G.O. No. 1320 W dated 13th May 1891 for larger offices.

The partition walls have been altered from 1'1½" to 1'6" owing to the use of laterite masonry & the eaves extended 2 feet instead of 1'6" to suit the wet climate of the West Coast.

Venetian shutters to windows protected by the verandah have been omitted as they are considered unnecessary. These windows will be fitted with glazed ~~and~~ inner shutters & iron

The

The site selected is Govt. land & it has been approved of by the Collector & the Dist. Registrar.

6. II. 93

A Compound wall 4'9" high has been provided for at the request of the Registration Dept.

A

No. 454 W d/ 21st Feby 1893.

PUBLIC WORKS DEPARTMENT.

PROCEEDINGS OF THE MADRAS GOVERNMENT.

454
6

READ the following

Print

From the Inspector Gl. of Registration No. 50 G d/ 10th Jany. 1893
Endorst. thereon in the Judicial Dept. No. 189 d/ 30th — do —

30

The estimate, amounting to Rs. 4,220, for constructing a subregistrar's office at Kuttipuram in the Malabar District, is sanctioned.

2. A sum of Rs. 4,000 has been provided for the work in the Provincial Civil Works Budget for 1893-94.

3. This sanction has been registered as Provincial No. 112 W of 1892-93 and classified as Civil Buildings, Original Works.

W.S. 15 Feb

~~Note~~
~~It is proposed to communicate the G.O. to the Editor's Table~~

To
The S.E. IV Circle with plans & estimates (6)
" Exar. P.W. Accts.
" Judicial Dept.
" Editor's Table

D 9/3

Rev. 14/2

16/2/93

14.2.93

154/7

17/2 R 20/2

No. 877

Govt. of {1893} Madras.
PUBLIC WORKS.

22/1/93

G.O. 21st Octr 1893 No. 454 W

Sub Registrar's office

Estimate of Rs 4220
for constructing a –
at Kuttipuram in
the Malabar Dt
sanctioned. –

1/4

3.C. 22/2 F 22/2 1-4