

2317 NOBR.

- (1) பக்கங்களின் எண்ணிக்கை 12
(2) புதுக்கித் திருப்பிய நாள் May 90
(3) ஆதாரங்குறிப்பவர் கருக்கொப்பம் lop

தமிழ்நாடு ஆவணக் காப்பகம்.

தமிழ்நாடு அரசு

P.W துறை

அரசாணை எண். <u>P.W.D. 505</u>	அச்சகம் பலவகை
மு. கோப்புத் தாள் எண்.	
நாள் : <u>27-2-1983</u>	1983

✓ மடிக்கவோ கண்டபடி கையாளவோ கூடாது

ஆவண. கா-1-18,000-15-6-87.

செவ்விய

27TH FEBRUARY 1893, No. 505 W., PUBLIC WORKS.

GOVERNMENT OF MADRAS.
PUBLIC WORKS DEPARTMENT.

Buildings and Roads.
Civil Works.

READ—the following paper:—

From H. W. FOSTER, Esq., Registrar of the High Court of Judicature, Appellate Side, to the Chief Secretary to Government, dated Madras, 18th January 1893, No. 57.

I am directed to forward, for the sanction of the Government, the accompanying plans and estimate, amounting to Rs. 17,300, for the construction of a court-house for the District Munsif of Narsaraopet in the Kistna district.

2. The house in which the court is at present held is incommodious and early sanction and allotment of funds are therefore solicited.

No. 188, Judicial.

Approved and transferred to the Public Works Department.

(By Order.)

30th January 1893.

(Signed) A. BUTTERWORTH,
Ag. Under-Secy. to Government.

ORDER—dated 27th February 1893, No. 505 W., Public Works.

The estimate, amounting to Rs. 17,300, for constructing a court-house for the District Munsif at Narsaraopet in the Kistna district, is sanctioned.

2. A sum of Rs. 10,000 has been provided for the work in the Provincial Civil Works budget for 1893-94.

3. This sanction has been registered as Provincial No. 116 W. of 1892-93 and classified as Civil Buildings, Original Works.

(True Extract.)

Major, R.E.,
Under-Secy. to Govt., P.W.D.

To the Superintending Engineer, II Circle, with plans and estimates (7).
" Examiner, Public Works Accounts.
" Judicial Department.
Editors' Table.

Encl. T. K. Naranaya Aiyangar.
Spare Copies

BUILDINGS AND ROADS.
CIVIL WORKS:

Govt. of {1893} Madras.
PUBLIC WORKS.

Dated February, 27th.

Recd.

Encl.

G.O., 27th Feb. 1893, No. 505 W.

FEBRUARY.

Court House

Estimate of Rs. 17,300 for constructing
a — for the District Munsif at Narsaraopet
in the Kistna district, sanctioned.

N^o 57. 505

High Court of Judicature,
Madras, 18th January 1893.

From

H. W. Foster Esquire,
Registrar of the High Court
of Judicature, Appellate Side,
Madras.

To

The Honorable C. A. Galton,
Ag. Chief Secretary to Government,
Fort Saint George.

Sir,

I am directed to forward for the sanction
of the Government, the accompanying plans
and estimate amounting to Rs. 17,300 for the
construction of a Court-house for the District
Munsif of Narsaraopet in the Kistna District.

2. The house in which the Court is
at present held is inconvenient and early
sanction and allotment of funds are therefore
solicited.

I have the honor to be,
Sir,
Your most obedient servant,

(Signature)

Registrar.

507
3

CURRENT NO. 170

P. W. CURRENT No. 878

Gp 1154: 2.6.87ms

Judicial {1893} Department.

No.

From

THE REGISTRAR OF THE HIGH COURT
OF JUDICATURE AT MADRAS,
APPELLATE SIDE.

Emb 7 (2 plans)

Recd 31.1.93

Dated 18 January

Received

1893

SECRETARY
10 JAN 93
MADRAS

No. 57

Enc

Submitting for sanction
plans and estimate amounting
to Rs. 17,300 for the construction
of a Court-house for the
District Munsif of
Narsaraopet.

R-23/1
R-27/1

Over

C-23/1
R-27/1

NP ✓

Am 2730 January 1893 Rs. 100

Endorsement 27 Jan

Approved and transferred
to the Public Works Dept
(By order)

Attestation

As Under Secretary

23/1

No. 802 w of 17-3-91

5
11
7
18
11
31
82

505/3

Public Works Department.

Current No. 898

Letter No. 188

Dated 30 January 1893

From the Judicial Dept

TECHNICAL NOTE.

Name of Work Constructing a District
Munsif Court house at Narsaraopet,
Kistna District

Amount of Estimate, Rs. 17,300.

PARTICULARS OF ESTIMATE.

Main Building Court house	Rs. 13,414
Compound wall & gate	1,889
Subsidiary Buildings Record room	285
Chamber over drain	350
Sheds for materials & labour	300
Contingencies 5%	710
Petty Supervision 2 1/2%	352
Land compensation	100

Total Rupees 17,300

PARTICULARS OF CONSTRUCTION.

Surface soil hard earth to a depth of 2 feet
Sub soil gravel
Foundations on the ground & feet deep
The lower 2 feet to be of concrete &
the upper 2 feet built with stone in
chunnam
Basement in the raised 2 feet high &
built with stone in chunnam
Walls are to be raised as per height
indicated in the type design & built
with stone in chunnam with arch
work of brick in chunnam over
doors & windows.

Plastering or Pointing interior faces of walls are
one thickness with 2 coats of chunnam
& the exterior faces pointed with chunnam
 Flooring is to be of teak planks laid on a
bed of concrete 4 1/2" thick.
 Roofing is to be of Mangalore tiles laid over
teak rafters & ceiled with 1/2" pine
ceiling except the verandah which
will not be ceiled.
 Doors and Windows as per the descriptions
noted in the estimate of teakwood &
pointed with 3 coats of chunnam paint
 Roof timbers as per the descriptions & pointed
with 3 coats of chunnam paint.
 Scantlings are correct.

Rates many of the rates are in excess of the
Divisional schedule but data are
submitted.

The plinth area of the main building is
 5000 square feet, and the cost per square
 foot will be Rs. 3.13.9.

The plans and estimates have been countersigned
 by the District Judge
 and approved in the Judicial Dept.
 Department.

REMARKS.

This estimate has been framed
 with reference to item 22 Part I Class
 B works of the Provincial Budget for
 1893 & it provides for constructing
 a Court house for the District Municipality
 at Narsaraopet in the Krishna Dist.
 as per type design approved in G.O.
 No. 1098 dated 21st Apr 1894.

Provision has been made in the
 estimate for fitting the Court house
 with 5 wooden screw racks & a room
 with steps ladder also for erecting
 a compound wall with gate, culvert
 over drain & sheds for materials
 & labour.

The site selected appears to be
 private land for which compensation
 to the extent of Rs. 100 has been
 provided in the estimate.

Submitted for the compound wall
 though in the abstract estimate it
 is mentioned "as per separate
 estimate attached"

The verandah posts are pro-
 posed to be made of teak wood
 15 ft each at Rs. 600 for the
 if teakwood be substituted
 provided for in the estimate. In
 estimate the saving will be Rs. 300
 Thus 75 cfr of teakwood at Rs. 4
 per cfr = Rs. 300 against 600
 for teak wood posts.

See floor plan
 with better

The masonry is placed on
 walls in the Gornistah & Vakid
 room the type design also shows
 the masonry is in walls, the do-
 orways being the slightly above
 even as the present the line has
 coming just near them.

No. 505-W.d/27 February 1893
 PUBLIC WORKS DEPARTMENT.

PROCEEDINGS OF THE MADRAS GOVERNMENT.

Read the following

From the Registrar of the High Court No. 57 of 18 Jan. 1893
 Endorsed thereon in the Judicial Dept. No. 188 of 30 - do -
 310

The estimate, amounting
 to Rs. 17,300, for constructing
 a Court house for the District
 Munsif at Narsaraopet
 in the Krishna District, is
 sanctioned.

2. A sum of Rs. 10,000 has been
 provided for the work
 in the Provincial Civil
 Works Budget for 1893-94.

3. This sanction has been
 registered as Provincial
 No. 116 W of 1892-93 and
 classified as Civil
 Building, Original Works.

Not
 His proposed
 to communicate
 the G.O. to the
 Editor's Table

So the S.E. II Circle
 with plans & estimate (T)

Exas. P.W. Accts.
 Judicial Dept.
 Editor's Table

for 22/2/93
 1893
 1893

805
b

CN^o 878

Govt. of Madras.
PUBLIC WORKS.

28/2/93

27 July 1893 505 W

Court House

Estimate of Rs 17,300
for constructing a
for the District Mining
at Narasaspet
in the Kistna D.,
sanctioned.

90
16

50-11-1892